This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

RENSHAW'S MANUALS

In Fcap. 8vo, cloth.

DRUITT'S SURGEON'S VADE MECUM	14/0
GUY'S FORENSIC MEDICINE	12/6
HOOPER'S PHYSICIAN'S VADE MECUM	12/6
CHURCHILL'S MIDWIFERY	12/6
KNOX'S MANUAL OF ANATOMY	12/6
SILVER'S PRACTICAL MEDICINE	12/6
FOWLER'S MEDICAL VOCABULARY	12/6
TANNER'S INDEX OF DISEASES	10/6
GREEN'S PATHOLOGY AND MORBID ANATOMY	10/6
MEADOWS' MIDWIFERY	10/6
HILLES' ESSENTIALS OF PHYSIOLOGY	10/6
LAWSON ON THE EYE	10/6
CLARKE'S MANUAL OF SURGERY	10/6
WHITLA'S PHARMACY, MATERIA MEDICA AND THERAPEUTICS	10/6
MILNE-EDWARDS' ZOOLOGY	8/6
ROSER'S SURGICAL ANATOMY	8/6
TANNER'S CLINICAL MEDICINE	7/6
SILVER'S OUTLINES OF BOTANY	7/6
WARD'S HUMAN OSTEOLOGY	7/0
THOMPSON ON THE CHEST	6/6

HOOPER'S

CIAN'S VADE MECUM.

HOOPER'S

PHYSICIAN'S VADE MECUM.

Ballantyne Press
BALLANTYNE, HANSON AND CO., EDINBURGH
CHANDOS STREET, LONDON

HOOPER'S

PHYSICIAN'S VADE MECUM:

A Manual of the Principles and Practice of Physic;

WITH AN OUTLINE OF GENERAL PATHOLOGY, THERAPEUTICS, AND HYGIÈNE.

TENTH EDITION.

BIBLIOTHECA BODLEIANA

REVISED

BY

WILLIAM AUGUSTUS GUY, M.B. CANTAB., F.R.S.,

FELLOW OF THE ROYAL COLLEGE OF PHYSICIANS;
LATE PROFESSOR OF FORENSIC MEDICINE AND HYGIENE, KING'S COLLEGE, LONDON;
CONSULTING PHYSICIAN TO KING'S COLLEGE HOSPITAL; ETC. ETC.

AND

JOHN HARLEY, M.D. LOND., F.L.S.,

FELLOW OF THE ROYAL COLLEGE OF PHYSICIANS;
HONORARY FELLOW OF KING'S COLLEGE, AND LATE PHYSICIAN TO THE LONDON FEVER HOSPITAL;
LECTURER ON GENERAL ANATOMY AND PHYSIOLOGY AT, AND PHYSICIAN TO, ST. THOMAS'S HOSPITAL.

LONDON:
HENRY RENSHAW; WHITTAKER & CO.; SIMPKIN & CO.
J. & A. CHURCHILL; HOULSTON & SONS.
EDINBURGH: A. & C. BLACK; MACLACHLAN & CO.
DUBLIN: FANNIN & CO.
1882.

151. o. 582.

EDITORS' PREFACE.

The original work of Dr. Hooper, published in 1823, was so successful, and passed through so many editions, as to induce the proprietors to place it in the hands of successive Editors, by whom it was improved and enlarged.

From Dr. Hooper's Preface, it appears that the object he contemplated was to furnish a concise treatise on the practice of medicine for the use of Student and Practitioner. After his death an Introductory Part was added, containing a short outline of Physiology, Pathology, and Therapeutics, some brief directions for Clinical Examination, and a sketch of Symptomatology and Semeiology. This, which did not occupy more than sixty-five pages, was entirely re-written in the first edition entrusted to Dr. Guy, who is largely responsible for the additions and alterations made in this part in all the subsequent editions; while Dr. Harley is now similarly responsible for the matter contained in the second part. Both parts are largely illustrated by wood-engravings, of which several, and those chiefly microscopic, are from original drawings by Dr. Harley. Many old cuts have been replaced by others, and some new ones have been added. The total is now 118.

The general aim and scope of the work is fully explained in the Introduction.

In making the extensive changes and additions above indicated, the original intentions of the Author, to make this work practically useful to the Student and Practitioner' have been strictly adhered to, and we believe it will now be found the most comprehensive work of the kind hitherto published in this country.

Many original observations and practical remarks, embodying the results of Dr. Harley's experience, are contained in the text of the second part. Those contributed by Dr. Guy to former editions are distinguished by the initial G.

William A. Guy,
12, *Gordon Street.*

John Harley,
39, *Brook Street,*
Grosvenor Square.

September, 1881.

INTRODUCTION.

THIS book is intended to be, in the largest sense of the term, a practical work; that is to say, it aims at bringing together, in a small compass, and in a form easy of reference, those items of information which the practitioner would wish to possess when he stands at the bedside, or when he studies a case with a view to its treatment.

The first and most obvious requisite for a practitioner is to be able to recognize a disease when he sees it, to distinguish it from others that resemble it, and to foretell its probable course and termination. The treatment he adopts will be judicious in proportion to the certainty with which he recognizes, and the accuracy with which he discriminates, diseases; and will be either rational or empirical, according as he does or does not understand their real nature and true cause.

But there is a vast amount of information of a truly practical character, which does not find a place in formal descriptions of individual diseases. For age, sex, and peculiarity of constitution, original and acquired, give rise to differences in health, or habitual departures from it, which determine the severity, and even modify the character, of diseases; and a knowledge of this order of facts is not less essential to safe and successful practice than is a description of diseases themselves.

Again, it often happens that great importance attaches to individual symptoms, and questions occur in relation to them, which cannot be answered in the short space devoted to the description of the disease of which they form a part. They may be common to several diseases, or though assumed to be symptoms of disease, they may be compatible with health. Moreover, there are many symptoms or signs of disease which are detected only by close examination, aided by the use of instruments or of chemical tests; in using which many precautions are necessary, not easily borne in mind, and as to which the practitioner may require to refresh his memory.

In the practice of medicine, again, new events and rare combinations constantly present themselves, which can only be understood and successfully encountered by the aid of general principles. Hence the necessity of a knowledge of pathology and therapeutics, as guides in treating obscure cases, or complications of which the physician has no previous experience.

A strong conviction that no man is truly practical who is not also possessed of an extensive scientific knowledge of his profession, has always presided over the preparation of this work, and has induced the Editors to extend it beyond the limits usually assigned to a so-called practical treatise.

In order to carry out these views, this work is divided into two parts of which the first embraces those facts and general principles that make up the sciences of General Pathology and Therapeutics, while the second contains, in a form easy of reference, a description of diseases, their diagnosis and prognosis, rationale and treatment, or what is usually known as tth Theory and Practice of Medicine.

The First Part consists of six chapters, under the following titles :—1. *Health and Disease;* with an account of their variations under the influence of age, sex, temperament, and mode of life, and explanations of the terms in common use for distinguishing diseases, and giving precision to our, views and statements concerning them.—2. *Causes of Death:* in which some idea is given of the relative frequency and importance of the diseases that prove fatal to human life.—3. *Outline of Physiology and General Pathology.*—In this chapter those facts and theories which bear most directly upon medical practice are briefly stated, more minute details being reserved for—4. *Examination of some of the more important Symptoms and Signs of Disease*, comprising the Urine, the Viscera of the Abdomen and of the Chest, the Pulse and the Respiration. Chapter 5 treats of *Hygiène*, private and public; while chapter 6 contains *An Outline of General Therapeutics*, as they bear on the preservation and improvement of health and the treatment of disease, with an account of the principal remedies, and their mode of operation; with a short section on nursing.

The Second Part, or Practice of Medicine, properly so called, is also distributed into chapters, as follows:—1. States of System, as distinguished from diseases properly so called.—2. Local Diseases, affecting all or several of the organs or textures of the body.—3. Febrile Diseases without essential local complication.—4. Febrile Diseases with essential local complication.—5. Febrile Diseases arising from local causes.—6. General Diseases (not febrile), with essential local complications. The remainder of the diseases are distributed into ten chapters, as follows:—1. Diseases of the Nervous System.—2. Diseases of the Organs of Circulation.—3. Diseases of the Organs of Respiration.—4. Diseases of the Organs of Digestion and Abdominal Viscera.—5. Diseases of the Urinary Organs.—6. Diseases of the Organs of Generation.—7. Diseases of the Organs of Sense.—8. Diseases of the Skin and its Appendages.—9. Parasitic Animals; and 10. Poisons, with the Antidotes to the principal poisons.

An extensive collection of Formulæ, preceded by classified lists of the preparations of the British Pharmacopœia, with their doses, is added; and glossarial and general indexes complete the volume.

PART I.

GENERAL PATHOLOGY AND THERAPEUTICS.

CONTENTS.

CHAPTER — PAGES

I.—HEALTH AND DISEASE . . . . 1 to 27

II.—CAUSES OF DEATH . . . . 28—31

III.—PHYSIOLOGY AND GENERAL PATHOLOGY . . . . 32—118

1. Of the Fluids.—2. Of the Circulating System.—3. Structural Physiology and Pathology.—4. Of the Nervous System.—5. Of the Mind.

IV.—EXAMINATION OF THE MORE IMPORTANT SYMPTOMS AND SIGNS OF DISEASE . . . . 119—206

1. Of the Urine.—2. Of the Abdomen and Organs of Digestion.—3. Of the Chest and the Organs of Respiration and Circulation.—4. Of the Pulse.—5. Of the Respiration.—6. Of other Symptoms and Signs of Disease.

V.—HYGIÈNE . . . . 207—229

1. Private Hygiène.—2. Public Hygiène. 3. Dietaries.—4. Deodorants, &c.

VI.—GENERAL THERAPEUTICS . . . . 230—252

1. Remedies applicable to Diseases of the Alimentary Canal.—2.—Remedies which modify the Composition of the Blood.—3. Medicines which act on the Organs of Circulation.—4. Remedies adapted to the Removal of the Solid Structures of the Body.—5. Remedies which act on the Nervous System.—6. Nursing.

For Contents of Part II. see p. 253.

THE

PHYSICIAN'S VADE MECUM.

CHAPTER I.

HEALTH AND DISEASE.

1. HEALTH may be defined as the integrity of every structure, and the perfect harmonious play of every function of the body; and its ready adaptability to variations in the external conditions of life, such as the temperature, pressure, and moisture of the atmosphere, as well as to changes in the quantity and quality of the food.

2. Perfect health is as rare as extreme old age. Perhaps, indeed, there is but one condition of the body to which the term "health" is applicable; but there may be departures from this standard of perfect health, to which, nevertheless, the terms disorder or disease would be inapplicable.

3. That health is a condition admitting of degrees is shown by the familiar use of such terms as "*good,*" "*perfect,*" "*strong,*" "*vigorous,*" "*robust,*" "*feeble,*" "*delicate*"—differences generally recognized, not only as belonging to the same person at different times, and at different periods of life, but also as distinguishing one individual from another.

4. But besides these differences in degree there are differences in kind, corresponding more or less to peculiarities of external form and indicating a tendency to particular diseases, or to a peculiar character pertaining to all the diseases to which the person may become subject. These differences are recognized as *Temperaments*—a word wanting in precision, but embodying a useful generalization.

5. Four temperaments are generally recognized—the *sanguine*, the *phlegmatic*, the *bilious*, and the *nervous*.

6. The *sanguine* temperament is characterized by moderate plumpness of person and firmness *of flesh*. *The hair* is red or light chestnut, *the eyes blue, the complexion fair* and florid, the skin soft

19. Hereditary diseases, as distinguished from hereditary tendencies to disease, are comparatively rare. Few children, for instance, are born with tubercles in the lungs, or with apoplexy.

20. A peculiarity of form, character, or morbid tendency, has been known to disappear in one generation, and reappear in the next. This form of hereditary predisposition has been termed *Atavism.*

21. Hereditary diseases or predispositions to disease may be transmitted without any fault or imprudence on the part of parents. But children are often born into the world of infirm constitution and prone to disease, in consequence of circumstances referable to the marriage of the parents, such as extreme youth or advanced age, great disparity of age, or too close alliance in blood.

22. The habitual state of health of the parents, or even their state of health at the time of conception, and that of the mother during pregnancy, may also determine the constitution of the offspring.

23. Vice is the fruitful parent of disease, not only to the vicious themselves, but also to their innocent offspring, who are usually the greatest sufferers. Thus inherent debility of constitution, and scrofula, with its numerous train of minor disorders, may be traced to syphilis in the parent. The abuse of alcoholic liquors in one generation not unfrequently imposes phthisis, epilepsy, or obesity, on the next. And vice-begotten disease often carries its ravages into succeeding generations.

24. The facts just stated with respect to hereditary predisposition are confirmed by observations on animals, which exhibit its effects not only in their outward form but also in their instincts and habits.

25. Among the morbid states that have been by general consent traced to hereditary taint, the most important is *scrofula.* It consists in an inflammatory deposit in the glands of the neck, or mesentery; in the substance of the lungs, liver, and kidneys; in the membranes of the air passages, intestines, brain, and spinal cord. This deposit usually breaks down, and leads to important structural changes, resulting in lingering and wasting maladies. It appears to acknowledge as its principal cause a certain weakness and unsoundness of constitution, which, after giving rise to one disease in the parent, may show itself in his offspring in different forms. Thus an epileptic parent may have children afflicted, not only with nervous and mental affections, but with scrofula or consumption.

26. From what has been stated concerning temperaments, diatheses, and hereditary predispositions, we may draw this practical inference, that we shall encounter at the bedside a vast variety of constitutions, and many degrees of vigour, by which our treatment of disease must needs be influenced and modified. Hence it is an advantage to a patient that his physician should know his constitution and peculiarities.

remedy in its strongest form. The second kind consists ›duction of poisonous effects by the most common articles is when fish, fruit, vegetables, and meat, usually accounted wholesome, occasion marked disorder of the digestive ıccompanied sometimes with cutaneous eruptions. The ss consists in the inversion of the characteristic effects ines; as when opium excites instead of soothing, and sleepiness attends the action of common Epsom salts. A ›ental idiosyncrasies might be added, consisting in strange es or aversions for objects usually deemed indifferent.

e differences arising from temperament, diathesis, hereditary ition, and idiosyncracy, may exist between males or f the same age; but other and very important differences pon sex and age.

x.—The constitution of men differs from that of women; e as in health. In the constitution of the male there is e and strength, and in the structure of his body more hence a greater proneness to inflammatory affections and morrhages; females, on the other hand, have more sensi- l excitability, and a more lax and delicate fibre, with a ndency to nervous affections and to diseases of an asthenic r. The functions of menstruation, parturition, and lac- lso exercise a marked difference on the health of the specially in the production of disorders of the circulation ous system.

e diseases of men, taken one with another, are more fatal se of women; men are also more exposed to accident and and more addicted to intemperance. Hence the lower a of females, their greater longevity, and the excess of diseases, and of females to asthenic and nervous disorders: so that, as a general rule, if a male and female are attacked by the same disease, the former will bear lowering remedies better than the latter.

34. *Age.*—There are several important practical considerations connected with age. In infancy, we have to bear in mind the gradual, and often imperfect, establishment of the function of respiration, and the consequent necessity of external warmth; in early childhood the disturbance produced by teething; and throughout infancy and childhood, the liability to disorders of the stomach and bowels on the one hand, and of the brain on the other. As the first exposure to contagious diseases usually occurs during the early periods of life, and their *sequelæ* often make a deep and lasting impression on the health, this is another source of modification which ought not to be overlooked. (See in Part II. the fevers, and febrile exanthemata.)

35. As childhood passes into youth, the disorders of the alimentary canal become less frequent and fatal, and react less severely on the nervous centres.

36. Puberty, which occurs in either sex about the age of 14, entails familiar changes, physical and mental; and, in women, the peculiar function of menstruation. The advent of these changes is often postponed for a few years, during which women are subject to disorders dependent on the imperfect establishment or complete suspension of the menses. Of these disorders anæmia is the most common; but chorea and epilepsy, melancholia, and even mania, attest its occasional influence on the nervous system.

37. The disproportion between the head and abdomen and the rest of the body lessens as age advances; by the twenty-first year the frame assumes its due proportions; and by the twenty-fifth year, or a little later, its full growth. In this period of youth disorders of the nervous system are rare, but febrile and inflammatory affections common; and scrofula, which had shown itself in the form of enlarged glands of the neck, white swellings of the joints, and disease of the mesenteric glands, may now take the modified form of pulmonary consumption.

38. From the twenth-fifth to about the forty-fifth year, the body remains nearly stationary, but with an increasing disposition to corpulence. During the first part of this period, febrile and inflammatory affections and pulmonary consumption are rife; but towards the fiftieth year, congestion and slow degeneration of the tissues of important organs take the place of inflammation, and apoplexy is henceforth a common and rapidly-increasing cause of death. In women, the interval from forty to fifty, with the years preceding and following, is marked by the cessation of the menstrual discharge, and the strange nervous affections which often accompany the "change of life."

39. From fifty to sixty years, the body begins to show signs

s of power and sluggishness of function, the prelude to that decay of which the progress is indicated by diminished ility, impaired memory, muscular weakness, scanty secretions, ous affections, osseous deposits, and organic visceral disease.

From this enumeration of the diseases prevailing at different it will be inferred that the risks to which life is exposed, as red by the death-rate, differ considerably. The most fatal period first year, during which one-fourth of all the recorded deaths place. During the four succeeding years, also, the number of s is so considerable, that the 25 per cent. of the first year ses for the first five years 42 per cent. By the completion of fteenth year, this proportion is increased to nearly one-half. g the forty years from 15 to 55, rather more than a fourth of e deaths takes place, each decade contributing in nearly equal rtion to the aggregate result. At 55 years three-fourths of opulation have succumbed. From 55 to 85, 23 deaths in the ed, or nearly another fourth, takes place; the ten years from 75 being the most fatal. Two per cent. of the entire mor- is accounted for by the deaths after 85. A small number of hy and vigorous persons of either sex reach, or even surpass, ge of 100, and a still smaller number were once thought to attained or exceeded a century and a half. The following is densed view of the distribution of the deaths according to age, distributed into four equal parts, taking place in unequal s:—

Under 1 year	one-fourth.
1 to 15 (14 years)	one-fourth.
15 to 55 (40 years)	one-fourth.
55 and upwards	one-fourth.

. These figures show the deaths registered at the several ages; s the numbers living at each interval of age differ greatly, they ot display the true risk to life. This is shown in the follow- able, both for males and females.

it of 1000 males and 1000 females living in England at each the deaths placed opposite to those ages occur, one year with her, among the English population. The asterisks indicate the vals of age at which the death-rate is the same in the two sexes—

ges.	Males.	Females.	Ages.	Males.	Females.
nder 5	74	63	*35 to 45	13	13
to 10	9	9	45 „ 55	19	16
„ 15	7	5	55 „ 65	32	29
			65 „ 75	68	61
„ 15	7	7	75 „ 85	150	137
„ 25	8	9	85 „ 95	303	281
„ 35	10	11	*95 and upwards	452	452

. The figures which represent the rate of mortality of females r a curious approach to regularity of increase in the five decades from 5 to 55, and in the six from 45 to the end of life; the mortality in the first series being nearly as the numbers, 7, 9, 11, 13, 15, while that in the last series is not very remote from the numbers, 15, 30, 60, 120, 240, 480. From the fifteenth to the fifty-fifth year therefore the rate of mortality increases by about 2 in the 1000 every ten years; and after the fifty-fifth year doubles every ten years.

43. It is important to understand that the same age does not always represent the same degree of growth, or perfection of function. This fact is well illustrated in the female by the variable time of occurrence of the changes indicated by the appearance or cessation of the menstrual discharge. The most usual age for its first appearance is the fifteenth year; but it may happen at any age from eight to twenty-five. In rare instances it has occurred earlier than the eighth year, and, still more rarely, even in the first year of life. So, also, with its cessation. It may happen as early as thirty-five, or even earlier, and as late as fifty-six, or even later; and, after ceasing for a time, may recur at very advanced ages.

44. Another important consideration in regard to age relates to the fatality of the same diseases at different times of life. As age advances, the structure of the vital organs, when damaged by disease, becomes less easy of repair. Hence, the diseases of childhood are more amenable to treatment than those of older persons.

45. This general principle is well illustrated by the special case of the deaths by fever. As, in most fatal cases, fever destroys life by setting up inflammation in some important organ, such as the lungs, the bowels, or the brain, the mortality may be expected to keep pace with, and to be a measure of, the liability of the vital organs to become diseased, and to increase as the restorative power diminishes. The calculations of Mr. Finlaison, founded on the experience of the London Fever Hospital, fully confirmed this expectation. If we suppose 100,000 patients to be attacked with fever, at each of the ages specified in the table, the mortality will be that shown in the column of deaths:—

Age.	Deaths.
5 to 16	8,266
15 „ 26	11,494
25 „ 36	17,071
35 „ 46	21,960
45 „ 56	30,493
55 „ 66	40,708
66 and upwards	44,643

The risk to life from fever is, therefore, more than twice as great at 30 as at 10; nearly twice as great at 40 as at 20, and at 60 as at 40; it is nearly five times as great at 60 as at 10, and nearly four times as great above 65 as at 20. Like results have been obtained for the exanthemata, which, like fever, first affect the whole body, but in their progress attack individual organs; for dysentery among troops in unhealthy stations, or under unwholesome circumstances, abroad; and for other fatal maladies.

46. The liability to illness, and its duration, also increase with age. This is shown in the following table, by Mr. Neison, based on a large number of returns from English and Scotch Benefit Societies:—

Age.	Percentage Sick during each Year.	Sickness per Annum among those Sick, in Weeks.	Mortality per Cent. among the Sick.
11—15	21·9	4·1	1·0
21—25	22·0	3·8	3·1
31—35	21·0	4·4	3·8
41—45	23·0	5·9	4·5
51—55	27·6	8·5	6·2
61—65	35·6	15·2	8·6
71—75	58·4	32·3	12·1
81—85	74·5	37·8	18·4

47. The differences due to temperament, diathesis, hereditary predisposition, sex, and age, are still further extended and increased by *Air and Climate*, *Place of Abode*, *Supplies of Food and Water*, *Occupation*, *Habits*, and *Mode of Life*.

48. The most powerful of these influences is the atmosphere, which not only affects the body by variations in its temperature, pressure, moisture, and electric condition, but by its contact with the skin and internal surface of the lungs, produces the most important chemical changes in the blood. Several subtle poisons, of which some spring from inorganic matter, others from the decomposition of animals and vegetables, and others from diseased living bodies, are also held suspended in the air, and, when concentrated, cause fatal accidents, or severe diseases; but when diffused in smaller quantity, weaken the body, and impair the health. Smoke, dust, and metallic particles, resulting from chemical or mechanical operations, also impair the functions of the skin and lungs, and lay the foundations of disease.

49. The temperature, moisture, pressure, and electric state of the air, modified and blended by situation, soil, and the conformation of the surrounding country, constitute *climate*, of which the prolonged effect on the frame is seen in the form and features, as well as in the condition of the several functions of the body. Some of these conditions deserve a separate notice.

50. *Temperature* is by far the most important; for it has been well ascertained that in *temperate climates sickness* increases as the *temperature rises, while the mortality is* greatest when the ther-

mometer is very low; so that a hot summer and a cold winter are both very fatal to life. The summer diseases are diarrhœa, cholera, dysentery, and enteric fever, among the young and middle-aged; in winter, pneumonia and bronchitis are rife, and are very destructive to infants and aged persons. As a high temperature promotes putrefaction, it is favourable to diseases dependent on atmospheric impurity. Hence, in former times, when towns and houses were in a very uncleanly state, sickness and mortality were both at their height in summer; and one result of their improved sanitary condition is to shift the maximum mortality from the summer to the winter months.

51. The influence of temperature on the occurrence of fatal maladies is best shown by the following table, in which the months are thrown into three groups of cold, hot, and temperate. The following are the death-rates for London:—

Four cold months (Dec., Jan., Feb., March)	21 deaths.
Four hot months (June, July, Aug., Sept.)	19 „
Four temperate months (April, May, Oct., Nov.)	18 „

From this table it appears that the coldest months are most fatal; while the hot months rank next in fatality, those of intermediate temperature being the least fatal.

52. The fatal effect of cold, first distinctly pointed out by the younger Heberden, is strikingly shown by a comparison made by Dr. William Farr, between the deaths in ten consecutive cold days in November and December, 1856, and ten warmer days preceding and following them. The ten cold days had a mean daily temperature of 34°, and a mean nightly temperature of 27°; the ten warm days a mean daily temperature of 51°, and a mean nightly temperature of 47°. The results are shown in the annexed table.

	10 colder days.	10 warmer days.
Consumption	232	163
Bronchitis, Pneumonia, and other diseases of the Lungs	502	394
Diseases of the Heart	73	51
Diseases of the Brain	170	172
Other Diseases	867	725

In consumption, bronchitis, and other diseases of the lungs, and in heart-disease, therefore, a fall of about 20 degrees of temperature caused the deaths to rise in the ratios of 16 to 23, 39 to 50, and 51 to 73; while the total deaths in the colder were to the total deaths in the warmer days as 18 to 15.

53. The influence of temperature in promoting disease is most distinctly displayed in the inhabitants of temperate climates, after long residence in either the torrid or frigid zones, especially if, as often happens, they do not adapt their mode of life to the climate.

54. The temperature in different parts of the world also contributes largely to modify the diseases of the natives themselves. The countries within and adjacent to the tropics are severely scourged by intermittent, remittent, and yellow fever, diarrhœa, dysentery, and cholera, and diseases of the liver; while the countries verging on the North Pole are the homes of catarrhal affections, influenza, diseases of the organs of respiration, and scurvy; and the countries in the temperate zone, between the tropics and the poles, of fevers of the continued type, typhus and enteric, with intermittent and remittent fevers of a more tractable character, consumption, rheumatism, and cutaneous diseases of great variety, and often of great severity.

55. The diseases proper to the several regions of the globe also prevail in countries which share with them a similar temperature; so that isothermal lines, or lines of equal temperature, are lines also of equal or similar disease. Thus the diseases incident to countries in or near the tropics prevail along the equator of heat, or mean annual isothermal line of 82·4° Fahr.; and in and near all that zone or region which is bounded north and south by the isothermal line of 68°; while the diseases of the temperate zone occur in the countries lying on or near the isothermal line of 50°; and those of the polar zone or region on or near the isothermal line of 41°. It may be useful to trace the course of these three isothermal lines, and to mention the countries or cities which they traverse or touch:—

(1.) The isothermal line of maximum temperature, or equator of heat (82·4° Fahr.), traverses, or passes near, the southern coast of the Gulf of Mexico, the Gulf of Guinea, the Straits of Bab-el-Mandeb, and the fortress of Aden, the southern point of Hindostan and the city of Madras, and the islands of Sumatra and Java.

(2.) The northern isothermal line of 68° traverses California, skirts the north coast of the Gulf of Mexico, touches Madeira, the fortress of Gibraltar and the city of Algiers, follows the south coast of the Mediterranean, and passes through China at the latitude of Nankin. The southern line traverses South America, from Potosi to Santa Fé, touches the Cape of Good Hope, and cuts off that southern portion of Australia which has become the home of English colonists.

(3.) The northern isothermal line of 50° touches New York and the southern point of Ireland, traverses the north coast of the Black Sea, Caspian, and sea of Aral, and passes between the northern and southern islands of Japan. The southern line traverses the southern point of South America, runs north of the Falkland Islands and south of Van Diemen's Land, and cuts off the southern angle of New Zealand.

(4.) The isothermal line of 41° touches Quebec, the south coast of Iceland, Stockholm, and Moscow, cuts in half the northern island of Japan, and runs south of the peninsular of Kamtschatka.

56. With regard *to these isothermal lines*, it should, however, *be borne in mind that the diseases incident* to the several zones

may pass beyond the limits assigned to them, whenever, from local causes, the mean temperature is raised or lowered, when the summer is unusually hot or the winter unusually cold. In the one case, the diseases of the temperate zone may assume a character allied to those of the tropics; in the other, they may approach closely to those that prevail among nations nearer the pole.

57. But the diseases that prevail in the several zones must not be attributed wholly to temperature. Thus scurvy, which is very prevalent and fatal in the polar zone, may be traced in part to cold, and in part to the imperfect diet which is its result—a diet which would occasion scurvy in any part of the world. Nor are the fatal diseases of the tropical zone due solely to a high temperature; for they are partly caused by heat acting on and developing the miasma of damp and rank soils. Hence, troops encamped on dry spots in the most unhealthy tropical districts, may escape, to a great extent, the prevailing maladies; and it is by the discovery and occupation of such spots that the inhabitants of temperate climates maintain their possessions in countries having a much higher temperature than their own.

58. The influence of *moisture*, as distinct from that of the emanations it promotes, is not so easy to trace. There is reason, however, to believe that the inhabitants of damp soils and low-lying districts have less vigour, and are more liable to pulmonary consumption, than those of gravelly and sandy soils and the summits of hills and mountains. Many invalids suffer most when the air is loaded with moisture.

59. It is also a notorious fact, that excessive humidity coexists with a high temperature in regions most fatal to human life; as on the south coast of Africa, the Sunderbunds of Bengal, and the deltas of rivers, marshes, and jungles, in and near the tropics. In more temperate regions the same combination of moisture with heat proves fatal to life during summer. But in both cases the unhealthy influence is probably due to the bad drainage which naturally exists in such situations, rather than to excess of moisture.

60. *Atmospheric pressure* has also its effect on health, and many invalids suffer even from slight changes in this respect. The oppression experienced in the diving-bell, the diarrhœa which attacks travellers on their arrival in very lofty situations, and the hurried respiration, quickened circulation, and hæmorrhagic tendency brought on by the ascent of high mountains, are illustrations of its more extreme effects.

61. The influence on health of the *electric condition* of the air is shown by the headache, and other uneasy sensations experienced by many persons before a thunderstorm.

62. The quantity of *ozone* (a modification of oxygen caused by repeated electrical discharges, and characterized by a peculiar odour and increased power of oxydation) bears some relation to the preva-

lence of certain diseases. Thus during attacks of intermittent fever and of cholera, the air has been nearly free from it, and during at least one epidemic of influenza, it was noted to be in excess.

63. But there are other atmospheric changes known to us only by their effects. Asiatic cholera, for instance, has, on four occasions, overstepped its usual limits, and spread over the greater part of the habitable globe; and the entire class of infectious and contagious diseases exhibits variations in intensity from year to year which cannot be explained by differences of temperature, moisture, and pressure, nor even by variations in the electric state of the air, and in the proportion of ozone. We are forced, therefore, to believe in the concurrence of some of these external agencies with certain local conditions, of which the chief may be safely assumed to be imperfect drainage and consequent contamination of drinking-water. Other causes at present unknown and unsuspected may hereafter be found to account for those changes of character which certain prevalent diseases have been observed to undergo from year to year and season to season—changes attributed by the older writers to what they termed the "*epidemic constitution*" of the air.

64. We may form some idea of the influence of these concurrent conditions by noting the annual fluctuations in the number of deaths from contagious disease. Thus in the fifteen years from 1840 to 1854, the deaths from typhus and enteric fever sank as low as 615, and rose as high as 1600; from erysipelas, as low as 113, and as high as 260; from whooping-cough, as low as 582, and as high as 1217; from measles, as low as 249, and as high as 1122; from scarlet fever, as low as 354, and as high as 2132; from small-pox, as low as 87, and as high as 890; and from influenza, as low as 35, and as high as 562. These are the deaths that took place in London in a million inhabitants in the years and from the causes specified. It will be seen that while the deaths from fever, erysipelas, and whooping-cough fluctuated nearly as the numbers 1 and 2, those from measles varied as nearly 1 and 5, from scarlet fever as 1 and 6, from small-pox as 1 and 10; while the deaths from influenza were 16 times as numerous one year as another. The deaths from small-pox have been subject to a high rate of fluctuation both before and since the practice of inoculation and vaccination.

65. These variations will appear the more remarkable if we contrast them with the slight annual fluctuations in the rate of mortality of many other diseases, especially of those which consist in structural change. The deaths from pulmonary consumption, for instance, in the same years and among the same number of persons, fluctuated between 2645 and 3941; pneumonia, between 1340 and and 2169; from cancer, between 253 and 432; and from apoplexy, between 264 and 607.

66. A still more vivid idea of the annual fluctuation in diseases of the contagious class is afforded by the fact, that no combination of causes within or beyond human control—neither the weather, nor

shipwrecks, nor the imports and exports of commodities, nor prices, nor the funds—is subject to such fluctuations from year to year.

67. It is also worthy of remark that the several diseases of this class are not all epidemic in the same years; for the smallest number of deaths from small-pox, erysipelas, and measles, and the largest from small-pox and influenza, occurred in years in which no other of the diseases specified in § 64 attained their highest or lowest numbers; while the least number of deaths from influenza coincided with the greatest number from measles; and the lowest from typhus fever with the highest from whooping-cough. It is true that the least mortality from scarlet fever and typhus coincided in the year 1841, and the greatest from scarlet fever, typhus, and erysipelas, in 1848. But the epidemic visitations of cholera occurred in years marked by no peculiar excess or defect of any of these diseases.*

68. Epidemic diseases often appear to precede, supersede, to run into, or even, to some extent, to supplant each other; so as almost to justify the belief that they arise out of the same conditions, the particular disease prevailing in any one locality being determined by slight variations in those conditions. Cholera, enteric fever, and the worst forms of intermittent fever are probably due to the same general conditions thus slightly varied.

69. *Contamination of the air* is a most efficient cause of impaired health, as well as a prolific source of disease. The air is made impure in rural districts by exhalations from stagnant pools and marshes, and from collections of manure; in large towns by the decomposition of animal and vegetable substances, the refuse of manufactories, the smoke due to the imperfect combustion of fuel, and the dust created by constant traffic.

70. These impurities in the air of large towns, existing within and without the dwellings of their inhabitants, modify the health of those otherwise healthy, and make them liable to diseases distinguished from those of rural districts by an absence of power or tone; so that a disease which in the country would bear, if it did not require, bloodletting, would, in a large town, scarcely admit of depletion, and might even demand an opposite treatment. This depressing effect of the air of large towns, displayed in the pallid aspect of those who are deemed healthy, and in the want of power accompanying their diseases, is a fact necessary to be borne in mind at the bedside.

71. A residence in large towns makes itself most felt in such of the inhabitants as work within doors, and who inhale both the impure air of the town itself, and the close heated atmosphere of shops and workshops, often in the absence of the wholesome stimulus of light. These persons exhibit, in an extreme degree, the influence of a town life, and their diseases are most distinctly marked by want of power. So that the indoor and outdoor labourers of large towns differ from each other as much as the inhabitants of town

---

See Dr. Guy's two papers in "Statistical Journal," years 1855 and 1857.

and country. A less marked difference is observable between those who work within doors, with little and with more exertion.

72. Many persons who follow indoor employments are further exposed to the exhausting influence of long hours of work or service, often extending far into the night, and even usurping almost all the time that should be devoted to sleep. The London bakers during the whole year, compositors (and, it is to be feared, many successful men in all trades and professions) during the session of Parliament, members of Parliament themselves, and milliners and dressmakers in the fashionable season, suffer greatly from this cause.

73. The injurious influence of the causes just specified may be inferred from the excessive mortality which prevails in large towns. Thus, while the annual mortality of rural districts varies from 18 to 22 in the thousand, that of town districts, not being seats of manufacture, will often amount to 25; and that of populous manufacturing towns and crowded sea-ports to 35 or more. The deaths in some continental capitals exceed 40 in the thousand, and the highest of these rates is exceeded in the worst districts of almost all our large towns.

74. These figures represent the number dying compared with the number living. When the ages of the living are taken into account, these differences are brought within narrower limits; but their relation to each other is not materially affected.

75. It must not, however, be supposed that the rural districts enjoy an immunity from the causes which impair vigour and shorten life in towns. Bad drainage and obstacles to the free movement of the external air often combine with overcrowding and neglect of cleanliness within doors, and a scanty and unwholesome diet, to counteract the wholesome influence of labour in the open air, and to predispose to diseases of the low type prevalent in crowded city populations. Nor is overwork an evil limited to town populations.

76. The country may also share with the least healthy parts of our large towns, the evil of a rich and ill-drained soil. Many a small village, or isolated country house, like the old town of Liverpool, stands on a swamp, catching the water from higher ground; and inviting a visit from every pestilence.

77. The diseases which cause the high mortality of town populations are, in accordance with what has been just stated, the scrofulous affections of children, and pulmonary consumption in the adult, together with febrile diseases and the exanthemata. Dusty occupations, such as those of the miller, the potter, and the collier, also give rise to diseases of the lungs, which exist in their most severe and fatal form among the scythe, knife, and needle grinders of Sheffield.

78. Next to impure air and unwholsome residences, as causes of debility, comes scanty or unwholesome food. Insufficient nourishment is a chief cause of that want of power and tone which marks

the inhabitants of large towns, and of some of our least favoured rural districts. In infancy and childhood, again, a diet not merely unequal to the wants of the frame, but unsuitable to the age, or destitute of some essential element of growth, often sows the seeds of future weakness and disease. At all ages, too, the poor either consume unwholesome food, or live on a diet wanting in the requisite variety of elements: hence land scurvy and other allied diseases. Hence also, in earlier periods of our history, that scorbutic state of the mass of the population, which, co-operating with fevers, plague, and small-pox, gave rise to a destruction of human life of which we have happily no experience.

79. Water supplied in quantities insufficient for cleanliness, or of a quality unfit for drinking, is also among the recognized causes of impaired health and actual disease. Water may also become the vehicle for the poison of lead, and as recent experience has shown, of animal poisons thrown off from the body itself. Hence the part it bears in the propagation of enteric fever, dysentery, and cholera. Recent painful experiences have also taught us that the poison of scarlet and enteric fever may be carried in milk, and so become the source of many and fatal attacks of those diseases.

80. Another cause of weakness and disease is the abuse of spirituous liquors, showing itself in the pallid and sodden aspect of the drunkard, in the fatal effects so often attending the slightest injuries in brewers' draymen and other intemperate persons, in many forms of disease, and in the shortening of life. Its power of shortening life is shown by such facts as the following:—

81. In men peculiarly exposed to the temptation of drinking, the mortality before thirty-five years of age is twice as great as in men following similar occupations, but less liable to fall into this fatal habit; and the rate of mortality among persons addicted to intemperance is more than three times as great as in the population at large. At the earlier periods of life the disproportion is still greater, being five times as great between 20 and 30, and four times as great between 30 and 50. The annual destruction of life among persons of decidedly intemperate habits has been estimated at upwards of 3000 males and nearly 700 females, in a population of nearly 54,000 males and upwards of 11,000 females addicted to intemperance. Most of these deaths are due to delirium tremens and disease of the brain, or to dropsical affections supervening on disease of the liver and kidneys.

82. This extensive prevalence of intemperance in England should be borne in mind, especially as no fact is better established than the great danger of treating the diseases of intemperate persons by depletion or lowering remedies. The same remarks apply in a less degree to tobacco, chewed or smoked. But the very general union of drinking and smoking, and the fact, that, up to this time, no special structural disease has been traced to the excessive use of tobacco, obliges us to speak with some hesitation on this subject.

83. LUXURY, too, like intemperance, tends to undermine health and shorten life. Hence the higher orders are short-lived, and we may therefore safely infer, unhealthy while they live. Our agricultural labourers, in spite of their many disadvantages, live much longer; and the aristocracy are nearly on a par with the members of benefit societies in Liverpool, the unhealthiest city in England. Of the classes, too, which enjoy the most ample means of self-indulgence, those are most healthy who are least tempted. Thus, the gentry are longer-lived than the aristocracy; the aristocracy than the members of royal houses; and these last than crowned heads. Those who occupy the highest place in the social scale are probably, in point of health and longevity, but little raised above the very meanest of their subjects. In wealthy communities, persons who have no occupation of sufficient importance to interest and occupy the mind always abound. They constitute a large proportion of the class of habitual invalids, and those among them who have retired from a life of active exertion appear to be the greatest sufferers.

84. But while the unfortunate possession of wealth unpurchased by exertion tempts young men to sloth, luxury, and dissipation, and older men to less active self-indulgence, other classes are exposed to similar evils. The soldier, in time of peace, suffers from the *ennui* of insufficient employment, is strongly tempted to indulge in dissipation, and is exposed, at the same time, to the evils of over-crowded and unwholesome barracks. Confinement, and the absence of employment calculated to interest and excite the mind, also undermine the health of prisoners and paupers. Recent inquiries have proved that the life of the soldier in time of peace is shortened by the causes now specified, and that the perfect sanitary arrangements of our prisons barely suffice to place their inmates on a level with the community at large; and it is highly probable that for every life which poor-laws have saved by averting starvation, a hundred have been sacrificed by the imprisonment they inflict, and the contagious maladies they promote. It is also probable that the self-imposed sloth of the wilfully destitute is as fatal as the involuntary privations of honest poverty.

85. The enumeration of the causes of the wide differences existing between individuals reputed healthy, would be incomplete if no notice were taken of that strange and inexplicable change wrought in the body by contagious or infectious maladies, and especially by the febrile exanthemata, which confer an immunity from, or greatly diminished liability to, a second attack of those diseases. A similar result is brought about in one instance by a disease nearly allied to, but not identical with, the disorder from which the body is protected—by vaccination as a preventive of small-pox.

86. Nor should we pass unnoticed a fact most important in its bearing, both on the treatment of disease, and the expectations we form of its success, namely, the existence of *latent disease* of the lungs, heart, liver, or kidneys. These organs, which seemed to perform their functions well, so long as they were not exposed to

any unusual strain, may prove quite unequal to the task imposed upon them by the congestion which attends febrile and inflammatory disorders. When the function of either of these organs is greatly hindered or suspended, the blood becomes charged with a poison which the frame, already diseased, is powerless to eliminate.

87. The foregoing considerations respecting health, and the differences that exist between one individual and another, may be thus summed up:—There are many original and many acquired differences between man and man. The original differences are those conveyed by the terms Temperament, Diathesis, Hereditary Predisposition, and Idiosyncracy; to which we may add those dependent on Sex and Age. The acquired differences are due to Air and Climate, Place of Abode, supplies of Food and Water, Habits, Occupation, and Mode of Life; and, in certain instances, to diseases previously undergone or to others latent in the system.

88. When, therefore, we take into consideration the original differences between individuals, and the various and complicated influences to which they are exposed in all states of society, but especially in highly-civilized communities, no additional argument will be needed to establish the first great principle on which the practice of medicine hinges—*that in health, and consequently in disease, every function of the body varies greatly in different persons*. This fact is the key to the imperfection of Medicine as a Science and its difficulty as an Art.

89. DISEASE.—To define disease we must first have defined health, for the one is but the negation of the other. In like manner, the description and right understanding of disease depend upon the description and right understanding of health. Without attempting a formal definition, it will suffice to state, that disease is present when any structure of the body is changed (provided that change be not the direct and immediate effect of external injury), or when any function is either unnaturally active, or torpid, or altered in character.

90. There is one important practical distinction which may be properly insisted upon in this place: a distinction between disease, structural or functional, and those unhealthy *states of system* brought about by the prolonged operation of the causes enumerated in §§ 69–86. Previously to the invasion of any well-defined disease, the constitution may have been brought, by the continued action of one or more of these causes, into a state which shall make the disease itself assume a more or less severe form, and even to depart in some respect from its usual character and course. Success in practice depends as much on the prompt recognition of these *States of System*, as on the individual peculiarities pointed out in §§ 4–46.

91. Diseases vary very much in their (*a*) nature; (*b*) form or type; (*c*) course and duration; (*d*) terminations; and (*e*) mode of occurrence. Under these heads certain terms in common use will now be explained.

(*a*) *Structural.*—Consisting in alteration of structure.

Functional.—Consisting in disordered action.

Common.—Presenting the usual characters of common inflammation, &c.

Specific.—Peculiar, or departing from the common character.

Malignant.—Diseased growths for which no remedy has yet been discovered, and which spread from texture to texture: such as cancer. Also diseases which assume a very dangerous and intractable character; such as malignant cholera, malignant typhus, malignant scarlatina.

Idiopathic.—Not dependent upon any other disease.

Symptomatic.—Dependent upon, or being a symptom of, some other disease; as dropsy following disease of the heart, liver, or kidneys.

Primary.—The first in a succession of diseased conditions: for instance, a primary venereal sore.

Secondary.—Following after or upon some other disease: as secondary syphilis.

92. (*b*) *Continued.*—Running their course without interruption in their symptoms.

Intermittent or *Periodical.*—Interrupted by intervals of health.

Remittent.—Having an alternate increase and decrease, but no complete cessation of symptoms.

93. (*c*) *Acute.*—Of short duration and great severity.

Chronic.—Of long duration and slight severity.

These may be combined, as in ague, which is *chronic* in duration, *acute* in severity; or they may run into each other, the acute subsiding into the chronic, and the chronic being heightened into the acute. The terms *acute* and *chronic* have also been used to indicate degrees of severity; as when rheumatism of the joints is called *acute* rheumatism, or rheumatic fever, and rheumatism of the muscles *chronic* rheumatism.

Sthenic.—Marked by vigour and excitement; nearly synonymous with acute.

Asthenic.—Characterized by want of vigour, and nearly synonymous with *typhous* and *adynamic*.

94. (*d*) Most diseases end in complete, many in partial or incomplete, recovery.

Recovery is generally gradual, but in certain cases the transition from disease to health is rapid and even sudden. The interval between the subsidence of the disease and the restoration to health is termed *convalescence*. If, during this period, the disease returns, the patient is said to suffer a relapse; and this is so common an occurrence in one form of continued fever that it has been called *relapsing fever*.

The diseases from which the recovery is slow, are mostly those that exhaust the patient's strength by their severity or long duration; such as fevers, acute inflammations, exhausting discharges, and paralytic affections. *The diseases from which* recovery is sudden *or rapid are for the most part dependent on* mechanical causes, such as calculi in the gall-duct or ureter. Neuralgia also frequently passes off suddenly, and returns with as little warning.

Sometimes diseases terminate suddenly by profuse discharges, eruptions, or external inflammations. Such events are called *critical*, or they are called *crises*. Observation, both ancient and modern, seems also to have proved the existence of *critical days*: that is to say, days on which febrile disorders are prone to take a favourable turn.

Local affections may also be said to terminate by *metastasis*, or transference from the part first attacked to some other, as from the joints to the stomach, heart, or brain, in gout; or by extension to a texture similar to the one originally attacked, as when acute rheumatism having commenced in the fibrous textures surrounding the large joints, seizes upon those in and about the heart.

95. (*e*) *Contagious and Infectious.*—Both these terms are now used to designate diseases communicable from one person to another; the first by contact, the second by being conveyed in the air.

Epidemic.—Attacking a number of persons at the same time, and recurring at irregular intervals; as fever and small-pox. Some of these diseases, as cholera and influenza, spread with great rapidity, and attack at or about the same time the inhabitants of whole continents.

Endemic.—Peculiar to certain localities, as ague, goitre, elephantiasis, &c. The same disease may be both epidemic and endemic: thus, typhus, which is endemic in certain districts of large towns, becomes epidemic in those districts in certain seasons or years; cholera, again, which is endemic in parts of India, may become epidemic in other parts of the same continent, and in Europe.

Sporadic.—This term is applied to epidemic and endemic diseases when they attack one or two persons only, in which case they are said to occur *sporadically*. Such attacks are common at the beginning and end of epidemics.

Zymotic.—This term, derived from a Greek word signifying ferment, is now applied to the entire class of epidemic, endemic, and contagious diseases. It is convenient as grouping together diseases allied to each other by similarity of cause, but objectionable as based upon a mere hypothesis obviously inapplicable to cases of sudden death due to the operation of atmospheric and other poisons.

96. *Names of Diseases.* (Medical nomenclature.)—No uniform plan has hitherto been adopted in giving names to diseases. The greater number have been named from some prominent symptom, as fever (from *ferveo*, to burn), hydrophobia, diabetes; others from their seat and nature combined, as hydrocephalus (water on the brain), or the seat is indicated by the root, and the nature of the disease by a common termination. Thus, the words pericard*itis*, pleur*itis*, ir*itis*, mean inflammation of the pericardium, of the pleura, of the iris. Words in common use have also been superseded by terms descriptive of the seat or nature of the disease: as *enteric* in lieu of *typhoid* fever; and *hyperæmia* (excess of blood), qualified by the words general, local, active, and passive, for plethora, inflammation, and congestion, and *anæmia*, similarly qualified, in place of chlorosis.

97. *Classification of Diseases.* (Nosology.)—It is not easy to devise a nosology resting on a sound scientific base; but for men engaged in learning, teaching, or practising medicine, that arrangement is best which classifies diseases according to their nature, when that is sufficiently ascertained, and in other cases according to the part of the body which they attack; just as for state purposes that nosological system is to be preferred which places most prominently before the public, as a distinct class, the diseases admitting of prevention or mitigation by sound sanitary measures. In this point of view, the classification adopted by the Registrar-General deserves commendation. A very complete classified list, comprising diseases, general and local; poisons and injuries; with an appendix of surgical operations, human parasites, and congenital malformations, has also been put forth by the College of Physicians.

98. There are some general considerations connected with disease of far higher importance than the use of terms, or the adoption of a correct nomenclature and scientific classification. These will be treated under the following heads:—(*a*) Causes; (*b*) Symptoms and Signs; (*c*) Diagnosis; (*d*) Prognosis; and (*e*) Treatment.

99. (*a*) *Causes of Disease.* (Etiology.)—The causes of disease may be conveniently divided into *proximate* and *remote.*

Proximate Causes (Causæ abditæ, continentes, occult causes).—This term has arisen out of the twofold meaning of the word disease. When it is named from the part it attacks, and the nature of the change that part is undergoing, as pericarditis, or inflammation of the pericardium, the proximate cause is the disease itself; but if the name is the representative of a group of symptoms, as cough, dyspnœa, hectic fever, emaciation, &c.—the symptoms of pulmonary consumption—then the term proximate cause means the suppurating tubercle which gives rise to all these symptoms. If we are ignorant of the seat of a disease, as is the case with fever, the search after a proximate cause is but an inquiry into its real nature.

Remote Causes. (Causæ evidentes.)—All constant antecedents of an event are called *causes* of that event, and all constant consequences are called *effects.* Hence the same thing may have many causes. Thus, an hereditary tendency, intemperance, or want, and a common cold, may unite in the same person as causes of pulmonary consumption. The tendency may have rendered the person liable to tubercle, intemperance or want may have occasioned its actual deposition, and the cold may have excited it into activity. All these are *causes* of consumption, and the consumption may become the cause of death. How, then, are such causes to be distinguished from each other? They are divided into *predisposing* and *exciting.* In this instance, the *predisposing* causes are the hereditary tendency and the mode of life; the *exciting* cause is the cold; and the *proximate* cause (if the term need be used) the suppurating lung.

The condition of the body itself, however brought about, is the *predisposing cause* of any disease which may befall it: the *exciting causes* are, for the most part, external agents, such as cold and heat;

these are also among the most powerful *predisposing* causes. Thus, that combination which we call climate is the predisposing cause of a great variety of diseases; and any one of the elements of which it consists may become an exciting cause.

Some of the principal predisposing causes of disease have been already considered (§§ 4–86) when speaking of temperament diathesis, hereditary predisposition, and idiosyncrasy: of sex, age, occupation, and mode of life: of residence and climate. The local or constitutional injuries which attend severe illness are also causes predisposing to fresh attacks of the same disease.

The exciting causes of disease are chiefly mechanical and chemical injuries, unwholesome food, undue exertion of mind or body, sudden and violent atmospheric changes, parasitic animals and plants, atmospheric poisons, poisons generated by the human body itself, and those of venomous insects, reptiles, and mammalia.

100. (*b*) *Symptoms and Signs of Disease.* (Symptomatology, semeiotics.)—All lesions of structure, whether from external injury or from internal change, cause some disorder in the functions of the body, and almost every disorder of one function leads to derangement in those most closely connected with it. These disordered functions are called *symptoms*. Thus, redness, swelling, heat, and pain are symptoms of inflammation; and fever, which is itself recognized by a certain combination of symptoms, is a symptom of inflammation.

101. In medical writings symptoms are often distinguished by such words as *diagnostic* and *pathognomonic* (meaning distinctive), *objective* (or objects of sense), and *subjective*, or sensations experienced by the patient himself.

102. The word *sign* has not the same meaning as the word symptom, though the two are sometimes used without much discrimination. The difference is best shown by an example. Cough, expectoration, dyspnœa, hectic fever, night sweats, and emaciation, are *symptoms* of pulmonary consumption, but they are not *signs*, for they may all occur in other diseases; but cavernous respiration and pectoriloquy are signs. So also expectoration is not a *sign* of consumption but a symptom, for it occurs in other diseases of the lungs; but a certain kind of sputa is a *sign* of that disease. *Signs*, therefore, are pathognomonic or diagnostic symptoms: that is to say, they point directly to the nature of the existing disease.

103. The term *physical* sign means a sign which is an object of sense. Thus, heat, redness, and swelling are physical signs of inflammation; pectoriloquy of phthisis; casts of the uriniferous tubes of disease of the kidney.

104. Between a symptom and a sign there is the same difference as between a *character* and a *characteristic*, and symptoms become signs when their import is thoroughly understood.

105. The symptoms of disease are of very variable intensity; and even the most characteristic are sometimes wanting, or replaced

by their opposites. Thus, a frequent pulse is a most constant symptom of pulmonary consumption; but in some cases it does not exceed its average in health; while in others it falls below it; and of two attacks of consumption occurring in the same person, and not otherwise different, one has been known to be marked by a frequent, the other by an infrequent pulse. This same symptom of increased frequency of pulse is among the most constant and characteristic attendants on fever, and yet some epidemics have been distinguished by a pulse below the healthy standard.

106. (*c*) *Diagnosis*, or the discrimination of diseases, is the necessary prelude to their treatment. It presupposes a correct observation and just appreciation of symptoms, and may be said to be the art of converting *symptoms* into *signs*.

107. The general appearance of the patient is always an important element in the diagnosis. In most cases it enables the physician to form some idea of the previous habits of life; to determine whether the illness is slight or severe; and, in many instances, to decide at once upon its nature. Thus, anæmia, consumption, pneumonia, emphysema, Bright's disease, fever, and severe disease of the heart are often written on the very countenance; and many other diseases, such as palsy and chorea, gout and rheumatic fever, tetanus and hydrophobia, several of the exanthemata, and skin diseases in general, betray themselves by single strongly-marked symptoms. The diagnosis in such cases is very easy; but the task of the physician is much more difficult when the disease is either imperfectly developed, as in the first stage of eruptive fevers, and in incipient phthisis, or when the only obvious symptom is one which, like dropsy, may depend on several causes; and it is still more difficult when the nature of the complaint must be inferred chiefly from the patient's description of his own sensations, or from a mere perception of the size and shape of a part of which the structure is concealed from view, as happens with the greater number of tumours, both external and internal. These are the cases which put the knowledge and skill of the physician to the test, and sometimes baffle both.

108. In some cases we have to wait until the characteristic symptoms show themselves; in others, to make minute stethoscopic examinations; in others, to test the urine, or to use the microscope; and in a few, to confess our ignorance. The effects of remedies, such as bloodletting and stimulants, also, in rare instances, serve as means of diagnosis. The symptoms which render us most assistance in distinguishing one disease from another will be carefully examined in a future chapter.

109. (*d*) *Prognosis*.—This word means foreknowledge, and, as used by the physician, the anticipation of the course and event of diseases. The power of foretelling the progress and termination of a malady is of the first importance, as regards the treatment to be adopted, the well-being of the patient, his own satisfaction and

that of his friends, and the reputation of the physician himself. A correct prognosis implies a just diagnosis, an accurate knowledge of the natural course and progress of disease, an appreciation of all the peculiarities, original and acquired, which distinguish one man from another (§§ 4–86) and a large experience of the virtues and power of remedies.

110. Among the questions which the physician may be called upon to solve, one of the most common is, whether the disease admits of cure? The answer is sometimes very easy. A case of hydrophobia or of hysteria would present no difficulty. The one is as certainly fatal as the other is curable. But in a case of tetanus, of pneumonia, or of pulmonary consumption, the prognosis is more difficult. The first would be most probably fatal; the second is always attended with danger, the amount of which will chiefly depend on the sex, age, temperament, and previous habits of the patient; the third is fatal in a large majority of cases, and the probability of ultimate and complete recovery is very slight.

111. This latter disease—pulmonary consumption—affords a good example of the necessity of caution in forming and stating our prognosis. The disease is incurable, and medicine, at best, only palliative; but if, in every case, a physician were to foretell a fatal result, his reputation would suffer severely, for the simple reason that consumption, though ultimately fatal in nine hundred and ninety-nine cases out of a thousand, is not necessarily fatal in any given attack, recoveries from several successive attacks being by no means unusual; and this happens, not because the disease is curable, but because its fatality depends on the amount of tubercular deposit, and the issue of any particular attack on the extent and activity of the suppurating process relatively to the power of the patient to bear the wear and tear consequent upon it. This is the true explanation of the asserted efficacy of medicines, regulated temperature, and change of climate in this disease, and of the reputed success of those irregular practitioners who select it as the object of their attention partly for the reasons assigned, and partly on account of the great number of people subject to its attacks.

112. This is the place to speak of that *vis medicatrix naturæ*—that power inherent in the human frame to right itself when suffering under severe disorders—which our predecessors were wont to acknowledge with such befitting modesty as their invaluable coadjutor in the treatment of disease. The homœopathist (slave of an hypothesis invented by a heated enthusiast, and mainly supported by imaginary sensations developed by experiments on his own person) attributes to infinitesimal doses virtues simply ridiculous, and results utterly impossible; but the regular practitioner can explain the cures alleged to have been thus effected by that very *vis medicatrix* which so constantly stands him in stead in his own treatment of disease, and to which he so rightly attributes so much of his own success. It is this *vis medicatrix* which, counter-

acted by active medicines, but restored to freedom by non-interference, constitutes the really efficient agent of a race of quacks whose treatment, if honestly carried out in accordance with their own principles, would be perfectly harmless, provided it did not shut out prompt and active treatment in those cases which demand it.

113. The history of every department of the healing art affords examples of the power of this *vis medicatrix*, which often reveals itself through some happy accident; as when Ambrose Paré, through his supply of boiling oil falling short, was led to substitute a cold slimy mixture, which, like the famous remedy of a contemporary, known as the "oil of whelps," had the happy effect of leaving Nature to work her own cure in her own way.

114. It follows, then, that to determine whether a patient's recovery has happened through the treatment adopted, or independent of it, or in spite of it, is often a task of extreme difficulty. The best physician may often decide amiss; the ignorant empiric and equally ignorant public are utterly unqualified to form an opinion.,

115. (*e*) *Treatment.*—A correct diagnosis, a knowledge of the nature of the disease itself, of the constitution of the sufferer, and of the virtues of remedies, are essential preliminaries to judicious treatment. The object to be aimed at will vary with each case. In one, it will suffice to remove the ascertained cause; in another, it will be necessary to restore the healthy function or repair the diseased structure; in a third, to palliate the suffering which the disease occasions.

116. Our treatment is usually founded on a correct knowledge of the nature of the disease and the mode of operation of our remedies, in which case it is said to be *rational;* in some instances, we act in ignorance of both, and then it is said to be *empirical.* Again, it may be *curative*, or such as to restore the patient to health; *palliative*, or adapted to the alleviation of suffering; *preventive*, or calculated to obviate the recurrence of disease, by maintaining habitually a better state of health, and removing its exciting causes.

117. The abstraction of blood in inflammation is an example of *rational* treatment, for we know both the condition of the part affected and the *modus operandi* of the remedy. The use of quinine or arsenic in ague is merely *empirical*, for we understand neither the nature of ague nor the mode in which these medicines affect the body in curing it. The treatment of malignant diseases is necessarily *palliative*, for, from their very nature it is obvious that they do not admit of cure.

118. In the treatment of many diseases we combine the rational with the empirical, the curative with the palliative. Thus, during an attack of remittent fever, we might abstract blood to subdue local inflammation, use cold sponging to diminish the heat of the surface, stimulants to counteract debility, and quinine to effect a cure.

119. Though the use of remedies, the *modus operandi* of which

we do not understand, is *empirical*, the act of generalization by which we infer the utility of the same remedies in analogous disorders, imparts to our treatment a more rational character. The employment of quinine and arsenic in ague, for instance, was, and continues to be, empirical, but the use of those remedies, in the whole class of intermittent disorders, as a consequence of analogical reasoning, is a rational procedure.

120. In treating disease we are necessarily guided by the existing state of the patient. If, for instance, the skin, gums, and tongue are pale, we prescribe some preparation of iron; if, on the contrary, they are florid, we shall probably order depleting or lowering remedies. Now these opposite states are said to afford *indications* of treatment—grounds or reasons, that is to say, for giving preparations of iron in the one case, and resorting to lowering measures in the other. On the other hand, these same states of system constitute grounds for avoiding the opposite modes of treatment: in other words, they are *contra-indications* of depletion and tonic treatment respectively. In like manner acute inflammatory symptoms, occurring in robust persons, *indicate* lowering remedies, and *contra-indicate* stimulants.

121. The considerations brought forward in this chapter will serve to show the extreme difficulty which attends the practice of medicine, and the necessity imposed on the physician of supplying himself with very extensive and precise information on all the subjects which can conduce to a knowledge of the body, and of the action of remedies upon its various functions. But, after all that can be done, the science of medicine must remain extremely imperfect, and the art of healing very difficult. Our general principles, derived originally from particulars made up of many variable elements, must be reapplied in practice to individual instances as complicated as those out of which they were originally formed, so that precision is, in the nature of things, impossible, and certainty of very rare attainment.

122. Other considerations, which go far to explain the acknowledged difficulty of medicine, both as a subject of scientific inquiry and of practical application, are:—the variable severity of diseases bearing the same name, the changes that occur in the progress both of acute and chronic cases, and the unequal strength of our remedies. When we reflect that, prior to the setting in of a given disease, the constitution of the patient, originally marked by hereditary peculiarities, has been subsequently modified by the powerful influences already examined; that the disease itself may vary within wide limits of intensity; that it passes naturally through many different phases; that it may fall under observation and treatment at any part of its course; that the remedies prescribed, being of variable strength, may be given with more or less care and regularity, and the patient tended with greater or less watchfulness and skill:—

when we take all these circumstances into consideration, we cannot be surprised that medicine should be as a science most uncertain, as an art most difficult.

123. One application of these remarks is obvious. Medical men, and still more the uninformed public, are apt to form unsound opinions on cases in which one physician following another has seemed to be successful, where his predecessor had failed. Is it not obvious that in many such cases the apparent failure and success were due not to difference of skill, but to the stages of the malady at which the two were consulted?

124. In epidemics, again, the physician who may happen to be called to the earlier cases would seem to be unskilful when compared with one who is called upon to treat cases of the epidemic in its more advanced stage; for epidemics are uniformly more severe at their onset than at their decline.

CHAPTER II.

CAUSES OF DEATH.

125. Though the causes of death interest chiefly those engaged in preventing disease, the practical physician profits by the study of them, inasmuch as he learns the relative frequency of the more severe diseases, and the demands they severally make on his attention.

126. The causes of death form three leading groups: of which the first comprises mechanical injuries, scalds, burns, and corrosions, the several forms of suffocation, cold, want, intemperance, and poison; the second, debility in infancy, and decay in age; and the third, disease properly so called. In England the deaths are distributed through these three classes in the following proportions per thousand deaths:—

Class I., 40 deaths; Class II., 160 deaths; Class III., 800 deaths.

127. In Class I. about half the deaths are caused by mechanical injuries; about a fourth by the several forms of suffocation (hanging, drowning, &c.); less than a fifth by burns and scalds; ten per thousand by cold and want; thirty per thousand by poison; and thirty per thousand by intemperance (exclusive of delirium tremens and other fatal diseases occasioned by excess).

128. In Class II. the deaths are divided between those that occur in early infancy from incomplete development and inadequate nutrition, and deaths from old age; the excess being somewhat on the side of the first division.

129. The 800 deaths in the 1000 that remain after subtracting Classes I. and II., may be distributed into a few leading groups of disease. A very large and important group consists of epidemic diseases propagated by contagion or infection, which destroy life by giving rise to severe local affections or by exhausting the vital powers. This comprises small-pox, scarlet fever, measles, whooping-cough, typhus and puerperal fevers, and erysipelas. A second class of maladies is due, like the foregoing, to external causes, which are local or endemic, and rarely, if ever, spread by contagion. To this belong ague, remittent and enteric fevers, influenza, diarrhœa, dysentery and cholera, diphtheria, quinsy, and carbuncle. A third class consists of diseases that prove fatal chiefly to infants and young children. They have their source in the local irritation of teething, worms, or constipation, and lead to fatal affections of the brain and of the intestinal canal. This comprises infantile fever,

arasmus, and hydrocephalus. A fourth—the largest class of all—made up of diseases which consist in a structural change or egeneracy of some texture or organ. To this belong scrofula, ulmonary consumption, and cancer. Diseases occasioned by some ecial impurity, or change of consistence, in the blood, constitute nother class, of which rheumatic fever, scurvy and gout, with yæmia, are members. The remainder of the list is made up of fatal iseases of special organs, and of the accidents attendant on child-irth. Of special organs, those of respiration (even after exclusion f pulmonary consumption) occasion the highest mortality; then, in rder, those of the brain and nervous system; organs of digestion; eart and circulation.

130. The 800 deaths from disease remaining after subtracting om the whole 1000 deaths those due to all other causes, are made p in the following manner:—

Diseases due to Structural Degeneration (including Pulmonary Consumption)	160
Diseases of the Organs of Respiration (exclusive of Pulmonary Consumption)	150
Contagious and Infectious Diseases	140
Diseases of Infancy and Childhood	90
Diseases of the Brain and Nervous System	70
Epidemic Diseases not being Contagious	60
Diseases of the Organs of Digestion and Assimilation	60
Diseases of the Organs of Circulation	40
Diseases due to changes in the Blood	10
Diseases of the Urinary Organs	10
Childbirth, &c.	10

131. If we distribute fatal diseases, as far as possible, in accordnce with the parts which they attack, we obtain, for 1000 deaths, e following results:—

Organs of Respiration	310	
Brain and Nervous System	144	
Organs of Digestion and Assimilation	104	
Heart and Organs of Circulation	35	
Urinary Organs	10	
Childbirth and Organs of Generation in the Female	10	
Joints and Organs of Locomotion	9	
Skin and Integumentary System	6	628
All other causes		372
Total		1000

132. If from diseases of organs and systems of organs we pass to ingle diseases, we obtain for 1000 deaths, the following figures:—

Pulmonary Consumption	125
Bronchitis and Asthma	78
Pneumonia	62

Convulsions	59
Scarlatina	41
Typhus and Enteric Fever	38
Diarrhœa, Dysentery, and Cholera	36
Whooping-Cough	24
Paralysis and Apoplexy, each	21
Hydrocephalus and Measles, each	18
Cancer	14
Tabes Mesenterica	11
Croup and Teething, each	10
Influenza, Inflammation of Brain, and Bowels, each	8
Scrofula	7
Small-Pox	6
Erysipelas, Epilepsy, and Rheumatism, each . .	5
Ileus, Intussusception, and Intestinal Stricture .	4
Inflammation of the Liver, Peritoneum, and Larynx, Jaundice, Pleurisy, and Thrush, each . . .	3
Syphilis, Ulcer of Intestines, Hernia, Ascites, Inflammation of Stomach, and Bright's Disease, each	2
Pericarditis, Remittent fever, Delirium tremens, Insanity, Diabetes, and Infantile Fever, each . .	1
Quinsy, Purpura, Aneurism, Cyanosis, Gout, Intemperance, Inflammation of the Bladder, Carbuncle, Inflammation of the Kidney, Stone, Stricture of the Urethra, Ovarian Dropsy, Noma, Tetanus, Ague, Ischuria, Fistula, and Chorea, each less than	1

The mortality from some of the last-named diseases is very small:—164 in the million from cholera; and 33 from hydrophobia.

133. A chapter on the Causes of Death would be incomplete if some notice were not taken of what are sometimes called the *proximate causes* of death, or "modes of dying."

Death may be said to happen when the heart ceases to beat. Hence, in considering the proximate causes of death, we are inquiring by what means the action of the heart may cease. The first and most direct mode affects the heart itself, which may be either paralysed by a nervous shock, or weakened by chronic disease. The second, by withdrawing, suddenly or slowly, the blood which should act as the stimulus to its action. The third, by cutting off, more or less suddenly, the arterial blood from the left side of the heart by an impediment to the breathing. These three causes of death, or modes of dying, may be fitly termed *asthenia*, *syncope*, and *apnœa*.

134. (1.) Death by *asthenia*. The heart of a perfectly healthy person may be suddenly stopped by causes acting with great force on the nervous system: by the lightning-stroke, by strong mental emotion, by a stunning blow on the head, by a blow on the pit of the stomach, or by the shock of cold drinks. One or two active poisons, such as prussic and oxalic acid in full doses, certain poisons

introduced directly into the circulation, air penetrating through an open vein to the right side of the heart, and the sudden effusion of blood on the surface, or into the substance of the brain, may also cause this sudden arrest of the heart's action. The chronic structural diseases that bring about this sudden or speedy death are fatty degeneration, which impairs the muscular tissue itself, or ossification of the arteries, which checks the supply of arterial blood to the walls of the heart. Either of these conditions may so weaken the heart, that the causes just enumerated, acting with comparatively slight force, may occasion a sudden and fatal pause in its action.

135. (2.) *Death by Syncope.*—This may be brought about either by a sudden pouring out of a large quantity of blood from a wounded or ruptured vessel, or by the slow drain of chronic hæmorrhage or exhausting discharges; the quantity of blood being so reduced, and its quality so impaired, that it ceases to act as an efficient stimulus to the heart. Ruptures and wounds of the heart destroy life partly by syncope and partly by impairing the propulsive power of the organ.

136. (3.) *Death by Apnœa.*—This is by far the most common form of death. The majority of persons die suffocated; a few by direct suffocation; a much larger number by that slow failure of respiration which attends the exhaustion of the strength by all severe diseases. Direct suffocation may be occasioned by constriction of the throat, as in hanging, strangulation, and throttling; by closing the mouth and nostrils; by pressure on the chest; by exclusion of air, as in drowning; by the substitution of a gas not containing oxygen for atmospheric air; by spasm of the glottis; by inflammation and swelling of the upper part of the larynx; caused either by hot water or corrosive poisons, or by disease; and by small foreign bodies wedged between the walls of the rima glottidis. Direct suffocation is of comparatively rare occurrence in disease. It may arise from causes affecting the larynx, or trachea, as laryngitis and croup, or from collections of blood, pus, or mucus filling up the small branches of the air-tubes and the air-cells. It may also arise from the admission of air into the pleura of one lung, the other being diseased, or from large effusion of blood or of serum rapidly poured out into the pleural sac. But, as has been just stated, the majority of deaths from apnœa are due to that gradual failure of the respiration which attends the exhaustion brought about by all severe diseases, and of which the quick laborious breathing and loud mucous râle (death rattle) are the well-known indications. It is in this way that apoplectic seizures, not sudden or violent enough to occasion death by *asthenia*, or shock, as well as most structural diseases of the brain, terminate.

CHAPTER III.

PHYSIOLOGY AND GENERAL PATHOLOGY.

137. The human body is a machine of finished workmanship and vast variety of uses, infinitely surpassing the most perfect work of man's hands; and containing within itself the means of ministering to its own growth and preservation, of repairing many injuries to which it is exposed, and of generating other machines of like structure and endowments. It is also a laboratory, in every part of which, at every moment, the most delicate chemical processes are being performed. This machine, with its exquisite mechanism and refined chemistry, is subject to change of place, to deprivation of the means of living, to violent death, or to slow decay, according to the dictates of a voluntary agent so dependent upon it, that all signs of his existence vanish before the last traces of its own vitality have disappeared.

138. All the minute structures of this machine were believed to be built up, all its movements to be regulated, and all its chemical processes carried on, under the direction of a force, acting through a machinery of its own, and manifesting its presence only by its effects. This force was called the "*vital principle.*" It was thought to be an independent entity, a ψυχή, or soul, pervading the tissues and causing them to live; while its disunion, or separation, from the body was death.

But, according to a more modern theory, life is the collection of phenomena in organized beings, dependent partly on a certain structure and chemical composition, and partly on external agencies which stimulate them to action; death ensuing when the structure is seriously damaged, or the external stimuli are withdrawn.

139. On closer examination, the body is found to consist of the following parts:—A framework for locomotion and for the protection of its more important organs; a digestive apparatus for the assimilation of its food; organs of circulation for distributing the nutrient fluid blended with the pre-existing blood; glands for the secretion of fluids needed in the economy; other glands for the purification of the blood, which is constantly being contaminated in the process of nutrition; a nervous network bringing all the important internal organs of the economy into harmonious action; and a nervous mass of brain and spinal cord, the centre of sensation, volition, and thought.

140. All these parts are most closely and intimately associated; so that if the heart cease to circulate blood, or the lungs to purify

it, the nervous system will no longer send forth those stimuli by which the heart beats and the chest breathes. If, on the other hand, the nervous centres suffer severe injury, respiration is prevented or impeded, and the heart soon stops. External influences also affect not the part only on which they act, but through it other organs, and through these the entire frame. Again, the mind acts on the body, and the body reacts on the mind, and both together form a being so intricate yet so perfect in structure, so complex yet so plastic in function, that the preservation of its health, and the continuance of its life, appear as wonderful as its slow decay and certain death. But experience proves that the body is so constituted that while under favourable circumstances it enjoys the free play of all its parts, under unfavourable ones it is subject to serious derangements of function and alterations of structure.

This brief outline will serve to indicate the following as the contents of the present chapter:—

i. The physiology and general pathology of the fluids, including digestion, chylification, sanguification, and excretion.

ii. The physiology and general pathology of the circulating organs, considered as instruments for the distribution of the blood.

iii. Structural physiology and pathology.

iv. The physiology and general pathology of the nervous system.

v. Mental physiology and pathology.

1. PHYSIOLOGY AND GENERAL PATHOLOGY OF THE FLUIDS.

141. Digestion, absorption, and assimilation of the food; the composition and properties of the blood and its constituents; and the functions and secretions of the lungs, skin, kidneys, and liver, are the subjects to be considered under this head.

142. *Digestion.*—The exhaustion and change of the materials of which the body is composed is a condition of vital action; so that every sensation, thought, movement, and act of secretion is attended by the conversion of a corresponding portion of the tissues into materials that are no longer fitted for the purpose of growth or nutrition, but actually impede both. They are, therefore, absorbed into the blood, and converted into definite compounds, which are separated and cast out of the system by glands appointed to this service. To supply the place of this waste is one of the uses of our food.

143. In an adult in perfect health and vigour, and using no undue exertion of mind or body, the daily waste is repaired by the daily food, and the weight of the body undergoes little or no change from day to day. But this nice balance of waste and supply may be destroyed by increased exertion without proportionate increase of food, by diminished supply, or by excessive muscular exertion, as in training for the turf; or, lastly, with great rapidity, by entire abstinence. In all these cases the body loses weight. On the other hand, in healthy persons, with unimpaired digestion, it gains weight by inactivity, or, within certain limits, by increase of food.

144. In certain diseases waste goes on with extreme rapidity; as in fever, when rapid destruction of the textures is combined with complete loss of appetite; in pulmonary consumption, when the local waste, added to profuse sweats or discharges from the bowels, exceeds the powers of assimilation; in tabes mesenterica, in which the diseased glands refuse to elaborate the chyle; in diabetes, when mal-assimilation of the food checks the process of repair of even a moderate loss of substance; during exhausting discharges, which drain the body of its blood; and in some local diseases or injuries, attended by a loss of substance which the most nourishing diet cannot repair.

145. During the early period of life food is required not merely to supply the material exhausted in the use of parts, but to furnish new material for growth. Hence the large consumption of food in childhood and youth in proportion to the dimensions of the frame.

146. One use of food, therefore, is to supply the waste constantly going on; and in order that it may discharge this function, it must contain all the elements and compounds, organic and inorganic, of which the body is composed. If the food be destitute of some essential element the health sooner or later suffers. The omission betrays itself in severe functional derangements, arrests of development, or well-marked structural lesions. Water is no less essential than the food, into the composition of which, as of the body itself, it enters so largely. It cannot be withheld, even for a few days, without serious consequences, and the want of it entails sensations far more distressing than those of hunger.

147. The sensations of *hunger* and *thirst* warn us of this twofold waste of the solids and fluids, and invite us to repair it.

148. In healthy temperate persons these sensations bear a just relation to the wants of the body; but there are some diseases in which they are disproportionate to them; and there are modes of life which blunt these sensations, or render them unduly acute.

149. A sensation of hunger disproportioned to the wants of the body is not uncommon. It is present in certain nervous disorders, in many cases of unsound mind, in some persons who lead an indolent and inactive life, and in rare cases it reaches a point of intensity known as *Bulimia*. The appetite, again, may be unduly stimulated by condiments, and by the arts of a refined cookery. On the other hand, it may be blunted by the abuse of opium, tobacco, and spirituous liquors; disregarded during intense mental application, or prolonged grief, and destroyed by sudden emotion. It is also impaired or suspended in most diseases, but especially in their acute form.

150. The sensation of hunger, though usually a fair measure of the wants of the body, sometimes deceives us as to its power of making a profitable use of food. In tabes mesenterica, for instance, the body wastes from disease of the mesenteric glands;

but as the stomach remains sound, the appetite bears a due relation to the wants of the frame, and is often voracious. In the advanced stage of the disease, however, when hectic fever sets in, the appetite and digestive power alike fail.

151. The same observations hold good in respect of thirst; which may become disproportioned to the wants of the body from the use of too stimulating a diet, salt meats, or spirituous liquors in excess. Intense thirst is also highly characteristic of the action of irritant poisons, partly due to inflammatory heat of the throat and fauces, and partly to the pressing necessity for the dilution of the poisoned blood. The analogue of bulimia is morbid thirst, known as *Polydipsia.*

152. As, in a healthy state of body, the appetite is an index of the amount of food required to repair waste, so, in certain diseased conditions, does its utter failure point out the expediency of total abstinence. This is especially the case during severe febrile attacks, when, all the secretions being suppressed, and gastric juice no longer formed, digestion becomes impossible, and indifference to food is heightened into positive loathing, or *nausea.*

153. But though hunger and thirst, in a healthy person, and under ordinary circumstances, are accurate indications of the wants of the frame, they are not so exact as to supersede the influence of habit; for experience proves that a considerable latitude in the quantity of food and in the number of meals is quite compatible with sound health. Nature does not precisely direct either the quantity or the time.

154. Nor is the kind of food best adapted to our wants indicated with such precision as to preclude the use of dietaries varying greatly in different climates and among different races; for though the form of the teeth is held to prove that man may partake both of animal and vegetable food, experience proves that a diet consisting chiefly or exclusively of the one or the other is consistent both with health and strength.

155. In infancy, however, the diet best suited to the wants of the body is unmistakably indicated both by the absence of teeth and by the supply of the food itself. At this period a diet differing materially from that supplied by nature is often attended by fatal results. This is one of the causes of the great mortality of infants, and especially of foundlings, of those put out to nurse, and of those whose mothers are much separated from them by their employments.

156. The first step in digestion consists in the cutting and bruising of the solid portions of food by the teeth, the moistening of them by the saliva, and their propulsion into the stomach. The conditions of the perfect performance of this first act of digestion are, therefore, sound teeth, careful mastication, and sufficient saliva. Decayed teeth and mastication imperfectly performed, either from habit, or occupation of mind, are, therefore, very efficient causes of indigestion.

157. But the saliva serves another purpose. It has the power of promptly converting starch into sugar, and thus a portion of the starchy constituents of our food are digested in the mouth.

158. The food thus bruised, moistened, and changed in composition, when received into the stomach, undergoes a continuous churning movement, by means of the muscular contraction of the wall of the organ. This peristaltic action is such as to cause the food to rotate obliquely from above downwards, in two directions simultaneously: from the orifice of entrance by the orifice of discharge back to the entrance again. In this way the whole of the food becomes thoroughly mixed with the gastric juice. The part of the stomach near the orifice of discharge is meanwhile constricted, so as to form a sort of supplemental cavity, into which the fully-digested food is received, and out of which it is allowed to pass into the duodenum by occasional relaxations of the sphincter which closes the aperture of discharge.

159. The gastric juice, under the stimulus of the food, is clear, transparent, without odour, slightly salt, and perceptibly acid, the acidity being due to hydrochloric acid. Its essential constituent is a peculiar principle called *pepsin*, which promptly disintegrates the fibres of flesh; converts coagulated into soluble albumin, and checks putrefaction. It is poured out rapidly, in quantity proportioned to the food; but if the food exceed the wants of the frame and the indications of the healthy appetite, part remains undigested, and undergoing decomposition, generates carbonic acid and other gases.

160. When the food is solid or pulpy, the gastric juice acts on it almost immediately; but when liquids in excess are taken with it, they must be first removed by absorption; and this delay also favours dyspepsia.

161. The time required for digestion in the stomach varies in different persons, and in the same person under different circumstances; also with the quantity, quality, and consistence of the food itself, and the quantity of saliva and of other liquids mixed with it. After a full meal an interval of four or five hours should elapse before taking fresh food.

162. The states of body and mind favourable to digestion are, repose and cheerfulness. Strong exercise, and anxiety or preoccupation of mind, impair the power of the stomach. Short and long intervals between meals are also injurious; the one by overtasking the stomach, the other by depressing the nervous power.

163. The gastric juice, kept at the temperature of the body and in motion, acts out of the body almost as well as in the stomach. If the temperature is much lowered, its power is greatly impaired, and when raised to 115° or 120° Fahr. is destroyed and cannot be restored. An artificial digestive fluid may be made by soaking the fresh mucous membrane of the stomach of an animal in dilute hydrochloric acid (0·02 per cent.); and if kept at from 99° to 100° Fahr. it slowly dissolves coagulated albumin and meat.

164. Important facts relating to digestion, and the properties of different kinds of food, have been obtained by Beaumont, Londe, and others, who had opportunities of closely observing persons having fistulous openings in the stomach or small intestines. Their chief conclusions may be briefly stated as follows:—1. Animal food is more completely digested than vegetable food, is retained longer, appeases hunger more completely, and is more stimulating. 2. Vegetable substances leave the stomach with their texture only partially destroyed. 3. When animal and vegetable food are taken together the vegetable portion leaves the stomach first. 4. Fatty substances and oil are not digested in the stomach. 5. Boiled meats are more easy of digestion than roast, and roast than broiled. From Dr. Beaumont's observations on St. Martin, it appears that tripe was digested in an hour; eggs, salmon, trout, and venison in an hour and a half; milk, liver, and fish other than salmon and trout in two hours; turkey and lamb in two hours and a half; beef, mutton, fowls, veal, and pork required from three to four hours, beef being more digestible than mutton and fowl, and veal and pork requiring the longest time. Of ordinary vegetables, rice was digested in an hour, tapioca and barley in two hours; potatoes in two and a half hours.

165. The leading constituents of our food are differently acted on by the gastric juice. Woody fibre, the husks and skins of fruit and grain, horn, hair, and elastic tissue, are not digestible; albumin, fibrin, and coagulated casein, and all other varieties of protein, are dissolved and converted into "peptone,"—*i.e.*, a solution of albumin, which is no longer precipitated by neutralization, or by heat, and which, unlike an ordinary solution of albumin, is readily diffusible through an animal membrane; starch, fat, and oil pass from the stomach unchanged, being reserved for the action of the bile and pancreatic fluid.

166. Food of all kinds may be divided into four principal classes —the *saccharine*, *albuminous*, *oleaginous*, and *mineral*. Milk, the nourishment provided for the young, contains all these principles, and they exist in blood.

167. This division was suggested by Prout; but Liebig distributed all the organic constituents or elements into the *nitrogenous* and *non-nitrogenous*; the last consisting of all those substances that can be resolved into oxygen, hydrogen, and carbon, the first embracing all those which contain nitrogen in addition. The non-nitrogenous group comprises fats and oils, gum, starch and sugar, and spirituous liquors. The nitrogenous group includes the seeds of plants and the blood and tissues of animals, and the albumin, fibrin, casein, gelatin, and other analogous principles, that may be separated from them. The non-nitrogenous group, Liebig supposed to be heat-making or respiratory, the nitrogenous, tissue-forming or plastic. But it must be remembered that muscle, nerve, and gland-structure contain a considerable quantity of fat. This form of hydrocarbon may therefore be considered so far as tissue forming. On the other hand,

combustible material is formed to some extent from nitrogenized bodies in the changes which they undergo in the body.

168. Albumin, fibrin, and casein are constituents both of animal and vegetable matters; and they resemble each other so closely in chemical composition that if either of them be dissolved in a weak solution of caustic potash, by the aid of a gentle heat, we obtain from it, by adding acetic acid, the same greyish gelatinous matter, which on ultimate analysis yields about 55 parts of carbon, 23 of oxygen, 15 of nitrogen, and 7 of hydrogen, in every 100.

This is the *protein* of Mulder; of which a hundred parts, with one of phosphorus and two of sulphur, constitute albumin, as found in the serum of the blood; with one of phosphorus and one of sulphur, fibrin; and with one of sulphur, casein.

169. The food, then, before it leaves the stomach, undergoes a two-fold process of *reduction* and *conversion*. It is submitted to a chemical action, by which albuminous substances are rendered soluble; and it passes, as a homogeneous pulp, under the name of *chyme*, into the duodenum, where it is largely diluted, and submitted to further chemical changes by fluids poured into it from the liver and pancreas.

170. The *bile* may be briefly described as a thin soapy fluid, which by its alkalinity aids the pancreatic fluid in neutralizing the acid chyme and precipitating any imperfectly digested albumin (parapeptone), and in emulsifying the fatty constituents of food. It also facilitates the absorption of fatty matter; prevents by its antiseptic properties the decomposition of food during its transit through the alimentary canal; and at the same time facilitates its passage by a stimulant action on the muscular walls of the intestine. But when the bile is mixed with gastric juice out of the body, or when it regurgitates into the stomach, it arrests the process of digestion.

171. The *pancreatic fluid*, aided to some degree by the bile, forms the fatty matters and oil into an emulsion, in which state they are absorbed by the villi clothing the surface of the jejunum and ileum; converts any starchy matters which escaped digestion in the mouth, into sugar; neutralizes (with the aid of the bile) the acid chyme, and if any portion of the albuminous constituents have escaped complete digestion, precipitates them (as parapeptones) and ultimately decomposes them into leucin and tyrosin, intermediary (and often excretory) products between albumin and urea.

172. As one function of the pancreatic fluid is to dissolve fatty matters, the discovery of these in the stools affords a strong probability of disease of the pancreas.

173. The action of the pancreatic fluid ends here; but the bile appears to play an important part in the economy by subserving the function of respiration; its principal constituents *taurin*, *cholic acid*, and *glycocin*, being rich in carbon.

174. These highly-carbonized constituents of the bile in their passage through the intestines are absorbed into the blood; a small portion (estimated at a thirty-fourth part of the entire secretion) being rejected from the body in the fæces.

175. The fœtal liver doubtless performs analogous functions. The bile is secreted, and poured into the intestines, as in the adult: that portion which is fitted to form part of the circulating fluid is absorbed; while that which in extra-uterine life mixes with the undigested remnant of the food and other effete matters, and is periodically discharged from the bowels as *fæces*, collects in the intestines as *meconium*, and is expelled soon after birth or during delivery.

176. The portal vein formed by the convergence of all the veins which ramify on the alimentary canal, as well as those from the spleen and pancreas, contains all the products of digestion which have been absorbed by the blood vessels, and carries them into the liver. It is from this mixed blood that the bile is separated, and as the quantity of bile depends on the supply of blood from the intestines, the intestinal vessels are filled, and the functions of the intestinal canal promoted, by free action of the liver. Venous congestion of the liver, therefore, implies congestion of the mucous membrane of the stomach and intestines, and dyspepsia, as a result: also hæmorrhoidal discharges, which afford direct relief both to the liver and the alimentary canal.

177. Biliary congestion may originate in defective action of the lungs, or in overfeeding. The liver, as we have seen, separates hydrocarbons from the blood, and in a healthy state these are consumed in the process of respiration: but if this function be impaired, the bile accumulates, distends its vessels, and either transudes them and gets into the blood, producing jaundice; or it regurgitates into the stomach, causing bilious vomiting, or is poured out into the intestines in undue quantity, setting up bilious purging. In cold climates, a sedentary life, giving little play to the lungs, conjoined with indulgence in the pleasures of the table, leads to an increased secretion of bile, part of which passing into the intestines, doubtless tends to prevent pulmonary congestion, and part, being absorbed into the blood, tinges the conjunctiva and skin. Strong exercise in the open air, by calling the lungs into activity, lessens the necessity for the formation of bile, rapidly removes symptoms of indigestion, and restores the natural clearness of the complexion. In hot climates, again, the demand upon the lungs for the combustion of the carbon and hydrogen of the blood being diminished, if more food be taken than is required, bile is formed in increased quantity. In either case (whether in cold or hot climates), habitual excess in eating and drinking, and especially the free use of the liquid hydrocarbons (the several forms of spirituous liquor), leads to the same result—functional or organic disease of the liver.

178. Thus the intermediate position of the liver—between the

lungs (through the right cavities of the heart) and the intestines (through the vena portæ), accounts for the frequency of functional and organic diseases of the liver, occurring as indirect consequences both of pulmonary and of intestinal disorders.

179. The chemical process of digestion carried on successively by the saliva, the gastric juice, the bile, and the pancreatic fluid, is not completed in the duodenum, but continues throughout the small intestines, and is probably finally completed in the cæcum by the solution of the last undigested portions of vegetable matter.

180. As the solution of the chyme is effected, it is absorbed in its passage through the alimentary canal by the blood vessels, and in the small intestines by the lacteals also. The indigestible and superfluous portions mixed with the secretions contained in the upper part of the tube, pass into the large intestines, whence after the absorption of some of its liquid constituents, it is discharged as *fæces*, amounting in quantity to about 1-18th part of the food taken.

181. The indigestible part of the food mixed with the residuum of the bile, forms the natural stimulus to the movements of the intestinal canal; an excess of bile increasing the peristaltic action, a deficiency of it, whether through diminished secretion or obstructed flow, causing constipation. In like manner, an excess of undigested or ill-digested matters, produces diarrhœa; and the absence of all indigestible matter, one of the evils of an over-refined cookery, causes constipation. The passage of the fæces through the intestines is also greatly promoted by the movements of respiration, and by all exercises in which the abdominal muscles are called into play. Sedentary habits, on the contrary, promote constipation.

182. *The Chyle.*—It is the function of the lacteal vessels to absorb an emulsion composed of a mixture of fat and albumen in the finest state of subdivision. The lacteals convey the emulsion through the mesenteric glands. In its passage it is changed into *chyle*, which passing onwards reaches the *Receptaculum Chyli.* It there mixes with the lymph collected from the lower parts of the body, and the mixed fluid is conveyed by the thoracic duct into the left subclavian vein, and so becomes part of the blood.

183. The interruption or imperfect performance of this process of *assimilation*, leads to the formation of several secondary organic compounds, the presence of any one of which impairs the health. Thus mal-assimilation of the starchy constituents leads to the formation of sugar as in diabetes, of oxalic acid, as in oxalic acid lithiasis, of lactic and acetic acid, as in certain forms of dyspepsia, of lactic acid alone, as in rheumatic fever. Mal-assimilation of the albuminous constituents results in the formation of uric acid, as in gout, and the cystic oxide lithiasis.

184. A tendency to mal-assimilation is given by habitual excess in the use of the several constituents of food. If fatty sub-

stances, for example, be taken too freely, bilious derangement is apt to occur, and gout is a familiar example of the effect of the abuse of animal food.

185. The *Chyle* varies in its composition according to the nature of the food. When this consists of a due admixture of fatty and albuminous matters, it is a milky alkaline fluid, having in the thoracic duct a yellowish or reddish tinge. When removed from the body it coagulates spontaneously owing to the formation of fibrin. The quantity of fibrin is variable, but always less than that of blood. The clot is therefore much looser. The other constituents are fat, about 5 to 10 parts in 1000; albumin 30 to 50; salts from 4 to 5 parts; and the granular corpuscles—bodies which strongly resemble the white corpuscles of the blood, and have a vesicular nucleus which sometimes attains the dimensions and colour of the blood discs themselves.

186. The *Lymph* is a colourless, slightly milky, alkaline fluid resembling chyle in all respects, but that it contains only a trace of fat, less solid matter and fewer corpuscles.

187. The food has now been traced through the successive physical and chemical processes of digestion and absorption to its mixture with the mass of the circulating fluid. With regard to that portion which is absorbed by the villi, it is pretty conclusively proved that the emulsion of fat and albumin is formed in the mesenteric glands into chyle corpuscles, or leucocytes, indistinguishable from the white corpuscles of the blood (see pp. 42 and 44); and Mr. Wharton Jones, followed by other observers, has concluded that red blood corpuscle is the altered and escaped nucleus of the lymph corpuscle. The same process of cell formation takes place in the ordinary lymphatic glands, so that we may regard this whole system of glands as having for their proper function the renewal of the essential constituent of the blood—viz.: the red corpuscle.

188. The blood which flows in the veins varies in different parts, inasmuch as the general mass of venous blood is continually being mixed with the lymph and chyle. The blood of the portal vein abounds in water, alcohol, sugar, fat, unassimilated albumin, and other constituents of the food directly absorbed by the capillaries of the alimentary canal. The blood of the splenic vein is remarkable for the small proportion of red, and large proportion of white, corpuscles; and for a large increase in the quantity of albumin and fibrin. It is the function of the liver and lungs to convert this crude fluid into arterial blood.

189. The blood in the body of an adult has been variously estimated at from 8 to more than 30 pounds. The quantity which can be made to flow from the body of a decapitated criminal, added to that which can be washed out of its vessels, is about an eighth of the weight of the body itself. This, the highest ascertained proportion, would give 20 pounds of blood for an adult weighing 160 pounds. The quantity must, however, be subject to variation. It is a maximum

within a few hours of a hearty meal, a minimum after long abstinence.

190. The specific gravity of the blood is about 1055. It may reach 1059 in robust men, and fall as low as 1050 in women; in pregnant women as low as 1045. It is also low in very young infants. Its temperature is about 100° Fahr. Its colour a bright red in the arteries, and dark red in the veins. It is fluid when circulating in the living textures, but coagulates in from three to seven minutes after removal from the body.

191. The blood consists of red particles or corpuscles, to which it owes its colour, of colourless finely granular cells (white corpuscles), and of transparent colourless serum, holding fibrin, albumin, and certain salts in solution, and known as *liquor sanguinis* or *plasma*. The red corpuscles which form half its bulk have the high specific gravity of 1088. The white corpuscles bear to the red the proportion of 1 to 1000.

Fig. 1.



192. The blood in coagulating separates into two parts, the crassamentum, or clot, and serum. The clot is formed by coagulated fibrin enveloping the red and white corpuscles and part of the serum. The size and firmness of the clot depend on the quantity of fibrin.

193. The cause of the coagulation of the blood has attracted much attention, and it has been shown that fibrin does not preexist in the blood; but that it is formed when the blood is withdrawn from the living influences by the combination of two modifications of albumin called *globulin* and *fibrinogen*. Whenever solutions of these two substances are mixed, fibrin is deposited. Thus serum of blood pressed out of the clot, contains globulin in solution, and has no power to clot; but if it be mixed with a little exsudation-serum from a hydrocele, or any serous cavity, a clot is formed from the combination of the albumin (*fibrinogen*) of the serum with the globulin of the blood-serum.

194. It has also been shown that the walls of the living blood vessels have the power of preventing coagulation, and that this power is lost when the blood vessels themselves, or any part of them, are injured by direct violence or disease.

195. When blood-letting was much used, certain appearances in the clot were held to prove the existence of inflammation. The appearance supposed to indicate inflammation, to justify the past abstraction of blood, and to warrant a fresh recourse to the lancet, was a concave and buff-coloured clot. When it presented both these characters, it was said to be *buffed* and *cupped*.

196. Healthy blood drawn from a vein, and suffered to remain at rest, undergoes two principal changes—the subsidence of a portion

of its red particles, and a coagulation of the mass of the fluid. The red particles begin to subside as soon as the blood is drawn; coagulation rapidly follows, and in about ten minutes converts the blood into a loose jelly. The blood, thus transformed from a homogeneous fluid into a nearly homogeneous solid, undergoes a further change, often not completed within twenty-four hours or even more. This consists in the progressive contraction of the fibrin. If the coagulation take place within a few minutes of the removal of the blood, the whole of the clot is dark red; but in proportion as the process is delayed, so does the upper part of the clot become colourless, owing to the gradual subsidence of the heavy red corpuscles. The depth of the buffy coat may therefore be taken as the measure of the time required for coagulation.

197. But the colour of the clot may be influenced by more causes than one. An unusual tendency of the red corpuscles to coalesce and adhere (as has been shown to be the case in inflammation), will cause them to sink more rapidly, and the upper part of the clot will be more or less completely deprived of colour. Again, a great diminution of the red corpuscles favours their speedy deposit, and gives rise to the buffy coat. This is the case in anæmia and chlorosis, and a cupped and buffed clot was observed, by M. Andral and others, in 64 per cent. of these diseases. Again, the contractility of the fibrin being the same in two cases, if the quantity is increased in the first and lessened in the second, the clot will be large in the one, and small in the other.

198. The buffy and cupped coat, then, is no sure indication of inflammatory action, but only of an alteration in the relative quantities of the fibrin and red corpuscles, or an excess, either absolute or relative, of the fibrin.

199. The quantity of the *crassamentum*, or clot (the combination of fibrin and red globules with a variable proportion of serum) varies much: the blood of men being more rich in the chief constituents of the clot (fibrin and red corpuscles) than that of women; and being also in excess in persons of the sanguine temperament.

200. The quantity of *red corpuscles* differs in different persons at different times, and it probably varies with age, sex, temperament, and state of health. According to Becquerel and Rodier, it ranges between 113 and 152 parts (dry) in a thousand; the average for healthy males being 141, and for healthy females 127.

201. The red corpuscles are biconcave discs, consisting of a delicate, homogeneous, insoluble stroma, containing within its meshes a soluble red colouring matter. The stroma consists of paraglobulin, lecithin, and neurin, with a little cholesterin: the colouring matter is a compound called hæmoglobin. It may be readily separated from the corpuscles and crystallized. The form of the crystal differs in various animals. In man it is an acute rhombic prism (Fig. 2). Hæmoglobin is a remarkable body. It readily condenses and absorbs oxygen and some other gases, and gives them off again under

Fig. 2.



diminished pressure, the crystals meantime changing from bright scarlet to purple. Upon this quality of hæmoglobin depend the respiratory changes which are the source of vital action: 1000 parts of moist red corpuscles contain about 300 parts of dry hæmoglobin. Of this nearly 17 parts are hæmatin (C_{32} H_{34} N_4 Fe O_5). This is the non-crystalline coloring matter of the blood, and contains the whole (*i.e.*, according to the above formula, about 9 per cent.) of the iron of the blood. In water the red corpuscles swell by imbibition and become spherical; but in syrup or any other liquid of denser specific gravity than the blood, they shrink and become puckered from the exsudation of their liquid contents. It is probable, therefore, that by swelling when the specific gravity of the blood is reduced, and shrinking when it is increased, the red particles may serve to maintain a more uniform consistence of the circulating fluid. The white corpuscles are spherical and larger than the red. They present contracting and dilating movements of an irregular character, resembling those of the *amœba*. They are often called *leucocytes*.

202. The red corpuscles are variously affected by chemical agents and by some of the secretions. The bile completely dissolves them.

203. The *fibrin* in healthy blood varies from 1½ to 3½ parts in a thousand, the average being 2½. It is more abundant in arterial than in venous blood, in about the proportion of 5 to 4.

204. The *serum* is a straw-coloured fluid, holding albumin in solution. When heated to 167° Fahr., the albumin coagulates and separates. It ranges from 62 to 75 parts in a thousand, the average being about 70.

205. The fluid remaining after the separation of the albumin contains extractive matters and inorganic salts (principally of soda) dissolved in water.

206. The several constituents of the serum vary with sex, age, and temperament. The quantity of *water* is greater in females than in males; in children and aged persons than in persons of middle age; and in the lymphatic temperament than in the sanguine. In healthy males it has a range of from 760 to 800 parts in a thousand, and an average of 779; and in healthy females, a range of 773 to 813, with an average of 791.

207. Besides the constituents just mentioned, the blood contains oxygen and carbonic acid gases: 100 volumes of blood contain about 50 volumes of these gases collectively. The proportion of the gases varies considerably; but arterial blood always contains about twice as much oxygen and a third less carbonic acid than venous blood.

Traces of the secondary organic compounds—viz., urea, uric acid, kreatin, kreatinin, taurin, cholesterin, and leucin, are also found in the blood. When the excretions are checked, these matters accumulate in the blood, and cause serious, if not fatal, derangement.

208. The blood undergoes various changes in disease:—(*a*) Sen-

sible changes; (*b*) Variations in the proportions of its constituents; (*c*) Admixture of substances foreign to its healthy composition.

209. (*a*) *Sensible changes.*—The *quantity* of blood is increased by food, and in plethora. It is diminished by hæmorrhage and abstinence. It is also said to be diminished in anæmia; but the pallor which characterizes that disease is due to a deficiency of red corpuscles. Its *temperature* is increased in diseases accompanied by a rapid circulation, such as severe inflammations and inflammatory fevers: on the other hand, it is lowered in languid states of the circulation, and especially when the blood is imperfectly decarbonised, as in apnœa, poisoning by prussic acid, cholera, and cyanosis. The *colour* of the blood is more florid in the cases in which its temperature is raised; and darker in those in which its temperature is lowered. It is changed from dark blue to black by contact with acids, whether formed in the body itself or introduced from without; and it has been described as having a glimmering blue tint in some cases of poisoning by prussic acid.

210. (*b*) *Variations in the relative proportions of its constituents.*—The *red corpuscles* are in excess in plethora, and in defect in anæmia. They are slowly reproduced; hence the long continuance of pallor after hæmorrhages. The white corpuscles abound in anæmia and in disease of the liver and spleen. The *fibrin* is increased in acute inflammations, especially of the serous membranes, in acute rheumatism, pneumonia, phthisis, erysipelas, tonsillitis, and inflammation of the lymphatic vessels. The greatest increase takes place in acute rheumatism, being sometimes nearly four times as much as in health, and continuing in excess after repeated bleedings. It is also in excess in the pregnant female. On the other hand, its quantity is diminished after severe enteric fever, in cerebral congestions and hæmorrhages, in scurvy, in profuse hæmorrhages, and in inflammation of the mucous membranes. The quantity of the *serum* increases as that of the *clot* diminishes. The quantity of *water*, in like manner, increases as that of the more solid ingredients decreases. The *albumin* probably bears a near proportion to the fibrin: it is greatly diminished in cases of Bright's disease. The *fatty* matter is increased, according to Becquerel and Rodier, at the onset of most acute diseases, and in chronic nephritis and tuberculosis. Sometimes it is so abundant as to make the serum milky. This has been observed in diabetes and hepatitis. The *salts* of the serum are diminished in enteric fever, and in cholera.

211. The following table exhibits the variation observed in the quantity of the chief constituents of the blood in disease, compared with the average in health.

Albumin varies between	83	and 52	per 1000 parts—average in health	72
Fibrin	10·5	,, 0·9		3
Fat	117	,, 2		2·5
Corpuscles	185	,, 21		127
Solid matters of serum	114	,, 57		80
Water	9.6	,, 725		790
Salts of serum	8	,, 5		8

212. (c) *Admixture of substances not found in healthy blood.*—1. Results of malassimilation of the food. 2. Constituents of the natural secretions and excretions. 3. Morbid products. 4. Extraneous matters.

213. 1. The leading results of malassimilation of the food are alluded to in §§ 142, 183, and 184. 2. Traces of the proper constituents of the secretions are also normally found in the blood: but when the excreting glands are deranged through functional or organic disease, these substances are apt to accumulate to a dangerous extent. Thus, when the respiration is embarrassed by diseases obstructing the entrance of air, or by exposure to an atmosphere contaminated with carbonic acid, the blood becomes overcharged with this noxious gas. When the liver is inflamed or its duct obstructed, the constituents of the bile are retained in the blood, or pass into it by transudation. In acute nephritis urea is, in like manner, retained within the system and induces the gravest symptoms. 3. Of the morbid products which find their way into the blood, the chief is pus, which, under certain circumstances, is absorbed from the veins or from suppurating surfaces. 4. The extraneous matters are poisons and parasites, both of which are introduced by the stomach, skin, and lungs, or more directly by penetrating wounds.

214. The constituents of the blood may be separated and thrown out among the textures of the body, or on the surface of membranes, or discharged by the several outlets. Fibrin plays an important part in every process of reparation; serum is formed in the sacs of serous membranes, and in the cellular tissue; and the red corpuscles escape in peculiar states of debility. The white corpuscles also readily pass through the walls of the capillaries when the venous circulation is impeded, and, as they multiply very rapidly, they are regarded as very important agents in the inflammatory process, and in the formation of *pus.*

215. The chyle and lymph which are constantly flowing into the blood bring with them many useful and some hurtful principles which must be discharged from the body. The principal organs by which this is effected are the *lungs*, *skin*, *kidneys*, *liver*, and *intestines.*

216. *Respiration.*—The air tubes, after repeated divisions and subdivisions, terminate in small vesicular cells, on the walls of which a network of minute blood-vessels is distributed. The membrane of these cells, through which the atmosphere acts on the blood, is believed to be at least thirty times as extensive as the surface of the body. The lungs, therefore, constitute one vast excreting surface, from which there constantly escapes into the air a mixed cloud of carbonic acid gas and water. An interchange of carbonic acid and oxygen takes place through the membrane of the cells, by which the one is released and the other absorbed, the absorption of oxygen and the release of water changing the colour of the blood from purple to crimson.

217. Viewed as excreting organs, the lungs have this peculiarity, that they require for the due performance of their functions the contact and constant renewal of atmospheric air. This is brought about by the alternate expansion and contraction of the chest, coinciding with the depression and elevation of the diaphragm, movements which in healthy adults are repeated about eighteen times in a minute, but less frequently when the body is at rest.

218. The lungs are always expanded by air to some extent. After ordinary expiration, from 150 to 200 cubic inches of air remain. The quantity taken in and given out, in an ordinary breath, is from 20 to 30 cubic inches; and assuming the former quantity and 18 respirations in the minute, this will give 518,400 cubic inches, or 300 cubic feet of air exchanged in twenty-four hours. But if the body were to remain at rest during the whole of that time, the consumption of air would not be so great.

219. Of this 300 cubic feet of expired air, 4·3 per cent., or 12·9 cubic feet, is carbonic acid gas; and this contains a little more than 6 ounces of solid carbon. In a state of activity 10¼ ounces of carbon are eliminated from the lungs and skin of an adult male in twenty-four hours, and if the apartment occupied by the individual be so close as to prevent any renewal of air, he would require very nearly 2000 cubic feet of air for the twenty-four hours: so that if a man were shut up in a perfectly close apartment, opened only once every twenty-four hours, he ought to have this space allotted to him. On the same principle, a close bed-room occupied during a night of eight hours, ought to have nearly 700 cubic feet of air for each adult male occupant. This space may be safely curtailed where sufficient ventilation is practised; but that allotted to each adult during twelve hours, whether by day or night, ought not to fall greatly short of 1000 cubic feet, that is to say, a cube 10 feet in every dimension (the quantity stipulated for the prison-cell by Howard). In buildings for the reception of the sick, this quantity should be increased at least one-half. In apartments occupied for shorter spaces of time, 75 cubic feet per hour would be a sufficient allowance.

220. The air drawn into the lungs at each inspiration has been just taken at 20 cubic inches; but the quantity is variable, ranging from a minimum of 12 to a maximum of 40 cubic inches.

221. According to the lowest estimate, the carbonic acid formed in twenty-four hours amounts to 14,930 cubic inches, or 8,534 grains; according to the highest, to 39,600 cubic inches, or 18,612 grains. The mean of the three estimates (Lavoisier and Seguin, Davy, and Allen and Pepys) is nearly 28,736 cubic inches, or 14,985 grains. The quantity of carbon removed from the blood will therefore be, according to the lowest estimate 2,820 grains, according to the highest, 5,148. and the mean of the three estimates will give 4,273 grains, or nearly 10 ounces avoirdupois. Liebig found that an adult taking moderate exercise expires daily from the lungs and skin an average of 13·9 ounces of carbon.

222. *Cæteris paribus*, the quantity of carbonic acid formed is proportionate to the activity of the respiratory function. It follows that more is formed during the day than at night; that less is formed in females than in males; in young than in middle-aged persons; that it is increased by repletion and exercise, lessened by fasting and rest. It is also diminished by depressing passions, by fatigue, by spirituous liquors, tea, or vegetable food; and it is given off in larger quantity when the barometer and thermometer are low.

223. The water exhaled from the lungs in twenty-four hours amounts, according to different estimates, to from 2,880 to 13,704 grains, or from about 6½ ounces to 1 pint 11 ounces.

224. The chief function of the lungs, then, is to free the blood from carbonic acid and water. The separation of carbonic acid, and the absorption of oxygen, are necessary to enable the blood to nourish the body, and to act as the efficient stimulus to all its functions. The suspension of breathing for a few minutes is fatal to life, and the circulation of blood not purified by respiration has an injurious influence on all the organs, but particularly on the nervous system.

225. The carbonic acid exhaled from the lungs is greatly increased in the first stage of small-pox, measles, and scarlatina, as well as in various chronic diseases of the skin, but diminished in typhus fever.

226. The lungs also serve as channels through which many volatile matters taken into the stomach escape almost unchanged; and the sweet breath of some healthy persons and the tainted breath of cachectic patients proves that those organs may also serve as avenues through which volatile matters formed within the system, and circulating with the blood, find their way out of the body.

227. *The Sweat.*—The *Skin* performs two important functions; it is a respiratory organ, and as such is a necessary aid to the lungs; and it is an exhalant organ regulating the heat of the body by the amount of evaporation from its surface, and thus acting as an aid to the kidneys.

228. The chief constituents of the sweat are carbonic acid, urea, lactates, chlorides, sulphates, and phosphates of the alkalis. Excepting after free perspiration, the sweat is acid from the presence of acetic, butyric, and formic acids. The proportion of solid matter varies from 4 to 12 parts in 1000. The quantity of urea was estimated in the case of Funke at 157 grains in twenty-four hours; and this may probably be taken as the maximum amount. In disease, uric acid, sugar, and biliary colouring matters are present.

229. The carbon eliminated by the skin in twenty-four hours varies according to the activity of the skin from 60 to 120 grains, being about a forty-eighth of that excreted by the lungs. In common with the other excretions it is increased by moderate excitement of the circulation, and diminished by rest.

230. The exhalation of water from the skin varies greatly: 7 ounces may be taken as the average in twenty-four hours. It is increased by a dry and warm atmosphere, by air in motion, and by diminished pressure of the air; lessened by moist and still air, and by increased atmospheric pressure.

231. The perspiration is *diminished* when the watery constituents of other secretions are greatly increased; thus the skin is dry in diarrhœa, diabetes, cholera, and dropsy. It is also diminished in the cold stage of intermittent and continued fevers, and at the commencement of all febrile affections, as well as in acute inflammations, in the hot stage of fever, and in the febrile exanthemata. In the first class of cases a small quantity of blood circulates through the vessels of the surface; in the second, the circulation is increased beyond the secreting point.

232. On the other hand, the perspiration is *increased* in the sweating stage of intermittent fevers; in mild continued fevers; in catarrhal, miliary and rheumatic fevers; and in inflammatory affections of moderate severity. It is also increased whenever determination of blood to the skin is combined with debility of the capillaries, as in the hectic fever of phthisis, and other exhausting maladies: and in extreme debility, the perspiration is augmented through the mere weakness of the capillary vessels. Such are the cold sweats of collapse and of death.

233. Local perspiration may be taken generally as the result of a co-extensive paralysis of the sympathetic (vasomotor) nerves.

234. The *odour* of the sweat is due to lactic and acetic acids, and to an animal matter, which the axillary glands are chiefly concerned in eliminating. The sour odour predominates in some, the animal odour in others. The first is heightened in catarrhal, rheumatic, and arthritic diseases, in childbed, and in intermittent fevers; the last by strong exercise, by mental emotions, and in certain diseases, as pulmonary consumption.

235. Remedies act on the skin chiefly through the circulation, some by diminishing, others by increasing the heart's action. The passions of the mind also affect the secretion from the skin, by exciting or depressing the action of the heart, agreeable emotions producing a warm moist glow, the stronger depressing emotions, copious cold sweats.

236. *The Urine.*—The kidneys subserve the twofold purpose of relieving the system of excess of water, and of removing (in suspension or solution) solid matters which have been taken as food, or have resulted from the disorganization of the nervous and muscular tissues. These last occur under the form of urea and uric acid, and of certain sulphates and phosphates. The urine is also a channel for the removal of medicines and poisons.

237. The quantity of urine excreted in twenty-four hours varies according to the activity of the skin; 48 ounces is about the

average. Whatever the quantity, it should contain about 1 ounce of urea.

238. The most important constituents of urine are water, urea, and uric acid. The two latter ingredients consist of the following elements:—

	Nitrogen.	Carbon.	Oxygen.	Hydrogen.
Urea . . .	47	20	27	7
Uric acid . .	31	40	27	2

Urea contains so large a proportion (nearly fifty per cent.) of nitrogen, that it is the principal means by which the transformed nitrogenized constituents of the food are eliminated. The quantity excreted is dependent on the food; being increased by animal, and diminished by vegetable, diet. Uric acid is only important when it is in excess.

239. The quantity of the urine is increased by the suppression of other secretions, and lessened by their increase; and this is specially true of the cutaneous exhalation. As the urine attracts special attention at the bedside, it will be more minutely examined in the next chapter.

240. *The Bile.*—This secretion has been well described as a soapy solution of two peculiar fatty acids combined with soda, forming the so-called glycocholate and taurocholate of soda. These, dissolved in about nine times their weight of water, constitute about nine-tenths of the solid constituents of the secretion, every hundred parts of which contain 64 of carbon, 9 of hydrogen, 3 of nitrogen, and 24 of oxygen. The quantity of bile formed in twenty-four hours has been estimated at from 17 to 54 ounces. If, in the absence of precise data, we take the quantity at 1 pint, and suppose it to weigh 9,000 grains, it follows that, as the solid constituents form one-tenth of the entire secretion, their weight will be about 900 grains. As, again, nine-tenths of these solid constituents consist of taurocholic and glycocholic acids, it follows that about 810 grains of these acids are secreted daily. Now 64 parts in 100, or rather more than three-fifths of this, consist of carbon. This will give for the carbon contained in the bile nearly 520 grains; and as the bile daily voided with the fæces does not contain more than a scruple of solid matter, upwards of an ounce of carbon must find its way into the intestines, to be absorbed and carried into the circulating system as prepared fuel for the lungs (§ 173 *et seq.*).

241. The general surface of the large intestine, in addition to its absorbent function, probably takes an important part in eliminating noxious matters from the blood; and the *post-mortem* appearances present in and near the cæcum, both in man and animals, in cases of poisoning by antimony, arsenic, and mercury, as well as in typhoid fever, point to that part as the seat of greatest activity in the elimination of poisons, whether introduced from without or generated within the body itself.

242. The functions of the lungs, skin, kidneys, liver, and bowels, by which the blood is freed from useless or hurtful matters, have now been examined separately; but they should also be considered collectively, that the share each takes in removing effete matters from the blood may be clearly understood.

243. An average of fourteen experiments made by Dalton on his own person, on successive days in the month of March, gave the following results, the urine and fæces being ascertained by weight, and the secretions of the skin and lungs by calculation.

The ingesta and egesta both weighed 91 ounces. The egesta were as follows:—

Urine 48½ oz.; exhalation from the lungs and skin 37½ oz. (30¾ oz. by the lungs, and 6¾ oz. by the skin); fæces 5 oz.: *i.e.*, more than half by the kidneys; a third by the lungs; a thirteenth by the skin; and an eighteenth by the bowels.

244. The bulk of these excretions, and consequently of the food and drink by which they are supplied, consists of water. Of the 91 ounces, no less than 76 consisted of water, which was contained in the several excretions in the following proportions:—

Urine 45¼ oz.; lungs 20½ oz.; skin 6½ oz.; fæces 3¾ oz. Total, 76 oz.: or, about five-eighths by the kidneys; a fourth by the lungs; a twelfth by the skin; and a twentieth by the bowels.

245. The separation of water is evidently an important office of the lungs and skin, and it is easy to understand how one of these organs may become vicarious of the other in this respect. Thus, when the exhalation from the skin is increased by exercise or by any other cause, the urine is diminished; when, on the other hand, as in diabetes, the flow of urine is increased, the skin becomes dry and harsh. The functions of the lungs and skin are also closely connected. When, during exercise, the skin is moist, the respiration is free; but if, the skin being dry, the circulation is at the same time excited, the respiration is oppressed; but the moment moisture breaks out on the skin, the lungs are relieved as by a charm, and respiration becomes natural and easy. The pedestrian will recognise the truth of this statement. It is the rationale of the "second wind" of those who take strong exercise.

246. The quantity of water removed by the bowels being comparatively small, has little effect on the other secretions; but if increased by the operation of a purgative, the urine is diminished, and in violent diarrhœa, and in cholera especially, it is often entirely suppressed. The exhalation from the lungs is also probably affected by the quantity of the secretions poured out by the other organs.

247. Next to the water thus removed from the system, the most abundant material is carbon. It is eliminated by the different organs in the following proportions:—

Lungs 10¼ oz.; skin ¼ oz.; urine ⅛ oz.; fæces ½ oz. Total, 11⅛ oz. Hence the blood is freed from its carbon by the lungs, kidneys, skin and liver; and the lungs excrete so much the larger proportion, that no single organ, nor all jointly, can supply their place when their functions are much embarrassed. Some of the carbon contained in the fæces is furnished by the bile. The rest has never formed part of the circulating fluid.

248. The lungs and skin excrete carbon, with oxygen, as carbonic acid; the kidneys, with nitrogen and oxygen, and a small proportion of hydrogen, as urea and uric acid; and the liver, with oxygen, hydrogen, and comparatively little nitrogen, as cholic and glycocholic acids. As the carbon is similarly combined in the secretions of the lungs and skin, it is easily seen how the functions of the skin may become vicarious of those of the lungs. The relief afforded to the lungs during exercise by free perspiration probably arises in part from the excretion of carbonic acid; and the same may be said of the colliquative sweats in phthisis.

249. The close relation existing between the functions of the liver and lungs is proved by the frequent coexistence of diseases of those organs: that the one may be vicarious of the other is shown by the large size of the liver in the fœtus.

250. The essential constituent of the urine (urea) contains carbon in considerable quantity. It is directly derived by oxydation from uric acid, which contains twice the quantity of carbon, and is regarded as a product intermediate between the effete nervo-muscular tissues on the one hand, and urea on the other. Disordered function of the lungs or skin leads, therefore, to the accumulation of uric acid in the system.

251. Nitrogen in small and variable quantity is at one time absorbed, at another exhaled, by the lungs and skin. The appropriate organ for its removal from the system is the kidney. In uræmia the stomach attempts the elimination of urea.

252. The secretions of the skin, kidneys, and liver, abound in the ordinary salts; so that one of these organs may, to a certain extent, become vicarious of another. Certain saline substances are accumulated in large quantity in diseased organs at the expense of some secretion of which they form a normal constituent. Thus common salt, found in excess in the sputa from inflamed lungs, but absent from the urine, is restored to the urine on the subsidence of the disease, as has been shown by Dr. Beale.

253. In the similarity of the matters excreted by the several organs we recognise a provision for maintaining the normal constitution of the blood under slight functional disorders; while the efforts of one organ to supply the place of another probably account for some of the familiar symptoms of disease. When these efforts are unavailing, the blood becomes seriously altered, to the imminent danger of the patient.

254. The following table presents at one view the results of

on's experiments; the last three lines being rude approxima- :—

	Pulmonary Exhalation.	Cutaneous Exhalation.	Urine.	Fæces.	Total.
ta . . .	30¾oz.	6¾oz.	48½oz.	5 oz.	91 oz.
er . . .	20½oz.	6½oz.	45½oz.	3¾oz.	76¼oz.
l residue .	10¼oz.	¼oz.	3 oz.	1¼oz.	14¾oz.
nsisting of substances containing—					
on . . .	10¼oz.	¼oz.	½oz.	½oz.	11½oz.
gen and other gaseous elements of ea and uric acid, exclusive of carbon .			1½oz.	...	1½oz.
, &c.			1 oz.	...	1 oz.
due of undigested matters				¾oz.	¾oz.

5. In the foregoing statement and tabular summary no notice ken of the large quantity of oxygen received through the lungs. gas, as essential to the support of the frame as food itself, by ng with the effete textures, gives rise to compounds which ot support life, and these being absorbed into the current of the lation, seek their exit from the body through the excreting ns. If we suppose the weight of the body to remain unchanged, xygen introduced by the act of respiration, added to the food med, must equal in weight the matters rejected by the ex- ng organs. The part borne by each organ in this work of nation is shown in the following table, which embodies the s of two tables given by Vierordt in his "Grundriss der Physi- e," p. 192. 3952 grammes of food and drink are resolved into elements, and traced, so to speak, into the excretions through n they pass from the body.

Received as Food.	Grammes	Excreted by				
		Lungs	Skin	Kidneys	Bowels	?
r in food and drink	2,818	330	660	1,700	128	...
gen (from air 744, m food 38) . . .	782	651	7	11	12	101
ogen from food. .	19	...	..	3	3	13
on „ . . .	282	249	3	10	20	...
gen „ . . .	19	...	...	16	3	...
„ . . .	32	...	...	26	6	...
	3,952	1,230	670	1,766	172	114

ith the exception of 101 parts of oxygen and 13 of hydrogen, osed to unite as water, the watery, gaseous, and saline elements e food are here traced to the organs by which they leave the . It is worthy of remark that in the experiments from which figures are deduced, the oxygen received in respiration is little less than a fifth part by weight of all the solid and liquid matters taken as food, and very nearly twice as great as the oxygen, carbon, hydrogen, nitrogen, and salts contained in all that part of the food that is not water.

2. PHYSIOLOGY AND GENERAL PATHOLOGY OF THE CIRCULATING SYSTEM.

256. Having now examined the function of digestion; the blood, and its constituents; the secretions destined to further uses; and the excretions by which the blood is freed from useless or hurtful matters; it remains to consider the mechanical arrangements by which the blood is renewed, purified, and distributed through the frame; in other words, to examine the functions of absorption, secretion, nutrition and circulation. This will be done in the following order: the action of the heart; the motion of the blood in the arteries; the functions of the capillaries, of the veins, and of the absorbents.

257. *The Circulation.*—The heart is the centre of two incomplete circulations; one through the lungs, beginning at the right ventricle, and ending at the left auricle; the other through the body, commencing at the left ventricle, and ending at the right auricle; the two together forming a complete circulation, an uninterrupted stream of blood. A third circuit consists of the coronary arteries springing from the commencement of the aorta, and the coronary vein opening into the right auricle.

258. These three incomplete circulations consist of vessels, all of which are always, and in all states of the living body, full of blood, though more or less distended as it is increased or lessened in quantity.

259. The vessels in question consist of an arterial trunk split into numerous small branches, of a venous trunk formed by the union of equally numerous small veins, and of capillary vessels uniting the two, and this—arteries dividing into small branches, and corresponding small veins uniting to form venous trunks—is, with the exception of the vena portæ, and the minute vascular system of the kidney, the mechanism of the circulation throughout the body.

260. A general view of the circulation, including the portal system, is given in Fig. 3, in which *a d* represents the circulation through the body, *b c* the circulation through the lungs, *e e* the exceptional portal system, and *g g* the lymphatic and lacteal system. The darker parts of the plan, to the left of the diagram, represent the venous system, and the lighter, to the right, the arterial system. The arrows indicate the direction of the stream of blood. The circulation through the heart is apparent without the use of letters.

261. *The Heart's Action.*—The *heart* is the source, and chief cause, of the circulation through the blood vessels. The ventricles, expelling their contents with more or less frequency and force, in different persons, and in the same person at different ages and at different times, send out at each contraction the blood received into the auricles from the large venous trunks.

262. The average number of contractions in a minute may be set down at 70 for an adult male, and 80 for an adult female. The quantity of blood forced into the aorta at each beat of the heart in a healthy adult has been variously estimated at from 2 to 5 or 6 ounces; and the total quantity contained in the body at about 20 pounds (§ 189).

Fig. 3.



263. The force with which the blood is expelled by the left ventricle has been estimated at somewhat more than 4 pounds: that by the right at about 2 pounds.

264. The time required for the complete circulation of the blood through the right side of the heart, the lungs, the left side of the heart, and the whole of the blood vessels, from a given starting point to the corresponding goal, say from one jugular vein to another, is about half a minute. This is readily proved by the injection of such salts as ferro-cyanide or iodide of potassium. Hering found that the transit of the former of these substances from the jugular vein to the metatarsal artery occupied twenty-five seconds in one experiment, and forty in another.

The circulation is most rapid in the arteries, and least so in the capillaries, the rate, of course, diminishing as the sectional area of the vessels increases. Volkmann concludes that the blood moves 12 inches in a second in the aorta, and Vierordt 2¼ inches in the same space of time in the arteries of the foot, while the rate in the capillaries is not greater than 1 inch in a minute, the force of the circulation in medium-sized arteries, such as the radial, being equal to about 4 drachms. Valentin has calculated that the whole of the blood in the body passes through the heart in from forty-three to sixty-three seconds.

265. *The Arteries.*—The blood sent out by the heart is distributed to every part of the body by the arteries. The larger arterial trunks are highly-elastic tubes, destitute of muscular fibre, admitting of expansion, both transverse and longitudinal, and able to adapt themselves to the volume of their contents. With each contraction of the heart they are expanded and slightly curved; and Poisseuille has shown that they undergo an increase of size, amounting, in the carotid artery of the horse, to $\frac{1}{23}$rd of its capacity.

The larger arteries, by yielding to the impulse of the blood and reacting upon it, cause a delay in its motion which would not occur in rigid tubes; hence the pulse is somewhat later in the arteries remote from the heart than in those near it. This elasticity also equalizes the motion of the blood in the smaller vessels, and causes it to flow in an even stream. It also accounts for their empty state after death, their contents being forced into the veins. In old age this property is lost through degeneracy or ossification.

266. In dilating, the artery is stretched and curved outwards by the forcible injection of blood; and if the finger be applied to it with a tolerably firm pressure, this effort at change of place is felt. But this is not all; for the pressure of the finger is resisted by the blood forced into the artery; and this resistance is also felt. These two things together, the change of place, and resistance to pressure, constitute the Pulse, which will be more minutely examined in the next chapter.

267. The smaller arteries and veins have layers of muscular fibres, in the former arranged circularly, and in the latter in two

sets, an inner circular, and an outer longitudinal. In cases of obstructed circulation these muscular fibres have been found hypertrophied. The effect of the functional derangement of a single organ in causing hypertrophy of the whole vascular system, including the heart itself, has been demonstrated by Dr. George Johnson in chronic inflammation of the kidney (see chronic nephritis). The arteries intermediate between the large trunks and their smaller branches, have more or less muscular fibre as they approach to the one or the other class of vessels.

268. *The Capillaries* are vessels of extreme minuteness, consisting of a single membranous coat, through which the portion of the blood destined for secretion or nutrition finds its way. They form a network, between the meshes of which the proper substance of each organ lies, or they are so disposed as to adapt themselves to the form and arrangement of the several tissues; and they establish a communication between the last divisions of the arteries, and the first of the veins. The small arteries which do not lose themselves in veins have no other termination, and the veins no other origin; and there are no vessels terminating by open mouths. This continuity of the arterial and venous system through the intervention of the capillaries is shown in the annexed engraving of a villus, of the small intestine (Fig. 4), in which the shaded vessels represent the veins, and those in outline the arteries.

Fig. 4.



269. The motion of the blood is mainly due to the heart's action; its constant and equable flow to the elasticity of the arterial trunks. The capillary circulation is excited by the attraction of the tissues for arterial blood; while the onward flow of blood in the veins is secured by the active dilatation of the heart, and the inspiratory act, which sucks the blood into the lungs: as well as by the muscular walls of the vessels. The motion of the blood is slow in the capillaries, owing to the greatly increased area over which the blood is distributed when it enters the capillaries—an area which, compared with that of the arteries supplying them, is as 800 to 1.

270. In health, the capillaries subserve the important function of nutrition by allowing the ready exudation through their thin membranous wall of the materials which the several tissues require for their growth and repair; and in disease they play an important part in the changes known as *inflammation, irritation, and congestion.*

271. The minute arteries and capillary vessels are subject to changes in health, which enable us to understand disease. Shame

brings a blush to the cheek; fear blanches it. Warmth and exercise redden the skin; cold and continued rest deprive it of colour. These effects depend on variations in the calibre of the small arteries and capillary vessels.

272. Such variations may readily be observed in the vessels of the frog's foot (Fig. 5).

Fig. 5.



The velocity of the circulation is seen to increase, the outer portion, *a a*, of the calibre of the vessels to admit red particles, *c d*, and the size of the vessels, *b b*, to increase or decrease.

273. In the examples just adduced we have three distinct causes of determination of blood to the skin: in the first an emotion of the mind; in the second, a local application to the vessels; in the third, the increased action of the heart. From the first example it appears that the state of the small vessels may be changed without increased action of the heart, for if the enlargement were due to that cause, the blush would not be confined to the cheek; from the second, that local applications will affect them in the same way; and from the third, that the same result may follow from the stronger and more frequent contraction of the heart itself. The cases in which pallor of the skin occurs are equally instructive, proving as they do the local effect of emotion in contracting the small vessels, the equally local effect of cold, and the remote effect of a quiet action of the heart.

274. In the effects of emotion and of stimulating local applications we have examples of the active dilatation and contraction of the capillaries independently of the heart's action, and therefore solely due to nervous influence.

275. The rate of the circulation in the capillaries is, however, determined by the state of the small arteries on the one hand, and the greater or less vigour of the processes of secretion and nutrition on the other.

276. It appears, then, that, in one instance at least, the enlargement of the minute arteries is only to be accounted for by a diminution or suspension of their contractility. Now, this same enlargement of the small arteries occurs in inflammation. Is it due to the

same cause? A grain of sand gets into the eye, and in a short time the vessels of the conjunctiva become filled with red blood, and enlarged, obviously without any increased action of the heart, for the other eye, equally affected by the general circulation, is not inflamed. Again, the immediate effect of ice applied to the finger is to contract the vessels; but no sooner is it removed, than the pale skin resumes its colour and becomes even redder than the surrounding skin. This change, too, is strictly local, and independent of the heart's action. The same contraction of the small arteries, followed after a variable interval by dilatation, has been shown, by experiments under the microscope, to follow the application of mechanical and chemical irritants. So that it may be stated as a general fact, that the agents which excite inflammation may first cause contraction of the small vessels; and that this contraction is followed by dilatation.

277. These actions take place in obedience to a general law, that stimuli applied to any part of the body, acting through its nerves, develop the special functions of that part for a time, but that the nervous force suffers an exhaustion proportionate to its intensity and duration, and results in a condition the very reverse of that which existed when the stimuli were first applied. In the case now under consideration the stimulus first excites the contractility of the small arteries; after a time exhaustion ensues, the vessels expand, and become unduly loaded with blood. When the exhaustion is complete, the vessels are distended and stagnation ensues.

278. During this first period of contraction the flow of the blood is retarded; but when the vessels become dilated, the circulation is accelerated, to be again retarded after an interval of time. The small vessels, in becoming dilated, are also stretched and twisted, and here and there even become varicose, as is shown in the annexed engraving from Valentin, after Harting (Fig. 6). In consequence of this increase of size, the vessels admit a larger number of red particles; and those that previously conveyed only colourless blood, now become carriers of red blood.

Fig. 6.



279. The changes that occur in an inflamed part are not long confined to the small vessels. The larger arteries and veins suffer the same dilatation; and if the inflammation prove severe and extensive, the arterial trunks themselves participate: and thus large portions of the body—a hand, a foot, a limb, or an internal organ—become so many congeries of enlarged vessels containing more blood than those of the corresponding part of the body. An inflamed hand, for

instance, contains much more blood than the sound one; its radial artery is evidently enlarged, through loss of contractility and increased action of the heart; and if a vein of that side be opened, it will pour forth much more blood than the vein of the opposite side.

280. Through the increased action of the heart, which occurs in all acute inflammations, blood is sent in greater quantity to every part of the frame, and gives rise to *symptomatic fever*, converted, if the nervous system suffer much, to the state known as *irritation*, *constitutional irritation*, or *irritative fever*; should the power of the constitution have been previously exhausted, the fever may assume the *typhous* type in place of the milder form it assumes in the strong and robust.

281. It appears, then, that in acute inflammation the propelling and regulating action of the small arteries is diminished or annulled, and instead of aiding the circulation they are an impediment to it. The heart is called upon to overcome the obstruction, and hence the greater force and frequency of its pulsations.

282. Such being the general state of the circulation in inflammation, our attention must now be directed to the process as it affects the capillaries, because these and the tissues in which they lie are the parts most directly and severely implicated in the morbid action. The following important observation is due to Cohnheim. If the mesentery of a living frog be stretched over a ring of cork, and magnified about 100 times, the vessels are seen to dilate and the colourless blood corpuscles to begin to collect and adhere to the inner surface of the wall of the capillaries. Little bud-like processes of these corpuscles are then protruded through the wall of the vessel, and increase as the corpuscle on the inside diminishes, until at last the corpuscles pass entirely from the interior to the exterior of the tube. Having passed through the cells by virtue of the independent movements they possess (see Fig. 7), they leave the wall of the vessel and wander into and among the interstices of the surrounding tissue. Irritation of a particular point determines the direction which they take, and here they accumulate and form a mass of exsudation or formative tissue, which becomes the point of departure of all future changes. Simultaneously the tissue itself undergoes a change; the corpuscles of the connective tissue multiply, and the fibres of a compact part are pushed apart and

Fig. 7.



become loosened and absorbed in proportion as the exudation increases and occupies its meshes. Thus it is that we find the vessels in an inflamed part embedded far and wide in young cellular growths.

283. The effect of the inflammatory action on a free surface is well illustrated in the serous membranes and uriniferous tubules. The liquor sanguinis escapes with the colourless corpuscles, coagulated fibrin is intermingled with the formative cells, and the serum separates to form a fluid effusion.

284. When a gland is implicated in the inflammation, the first effect is a diminution of the appropriate secretion, and this is quickly followed by the rapid destruction of the secreting cells, and the retention of the constituents of the secretion in the blood, and thus general blood poisoning is in such a case the necessary consequence of inflammation. An excellent illustration of these facts is afforded by inflammation of the kidney. First the urine is notably diminished, this is followed by a rapid desquamation of the epithelial cells lining the urinary tubes; the detached cells clog the tubes; and blood or serum is extravasated from the Malpighian tufts. If the inflammation be very severe and affect both kidneys, urea is retained in the blood and symptoms of narcotic poisoning soon ensue. A train of symptoms very similar in the main follows acute inflammation of the liver (see Yellow Atrophy of the Liver).

285. The enlargement of the small vessels in inflammation, then, is quickly followed by effusion. When the skin is inflamed, as by a burn, serum is thrown out from the surface under the cuticle, and a blister rises: when a mucous or serous membrane is inflamed, fluid exudes from its surface: when the cellular membrane is attacked, the fluid is poured into its cells. This effusion varies with the constitution and state of system, the condition of the part, and the intensity and nature of the inflammation; and may present every variety between a lymph abounding in fibrin, and a lymph rich in granules or corpuscles.

286. The lowest degree of inflammation merely increases the watery secretion of the part attacked—of serum, in the case of serous membrane—of mucus, when a mucous surface is inflamed. A higher degree of inflammation causes the effusion of solid matter or formative material. The increased secretion of the serous membranes is *dropsy*, or, when of limited extent, *œdema*; that of the mucous membranes, *flux*. Both these membranes, also, when the inflammation is more intense, pour out lymph or pus. In the former case the inflamed surfaces of the pleura or peritoneum become glued together, and the effused matter, becoming organized, forms permanent adhesions. The mucous membranes, too, when highly inflamed, pour out lymph of such tenacity as to assume the shape of the tubes which they line, and even to be mistaken for the detached lining membrane itself. This occurs in the larynx, in diphtheria and croup; in the bronchial tubes, in a peculiar form of

bronchitis; in the intestines, in dysentery; in the kidneys, in inflammatory affections of those organs. Of purulent effusion from serous membranes, empyema is an example; and of the formation of pus by mucous surfaces, purulent ophthalmia.

287. When the small vessels return to their natural size, and any effusion (that may have taken place) into the surrounding textures is absorbed, the inflammation is said to terminate by *resolution;* when blood is thrown out, by *hæmorrhage;* when serum, by *effusion;* when fibrin or lymph is formed and organized, by *adhesion;* when pus is effused, by *suppuration;* when the part dies, by *necrosis* or *gangrene.* Inflammation of mucous surfaces, or of exposed portions of cellular membrane, accompanied by the effusion of pus, and the more or less rapid removal of the part affected, constitutes *ulceration;* and a similar process in the substance of organs is known as *ramollissement,* or softening.

288. The generic term inflammation is often qualified by other words indicative of its character. Thus we have *œdematous* inflammation, or inflammation terminating in, or accompanied by, *œdema; adhesive,* or inflammation terminating in *adhesion; suppurative,* or inflammation issuing in *suppuration; gangrenous,* or inflammation ending in *gangrene.* The terms *acute* and *chronic, healthy,* and *unhealthy, common* and *specific, phlegmonous* and *erysipelatous,* are also used to designate varieties of inflammation.

289. When inflammation attacks the cellular membrane, whether in the skin or in the substance of internal organs, it takes different courses according to its intensity. If slight, it terminates in *resolution;* if more severe, *effusion* may take place; if more severe still, *suppuration;* if still more intense, *gangrene.* If a portion of the cellular membrane die, or if blood, serum, or fibrin be poured out so abundantly as to distend and break down the tissue, pus is formed in small detached portions, which, by solution of the intervening parts, coalesce, so as to form one single collection of purulent matter, round which a wall of fibrin or coagulable lymph is built up, becomes organized, and constitutes a *cyst* or *sac.* This collection of pus in a cavity, bounded by a wall of effused and organized fibrin, is called an *abscess*—a term which, like the word inflammation, is qualified in practice by phrases indicative of its character or progress, such as the *acute* or *phlegmonous,* and the *chronic* abscess.

290. *Resolution.*—In order to facilitate the dispersion of the amœboid cells we apply heat, which is known to facilitate their movements; but we must remember that the untimely use of hot fomentations may encourage the issue of the cells from the capillaries and so increase the effusion. The effusion may also be removed by fatty degeneration of its cellular constituents; for when cells cease to be active, they are rapidly invaded by fatty molecules, and ultimately soften down into a milky fluid, which is readily and completely absorbed.

Suppuration.—Pus is composed of fine granular corpuscles ded in colourless serum in which are dissolved several forms min, mucus, lecithin, glycogen, and salts; and suppuration e regarded as the direct continuation of the inflammatory s. The pus corpuscles are derived from the multiplication of travasated colourless blood corpuscles and the free cells *ytes*) of the connective tissue, both of which appear to be e of unlimited reproduction as soon as blood vessels appear effused products.

Sometimes the constitution is not strong enough to build up ganize a wall of fibrin about the dead part, and then the pus ts way into the surrounding cellular texture, and forms a *d abscess*, or the inflammation is peculiar, as in erysipelas, ppuration takes place with little or no adhesion.

. In rare instances the pus undergoes fatty degeneration and rbed, and the abscess is said to be *dispersed;* but in the ty of cases fresh pus is formed, the abscess increases in size, resses on surrounding parts, some of which yield to the re, and then the abscess is said to *point;* and if it is near the e, the skin itself offering least resistance, is protruded, and ed more and more till it bursts.

. *Organization after Suppuration.*—When the matter of an s is discharged, the cavity contracts, the fibrinous lining is f, and the walls become a suppurating surface, on which fresh is effused. Part of this fibrin becomes organized by vessels, either form within it, and then connect themselves with those rounding parts, or gradually extend into it from those parts. newly organized portions of fibrin are arranged side by side all rounded vascular points, called *granulations.* The fresh e thus created secretes pus, which protects it from the air. the granulations approach the surface, the pus hardens into , which forms a still more efficient protection. In healthy s the granulations are numerous, small, and florid, and coated creamy pus, known to the older surgical writers as *laudable* Unhealthy granulations, on the other hand, are large, pale, abby, and discharge a thin flaky pus.

. When the tissues are divided, and the two edges of the l thus formed are brought close together, and kept in contact, dy and perfect union may take place, and the wound is then have been healed by the *first intention.* But the part may al in this simple way: the wound may gape, and an open r *ulcer* be formed presenting the same granulations as the f an abscess that has burst. These, once completely organized, fresh lymph, and this, in its turn, is moulded into new lations; and thus the ulcer is at length filled up to a level he surrounding skin, and protected by a scab; a small portion tissue is meanwhile formed between the edges of the wound, gradually contract as the surface heals. Ultimately the scab falls off and exposes the newly-formed tissue. The *scar*, or *cicatrix*, is at first red, but the colour gradually fades, and at length the scar is recognized by its whiteness.

296. As a general rule, abscesses, whether in the integuments or in the solid viscera of the body, tend towards the surface; but to this rule there are exceptions. If, for instance, an abscess form in such an organ as the liver, its firm close structure may offer more resistance than the loose texture of an adjoining intestine: the abscess presses upon its coats, and adhesive inflammation is set up between the two layers of serous membrane; the peritoneum and the coats of the intestine are thus so glued together as to form one continuous texture through which the abscess, continually increasing, forces its way, till it bursts and discharges its contents. Sometimes the course of an abscess is more circuitous, as when an abscess of the liver finds its way through the diaphragm, and opens into the lungs. Sometimes, again, an abscess in a solid viscus discharges itself into the serous cavity which surrounds it, as when abscess of the lung opens into the pleural sac.

297. As a general rule, the matter of an abscess takes the shortest course to its place of discharge; the most common exception being in the case of collections of matter formed beneath fasciæ, by which they are bound down and directed to a distant part.

298. *Ulceration* is the result of suppuration. Ulceration of the skin, for instance, begins with inflammation, and is followed by the effusion of serum or pus, known as a vesicle or pustule. This breaks, and leaves an uneven surface, covered with flakes of lymph, and moistened with pus, which may either heal in the way just described, or extend and enlarge by the destruction of the skin and subjacent textures. In ordinary cases the parts are removed gradually, and almost imperceptibly; in others, with great rapidity, when the ulcer is called *phagedenic;* in others, again, the inflammation is so intense as to cause the death of considerable portions of the cellular membrane, in which case it is called a *sloughing* ulcer. The most rapid destruction of parts with which we are acquainted has received the name of *sloughing phagedena* or *hospital gangrene*. Ulcers are further designated as *acute* and *chronic; healthy* and *unhealthy; inflamed, indolent*, and *irritable; congestive, varicose, fistulous, rodent*, &c.

299. *Gangrene* is one of the terminations of inflammation; and the death of a limited portion of the cellular or other texture is an occasional cause of abscess. The common *boil* is an example of a more extended death of the cellular tissue, and *carbuncle* of the worst form of boil. But gangrene may take place without the formation of an abscess. It may attack a limb, in consequence of the extreme languor of its circulation; and, beginning in the foot, extend upwards till it reaches a part where the circulation is active enough to allow of adhesive inflammation. Coagulable lymph is thrown out in a circle, dividing the sound from the dead parts;

ıulations are formed, pus effused, and at length natural ampu-
ɔn of the dead member will be effected. Thus, through the
›rent effects produced, and the different secretions poured out
ifferent degrees of inflammation, the body sets limits to its own
ases, and repairs the most severe injuries.

00. Gangrene may exist for a long time without inflammation,
n a limb of which the arteries are ossified, or in cases of poison-
with ergot of rye: this is distinguished as *dry* gangrene. When
grene, from extreme languor of the circulation in the lower
emities, attacks aged persons, it is known as *senile* gangrene.

01. The most frequent constitutional or predisposing cause of
grene is debility; the most common exciting causes are severe
hanical injury, the action of violent irritants, pressure, and
nse cold. The immediate or proximate causes are a deficient
ply of arterial blood, impediments to the return of the venous
d, and injury or division of the nerves. The term *mortification*
ommonly used as synonymous with gangrene; and the word
celus, or *slough*, is employed to characterise a part which can-
be restored to life.

02. Further descriptions of inflammation, its causes, phenomena,
ninations, and the various modifications it undergoes in different
es of health, in different constitutions, and in each texture of
body, will be found under the head of the various diseases
ribed in Part II.

03. *Congestion* is nearly allied to inflammation. It consists in a
sive enlargement of the small vessels, without inflammatory
ıptoms or effusion unless it be excessive, when there is an in-
se of the natural moisture of the part. This enlargement of
vessels is the effect of debility; and, as such, is apt to continue
arts in which the symptoms of acute inflammation have been
dued. It is common in the aged, and in persons exhausted by
ase. From its involving the veins rather than the arteries, it
ften termed *venous congestion*. Pressure is a common cause of
state: hence congestion of the veins of the leg after long stand-
, of the vessels of the head from wearing a tight cravat, and in
lungs from hindrances to the respiration.

04. *Congestion of internal organs* is a common occurrence, and
ys an important part in the development of organic disease, and
he hæmorrhage and dropsy which so frequently accompany it.
ne of the causes of visceral congestion, such as cold applied to
surface, a continued dry state of the skin in febrile disorders, and
plethora induced by a rich and stimulating diet combined with
fficient exercise, are very simple and obvious. The continued
ion of these causes leads sooner or later to organic disease in
e predisposed organ, such as the brain, the lung, the liver, or
kidney.

05. *Hæmorrhage* is a frequent consequence of congestion, when

it is termed *passive;* but it sometimes seems to flow immediately from the arteries, when it is termed *active*. Hæmorrhage from the lungs is generally caused by rupture of an artery; but in case of the stomach and bowels, the blood seems to exude through the coats of the vessels. Hæmorrhage may also take place into the ducts of secreting organs, such as the liver or kidney. In scurvy and in putrid fevers the hæmorrhage is due partly to weakness of the vessels, and partly to thinness of the blood. Hæmatemesis, melæna, and hæmorrhoids, are examples of passive hæmorrhage. The copious discharge of red blood from the bowels, traceable by the use of the *speculum ani* to a small spot in the mucous membrane of the intestine, is a good example of the active form.

306. *Nutrition and secretion.*—These two processes are essentially the same; for they consist in the development of simple cells endowed with independent vitality, and capable of assimilating from the blood their own peculiar fluids.

307. The *secreting organs* assume various forms: but consist essentially of a basement membrane, lined with epithelial cells, and covered externally with a network of blood vessels.

308. In *nutrition* each cell runs through its course of gradual development and decay, and the products of its decomposition (the first in order being, as in all forms of decay, carbonic acid), are absorbed into the blood, and discharged by appropriate excreting organs.

309. In *secretion*, too, the cells which form the essential secreting organ ripen by the absorption of materials constituting the secretion, and then break up and decay; the mixed products being poured into tubes fitted for their reception and discharge.

310. The fluids thus poured out by the secreting organs are known as *excrementitious* and *recrementitious;* that is to say, they are expelled as hurtful, or retained to serve some useful purpose.

311. To the class of *excrementitious* matter belong the urine, the sweat, the water and carbonic acid exhaled from the lungs, a small portion of the bile, the secretions of the mucous membranes, the menstrual discharge, and the hair, cuticle, and nails. Milk and semen, the one nutritive, the other reproductive, form a class by themselves.

312. Of the *recrementitious* secretions some (as those of the salivary glands, stomach, liver, and pancreas) subserve the process of digestion; others (as the tears, and the watery secretion of the Malpighian tufts of the kidney) cleanse the surface of the eye and the urinary tubes respectively; others again (as the sebaceous secretions of the skin, the mucus of the mucous membranes, and the aqueous secretion of the serous membranes) protect the parts which they moisten from injury, and facilitate their movements.

313. Another secretion not destined to immediate expulsion from the body consists of the fat deposited in cells of the adipose tissue,

undness to the form, facilitating motion, protecting the ist changes of temperature, and serving as a store of nt.

secreting organs in the membranous form the serous s (the pleura, peritoneum, arachnoid, and the synovial s of joints, &c.) are examples, as well as the mucous s (that lining the mouth and nostrils, the windpipe and alimentary canal and the parts communicating with it, lining the urinary passages and organs of generation). s a compound organ, containing odoriferous, sudoriferous, eous glands.

lands, in the usual acceptation of the term, are of three collections of blood vessels, as the spleen and placenta; congeries of lymphatic vessels (lymphatic glands); and creting organs. These latter possess an excretory duct, ced backwards from its trunk, divides, like the root of a fine branches, of which the smallest terminate in blind s of various shapes, called follicles, acini, tubules, &c. tside of these minute terminations the capillaries ramify, ppropriate secretion is abstracted from the blood by the cells which line the passage, where the branches of the and it is then shed by these into the duct, and distils from The blood thus freed of the secretion passes onwards to

the kidney, the secreting apparatus is more complicated, of a tuft of vessels (the Malpighian body), which secrete l tubes lined with epithelium, which eliminate the solid its of the urine. The water serves to wash out these solid an operation assisted, in reptiles and fishes, and probably alia also, by the cilia which line a portion of the tubes.

cretion, like nutrition, is subject to differences in degree ind. The natural secretion of a part is augmented by flow of blood, provided it be not excessive. Thus on follows exercise, and free action of the bowels irritation ntestinal mucous membrane. Secretion may also be by debility of the small vessels, when the circulation is as in the cold sweats following a faint, or preceding n. These two causes of increased secretion—augmented ood, and weakness of the vessels—combine to produce the eats of hectic fever. On the other hand, the natural of a part is diminished when the supply of blood is either ssened or augmented, as is the case with the skin both in nd in the hot stage of fever. In this latter case, as soon ver subsides, and the quantity of blood sent to the skin certain point, sweating begins. The nerves, too, have ct on the secretions, as is seen in the flow of tears from or rage, and in the effects of fear or anxiety on the skin, and bowels. Mental emotion, however, checks some secretions. Thus fear, which increases the secretion of the skin checks that of the salivary glands.

318. But the secretions vary in *kind* as well as in degree; i other words, they are liable to morbid changes. Thus, the serou membranes, which in health secrete a watery mist or vapour, unde a certain degree of inflammation pour out serum, and drop results; under a higher degree liquor sanguinis is poured out under a different kind, and perhaps higher degree, pus. Th mucous membranes, according to the amount of inflammation secrete a glairy fluid, tough mucus, pus, or fibrin, or all thes secretions blended in different proportions, as may be observed i the course of a severe attack of catarrh.

319. Serious consequences result from the suppression of secretions or from the non-elimination of some of their important constituents The rapidly fatal result of acute atrophy of the liver is due to th suppression of the bile; and alarming symptoms of uræmia follow the retention of urea in diseases attended by suppression of urine.

320. What has been said of the similarity of structure in th several secreting organs will prepare us to view, without much su prise, the assumption by one secreting organ of the function belonging to another. This is termed *metastatis* of secretions. Th secretion of urine, or of a fluid nearly resembling it, by the ski and several of the mucous surfaces; of bile, by almost all th secreting organs, as in jaundice; of milk, by the skin and lungs and of the menstrual flux, by the vessels of the nose, lungs, an stomach, and from the surface of ulcers, are familiar examples o this vicarious secretion.

321. *The Veins.*—The veins are larger than the arteries. The are provided with longitudinal as well as circular muscular fibre in their elastic walls. The larger veins of the extremities ar provided with valves to prevent regurgitation, and give support t the blood which they contain.

322. The venous circulation is effected mainly by the impuls of the heart continued through the capillaries; but it is assisted b the contraction of the muscles of the extremities pressing the bloo towards the heart. The movement of blood in the great veins nea the heart is further accelerated by the act of inspiration, and partl by the suction of the heart in the act of dilatation of the ventricles.

323. At each inspiration the chest is enlarged by the descen of the diaphragm, and the elevation and tilting outwards of the ribs This tends to produce a vacuum, which is prevented by the entranc of air, of blood, or of both. That the motion of the blood in th large veins is thus accelerated is shown by experiments, and by th phenomena attending the admission of air into wounds in the large venous trunks. It has also been shown experimentally that a each systole of the heart a tendency to a vacuum exists in th pericardium, counteracted by the blood of the large veins distendin the auricles.

324. During expiration the blood is forced on by the lungs into the left side of the heart, and thus they are prepared to receive a fresh supply of venous blood from the right ventricle on the next inspiration.

325. When the right auriculo-ventricular valve allows of regurgitation, the blood flows back into the descending cava and jugular vein, causing a *venous pulse*.

326. Poisonous substances introduced into wounds permeate the capillaries, and soon find their way into the veins. Thus directly absorbed into the circulation they act very rapidly; hence the efficacy of ligatures applied above wounds, of the abstraction of the blood below the ligature, and of the application of cupping-glasses, which answer the double purpose of ligatures and evacuators.

327. *Absorption.*—This term is applied to the act of taking up into the circulation both fluid and solid matters. The capillaries may be regarded as general absorbents; the lymphatic vessels and that portion of them which is called the lacteal system as special absorbents; the capillaries taking up any surplus of fluid or formative matters that has been poured out in the process of nutrition and returning it to the general circulation, and the lacteals absorbing special nutritive material from the intestines.

328. Absorption is certainly effected in more ways and by more means than one. Living and dead tissues allow the passage of fluid and gaseous matters through them. This is called *imbibition*. If two gases are separated by a partition of moist bladder, both will permeate it till they are completely mixed. A gas, likewise, will pass through a moist bladder to mix with a fluid within it. This takes place in the lungs. Again, if a moist bladder be tied over the mouth of a vessel filled with water, a salt strewed over its surface will be dissolved by the water which permeates its pores. If a tube filled with a solution of salt or sugar, and closed by a bladder, be placed in water, the water permeates the bladder, mixes with the solution, and rises in the tube. At the same time, part of the fluid contained in the tube traverses the bladder in an opposite direction, and this interchange takes place till the fluids on both sides have become homogeneous. If the arrangement be reversed, so that the denser liquid is outside the bladder, and the rarer liquid in the tube, the liquid in the tube passes through the bladder, and gradually sinks to a lower level. These phenomena constitute the "endosmose" and "exosmose" of Dutrochet. Lastly, if a vessel made of vegetable parchment, or other permeable material, filled with a liquid consisting of animal, vegetable, or mixed matters holding some salt or metallic oxide in solution, be floated on the surface of distilled water, the salt or metallic oxide will traverse the membrane and lose itself in the water, the glutinous and uncrystallisable matters remaining behind. To this process, devised by Graham, the term *dialysis* has been applied. These processes of *imbibition*, *endosmose*, and *exosmose*, and *dialysis*, bear important parts in the work of absorption.

329. Matters in solution pass into the capillaries, and thence into the veins by the process of "endosmose," which goes on the more rapidly as the denser fluid (the blood) is no sooner diluted than it gives place to a fresh portion, and thus endosmosis into the blood takes place more completely, and goes on more constantly, than into fluids at rest. The alkalinity of the blood also aids the absorption.

330. This process of absorption is very rapid. In a part free from epidermis it is almost instantaneous; and minute portions of fluid, or of substances held in solution, may be absorbed, and distributed through the body in from less than half a minute to two minutes. In this way the rapid action of the more energetic poisons is explained; and it is only in rare instances, if in any, that a different explanation is needed.

331. The rapidity with which absorption takes place is shown by the passage of certain salts from the stomach to the kidney. In one experiment made by Westrumb, prussiate of potash was detected in the urine after two minutes; and in the history appended to a cast of the Epispadian Arburg, in the museum of King's College, it is stated that fluids may be seen trickling from the ureters into the bladder in from two to three minutes after they have been swallowed.

332. Several agents affect the rapidity with which imbibition and absorption take place. Of these galvanism is the chief. Thus, Foderé showed that when a solution of sulphate of iron is poured into the peritoneum, and one of prussiate of potash into the pleura, five or six minutes usually elapse before the two combine, but that this happens instantaneously when a slight galvanic current is passed through the diaphragm. Absorption is also promoted by friction. Again, distension of the vessels retards absorption, while depletion accelerates it. Hence the use of venæsection in dropsy. Absorption also takes place slowly in parts covered by dense membrane. Hence the absorbing power of the skin is much increased by removing the cuticle. Absorption takes place readily from the areolar tissue.

333. All these means of promoting absorption are used in the practice of medicine—*galvanism*, especially in the case of effusions into joints; *depletion* in dropsies of the skin and serous cavities; *abrasion* by blisters, followed by narcotic applications, in severe neuralgia; *friction* of the surface with nutritious fluids in cases of extreme emaciation, and with preparations containing mercury, iodide of potassium, &c., in the treatment of tumours and morbid growths; *subcutaneous injection* of narcotic solutions to relieve pain.

334. The absorption of fluids less dense than the blood is easily accounted for by endosmose, which takes place chiefly through the coats of the capillaries; and it is by this means, as just stated, that poisons find their way into the system. But the absorbent vessels also take up and restore to the circulation the serum which

in the processes of nutrition has exsuded through the parietes of the capillaries.

335. Of disordered functions of the absorbent vessels little is known. Formerly all dropsies were attributed to inaction of the absorbents, and such remedies were given as were thought to stimulate those vessels. It was obviously reasonable to suppose, that the functions of the absorbents, like those of other vessels, vary in activity at different times and under different circumstances; but as the capillaries have been proved to possess the power of absorption as well as the lymphatics, it is difficult to assign to each class of vessels its proper sphere of activity, whether in health or disease. A special absorbent function of the lymphatics appears, however, to be indicated in certain cases, such, for example, as the swelling of the axillary glands in injuries to the fingers, or of the inguinal glands in primary syphilis—results which are attributed, and probably with justice, to the absorption of the poison by the lymphatic vessels.

336. But whatever the share taken in the work of absorption by the blood vessels and absorbents respectively, there is no doubt that the part played by the absorbents in the production of dropsies has been much exaggerated. These arise in various states of system, and from various causes. Mechanical obstruction, venous congestion, inflammation, or debility, may give rise to an effusion of serum too abundant to be removed by the unaided, though still healthy, action of the absorbent vessels. If the obstruction be overcome, or venous congestion removed, or inflammation subdued, or the strength restored, the effusion ceases, and time alone is required to enable the absorbent vessels, whether capillaries or lymphatics, to take up the fluid which has been poured out.

337. The removal of solid diseased structures has also been attributed to the increased action of the absorbents, but perhaps without sufficient reason. Pressure, friction, and electricity, as well as mercury and iodine, are as likely to affect the small vessels which cause the morbid growth, as the lymphatics or capillaries which are instrumental in removing it—moderate pressure, by giving support to the vessels; stronger pressure, by still further diminishing their size; friction and electricity, by stimulating their coats and restoring their contractility; and iodine and mercury, by a local action on those vessels, whether through the skin, or more circuitously through the circulation.

338. In the case both of dropsies and tumours, the result would be the same, whether the small vessels, ceasing to exsude fresh fluids or solids, the absorbents, without increase of activity, remove by degrees that which has been effused; or the vessels, continuing to exsude, the absorbents are excited to a corresponding increase of activity. According to the first supposition, the cause is removed; according to the second, the effect is counteracted. The first supposition seems the more correct.

339. An account of the circulation would be incomplete if no reference were made to the peculiarities of the circulation through the *liver* and *brain.*

340. The liver differs from the kidneys in being supplied for the purpose of secretion with venous instead of arterial blood. It is true that the solid constituents of the urine are also secreted from blood which has previously been submitted to the action of the Malpighian tufts; so that a circulation analogous to that of the portal system of the liver exists within the kidney. But in the liver (and this is true also of the lungs) the secretions are immediately derived from the venous blood conveyed to it by the vena portæ, which is formed by the union of the veins of the stomach and intestines, of the spleen, pancreas, and gall-bladder, of the mesentery and omentum. With a slight and unimportant exception, it gathers the venous blood of the entire intestinal canal and of all the organs engaged in the work of digestion and conveys it to the liver, where the bile is secreted from it. The position of the liver, intermediate between the whole apparatus of digestion, on the one hand, and the right side of the heart and lungs on the other, explains its liability to congestion, from fulness of the portal system no less than from impeded circulation through the lungs.

341. The *brain* differs in its surroundings from every other organ. The viscera of the abdomen are contained in a yielding cavity with muscular walls; those of the chest in a cavity consisting partly of bone and partly of muscle, but allowing of considerable increase and decrease of size in all directions; but the brain is shut up in an unyielding bony cavity. All these cavities are air-tight; but that of the cranium alone is both air-tight and unyielding, at least in the adult. It follows, then, that while all the cavities of the body must always be full, the cranium alone must always contain the same amount of matter, for the atmospheric pressure of 15lbs. on every square inch of the surface of the body keeps the brain full, as it does a syphon. Now, the brain consists of a mass of nervous matter, supplied with blood by numerous vessels, and there is no reason to believe that this matter can suffer more compression than so much water; so that the strongest pressure which can be exerted upon it in the living body would probably not be rendered perceptible by the most delicate instrument. It is also an undoubted fact that the brain of a healthy man is not affected by a change in the pressure it ordinarily sustains. The descent in a diving-bell thirty-four feet below the surface of the water entails an extra pressure of 15lbs. on every square inch of the body, but the brain does not suffer. On the other hand, the ascent of a lofty mountain, or going up in a balloon, materially lessens the pressure on the body, and, consequently, on the cerebral vessels, and yet the brain is not affected. The inhabitants of some of the valleys among the Andes, who live as far above the sea as the summit of Mont Blanc, suffer only half the pressure the body has to bear at the sea level, and yet they enjoy health, bodily and mental. Again, the head of the infant suffers severe

pressure during birth, and the yielding cranium of the child allows of large accumulations of fluid, and yet the brain suffers nothing during birth, and often very little in hydrocephalus.

342. Mere pressure, then, does not permanently affect the functions of the brain, and yet when blood, or serum, or lymph are found on its surface or in the ventricles, or a tumour in its substance, or a larger quantity of blood than usual in some of its vessels, death is said to have been caused by pressure. This statement is inexact. The blood encroaches on or displaces brain substance, but there is no alteration of pressure.

343. When blood is poured out suddenly, as in the common form of apoplexy, the symptoms are often more strongly marked, though the quantity of blood is very small, than in cases of slow effusion, or slow growth within the cranium, in which the brain adapts itself by degrees to the changes that are going on. If, in cases of apoplexy, the quantity of blood actually effused seems too small to account for the serious disturbance of the functions of the brain, we must take into account the injury the texture of the brain itself has suffered, as well as the disturbance in the balance of the circulation that must have preceded and accompanied the rupture of the vessels. That this disturbance is in itself sufficient to account for the symptoms is evident from reported instances in which all the symptoms of apoplexy have been present without a single morbid appearance after death, except a disproportionate quantity of blood in the veins and sinuses.

344. Though the bony walls of the skull are unyielding, and the brain incompressible, it is obvious that enlargement of the blood vessels of the brain may result from diminution of the serum contained in the ventricles and the subarachnoid spaces; and that the intimate connection existing between the vessels of the brain and those of the scalp and face may become a source of relief and safety in sudden determinations of blood to the head. The flushed and turgid face of apoplexy, and the engorgement or rupture of the vessels of the scalp, in cases of death by hanging or strangulation, are familiar consequences of this vascular connection.

345. There are cases, then, in which the functions of the brain are greatly impeded, for which no other cause can be assigned but a want of balance in the cerebral circulation. The arteries contain scarcely any blood, while the veins are full; and it must be obvious that the brain thus imperfectly supplied is incapable of performing its functions, and manifests symptoms of oppression.

346. When the venous blood is less decidedly in excess, the functions of the brain, of course, suffer less; and these slighter disturbances in the balance of the two circulations probably account for the conditions of the mind waking and sleeping. On the other hand, if the circulation through the arteries be increased, instead of torpor we have excitement characterised by heightened sensibility, strong muscular contractions, violent delirium, mania.

347. The balance of the circulation may be disturbed in various ways. Pressure on the jugulars or diseases of the lungs which obstruct the ingress of venous blood into the right side of the heart, followed by sleep more or less profound, by coma, or apoplexy, are examples of such disturbance originating in the venous system; while the sleep that follows pressure on the carotids is an instance of disturbance originating in the arterial system. An arrest of the heart's action, by putting a stop at once to the circulation through the brain, produces syncope, which differs from apoplexy merely in degree, the one arresting every function of the body, the other only oppressing them. A very feeble action of the heart will be attended with a like result; for the arteries receiving little blood, and the change from arterial to venous blood still going on, the brain will contain but a small quantity of arterial blood, and must consequently perform its functions imperfectly. Hence the deep sleep, or coma, which often attends extreme debility, and the turgid condition of the veins of the head when death follows upon hæmorrhage or other exhausting cause. In these cases, however, an effusion of serum generally accompanies the turgescence of the veins.

348. *Sleep* comes on, for the most part, at night, and in the recumbent posture. As a general rule, the pulse falls towards evening, and is also less frequent in the horizontal than in the erect posture. These two circumstances, then, which favour a slow circulation, also favour sleep, and partly explain its occurrence. But other causes must be taken into account, such as the darkness and silence, the absence of the usual impressions on the senses, and the exhaustion of the nervous system, this exhaustion reacting on the circulation, and the circulation, in its turn, reacting on the brain. Sleep, then, may be considered as due partly to exhaustion of the nervous system, partly to the absence of impressions on the organs of sense, and partly to the languid cerebral circulation. Intense cold, another familiar cause of sleep, probably acts partly by causing an accumulation of blood in the internal organs, and partly as a direct sedative. A languid cerebral circulation will result on either supposition. In the cold stage of ague, the same state of circulation exists, and the same condition of brain.

349. Among other causes of sleep may be mentioned repletion, and a certain stage of intoxication, the one leading to the circulation through the brain of the products of digestion not fully converted into blood; while spirituous liquors act as a stimulant in a small dose, and as a narcotic poison in a larger one.

350. The cerebral circulation varies much with the posture of the body. In the erect posture, the heart, in sending blood to the brain, has to oppose the force of gravity; but in the horizontal posture it has much less resistance to overcome. Hence, when the heart is feeble and the system drained of blood, a sudden change from the recumbent to the sitting or erect posture may cause fatal syncope; and, on the other hand, a patient who has fainted in the *erect* posture is soon restored by being laid on the back. When the

head is lower than the rest of the body, the return of blood to the heart is opposed by gravity; the balance of the circulation is therefore destroyed, and coma is threatened. This unfavourable position, combined with sudden exertion, as in stooping to tie a shoe-string or pull on a boot, is an occasional cause of apoplexy.

351. The fact that the flow of blood to the head is favoured by the recumbent posture, suggests the proper position in the treatment of diseases of the brain. When there is a high arterial action, the head should be raised; when great exhaustion, the body should be laid horizontally. Such changes of posture are often attended with the best effects: thus instances are recorded in which pain, intolerable in the horizontal posture, has been at once removed by assuming the erect position.

352. When, again, we wish to produce a sudden and strong effect on the system by bleeding, or to obtain the greatest effect with the least expenditure of blood, the patient is placed in the erect posture, for the heart soon loses the power of sending the blood upwards to the brain, and fainting ensues.

353. Wakefulness, excitement, and delirium are the direct opposites of the states of drowsiness and sleep, and arise from an opposite state of the cerebral circulation. The degree of activity displayed bears a pretty exact relation to the rapidity and force of the arterial circulation, and to the strength of the patient. In the strong and robust, the outward manifestations in delirium are violent, and the muscles contract with great force; but if the strength is much exhausted, the loud talking of furious delirium is exchanged for low muttering: the violent muscular efforts for subsultus tendinum; and the distinct impressions on the senses for muscæ volitantes, and tinnitus aurium.

3. STRUCTURAL PHYSIOLOGY AND PATHOLOGY.

354. In the two previous chapters the human body has been examined: first, as a chemical laboratory, in which the functions of digestion, assimilation, and sanguification are carried on; and, secondly, as a hydraulic system, by which the blood is collected and distributed. It is next to be considered as an assemblage of minute structures, by which all its parts and organs are built up.

355. It has been already stated that the circulating system, consisting of arteries, capillaries, and veins, forms a continuous and unbroken, though most minutely divided, reservoir of blood in motion. The arteries serve as carriers of pure blood *to* the several tissues, the veins as carriers of impure blood *from* them, while the capillaries, the immediate agents of growth and nutrition, connect the two classes of vessels.

356. As the capillaries have no open mouths, the tissues can be nourished only by transudation through their walls. The fluid employed in this work of nutrition is the *liquor sanguinis;* in

other words, the blood itself less its red particles. As this fluid contains albumin and fibrin, and all elementary substances necessary to nutrition, it is obviously equal to the use thus assigned to it. At times, many of the capillaries transmit only this colourless liquid.

357. The liquor sanguinis exsuding through the coats of the capillaries, and brought into contact with the tissues, subserves the purposes of nutrition and growth, by being converted into cells (Schleiden and Schwann), or "germinal matter," and "formed material" (Beale).

358. According to the first-named authorities, all the tissues of the body are made up of cells, which consist originally of three distinct parts:—the cell-membrane, the nucleus, and the nucleolus. The cells are developed in a semi-fluid molecular substance derived from the blood, termed *blastema*. Fig. 8.*

Fig. 8.



359. Cells, which in their free state have the rounded form of Fig. 8, assume the hexagonal form from mutual pressure in a solid tissue, as in the more compact forms of the adipose tissue. In some structures, such as cartilage and tendon, there is an abundant intercellular substance or matrix, in which separate cells or small clusters of cells are imbedded. Cells are readily converted into fibres, Fig. 10 (*b*), by elongation, and into tubes by arrangement into lines and absorption of the opposed extremities. In the former case a fibrous tissue results, in the latter an organ such as a capillary, absorbent, or nerve fibre.

360. Cells readily multiply by splitting and budding, processes which may affect the whole cell, or only the nucleus. The latter may divide into many parts, the cell contents increasing and the cell membrane enlarging *pari passu*. Each portion of the divided nucleus grows, attracts to itself its due portion of the cell contents, the outer surface of which condenses into a membrane. The new cells thus formed may be set free by rupture of the membrane of the parent cell.

361. Cells also enter into the composition of some of the fluids both in health and disease. The white particles which float in the liquor sanguinis of the blood are nucleated cells; so also are the lymph globules; and the mucous and purulent secretions, thrown out from inflamed surfaces, contain mucus and pus-globules.

Fig. 9.



362. Suppuration consists in the growth of pus-corpuscles (Fig. 9), from the plastic exsudation (blastema) which is thrown out in the process of repair;

---

* Mammalian ovum in its several stages of growth.

while the more internal portion is developed into blood vessels and connective tissue.

The development of cells is well illustrated in the formation of malignant tumours, which as a rule are entirely made up of cells; and it is in these perverted growths that the greatest activity of cell production is witnessed. Fig. 10 (*a*) represents the *round-celled sarcoma* from a cervical gland; (*b*) the *spindle-celled sarcoma*, from a case of cancer of the uterus; (*c*) the *large-celled spindle-celled sarcoma* from a recurrent tumour of the scapula.

363. Structural changes may consist in a simple enlargement of parts and organs, such as the stomach and urinary bladder, from habitual distension; the heart from valvular disease, or pulmonary or systemic obstruction; the veins of the extremities from pressure on the large venous trunks; and the anastomosing branches of arteries as a consequence of the ligature of the main trunk. This is called *Hypertrophy*.

Fig. 10.



364. A second class of structural changes consists in defective *nutrition*, leading to a diminution in the volume or weight of the particular structure affected. This constitutes *Atrophy*.

365. The principal cause of *hypertrophy* is increased action; of which illustrations are afforded by the muscles of the athlete, by the heart and bladder when they encounter an obstacle to the evacuation of their contents, by the uterus during pregnancy, by the mammæ during lactation, by the mucous membrane of the bladder exposed to irritation from stone or gravel, and by the small arteries in organic disease of the viscera which they supply.

366. *Atrophy* arises from opposite causes; from disuse of parts, as of the muscles in the sedentary, paralytic, and bed-ridden, from obstruction to the flow of blood by ligatures, or from the operation of such powerful medicines as iodine and the salts of lead. Internal organs may also become atrophied from a cause described in § 372. Atrophy is marked by paleness of the parts affected, as hypertrophy is by increase of colour.

367. Hypertrophy and atrophy are sometimes limited to one constituent part of a texture. Thus bone may become unusually hard from the crowding of many earthy particles into the space commonly occupied by a few, or soft, from absence of the earthy matter.

368. A third class of structural changes consists of the effects of common inflammation. (§ 276, *et seq.*)

369. A fourth class comprises the effects of inflammation due to specific causes—to poisons introduced into the body from without by insertion or *inoculation*, by application to the skin, by inhalation through the lungs, or by admixture with food or drink. The local effects, direct and transferred, produced by wounds received in dissection, by syphilis, by mercury, arsenic, lead, copper, and phosphorus used in the arts, by the contagion of plague, typhus fever, and the exanthemata, and by drinking water or milk polluted by sewage, afford examples in point.

370. A fifth class consists of those which are brought about by causes acting within the body itself, originating in the blood vessels, and producing structural changes either by simple mechanical impediment or by a taint imparted to the blood. To the first class belong the fibrinous clots formed in arteries or veins, or in the heart itself, which may either continue in the spot where they were formed, or be transferred by the current of the circulation to some smaller vessel often very remote from the origin of the mischief, there to give rise to obstructed circulation and consequent structural change. To the second class belong those local abscesses in the liver, lungs, serous cavities, and joints which spring up as a consequence of the blood becoming the carrier of purulent matter formed in some venous trunk, or in the open mouths of veins wounded or otherwise exposed. The mechanical impediments of the first class are now familiarly known by the names of *thrombus* and *embolus*; the purulent deposits of the second class as *secondary abscesses*.

371. *Fatty Degeneration.*—All the tissues of the body, as well as the morbid growths which are developed amongt them, are liable to a fatty metamorphosis. The deposit of fat or oil globules in the secreting cells of the liver and kidney constitutes the condition known as fatty degeneration of the liver, and certain forms of Bright's disease of the kidney. The oil-globules are deposited in the epithelial cells of the secreting surfaces, and in the cellular tissue connecting the vessels. The annexed illustrations show the mode in which oil-globules are deposited in the cells of these organs. In Fig. 11, *a* represents healthy cells of the liver, free

Fig. 11.



Fig. 12.



l-globules; and, *b*, cells from a liver in a state of fatty degenera- n Fig. 12, *a* represents healthy epithelial cells of the kidney; cells loaded with oil-globules. In disease of the kidney, the ig tubes lined with cells containing oil-globules are expelled ie urine, so as to furnish evidence of the true character of the .

The first effect of these abnormal deposits is to increase ; of the deceased organs without materially affecting their ns; but as the disease advances the fatty deposits encroach and more on the vessels and gland structure, so as on the one o restrict the supply of blood, on the other to impair the ig power of the cells. Hence, in extreme cases, the organs l are rendered *anæmic*, and become quite unequal to their ns; and instead of increasing in size, they lose m failure of nutrition and the absorption of the ules, which were the first result of the disease.

Fig. 13.



But deposits of oil or fat are not limited to the ig organs: they take place also in the tissues. are laid down, for instance, in the muscular e of the heart, and enfeeble it by encroaching displacing the healthy muscular tissue. (See .)

Associated with earthy matter, as *atheromatous* deposits, fat ccurs in the coats of arteries, in subjects affected by similar of the liver and kidneys. These deposits are situate either nner coat, or in the fibres of the middle coat itself. Fig 14,

Fig. 14.



e corpuscles of connective tissue developed in the middle id converted into fatty sphericles. This change leads to nent of elasticity, and consequent dilatation of the artery. he coronary arteries are thus effected, the muscular substance heart becomes atrophied. These deposits are found to obey of symmetry, attacking equally and similarly the vessels sides of the body.

Atheromatous deposits in the coats of arteries often become t of ulceration, leading to perforation and sudden death from hage. When the ulcers make their way through the inner the arteries, they project from it as ragged uneven tumours, and when they occur in the aorta, are frequent causes of abnormal blowing and sawing sounds. In other cases the atheromatous spot becomes the nidus of calcareous deposit, in which case the vessel is said to degenerate into bone.

376. The small vessels of the brain are also subject to fatty degeneration. Oil-globules are deposited in the transverse muscular coat of the arteries, and in the corresponding coat of the veins. They may be seen under the microscope, either as "minute, shining, black-edged particles, like molecules of oil, thinly and irregularly scattered beneath the outer surface of the small blood vessels;" as globules of larger size more closely packed together; or in round or oval clusters, "like large granule-cells." The engraving (Fig. 15), from a paper by Sir James Paget, in the 'London Medical Gazette,' 1850, shows the microscopic appearance of small arteries under this form of degeneration.

Fig. 15.



377. This deposit of oil-globules destroys the even outline of the vessels, and, their proper structures gradually wasting, the smaller vessels dilate into minute aneurismal pouches. The proper vascular structure being thus weakened, softening of the brain ensues, followed by rupture of the vessels. This is one cause of apoplexy.

378. In certain conditions of the blood fibrinous deposits form on the inner surface of the arteries. Their most common seats are the valves of the heart and aorta, the larger vessels at the points where they give off branches, and the smaller arteries throughout their whole extent. They undergo induration and are often converted into gristly or bony tissue. Calcareous deposits, having the hardness of bone, are also of frequent occurrence in the heart and arteries as independent formations; that is to say, they take place where the structures have not previously undergone any other form of degeneration.

379. Recent researches have attached a new and unexpected interest to these valve-deposits. They occasionally become detached from the mitral valve, and, being borne forward by the current of the circulation, lodge in an artery of the brain, impede or stop the circulation through it, cut off the supply of blood to a part of the brain which becomes softened, and so give rise to hemiplegia. This formidable accident is now grown familiar to us under the name of *embolism*.

380. Another instance of fatty degeneration has been pointed out by Mr. Canton in the *arcus senilis*, or white line, seen just within the circumference of the cornea in many aged persons, in some who have passed the middle of life, and occasionally as early as 35 years of age. It is sometimes associated with fatty degeneration

of more important organs. Fatty degeneration of the ovum has also been shown to be a frequent cause of abortion.

381. It will be seen, then, that deposits of oil-globules or fat, whether in the cellular membrane uniting the vessels of secreting organs and in the coats of arteries, or in the epithelial cells of secreting membranes; whether continuing in their original form, and encroaching gradually on the healthy structure of the organs they attack, or becoming the seats of ulceration, or of calcareous deposit—play a most important part in the history of organic disease.

382. These fatty deposits may sometimes be confidently traced to imperfect oxygenation of the venous blood. Fatty degeneration of the kidney, for instance, is a common occurrence both in men and animals living in dark, filthy, and ill-ventilated places, where the air is unfit to support the process of combustion in all its vigour, at the same time that the constitution is enfeebled. Again, fatty degeneration of the liver and kidneys, atheromatous deposits in the arteries, and fatty degeneration of the heart, are often found associated in the spirit-drinker, who constantly introduces into his system a large supply of a liquid hydrocarbon, of which the gaseous elements attract the oxygen that ought to be devoted to the combustion of the carbonaceous matters derived from the food, and from the effete textures of the frame.

383. French epicures, by producing fatty livers in geese, through a combination of high feeding and heat, have given us another lesson as to the causes of this diseased condition—causes which find their combined application in the production of liver disease in Europeans who carry the dietetic customs of England to the hot climate of India.

384. Morbid growths generally may be divided into two classes—*non-malignant* and *malignant*. The first comprises *tubercle*, the second the several forms of *cancer*. Tubercular diseases generally fall under the care of the physician: malignant diseases more commonly into the hands of the surgeon. But both classes may attack either the internal or external organs of the body.

385. *Non-malignant Diseases.* — *Tubercle.*—This is deposited on the surface of membranes, or in the texture of organs. It has two different forms—the one, whitish-grey, semi-transparent, and dense; the other, yellow, opaque, and friable. The first is an earlier stage of the second. The grey tubercle is scattered through the lungs as miliary tubercles, or on the surface of serous membranes. The other variety is found in the same situations, as well as on the surface of the mucous membranes and in the substance of organs—in the follicles of the intestines, in lymphatic glands, in the liver, spleen, brain, uterus, &c. It assumes different forms in different situations. It may be collected in a distinct mass, or diffused through the tissues of an organ as a homogeneous cheesy matter; or it may be so thoroughly blended with the textures as to assume the very form of the organ attacked.

386. Tubercle consists of albumin, fibrin, gelatin, salts of soda and lime, and water, with a little fatty matter. Under the microscope *miliary* tubercle presents the appearance of molecular matter, and granules blended with nucleated cells, indistinguishable from plastic exsudation. The yellow variety also consists chiefly of granules, interspersed with minute spherules, irregular flakes, numerous oil globules, and a few perfect cells.

387. Tubercle is rarely deposited before birth; it is not common before the fourth year; is frequent between the fourth and fifth; less frequent, again, from this time till puberty; most frequent of all between puberty and the age of fifty. The lungs are its most common seat, so that after fifteen it is almost never met with in other organs without existing in them at the same time. The state of constitution (*tuberculous cachexy*) which leads to tubercular deposit may be either inherited or acquired.

388. Tuberculous matter is deposited slowly, without causing pain or inconvenience, and may remain quiescent for a very considerable period. At length, in the course of a common cold, or slight febrile attack, the tubercle begins to act as a foreign body, and sets up inflammation in the surrounding tissues. When this change takes place in the absorbent glands, serum and pus are poured out, and an abscess is formed, which slowly approaches the surface, bursts, and discharges the tubercle softened and broken down by the effused fluids. The walls of the abscess then generally contract and heal. Tubercles in the lung undergo the same change, the matter being expectorated; but sometimes they are converted into a chalky or earthy matter, and remain quiescent for the rest of life. When the deposit is in the mucous membrane of the larynx or intestines, the membrane ulcerates

389. Scrofulous subjects are not only liable to tubercular deposits but also to the chronic forms of inflammation, suppuration, and ulceration. The lymph effused, as the result of inflammatory action, is curdy, and wanting in consistence, the pus serous and flaky, and granulations, when formed, are large, pale and flabby. Pustular, scabby eruptions of the ears and mouth, discharging a thin acrid matter, enlargement, inflammation, and suppuration of the absorbent glands, especially of the neck, and a similar affection of the mesenteric glands, are also common in scrofulous children.

390. It has been shown experimentally that tubercular deposits may be produced at will in animals by confining them in close dirty places, and feeding them on unwholesome food.

391. *Malignant Diseases.*—These formations resemble tubercle in affecting almost all the organs of the body; in being frequently traceable to hereditary predisposition; and in their tendency to excite destructive inflammation of the parts attacked. On the other hand, malignant growths are distinguished by extending into surrounding textures, stirring up inflammation in them, and progressively destroying them; by following the course of the absorbents and attack-

ing the lymphatic glands; and by reappearing, after removal, in or near the cicatrix, or in some internal organ nearly connected by the absorbent system, with the part first attacked. Malignant growths may be all comprised under the general name of Carcinoma or Cancer.

392. *Carcinoma* (*Cancer*).—This term was originally applied to a malignant ulcer supposed to bear a resemblance to a crab (*καρκίνος*, cancer). It now comprises many changes of structure, differing widely in their physical characters: as scirrhus, or hard cancer; medullary, or soft cancer (with its most vascular form, fungus hæmatodes); epithelial cancer; melanotic cancer (characterized by the presence of pigment); osteoid cancer; and colloid cancer, characterized by the transparent or gelatinous substance of which it consists.

393. *Melanosis*.—This is an unorganised product, of a dark brown, dull bistre, or sooty-black colour, deposited in masses with or without cysts, or in patches on membranous surfaces. Sometimes it is met with in small points and occasionally it has been found liquid. Its most frequent seat is the liver; but it is sometimes found in the eye, skin, brain, lungs, kidneys, and other glandular organs. Its chemical constituents are albumin, fibrin, and the salts usually found in the blood, with a colouring matter abounding in carbon. When associated with malignant growths, the cells, instead of continuing free, are attached to the surrounding tissue. Deposits of a black pigment are often found in the bronchial glands and on the surface of the lungs both before and after birth. Such deposits are not malignant.

4. THE NERVOUS SYSTEM.

394. It is not possible to represent in a single diagram (such as that which, at p. 55, is used to illustrate the mechanism of the circulation) that complex arrangement of nerve-masses and nerve-fibres, known as the nervous system. The brain and spinal cord, shown in plan in Fig. 16, and the brain, shown

Fig. 16.



in vertical section in Fig. 17, are but the conspicuous parts of a whole which requires the sympathetic nerve for its completion, and of which the delicate terminations are to be found, accompanying the smallest vessels, in every organ and texture of the body.

395. The *brain*, of which the base, with the nine pairs of nerves arising from it, is shown in Fig. 16, and the vertical section, displaying the three leading divisions (cerebrum, cerebellum, and medulla oblongata), in Fig. 17, is the centre to which all sensations are referred, and from which all voluntary efforts originate. The *spinal cord*, with thirty-one pairs of nerves springing from it; for distribution to the trunk and limbs, may be said to occupy an intermediate position between these nerves and the brain; while the brain and spinal cord together form the joint source from which all the nerves of sense and of voluntary motion arise, from which all the mandates of the will are sent forth, and to which the intelligence of every sense is conveyed. From these centres, too, the nerves which control the movements of respiration and circulation take their rise. The *sympathetic* nerve, connecting itself with the several nerves of sensation and volition which spring from the brain and cord, presides over the functions of many of the organs most essential to life, is the source of some of those movements which are independent of the will, of many of those sensations by which life is preserved, and of the chemical changes peculiar to living beings. The spinal marrow, again, is the centre of union of certain nerves which form with it the excito-motory system, the seat of the reflex function. One set of nerves passing from the skin and mucous membranes convey to the cord certain impressions which, not passing onward to the cerebrum, are not perceived; while another set, arising from the cord, and being distributed to the muscles, give rise to contractions which, as the impulse does not originate in the brain, are involuntary. This excito-motory system and reflex function bear a very important part in all those movements which subserve the most pressing wants of the frame, such as the ingestion of food, and the supply of air in breathing. Lastly, the *cerebellum* has been shown to be the centre and source of a co-ordinating function, or harmonising control, exercised over those voluntary muscles which have come to act in unison for the

Fig. 17.



production of certain complex movements, such as those of standing, walking, working with the arms and fingers, speaking, and singing.

396. The following scheme, then, represents the leading functions of the nervous system, as well as the portions of the nervous centres by which they are performed:

(1) Sensation and voluntary motion, of which the brain is the centre.

(2) Co-ordination of voluntary movements, of which the cerebellum is the centre.

(3) The excito-motory, or reflex of which the spinal cord is the centre.

(4) The vaso-motor, of which the sympathetic or ganglionic system forms the principal portion.

397. (1.) The first order comprises all the nerves of *sensation* (the olfactory, the optic, the auditory, the gustatory, and the nerves of touch), and all the nerves of voluntary motion, with their common centre in the cerebrum. The greater part of the nerves of touch, or common sensation, and the nerves of voluntary motion form the external portions of the spinal marrow, and through it communicate with the brain.

398. (2.) Of the second order it must suffice to state that pathology and experiment combine to prove that the cerebellum, with the posterior columns of the spinal cord, which are downward prolongations of it, is the centre of a co-ordinating function voluntarily exercised over the motor nerves. The reason for associating the posterior columns of the cord with the cerebellum as the seat of this function are:—that they are not sentient, that motion is not destroyed when they are divided, but that by such division, muscular movements are thrown into disorder.

399. (3.) The third order consists of two sets of nerves, of which the one passes chiefly from the mucous surfaces to the interior parts of the medulla oblongata and spinal cord, and the other from those parts of the medulla and cord to muscles which are chiefly subservient to ingestion and egestion. Some fibres of the same order of nerves are probably distributed to the skin and voluntary muscles. That part of the spinal marrow to which these nerves run has been called the *true* spinal marrow, in contradistinction to those parts of it which are formed by longitudinal (commissural) fibres going to the brain. The motions due to this system are said to be *excited*, and the nerves are distinguished as *afferent* and *efferent*, *incident* and *reflex*. Through these nerves the mouth of the infant, when applied for the first time to the mother's breast, performs the movements of suction—movements which take place even in the acephalous infant; through them, too, the contents of the bladder and rectum are expelled; and foreign bodies discharged from the air-passages by sneezing and coughing.

400. The fourth order of nerves, or the ganglionic, consists (*a*) of the *internal* ganglionic, or sympathetic; and (*b*) the *external* ganglionic, embracing the ganglia on the roots of the fifth and eighth pairs of cranial nerves, and those on the posterior roots of the spinal nerves. These latter are supposed to preside over secretion and the nutrition of the external organs, and hence are called *trophic* or *excito-secretory* nerves. The former, the sympathetic proper, presides over the movements of the involuntary muscular fibre (of the heart, blood-vessels, intestines, &c.), and is therefore called *vaso motor*. This regulative action, as it affects the bloodvessels of the glands, results in an increased or diminished amount of secretion; and hence this system of nerves may be assumed to possess an "*excito-secretory*" function, so called.

401. The leading functions of the nervous system, then, are;—1, sensation and voluntary motion; 2, co-ordination of muscular movements; 3, excitements to action without sensation, and combined motions without volition; and 4, nutrition, secretion, and the motions connected with them. To these must be added the mental functions, which have their seat and organ in the cerebrum, and which will have to be considered in the next section.

402. The nerves consist of bundles of minute fibres, enclosed in sheaths. Each fibre is distinct through its entire course, and connected at its origin with a nerve vesicle. It remains unbroken till it arrives at the part to which it is distributed, when it begins to branch freely, and, uniting with similar branches of other nerves, forms at last a network of excessive tenuity, associated in some cases with special "end-organs."

403. Experiment has revealed to us the functions of the more important nerves, but has left much yet to be discovered. It has also thrown light on the laws that govern the transmission of nervous force, though it has left the nature of that force involved in the same obscurity which hangs over the real essence of light, heat, or electricity, with which last, however, it appears to have many points in common.

404. The effect of the division of a nerve is well known. If it be one of sensation, irritation of its branches or trunk below the point of division causes no pain: if it be one of voluntary motion, neither the will nor a stimulus applied to it above the point of division can cause the muscle to which it is distributed to contract. On the other hand, if the voluntary nerve be irritated below the point of division, or the sentient nerve above it, motion takes place in the one case, and sensation in the other; the sensation being referred to the parts to which the nerve is distributed. This law of sensation is strikingly illustrated in cases of amputation of a limb. Irritation of the cut end of the nerve is referred to the fingers or toes of the lost limb for years after its removal.

405. The fact that irritation of the trunk of a sentient nerve causes pain, not in the trunk itself, but in the parts to which its

branches are distributed, admits of practical application, and tends to destroy confidence in the division of nerves as a remedy for pains in the parts they supply. But the failure of this remedy in some cases has been explained by the discovery of some permanent cause of irritation, such as a tumour or spicula of bone, at the origin of the nerve.

406. Pressure applied to a sentient nerve causes pain in the parts supplied by its branches, but a firmer pressure produces pain in the trunk of the nerve itself. Severe injury to a nerve of sensation or voluntary motion destroys its power as a conductor of nervous force, but it affects the nerve itself only locally; for irritation of the part of the uninjured sensitive nerve connected with the brain causes sensation, and irritation of the part of the nerve of volition connected with the muscles excites muscular contraction. When, however, a nerve of motion is stretched violently through its whole length, it can no longer conduct the stimulus of muscular contraction, and sometimes the muscle itself loses its irritability, and cannot be made to contract by the most powerful stimulus.

407. Experiments on animals have brought to light other properties of the nerves which may be advantageously borne in mind by the pathologist. It has been proved that all stimulants applied to the nerves of the dead body act nearly in the same way, though with different intensity; but electricity and galvanism are the most effectual. The muscles cannot be made to contract by any degree of mechanical irritation applied to a nerve of sensation, while the slightest irritation of a nerve of motion gives rise to very strong contractions. Hence it appears that the motor nerves themselves can excite muscular contractions on the application of stimuli, independent of the brain and spinal cord. It has been further shown that this property may be exhausted by the continued application of a stimulus, to return after an interval of rest.

408. These experiments on dead animals are in accordance with the results of observation in the living human body. The exhausted nervous power must be restored by rest; the exhaustion of the entire frame repaired by sleep; and stimuli, whether mechanical, chemical, or electrical, cause the nerves to which they are applied to manifest their characteristic properties. Irritation of a nerve of common sensation causes pain; of a nerve of motion, muscular contraction; and the stimulus of galvanism excites in each organ of sense the sensation proper to it—taste in the tongue, a peculiar odour in the nose, light in the eye, a musical sound in the ear. Lastly, irritation of the origin of the pneumo-gastric nerve gives rise to a derangement of the digestive process manifested by the elimination of sugar by the kidney.

409. Heat, cold, and electricity are used as remedial stimulants. Both heat and cold cause the muscles to contract, and, when excessive, destroy their irritability. Cold water injected into an artery causes contraction in the muscles which it supplies; hence in uterine

hæmorrhage following delivery, cold water is injected with effect into the vessels of the still-adhering placenta, and cold suddenly applied externally or internally causes contraction of the uterus. The good effect of electricity and galvanism is manifested in some cases of paralysis.

410. Stimuli of great intensity destroy the excitability of the nerves, as happens with the optic nerve when a flash of lightning produces permanent blindness; and with the brain and spinal cord when it causes sudden death. Permanent paralysis may arise from the same cause. A weaker stimulus applied for a longer time may produce the same effect. Thus, snow-blindness sometimes follows the continued strong reflection of light on the retina, and paralysis of the muscles violent and long-continued exercise. Weaker stimuli or the same stimuli applied for a shorter period, impair the excitability of the nerves and cause fatigue. Thus the eye fixed for a long time on the same colour becomes insensible to it; and if the same set of muscles is kept in action only for a few minutes, as when we hold an arm extended, or stand quite still, we feel extreme fatigue, from which the slightest change of posture affords instantaneous relief.

411. Nervous exhaustion is always accompanied by severe pain. Thus, the long-continued application of the stimulus of light to the eye, or of cold or heat to the skin, gives rise to acute suffering; and prolonged action of the muscles in walking may occasion the most excruciating agony.

412. A stimulus, then, applied to the nerves of sensation or voluntary motion, produces, according to its degree and duration, destruction or exhaustion of the nervous power, accompanied in extreme cases by severe suffering; and the functions of the nerves are not restored till after rest proportioned to the exhaustion. The brain and spinal cord are the sources of the restorative influence; and motor nerves, permanently cut off from those centres, no longer excite muscular contraction.

413. Stimuli, therefore, first excite the nerves, and then exhaust them. But there are substances known as *narcotics* which have the effect of deadening the excitability of the nerves, and, in a concentrated form, of destroying it. If, for instance, the sciatic nerve of a frog be dissected, and allowed to hang in a solution of opium or morphia, the nerve is deprived of its power of exciting muscular contraction, and the leg of a frog steeped in a solution of opium, or of hydrocyanic acid, is similarly affected. The same effect is produced upon the heart by infusions of opium and tobacco; on the intestines by opium and ticunas; on the circular fibres of the iris by belladonna; on the hands by lead; on the lips and tongue by chewing monkshood; and on the fingers by the vapours of strong hydrocyanic acid.

414. Narcotic poisons introduced directly into the circulation, or indirectly through the stomach or other circuitous channel, also act

locally on the nerves. Thus, Müller, having divided all the vessels and muscles of the thigh of a frog, poisoned the animal with nux vomica, and found that the irritability of the sound leg was lost much sooner than that of the mutilated one. This loss of irritability in the sound leg can only be explained by the circulation through it of blood containing the poison, and the consequent local effect of the poison on its nerves; and it is by such local effect on the nerves most essential to life, or on the nerves supplying the heart or lungs, that narcotic poisons, after being absorbed and circulated with the blood, prove fatal.

415. Poisons introduced into the circulation act with greater force than when applied directly to the nervous trunks. Thus, strychnia applied in powder to the moist spinal cord of the frog excites no twitchings of the muscles, while the most violent contractions are produced by very small quantities absorbed into the blood. Other experiments may be adduced to prove that poisons circulating with the blood produce their effect chiefly by acting on the spinal cord and brain. Thus when an animal is poisoned by strychnia, if the nerves of one limb are divided, the spasms of that limb cease: and if the spinal marrow is cut through before an animal is poisoned with upas, the parts supplied by nerves from the lower portion of the cord are not convulsed. Narcotic poisons generated within the body itself also act on the nervous centres through the circulation. Thus urea, when it accumulates in the blood from loss of power in the kidneys to eliminate it, acts on the brain, and causes fatal coma.

416. The foregoing observations apply chiefly to the nerves of sensation and voluntary motion, which have the brain and certain portions of the spinal cord for their origin and centre. The sympathetic nerve and the excito-motory system yet remain to be examined.

417. The *Sympathetic.*—The functions of this nerve are threefold: it presides over the involuntary muscular fibre; it is the medium by which all impressions are conveyed from the parts to which it is distributed to the nervous centres; and it regulates the processes of secretion and nutrition in every part of the frame.

418. With regard to the first of these functions—that of directing the involuntary motions of the more important viscera—it has been ascertained that the parts which this nerve supplies continue to move long after they are separated from the rest of the sympathetic system, and even after their removal from the body, whether the motions are rhythmic, as in the heart, or continuous, as in the intestines: and that the contractility of these parts survives that of the voluntary muscles. The effects of stimuli applied to the sympathetic nerve are also more permanent than those of stimuli applied to the nerves of voluntary motion.

419. All the parts supplied by the sympathetic nerve are, to a certain extent, independent of the brain and spinal cord. Thus, the

heart will continue to beat long after the division of its nerves, after severe injury of the brain and spinal cord, and even after its entire removal from the body. That the spinal cord, however, does influence the contractions of the heart has been proved experimentally; and that the brain acts upon them is shown by the familiar effect of mental emotions. Certain excitations of the brain and spinal cord are doubtless conveyed to the sympathetic by means of the *rami intercommunicantes* existing between the two systems of nerves, and by the same channels impressions on the sympathetic may be conveyed to the spinal cord and brain, and excite either sensation or movement in parts to which the cerebro-spinal nerves are distributed.

420. The impressions made on the fibres of the sympathetic are not usually conveyed to the brain; in other words, they are not of the nature of sensations; but violent irritation may give rise to sensation in parts supplied by nerves from the sympathetic as well as in those supplied by cerebro-spinal nerves. When these last-named nerves are the seat of the irritation, the painful sensations are usually experienced in the extreme parts of the organs which they supply: thus we have itching of the nose and anus from worms in the intestines, and pain and itching in the glans penis from disease of the kidneys and bladder. But irritation in the intestines, or a disordered condition of the uterine functions, is a familiar cause of reflected sensations of a still more marked character, such as acute pains in the muscles of the chest and abdomen in hysterical females, accompanied by tenderness of the spine itself, and sometimes removed by remedies applied to that part.

421. The same irritation conveyed to the spinal marrow, and accompanied by tenderness there, may also be reflected through the motor nerves, and give rise to spasmodic seizures. Thus, intestinal irritation occasions convulsions, chorea, and tetanus, in infants and young children, and hysteria affecting the muscles of voluntary motion, but especially those of respiration, in adults. Vomiting and hiccough are also produced by irritation of the nerves of the intestines, kidneys, or uterus.

422. The sympathetic nerve has been shown to preside over secretion and nutrition, and consequently over the functions of the parts concerned in these processes: the minute vessels, therefore, and the arterial system generally, fall under its influence. Section of the sympathetic on one side of the neck causes permanent dilatation of the capillaries of the corresponding side of the face, and on irritating the trunk of the nerve they again contract. But although the organs of circulation are thus placed directly under the influence of the sympathetic, the occurrence of syncope and blushing through mental emotion proves that impressions on a sentient nerve may be reflected on the parts which it supplies. These reciprocal phenomena are due to the interchange of fibres between the two systems of nerves. The alteration in the size of the capillaries under the

influence of emotion and in inflammation has been already adverted to (§ 271 *et seq.*).

423. Such being the functions of the sympathetic, it follows that the circulation, both general and local, must be closely dependent upon the condition of this nerve. It is probable that the various states of circulation indicated by a pulse, ranging between a sharp, hard, and excited beat on the one hand, and a full, weak, compressible one on the other, are due to variations in nervous force transmitted by the sympathetic to the muscular tissue of the heart and arteries. It is also probable that the dilatation of the small vessels in inflammation is due to diminished nervous power in the sympathetic.

424. In the general, as in the local affection, we may have first the application of a stimulus, accompanied by increase of nervous force and consequent contraction of vessels, and then, as a necessary consequence, diminished nervous force, and a relaxation of vessels. This contraction of the vessels is not overcome by a reaction in the centre of the circulating system, but yields to that diminished contractility which follows as certainly upon increased action as blunted sensibility upon over-exertion of the organs of sense, and fatigue upon long-continued or violent action of the muscles.

425. The sympathetic nerve, as the name implies, is assumed to be the organ of many of those combined sensations, motions, and secretions which we call *sympathies*, by which we mean the reflection of impressions from one part of the nervous system to another and different part. It may be otherwise defined as reciprocal feeling or action between different nerves, and therefore between different parts, caused by reflex nervous action. The nerves of the surface and the central organs of the nervous system, for instance, react on each other; the affection of the central organs in fever causing the various conditions of the skin, and shocks to the skin exciting the brain and spinal cord. Again, cold water poured on the head restores the brain exhausted by long-continued inflammation; and dashed in the face or thrown on the chest, removes an hysterical or fainting fit, excites the nervous centres in cases of narcotic poisoning, and is the most efficacious of remedies in asphyxia.

426. Sensitive nerves sympathise with sensitive, motor with motor, and sensitive and motor with each other. The optic, the olfactory, the auditory, and the ciliary nerves of the two sides are affected at the same time and in the same way, and an affection of one side often leads to a similar affection of the other: inflammation of one eye to inflammation of the other. This sympathy between nerves of sensation supplying double organs extends also to nerves of different kinds and functions: thus, a strong light on the eye produces tickling in the nose; tickling the feet throws the whole body into convulsions; certain sounds put the teeth on edge; a tumour on a nerve may cause pain or spasms in parts of

the body not directly connected with it. To such phenomena the term *radiation of sensations* has been applied. Sympathies of motor nerves with each other occur in all associated movements; those of motor with sensitive nerves belong to the class of excited or reflected motions.

427. The sympathies of entire organs with each other are very important. They may be classed as follows:—1. Sympathies between organs having similar structure and function; as the different salivary glands, the heart and blood vessels, the stomach and intestines. 2. Sympathies between organs belonging to the same system: as the digestive, the urinary, the generative, the respiratory system, and the united respiratory and circulating system, the lungs and heart. Thus, vomiting attends the passage of a gallstone into the intestines. 3. Sympathies of important viscera with the central organs of the nervous system: as in the convulsions from teething, or intestinal irritation; the sick headache, caused by the presence of indigestible food in the stomach; and, conversely, the disorders of the stomach resulting from irritation or concussion of the brain. Epileptic fits often have their source in irritation of the stomach, uterus, &c. 4. Sympathies between organs not connected in any of the foregoing ways: such as the parotid gland with the testicle; the mamma with the uterus; the larynx, and the glands which secrete the hair, with the organs of generation. To this class, too, belong the sickness attending the passage of a renal calculus into the bladder, the rigors that sometimes follow the use of the catheter, or the pain of acute orchitis.

428. The *excito-motory system.* The following plan will exhibit the extent and importance of this system:—

Incident branches.	*Reflex motor branches.*	*Excited actions.*
I. Trifacial, arising from		
a. The eye-lashes. *b.* The alæ nasi.	The trochlearis The abducens } oculi.	Protective movements of the eyes and eyelids. Of the iris?
c. The nostrils. *d.* The fauces.	Minor portion of the fifth,	
e. The face.	Orbicularis Levator alæ nasi } from the facial	Facial respiratory movements. Sneezing, laughing, &c.
II. Pneumo-gastric from		
a. The œsophagus and stomach.	The pharyngeal plexus.	Suction and deglutition.
b. The mucous membrane of larynx.	The inferior laryngeal.	Closure of glottis, &c.
c. The bronchia.	The bronchial, &c.	Motions of air-passages in respiration.
d. The heart, kidney, and liver.	The œsophageal and cardiac.	Motions of gullet and stomach.
III. Glosso-pharyngeal, from base of tongue and membrane of pharynx.	The pharyngeal plexus of the pneumo-gastric.	Associated movements of tongue and pharynx in deglutition and rumination.

Incident branches.	*Reflex motor branches.*		*Excited actions.*
IV. Posterior spinal from			
a. The general surface.	The spinal accessory.		Movements of muscles of respiration.
b. The glans penis and glans clitoridis.	Diaphragmatic, Intercostal, Abdominal.	from the spinal.	Expulsion of fæces, urine, and semen; and of the fœtus.
c. The anus. *d.* The cervix vesicæ. *e.* The cervix uteri.	The sphincters, expulsors, ejaculators, Fallopian tubes, uterus, &c.	from the sacral.	Retentive movements of sphincters—of the cardia, of the valvula coli; of the anus, bladder, neck of uterus? and vesiculæ seminales?

Tone and irritability of the muscular system.

This table is compiled from data contained in Marshall Hall's work 'On the Diseases and Derangements of the Nervous System,' the excited actions being placed opposite to those divisions of the first two columns with which they are most obviously connected. The excited actions in the third column are not produced by irritation of the incident nerves of the first, but correspond more closely with the action of the reflex motor branches of the second. Thus, the incident excitor branches of the nostrils, when irritated, give rise not merely to the facial respiratory movements, but also to violent action of the muscles of respiration; and irritation of the bronchial incident nerves excites not only the muscular fibres of the bronchial tubes, but the muscles of expiration also, to the act of coughing.

429. The following table presents the pathology of the true spinal system; also in accordance with the views of Marshall Hall:—

PATHOLOGY OF THE TRUE SPINAL SYSTEM.

Diseases of the Incident Nerves.

I. Dental, gastric, and intestinal irritation in infants.	1. Crowing inspiration. 2. Strabismus, spasm of fingers and toes, strangury, tenesmus, &c. 3. Convulsions. 4. Paralysis.
II. Gastric, intestinal, and uterine irritation in adults.	1. Hysteria. 2. Asthma. 3. Vomiting, hiccough, &c. 4. Epilepsy. 5. Puerperal convulsions.
III. Irritation of textures supplied with nerves of common sensation.	1. Traumatic tetanus. 2. Hydrophobia, &c.

Diseases of the Reflex or Motor Nerves.

I. SPASM.	II. PARALYSIS.
a. Spasmodic tic. *b.* Torticollis. *c.* Contracted limbs, &c.	

Diseases of the Spinal Marrow itself.

I. Inflammation and other diseases.
II. Diseases of the vertebræ and membranes.
III. Counter-pressure, &c., in diseases within the cranium.
IV. Centric epilepsy, tetanus, &c.
V. Convulsions from loss of blood, &c.

430. As we have seen, the condition of the nervous system and that of other functions of the body reciprocally affect each other; but this mutual dependence is so strikingly displayed in the case of the circulation as to merit further consideration.

431. The effect of the emotions and passions, and of all violent exertions of the body, on the heart, is a matter of daily observation; and so surely does the circulation participate in every change of the nervous system that it becomes the best test of its degree and amount. Every violent exertion, or long-continued exercise of the muscles, strongly excites the pulse; and rest not only restores the number which it had before the effort, but still further reduces it. The various causes of excitement to which we are exposed affect the circulation in the same way; and it is the fatigue thus produced that causes the pulse to fall towards evening, to regain its frequency when the body has been refreshed by sleep. Precisely the same effects are produced by disease. Thus, in febrile affections the pulse during the height of the disorder is much more frequent than in health, but during convalescence falls many beats below its natural frequency, to regain it as health and strength return.

432. Another remarkable fact established by careful observation of the pulse is, that it is much more affected by all causes of excitement when we are in full possession of our strength, than when exhausted by fatigue. Thus all stimuli—muscular exertion, food, drink, and even mental application—have a much greater and more enduring effect on the circulation in the morning than at night.

433. But there are states of debility in which the heart's action is more frequent than in health. This occurs in an advanced stage of convalescence, when the patient begins to recover strength, and also in the decline of febrile affections, so long as any degree of fever continues. A greater degree of debility in the absence of actual disease is characterized by a very small and very frequent pulse; but such debility is rare, except as the consequence of diminution in the quantity of the blood, whether from hæmorrhage or from excessive discharges.

434. When nervous exhaustion is accompanied by local disease, whether functional or structural, that state of system exists to which we give the name of *irritation*. It occurs in slow convalescence from fever, when some local affection supervenes; as an immediate consequence of severe injuries in subjects weakened by disease or bad habits of life, and as a more remote consequence in sound constitutions, the injury itself producing in these the same nervous exhaustion which bad habits or previous disease had occasioned in those.

435. Another example of the action of the nervous system on the circulation is afforded by that temporary arrest of the heart's action known as *syncope*, or fainting, brought about, as it may be,

either by violent shocks, originating from without, as in accidents, or from within, as in violent emotions. Sometimes the heart is paralyzed by the shock, and death results.

436. The movements of the heart are indirectly influenced by derangements of the pneumo-gastric nerve; hence, when the functions of the centre in which this nerve originates are interfered with by cerebral effusions, or by injury of the medulla oblongata, the circulation through the lungs is impeded, and the action of the heart embarrassed. It has also of late been assumed that the cardiac branches of the pneumo-gastric have a restraining, or inhibitory influence on the action of the heart, but we regard the evidence on this point as unsatisfactory.

437. The effect produced on the nervous centres by changes in the circulation is more important even than those which the circulation suffers by alterations in the state of the nervous system. The exhaustion that follows strong nervous excitement has its counterpart in that produced by loss of blood, which causes syncope or death, partly by depriving the heart of its stimulus, and partly by paralysing the nervous centres.

438. In healthy persons loss of blood occasions debility proportionate to the loss; but in persons afflicted with local disease, or of a broken constitution, the debility reinforced by nervous excitement becomes *irritation*. The same effect follows when the quantity of the blood is diminished by profuse discharges, such as leucorrhœa or diarrhœa, or by the excessive and continued drain of natural secretions, as in menorrhagia, and in prolonged suckling. But the puerperal state, combining, as it does a local affection, nervous exhaustion, loss of blood, and a sudden disturbance of the equilibrium of the fluids, presents the highest development of this state of irritation.

439. In this condition of irritation, as in that originating in the nervous centres themselves, the circulation is affected, and the frequent quick pulse is easily excited by emotion, or by strong and sudden impressions on the organs of sense. The functions of the brain also suffer; and according to the degree of irritation, mental excitement, delirium, or mania occurs. The nervous influence conveyed to the muscular system betrays the same derangement by restlessness, jactitation, convulsions, and spasms in the voluntary muscles, and frequent or irregular breathing, laughing, crying, sighing, sobbing, and yawning, in those of respiration. The nerves of sensation also participate in the general derangement, and there are intolerance of light and sound, excessive sensibility of surface, and acute reflected pains in the walls of the chest and abdomen. The stomach likewise shows its sympathy with the nervous centres by nausea, vomiting, or hiccough.

440. Such are the phenomena of irritation, whether originating in the nervous system, or in the circulation. It is a state aggravated by depletion, but relieved by remedies that impart strength while they allay excitement.

441. The influence of the nervous system over muscular movements has already been alluded to, and two classes of movements have been described, the involuntary and the voluntary. In disease, disordered contractions both of the voluntary and involuntary muscles are of frequent occurrence; the voluntary muscles performing involuntary contractions, and the involuntary becoming the seat of spasm.

442. In a few instances some portion of the involuntary muscles has been brought by peculiarity of constitution, or by habit, more or less under the control of the will. Of this the well-authenticated case of Colonel Townsend, who possessed the strange faculty of stopping the beat of his heart at will, affords an example.

443. The most striking examples of involuntary actions of voluntary muscles occur in chorea, hysteria, epilepsy, catalepsy, convulsions, tetanus, and hydrophobia; of which diseases some depend on the direct influence of the nervous centres, but the greater part are examples of reflex action.

444. When the contractions abide in the same muscles, producing a state of continuous rigidity, they are said to be *tonic;* when the muscles are alternately contracted and relaxed, they are called *clonic.* Tetanus, hydrophobia, and catalepsy are examples of *tonic* spasm; chorea, hysteria, epilepsy, and convulsions (unless the term is qualified by such words as *rigid* or *tetanic*) are cases of *clonic* spasm.

445. In chorea and hysteria, voluntary and involuntary impulses are strangely blended; but the will exercises a different degree of control in the two cases. When the patient in chorea wills a movement, the involuntary action, mixing with the voluntary effort, causes grotesque distortions, which attempts at restraint only increase; but the movements of the hysteric patient are less grotesque, though more violent, and can often be restrained by a strong effort of the will.

446. Convulsions are examples of involuntary contraction, commonly due to reflex action; but when they follow the loss of blood, they probably arise from the suspension of the will. Thus, left to themselves, the stronger muscles prevail over the weaker. The flexors, which are the stronger, contract; the extensors, being put on the stretch, are in their turn brought into action, and thus an alternate or clonic contraction of the two sets of muscles takes place; but the flexors at length overpower the extensors, and if death ensue, the fingers and toes are found flexed.

447. The nerves of sensation, like those of motion, are subject to various derangements. Sensation may be lost (anæsthesia), or exalted (hyperæsthesia), or perverted (noseræsthesia). The loss of sensation which sometimes accompanies palsy is an example of anæsthesia affecting the nerves of touch; and amaurosis, of *anæsthesia of* the optic nerve. Intolerance of light and sound, and violent

hunger and thirst, are examples of hyperæsthesia. The strange pains and anomalous sensations of hysteria and hypochondriasis, are instances of noseræsthesia.

448. In some hysteric females there seems to be diminished sensibility of the nerve of touch, with increased sensibility of other nerves, the sensibility appearing to be withdrawn from the one to be concentrated in the other. Hence some of the strangest phenomena of nervous affections, including those induced by the manipulations of the mesmeriser and electro-biologist.

449. There still remain to be considered two functions closely dependent on the nerves, and originating in the changes which are constantly taking place in the fluids and textures of the body:—the generation of heat and electricity.

450. *Animal Heat.*—The heat of the body is due to the combination of the hydrocarbon of the food, or of the body itself, with the oxygen of the air. This combination occurs in the minute structures of every part of the system by means of the oxygen absorbed by the lungs. As the glands, the nerve matter, and the muscles are the parts chiefly engaged in chemical action, it follows that the temperature of these parts exceeds that of the rest of the body, and that the venous blood which flows from them is warmer than the arterial blood which passes into them. Thus, while the blood which leaves the liver is about 101° Fahr. (38·5° Cent.), that distributed to the body generally is about 98° Fahr. (37° Cent.), which may be taken as the mean average temperature of the body. Owing to the regulating influences of the skin and lungs, man, with suitable food, shelter, and clothing, is able to maintain this temperature, without appreciable variation, on any part of the earth's surface. A rise or fall of 2° is indicative of some morbid influence.

451. The temperature of those internal parts which are most accessible—viz., the mouth and rectum—is about 97½° or 98½° Fahr. That of the external parts is somewhat lower, and it has been observed to differ in parts near to and remote from the heart: thus, Dr. J. Davy observed that the temperature of the axilla being 98° F., that of the loins was 96½°, that of the thigh 94°, that of the leg 93° to 91°, and that of the sole of the foot 90°. The temperature of the blood was about 101°.

452. In disease great deviations from the standard are observed both in excess and in defect. Inflamed parts are found to have as high a temperature as 105° or 107°, and the heat of the whole surface may reach the same degree in high fever. In continued fever —specific or symptomatic—the temperature rarely rises above 105° or 106° Fahr. (41° Cent.), but 112° Fahr. (44·5° Cent.) has been recorded in some cases. Immediately after death a rise of from 1° to 3° is occasionally observed. On the other hand, in morbus cæruleus and in the cholera, the temperature has been observed as low as 77½° or 77° Fahr.

453. In most diseases the temperature bears a pretty exact proportion to the pulse; but remarkable exceptions to this rule have been observed, and notably in cases of fever. Thus, in fever a pulse of 45 has coincided with a temperature of 105°; and in hydrocephalus a pulse of 60 or 70, with a temperature of 100°.

454. *Electricity.*—The facts ascertained with regard to free electricity in man are the following:—No two parts of the body, excepting those that exactly correspond on the two sides, are in the same electrical condition: as a general rule the electricity is positive, but in the female more frequently negative than in the male; it is more abundant in persons of a sanguine than in those of a lymphatic temperament; greater in the evening than in the morning; greater when the temperature of the body is high than when it is low: it is increased by spirituous liquors, and reduced to zero in rheumatic affections. The free electricity of the body is generally of very feeble intensity; but in peculiar states of system sparks have been given out in great abundance. There exists in the nerves of all animals, independent of all mechanical and chemical actions in the body or external to it, a natural electricity, circulating in closed currents from the central parts of the nerve fibres which are in a − condition, to the surface which is in a + state. There is, in fact, an electrical antagonism between the transverse and vertical sections of the nerve. The same phenomena are presented in muscular fibres, but they are no doubt due to the nerves contained within them.

5. MENTAL PHYSIOLOGY AND PATHOLOGY.

455. Mental disorders more or less permanent, and more or less dependent on bodily disease, are of common occurrence, and some of the most difficult and responsible duties of the physician have relation to these. Hence the physiology and pathology of the brain claim his most attentive study.

456. Indeed the brain, the mind's instrument, built up and nourished as other structures are, deriving its supply of blood from the same centre, through the same intricate network of arteries and veins, is affected by every change in the composition of the blood, and in the balance of the circulation; and is subject to like functional and structural diseases with other organs of the body.

457. Between brain and brain, as between body and body, it is reasonable to expect important original and acquired differences: original differences in size, shape and consistency, and others more difficult to define, resulting from temperament, diathesis and idiosyncrasy, from age, sex, and race; and acquired differences, due to climate, residence in town or country, education,, occupation, and habits of life.

458. Many physical agents indeed, and especially excitement, fatigue, dissipation, intemperance, and inaction, act on the brain and nervous system more promptly and forcibly that on any other part

of the body. Many poisonous agents, too, chiefly affect the nervous system, and prove fatal by the functional disturbance to which they give rise.

459. Again, the brain is influenced by inaction, wholesome exercise, or over-exertion, according as education is neglected, promoted or enforced in early life, and in proportion to the necessity that exists for self-culture and labour in after life.

460. If, then, we consider the brain from this twofold point of view (as a constituent part of the body, subject to all the influences by which it is affected, and as the material organ of the mind developed by mental exercise), we shall be prepared to find the differences between mind and mind, in health and disease, equalling and even surpassing those already pointed out (§ 87) as existing between body and body.

461. The brain, as already stated (§ 395), is the centre both of intelligence and of action, to which all sensations are referred, and from which all volitions emanate. It performs these functions subject to the condition that the nervous communication in both directions (inwards from the organ of sense, and outwards to the muscles) shall be unbroken.

462. Each organ of sense consists of three parts: 1, an external apparatus on which the impression of the object is made by contact as in the senses of touch, taste, and smell, or by intermediate undulations or vibrations, as in the senses of sight and hearing; 2, a nerve transmitting this impression to the brain; and, 3, a portion of the brain itself set apart, as is probable, for taking cognizance of the impression thus produced and conveyed; and (as in the case of the two eyes) combining two distinct impressions into a single sensation. Each distinct apparatus of volition, such as the organs of speech and of locomotion, consists, in all probability, of similar constituent parts; 1, of a portion of brain in which the act of volition originates; 2, of a nerve or nerves by which the mandate is conveyed; and, 3, of a group of muscles by which the mandate, thus originated and transmitted is obeyed.

463. The parts of the brain to which the sensations are conveyed and from which the mandates of the will issue, are subject both to original deficiency and to the disabling effects of disease. Some persons, for instance, are unable to distinguish colours, others to recognise musical notes and intervals; and, on the other hand, a few, with perfect hearing and well-formed organs of speech, are never able to articulate. Blindness from disease of the parts of the brain to which the optic nerves join themselves, and loss of speech from apoplexy affecting the base near the origin of the hypoglossal nerves are familiar examples of the disabling consequences of disease.

464. In tracing the path of sensation from without to within—from the impression on the organ of sense to the part of the brain that takes cognizance of it—we come in contact, so to speak, with

two important operations, or faculties, of the mind, *volition* and *memory*.

465. Volition plays an important part, not merely in directing all those muscular movements by which we provide for our subsistence and communicate with our fellows, but also in perfecting the work of sensation begun by the organs of sense. Without that act of volition, which, when brought to bear on our sensations, constitutes *attention*, no external object could be either distinctly perceived, or recollected. On the other hand, without that power of reproducing sensations which constitutes *memory*, the more complicated acts of volition could have no existence. Hence, volition and memory appear to be closely linked together, to have their material instruments nearly connected in certain parts of the brain, and to be subject to simultaneous impairment by disease. But the will and memory are not limited in their operations to muscular movements and bodily sensations; for the will also directs and controls the operations of the mind, and the memory stores up and reproduces not sensations only, but trains of thought, processes of reasoning, complicated transactions, and the workings of emotion and passion.

466. The impressions made on the senses, in order that the mind may take cognizance of them, must therefore be accompanied by an act of volition known as *attention;* and whenever an object of sense becomes an object of attention, it is said to be perceived; in other words, sensation becomes *perception*.

467. Perceptions vary greatly in intensity in different persons, at different ages, and in different states of body; and the same difference exists in regard to that reproduction of perceptions which constitutes memory or recollection. In some persons, perceptions are reproduced with extraordinary quickness, vividness, and fidelity, while in others they can scarcely be reproduced at all; and one of the principal features of the mind in old age, and of the unsoundness peculiar to the aged, consists in the obtuseness of the perceptions, and the extreme difficulty with which they are recalled or reproduced. Perception and memory, indeed, bear a pretty exact relation one to the other. Objects best perceived are best remembered, and those that make little impression on the senses are not reproduced at all, or with great indistinctness.

468. In a few individuals, perceptions are reproduced with such vividness and fidelity that objects formerly perceived, are, as it were, painted on the retina, or transferred to other organs of sense by an effort from within. This perfect operation of memory, this power of depicting objects on the retina by the force of thought, is sometimes attributed to the imagination, and is termed *conception*. The poet Goethe had it during the whole of his life; some few persons have it during childhood.

469. When this transference of thought to the organ of sense is *involuntary*, it constitutes *illusion*.

470. Objects of sense, then, make impressions varying in intensity with the attention bestowed on them. When the mind is preoccupied by thought, external objects make little or no impression, and are neither observed nor remembered; and this preoccupation, or *absence of mind*, explains the eccentric acts of *absent* men, and some of the strangest actions of madmen.

471. By that effort of the will, then, which we call *attention*, we perceive objects with more distinctness, and reproduce perceptions with more facility. Now, sensations do not come into the mind singly, but in groups; and our knowledge and experience of objects are compounded of many sensations. Thus, an orange produces a sensation of size, shape, colour, weight, odour, taste; and it is by an act of the *will* alone, in other words, by an effort of *attention*, that we single out any one of these sensations for a separate contemplation. This separation of one sensation from another is called *abstraction*, and reasoning on sensations thus separated is *abstract reasoning*.

472. This power of abstraction is needed to control and correct a directly opposite faculty, or mode of action, of the mind—that of *association*. As attention separates and isolates sensations one from another, so does *association* combine, and cause to reappear together, or in quick succession, those sensations or ideas which either took place simultaneously or successively, or have in any way been previously conjoined.

473. This tendency of sensations and ideas to reappear in the connection or succession in which they had previously entered the mind, may be obviated by an effort of the will; but when such effort has repeatedly placed in combination or succession a number of sensations or ideas, this very combination or succession, though originally forced and voluntary, soon submits to the law of *association*, and a fresh effort is necessary to separate and disarrange them.

474. That repetition of sensations, thoughts, or movements, at first distinct, difficult, and voluntary, which at last transfers them from the dominion of attention to that of association, is called *habit*, of which, when this transference is complete, a man is said to become the slave.

475. By a faculty allied to, if not identical with, this of association, the mind also passes from one thought or recollection of an agreeable or of a painful character, to another of the same complexion.

476. Attention directed to different sensations or ideas in alternation or succession implies a faculty of *comparison;* and this, in a being possessed of free will, implies also a power of choice.

477. This faculty of comparison is essential to the acquisition of knowledge, as well as to the regulation of our actions. The impressions made on one sense must be compared with those made on

another: the eye must correct the ear, and the sense of touch the eye, in order that we may form distinct and precise notions of the properties of objects. The ideas reproduced by the memory must also be contrasted with those caused by objects present to the senses. In the unsound mind, this power of comparison is lost, and intrusive memories or passing fancies are taken for realities.

478. Without the exercise of this faculty of comparison it would be impossible to make a single step in art or science. Orderly arrangement and scientific classification are wholly dependent upon it.

479. The objects grouped by the aid of this faculty are either the same or similar; that is to say, all their properties agree, or only some. Hence, we are able to say of any one object contained in a group or class what we are able to say of every other, either in respect of all its properties, or of that one property which formed the basis of the classification. Now this twofold process of constructing groups of individuals, and then affirming of them that they possess the property or properties which first led to their being thrown into groups, is the secret of all our knowledge—of science in its highest and its lowest forms.

480. When the objects thus grouped are simple and exactly alike, and when the words used to describe or define them can be understood only in one sense, our knowledge is absolutely certain; but when they are complex and only similar, and our words less precise, we must content ourselves with knowledge less definite and exact. There is only one class of objects to which the first part of this description applies, and these objects are mere *abstractions;* that is to say, they consist of the universal relations, as distinct from the special properties, of matter, such as space, time, number, position, direction; with regard to which we can make assertions that can neither be doubted nor denied, and definitions that cannot be misunderstood: and *Reason*, availing itself of these *assertions* or *axioms*, and of these plain definitions, and using a language at once condensed and intelligible, has built up that vast and wonderful fabric of abstract knowledge known as the *mathematics.*

481. Every comparison of one object with another, or of one object with a group to which it belongs, results in an inference expressed or understood; and these acts of comparison, with the inference drawn from them, constitute a process of *reasoning.* So that *reason* may be defined as the faculty by which we draw inferences from comparisons.

482. Now every process of reasoning, however complicated it may seem, consists of two assertions, containing the elements of a comparison, and an inference. The first assertion is, that a *group* of objects possesses this or that *property* or *properties;* the second, that an *individual* object belongs to that group; and the inference is, that, as a necessary and inevitable consequence, this individual has the properties of the group to which it is asserted to belong. These two assertions are technically called *premisses* (major and

minor), and these, with the conclusion or inference, constitute the *syllogism* of the logician.

483. It is of the first importance to understand that when fallacies creep into a process of reasoning, they lurk in the premisses, from which the inference, or conclusion, is a necessary consequence: and this is true of the operations of the unsound, as well as of the sound mind. For there are forms of unsoundness in which the power of making just comparisons is retained; the defective reasoning consisting in erroneous premisses dictated by distorted perceptions, a perverted imagination, or over-excited feelings.

484. In some cases this power of drawing just inferences from false principles is seen in action. A patient who thinks that his food is poisoned, or that his body has been changed from flesh and blood into glass or butter, will not merely reason correctly on the false and incredible assumption, but will shape some at least of his actions in obedience to it.

485. There are, however, forms of mental unsoundness in which the reasoning faculty is so impaired, that even the formation of a simple syllogism is impossible. This happens in extreme cases of *dementia*, and in *idiocy*, or marked *imbecility*, in which the reasoning faculty has never been developed, even to the extent of comprehending or employing the simplest and easiest arguments. There is also a form of unsoundness characterised by complete *incoherence*, all the faculties being in a state of intense hurry and excitement, so that there is not, so to speak, breathing-time for the deliberate exercise of thought or reflection.

486. Some account has now been given of those organs and faculties by which we obtain knowledge; of the *senses* as its prime source; of *sensations*, as the impress of outward objects on the sensorium; of *perceptions*, as sensations recognised and strengthened by attention; of *conception*, as sensations without corresponding outward objects, reproduced by the intense operation of the mind itself; of *memory*, as the faculty by which sensations are less distinctly reproduced; of *attention*, as that by which sensations are strengthened, separated, or arbitrarily combined; of *association*, as the faculty by which sensations are linked together in their original or acquired relations; of *comparison*, as that by which sensations or ideas are contrasted; and, lastly, of *reason*, as the faculty by which conclusions or inferences are drawn from premisses.

487. By the aid of these faculties alone we might have accumulated knowledge, and created arts and sciences; learnt much of the properties of matter, and got some mastery over it; and we might have made some advances in civilization. But without that inventive, suggestive, anticipating, exaggerating faculty which we call *imagination* or *fancy*, hypothesis, theory, poetry, and high art would have been impossible, and several forms of unsound intellect unknown.

488. The province of imagination would seem to be to select and arrange, in new and arbitrary combinations, forms, colours, sounds, descriptive words and phrases, and even the simplest and most abstract facts of science, with a view to please, persuade, and amuse; to excite in the minds of others, by every kind of skilful combination and contrast, emotions pleasurable or painful. The most arbitrary of these combinations, when relating to matters of science, are termed hypotheses; when employed on trivial subjects, and directed to mere amusement, they are known as wit and humour. For practical purposes it may suffice to state that men exercise the imagination, or fancy, whenever, without intention to deceive, they make assertions incapable of proof, or unsupported by the concurrent testimony of other persons having the same opportunities of observation or experience with themselves.

489. Among the intellectual faculties, the imagination is the one which has the strongest affinity with the emotions and passions, for its operations, like theirs, are attended by excitement. It seems, indeed, to hold a middle place between the intellect and the passions; adding vigour and originality to thought, while it lends attraction to objects of desire, and gives intensity to every effort by which they can be compassed.

490. The powers or faculties of sensation, perception, conception, comparison, reasoning, and imagination, make up the sum of what are commonly known as the intellectual faculties. They may all be said to be dependent, primarily, on the senses, and to subserve the work of contemplation; but the faculties now to be considered lead direct to action. They are known as *passions* and *emotions*, as active and passive emotions, or as propensities and sentiments.

491. Between emotions and passions it is not easy to draw an exact line of demarcation; but it is usual to characterise *benevolence*, *veneration*, *hope*, *fear*, *grief*, *remorse*, as emotions; *lust*, *anger*, *ambition*, *vanity*, as passions. Although there is undoubtedly a distinction between them, yet they resemble each other in this—that they arise in the mind spontaneously whenever the object calculated to excite them is presented to it, whether from without by the *senses*, or from within by the *memory*. They do not spring from any process of *reasoning*, or from any exercise of comparison, but resemble instincts in the rapidity with which they spring up, the certainty with which they are directed to their objects, and the promptitude with which they act. When very strongly developed, or excited, they act even in persons of sound mind so quickly as to forestall the exercise of reason. Indeed *reason*, in the sense of the *reasoning faculty*, is in the very nature of things too slow in its movements to form an efficient check to passion, or a safe guide to emotion. To check the one and regulate the other is the work of *conscience*, an original and innate faculty, but one in some degree formed and moulded by instruction communicated in early life, and modified by the habits of society. Acting with [illegible] the quickness and precision of an instinct, it is the only

faculty prepared to offer effectual resistance to the feelings and passions.

492. As the intellectual faculties exist both originally, and as a consequence of habit and culture, in very different proportions in different persons, so also do the *emotions* and *passions;* and just as education gives acuteness to the perceptive and reasoning faculties, indulgence gives power to the emotions and passions, and restraint, on grounds of reason and right, supremacy to the conscience.

493 This sketch of the mind in its sound state would be incomplete if some allusion were not made to those first truths in which all sane men believe, without any conscious operation of the intellect. These are a belief in our own personal identity; in the real existence of objects of sense; in the uniformity of the operations of nature; and in the necessary connection of cause and effect.

494. Having now considered the faculties by which we gain and impart knowledge, the emotions and passions that move us to action, the conscience which counsels and restrains, and the first truths without a belief in which life itself could scarcely be preserved; our attention is naturally directed to certain states of the senses and of the mind, which, while they do not constitute mental unsoundness, often enter into that state as constituent parts, and serve to throw valuable light upon it. The first of these is *illusion* of the senses, among which *spectral illusions* are the most interesting.

495. All the senses, without exception, may become the seats of abnormal impressions—the eye, of bright or dark spots, and circles of colours; the ear, of humming, hissing, or blowing sounds, or distinct musical notes; the taste, of bitter, salt, or sour savours; the sense of smell, of unreal odours; and the sense of touch, of a feeling of local pressure, of heat or cold, of creeping, itching, pricking, and tingling. These false sensations are due to changes in the circulation through the brain, or through the nerve of sense.

496. Real objects are also apt to be exaggerated, or the reverse, in peculiar states of the organs of sense, or of the brain; and especially during slight febrile attacks, or in the early stage of convalescence from febrile disorders. Visible objects grow to enormous dimensions, or dwindle to the smallest size; and sounds seem lower or louder than they really are.

497. Like exaggerations often occur under the influence of fear, or other strong mental emotion. Good examples of this sort are supplied by two cases of theft. Sticks of a certain length were given to a number of suspected persons, with the assurance that the stick of the thief would grow by supernatural power. The culprit, imagining that his stick had actually increased in length, broke a piece off, and was thus detected. A farmer detected depredations on his corn-bin by making his men mix up a quantity of feathers in a sieve, assuring them that the feathers would infallibly stick to the hair of the thief. After a short time one of the men raised his hand repeatedly to his head, and so betrayed himself.

498. Another affection of the organs of sense allied to spectral illusions, consists in an extraordinary permanence of impressions. An instance in which the notes of a bugle haunted the ear nine months is mentioned by Abercrombie; and another, in which the spectrum of the sun impressed the retina ten years, is cited by Feuchtersleben from Boyle.

499. Impressions made on the senses may also be reproduced with great exactness after an interval of time. When Dr. Ferrier was about fourteen years old an interesting scene which he had witnessed during the day was, on entering a dark room, reproduced with great fidelity, and continued visible for some minutes.

500. From pictures on the retina, conjured up by an effort of the will, without corresponding external object, and from similar pictures the reproductions of vivid impressions previously made, the transition is easy to those illusions of the senses, and especially of the sense of sight, over which the individual affected by them has no control, and which have also no relation to objects previously perceived. Such illusions are of special interest; for, though quite compatible with perfect sanity, they are very common in cases of unsound mind.

501. Several cases of ocular spectra, so closely resembling real objects as to be distinguished only by the most careful exercise of comparison and judgment, are recorded in Sir David Brewster's 'Natural Magic,' and Sir Walter Scott's 'Demonology and Witchcraft.' A lady, whose case is related by Sir David Brewster, had the sense of hearing first affected, her husband seeming to speak to her, though not near her. Illusions of the sense of sight followed. She saw spectres of her husband, of a near relation in a shroud, of a deceased friend, and of a cat. But whether the illusion was of the ear or eye, she was quite aware of its real nature.

502. The woman in the red cloak, seen by Mr. Abernethy's patient, the ghastly spectre which appeared to Lord Castlereagh at night, and the figurantès in green who drove Sir Walter Scott's young man of fortune out of England, all belong to this class.

503. Many remarkable men have been subject to these false impressions. The list comprises the names of Luther, Oliver Cromwell, Pascal, Goethe, Cellini, and Swedenborg. The student worn out by application, the religious enthusiast exhausted by watching and fasting, Silvio Pellico in his solitary confinement, the sailors of the 'Medusa' suffering from mingled privation and excitement, the drunkard and the opium-eater, and persons under the influence of poisons of the narcotico-acrid class, have all afforded examples of spectral illusion.

504. Spectral illusions, too, are not rare in females at or about the change of life, when suffering from the group of nervous symptoms so common at that period (*mimosis inquieta*).

505. Spectral illusions may occur in either sex, and at any age *from* 4 to 80; and they are common in dreams, in delirium, and in

madness. So common are they in this last condition, that Esquirol estimates at 80 per cent. the proportion of the insane who are subject to illusions of one or other of the senses. The insane are also very subject to a modified form of illusion, to which no better name can be given than *Illusive Transformations*. When they affect the sight, a keeper may be transformed into a good or bad angel, or the Deity himself. When they affect the hearing, footsteps and other familiar sounds are changed to supernatural words of command.

506. Though illusions of the senses occur in persons both of sound and of unsound mind, they differ in this, that the madman believes in their reality, while the sane man soon learns their true character by the use of the other senses, or by some simple effort of comparison. There are, indeed, two ways in which these false perceptions may be corrected: 1, by confronting them with some real sensation, as in a case mentioned by Abercrombie, in which the lock of a door was seen through the spectral figure; and 2, by a comparison with the perceptions of other persons, as in Mr. Abernethy's case of the woman in red. A blind man subject to spectral illusions, was always struck with the circumstance that his figures moved about quite silently. The man of unsound mind neglects all these means of undeceiving himself, or cannot use them; or, if he entertain a doubt, he has some false reason to assign in favour of the reality of the supposed object of sense. A religious maniac, for instance, will think it impious to doubt.

507. Spectral illusions can sometimes be traced to thoughts or wishes which had previously passed through the mind. A patient recovering from a slight attack of fever, preceded by a severe family affliction, slept, during the heat of summer, in a room commanding a view of a large pond. One day he was seized with a great desire to bathe, and on the evening of that day a spectre appeared at his bedside, drew aside the curtains, and invited him to the water. This fact is rendered the more interesting by the circumstance, that though the patient's mind was so far recovered as to allow of his reasoning calmly about the occurrence, his mood of mind and expression of countenance changed in an instant, and he affirmed with great energy his determination to accompany the spectre should it appear to him again. A similar illustration of the occasional dependence of spectral illusions on the natural workings of the mind was afforded by an old lady, who, on two occasions, under the apprehension of the fatal issue of severe attacks of illness in her children, saw the whole paraphernalia of a funeral cross her room.

508. In that form of unsound mind known as *incoherence*, it is probable that illusions succeed each other with a rapidity only to be compared with the hurry of the thoughts to which the patient gives utterance.

509. Considerations of great interest and practical importance connect themselves with spectral illusions.—1. They are independent of the will; for they form the very staple of dreams in which the will is suspended, and they appear to the waking man not

merely without the will, but in spite of it. 2. They are sometimes the false impressions of dreams continued in the waking state. 3. They are not merely vivid reproductions of former impressions on the senses, but new combinations and creations. 4. They often occur in persons in no way remarkable for talent or imagination. 5. They are often dependent on such changes in the balance of the cerebral circulation as occur in sleep, or in comparatively trivial departures from health. In Nicolai they were clearly traced to the suppression of a hæmorrhoidal discharge, and the immediate excitement of a fit of passion. 6. They are not mere reflex impressions on the retina, originating in the brain, and conveyed back through the optic nerve: for they occur in blind persons, and in cases in which the optic nerve has been found so injured or diseased as to be unable to perform its proper function.

510. These facts have an obvious bearing on the phenomena of unsound mind. If a change in that part of the brain by which impressions on the senses are perceived, or of the whole brain, can conjure up illusions so like realities as to require a strong effort of the sound mind to distinguish them, it is reasonable to suppose that those parts of the brain which bear to thought, emotion, and passion, the same relation as these perceiving portions do to sensation, or the entire brain, as the case may be, may undergo such changes as shall generate involuntary imaginations having no foundation in fact, words without meaning, emotions springing from no sufficient cause, and passions admitting of no control.

511. The same impressions on the organs of sense which, when they occur to waking persons, are called illusions, form, as already stated, the very staple of our dreams, which have an air of reality, partly due to the vividness of the impressions, and partly to their not being corrected by the judgment. But this is true not only of impressions on the senses: it holds good equally of mental operations, which often do not suffer by comparison with those voluntarily and consciously performed in the waking state. In other words, that change in the state of the brain whatever it be, which in waking persons occasions *illusions* of the senses, gives rise during sleep to every species of mental *delusion*.

512. These two terms, *Illusion* and *Delusion*, are here contrasted; and ought not to be confounded. The distinction between them will be made clear by the addition of three words to each:—an *illusion* of the senses, a *delusion* of the mind. The word *phantasm* is a synonym of illusion. The term hallucination, being sometimes used in the sense of illusion, sometimes of delusion, ought to be allowed to fall into disuse. When an illusion of the senses continues to be mistaken for a real sensation, through inability to distinguish the one from the other, it becomes a delusion.

513. *Dreaming* is a state of mind in which illusions and delusions arise spontaneously while the senses are closed to the external world, and every voluntary mental effort is suspended, or imperfectly exercised.

514. Many dreams have for their exciting cause some bodily sensation, which becomes blended with fanciful accompaniments. A blister applied to the head suggests a dream of being scalped by savages; and a loud noise, a dream of being shot as a deserter. And, wonderful to relate, the sensation which really gives rise to the dream may seem the last link in a chain of events which would have occupied hours, days, or even years. Uneasy sensations may link themselves in like manner with imaginary scenes more or less appropriate. The most painful of the dreams due to these causes are known as *nightmares*, in which the oppression at the stomach is converted into a hideous personality, from whose weight and pressure there is no escape; and the uneasy sensations in the rectum or bladder are woven into the texture of a dream, in which the impossibility of obtaining relief plays a prominent part. Excitement of the genital organs also gives rise to a peculiar class of dreams. But these uneasy sensations sometimes occasion dreams which resemble the sensation itself only in the one particular of being painful or distressing. Thus, a diseased hip-joint may give rise to distressing dreams having no reference whatever to the pain or to the part affected.

515. Recent impressions on the senses, or transactions in which the sleeper has been engaged, also stimulate the fancy to the invention of connected histories of unreal occurrences. Thus, a patient suffering from obstinate colic, which had not been relieved by mechanical means, received an encouraging opinion of his case, fell asleep under the influence of opium, and dreamed that his doctor was an engineer to a railway in which he was interested, and had assured him that there were no engineering difficulties that might not be overcome.

516. In many persons of unsound mind the mental operations bear an obvious resemblance to this class of dreams. Real sensations are mixed up, as in dreaming, with unreal accompaniments; and real events passing in the world receive fanciful interpretations, or are forced into unnatural relationship with their own thoughts. Thus a speculating madman, when railroads, the Oregon dispute, and the China war, were dividing public attention, wanted to establish a company to run a railroad from Oregon to China.

517. There are many striking illustrations of the analogy between dreaming and madness in the painfully-interesting autobiography of a religious maniac. The cold air that blows on him as he tries to suffocate himself, in obedience to the spirits that speak within him, becomes the breath of his sisters cooling him, and encouraging him to go through with his task. The familiar sensation of water trickling down the back is converted into the crystal tears of his father, whose venerable countenance he sees bending over him. His head is shaved, and he grieves that he has "received the tonsure of the Roman Catholic priesthood, a mark of the beast." The jets of gas from the fireplace become the utterance of his father's spirit, trying to save him, but obliged to return to be

purified in hell-fire, from the contamination of his foul thoughts. The lowing of cattle conveys to him articulate sounds and sentences, and a creaking chair speaks to him in his father's voice.

518. Another convalescent from religious mania would look on his keeper at one moment as a man, at another as the Deity; and he habitually converted the man's footsteps into articulate words and phrases, and sometimes into commands to strike him. Believing it his duty to obey, he was surprised and confounded to find his violence resisted.

519. This analogy is also well illustrated by Dr. Gregory, in a case in which insanity passed, so to speak, into dreaming. The maniac, for a week after his recovery, was harassed during sleep by the tumultuous thoughts and violent passions, which had agitated him during his illness.

520. Dreams are sometimes accompanied by voluntary acts, and persons talk or walk in their sleep, or even commit acts of fatal violence in their half-waking state, in pursuance of the train of thought by which the mind was occupied.

521. Closely allied to this last-mentioned class of dreams is the state known as *somnambulism*, or *sleep-walking*, of which there are several varieties. In one form, the somnambulist merely goes through, with the precision of an automaton, a succession of acts to which he is accustomed in his waking state; in another, he performs feats, and runs risks in doing them, which he would shudder at were he awake, such as walking on the edge of a precipice, or on the top of a lofty building. Or he will accomplish some intellectual task which had baffled him when awake.

522. Between this state of somnambulism and some forms of unsound mind there are analogies worth noting. In both there may be a remarkable increase of talent, a complete change of character, a distinct and separate affection of the intellect and of the moral faculties—an intellectual and moral somnambulism, an intellectual and moral insanity.

523. The change of character which sometimes happens during this state is well shown in the case of the Carthusian monk, who, while awake, was remarkable for simplicity, candour, and probity, but walked almost nightly in his sleep a thief, a robber, and a plunderer of the dead; or that of a pious clergyman who, in his fits, would steal and hide whatever he could lay his hands on, and once even plundered his own church; or the case of the suicidal somnambulist mentioned by Ray, who escaped from his watchers, and was found suspended to a tree by his feet.

524. From dreaming and somnambulism the transition is easy to certain states of mind, due to temporary and transient causes, and closely resembling certain forms of unsoundness; namely, *delirium*, *delirium tremens*, and *drunkenness*.

525. *Febrile Delirium* is present in many acute diseases, in fever, and in inflammation of the internal viscera; it also follows severe injuries, such as burns, wounds, and fractures, and surgical operations, and it is a common effect of several poisons. There are two forms of febrile delirium. In the one the patient lies prostrate, utterly helpless, and muttering indistinctly. This form is present in the advanced stage of most cases of typhus and other fevers, and is known as muttering or typhous delirium. The other form, which sometimes attends the early stage of fever, is accompanied by great excitement, and often by great display of strength; and it so closely resembles mania in some cases as to lead to the patient being treated as a lunatic. This is violent or furious delirium.

526. From the first form of delirium the patient is easily roused, by loud speaking, to short efforts of attention, and to the performance of slight muscular movements, such as protrusion of the tongue; but he soon suffers a relapse. In some cases the attendants are able to discover that the mind is occupied by a dream, in which real personages play a consistent part; or they recognise an eager wish to carry on some business in which the patient was engaged before the disease set in.

527. *Delirium tremens* has some peculiarities worth noting. There are *three* leading effects of an abuse of spirituous liquors. The first is the common drinking fit, in which, when the excitement takes the shape of noisy anger, no mischief is done, because there is not power or steadiness enough in the muscles to commit the threatened violence. The second state has all the characters of a maniacal paroxysm, and is brought on in certain persons whenever they indulge to excess. It is a dangerous state of violent incoherence. The third form is sometimes the consequence of long habits of drinking abandoned for a time; but in the inhabitants of large towns, enfeebled by sedentary occupations, overwork, or want of proper nourishment, it may be the immediate consequence of a single debauch.

528. The characteristic symptoms of this state are given in Part 2.

529. Of the important and extensive subject of *unsound mind*, only the merest outline can be given in this place. There are three distinct states of mind demanding attention under this head: —the *undeveloped*, the *degenerate*, and the *disordered*. The first consists in imperfect mental development, generally coinciding with a small and otherwise defective brain, and often with a stunted or deformed frame, dating from birth, or manifesting itself in infancy. The second supervenes in later life in persons previously of sound intellect, and consists in loss of mental power, sometimes sudden, but more generally gradual. The third consists in disorder of the mind, often attended by violence, and characterised by illusions, delusions, and excited or distorted passions.

530. The first is known as *Amentia*, the second as *Dementia*, and the third as *Mania*.

531. (1.) *Amentia*, comprises two sub-classes, *Idiocy* and *Imbecility*, both of which imply original defect of mind, but the first a greater defect than the second. The line may be most conveniently drawn by placing on one side, as Idiots, all who, being otherwise of defective intellect, cannot be taught to speak, on the other as Imbeciles those who can. The class of imbeciles comprises those whose mental development has been arrested in infancy or early childhood.

532. The idiot, thus defined, is an imperfectly-developed being, with a mere animal existence, obedient to the simplest calls and impulses of nature, incapable of being taught, dependent on others for support, and able, at the best, to utter a few meaningless articulate sounds.

533. Imbeciles, on the other hand, have a certain amount of intelligence, understand what is said to them, and make themselves understood, remember common events, form habits of decency and propriety, and are equal to common household occupations, or to trades easily acquired. The more intelligent can be taught to read, write, and cipher, and to know the use and value of money; and they may even attain to a certain excellence in mechanics, music, and the fine arts; but they cannot acquire the amount of knowledge, or practical skill, or exercise the prudence in the conduct of affairs, or the control over their passions, common among persons of their own rank and opportunities. The feeble control they are able to exercise over their passions, coupled with the imperfect idea they have of moral and legal obligations, explains the great number of imbeciles found among the criminal population.

534. Imbeciles in the upper ranks of society, being raised above the temptation to crime, make their defect of character felt by every kind of eccentric and irregular conduct, especially by pecuniary extravagance, and by intemperance. Among the middle classes they furnish a full contingent of fraudulent debtors, swindlers, and forgers.

535. There is, in fact, a moral as well as an intellectual imbecility, counterparts of the moral and intellectual insanity presently to be mentioned; and a general imbecility, combining defective intellectual development with unbridled passions. Striking examples of moral imbecility, characterised by reckless extravagance, and an utter want of perception of the disgrace and wickedness of habitual debt, are to be found among the most eminent poets and prose writers.

536. The crimes of imbeciles are characterised by the same insufficiency of motive, the same folly in execution, and the same futile attempts at concealment, which mark other parts of their conduct.

537. Idiots and imbeciles afflicted with every variety of bodily infirmity and deformity, are to be found in certain unhealthy regions in all parts of the world, but especially in low damp spots, shut out from intercourse with neighbours, and subject to the evil of constant intermarriages. The evil reaches its highest pitch of intensity in deep alpine valleys, where the enlargement of the thyroid gland, known as *goitre*, is superadded to other deformities. The persons so afflicted are called *Cretins*, and their malady is termed *Cretinism*.

538. (2.) *Dementia.*—This, as the name implies, consists of a loss of intellect, sudden or gradual: sudden, as when it arises from severe mental shocks or injury to the head; gradual, as when it follows attacks of fever, of inflammation of the brain, or of mania, and when it attends the decay of strength in the aged (*senile dementia*).

539. Sudden attacks of dementia produce a state of mind nearly allied to idiocy, the attention being sometimes rigidly fixed on the train of thought which accompanied the shock; while those which come on gradually (attended, as they often are, by epilepsy, and slowly increasing paralysis) resemble more closely the different degrees of imbecility. Indeed, many cases of so-called dementia are cases of imbecility, not recognized as such till the capacity comes to be tested and strained by affairs of difficulty, or till some mental shock developes more completely the weak points of the character.

540. In this class of cases it is often easy to trace the leading feature of the unsoundness, like a thread, through the whole history of the patient. An habitual debtor at school becomes an extravagant youth, and an embarrassed man; as an incipient madman he thinks he has a divine mission involving a large outlay of money, and he dies in the full conviction that he is the Saviour of mankind.

541. (3.) *Mania.*—This also consists of several sub-classes. Those commonly recognized are *general mania*, involving the intellect, passions and emotions; *intellectual mania*, involving the intellect chiefly, if not exclusively; and *moral mania*, involving the moral nature to the exclusion of the intellect. There is another term in common use, especially in courts of law, namely, *lunacy*. It is sometimes wrongly used as a synonym of mania, and serves to remind us of a class of cases in which there are intervals of sanity and freedom from excitement. The more correct term for such cases is *mania with lucid intervals*.

542. Mania, whatever form it assumes, sometimes comes on suddenly as the result of mental shocks, intense mental excitement, severe injury to the brain, intoxication, or sun-stroke; but more frequently it makes its approaches gradually during a period often of several years: the period of *incubation*. This is a time of painful consciousness to the patient, and of fearful misgivings or mischievous misunderstandings to the friends. The bodily health suffers with

the mind, and the disease assumes its full development under the influence of some temporary excitement or disappointment.

543. *General mania*, or that form in which the intellectual and moral nature are simultaneously affected, may be described as a state of raving incoherence, combining a rapid succession of thoughts, often brilliant and original, with passionate excitement and intense restlessness. In many of these cases reference is constantly being made, in language of extreme violence and gestures of intense anger, to events that occurred at or about the time of the first seizure.

544. *General intellectual mania*, or that which attacks the intellect alone, is admitted to be of rare occurrence. There is, however, a form of it in which some one emotion or passion, such as pride, vanity, or love of gain, obtains such ascendency over the mind as to fill it with a host of intellectual delusions. Thus, patients in whom the passion of vanity is greatly excited, appropriate to themselves all the great intellectual performances which they have heard praised; those in whom pride is predominant imagine themselves a series of great men, or supernatural beings; and those in whom the love of gain is excited believe themselves engaged in extravagant and impossible speculations.

545. *Partial intellectual mania* or *monomania*, otherwise designated as *melancholia*, may be subdivided into two classes, the one comprising those cases in which the unsoundness is not connected with any bodily sensation, the other in which such sensation forms an essential part of the malady. These latter cases are sometimes known as *hypochondriasis*, sometimes as *melancholia*.

546. Cases of monomania, without uneasy bodily sensation, are frequent; as in men who think themselves secretaries to the moon, or objects of persecution, or subjects of plots formed against their lives. In most of these cases the attack is gradual, but, like one form of dementia, it sometimes dates from a sudden shock. Such was the case of Simon Brown, a dissenting minister, who, having killed a highwayman in a struggle, fancied ever after that the Almighty had deprived him of his immortal soul, and, stranger still, that the reigning monarch had the power of restoring it to him.

547. The second class of cases of partial intellectual mania, or those connected with some disordered bodily sensation, are very common, and are remarkable not less for the extreme improbability of the interpretation the imagination attaches to the sensation than for its pertinacity. These cases are common in women, and often assume the shape of imaginary pregnancy. Thus, a woman with hydatids in the womb thought herself pregnant by the devil; and two females suffering from adhesion of the intestines after peritonitis, believed, the one, that a whole regiment of soldiers fought and struggled in her belly, the other, that the same narrow space was the scene of frequent interviews between the apostles and evan-

gelists, the patriarchs and the pope. In men the imagination is not less active, nor the delusions less remarkable. Thus, one dyspeptic attributes his discomfort to a Caffre who got into his stomach at the Cape; others to men on horseback; and others, again, forgetting their sex, believe, like the Scythians of old, that they have been transformed into women, and even become pregnant.

This form of unsoundness bears an obvious resemblance to those dreams which consist in an uneasy bodily sensation dressed up with imaginary accompaniments.

548. Bordering on this form of unsoundness, but less easily traced to disordered bodily sensations, are such cases as those of the man who was afraid of passing urine lest he should drown the town; or of those who fancy that they have noses of wax or glass, or feet of straw; perhaps also the case of the woman who was afraid to bend her finger, believing the world to hang on it, and that of the gentleman who thought himself the Crystal Palace, and, when Parliament decreed its removal, accused it of wishing to destroy him.

549. In the least unreasonable forms of this strange malady, as when patients believe that they have frogs, toads, and serpents in their stomachs, cures have been effected by ingeniously contrived surgical operations; and their complete success proves that the uneasy sensations may have entirely disappeared, and yet the mental malady remain.

550. One circumstance connected with this class of mental maladies, and which applies more or less strictly to all forms of unsoundness, is the consistency with which the patient supports the part his fancy has assigned to him. If a man believes himself made of glass, he moves about with caution; if of wax, he avoids the fire and sun; if he thinks his head has been turned, he dresses accordingly, and if he fancies that poison is being put into his food, he will eat eggs or fruit which he has gathered, and drink only water which he has drawn from the spring.

551. Closely allied to this last form, in this as in some other respects, is that class of cases in which, in lieu of a painful bodily sensation, there is an uneasy state of mind, due primarily to some painful shock or disappointment; and passing into a belief that some person or class of persons, is conspiring against the patient. Luigi Buranelli and McNaughten were madmen of this class. Buranelli's delusion, however, was purely personal, while McNaughten believed himself an object of persecution by whole classes of the community. As these suspicions are commonly associated with that exaggerated estimate of the importance of certain bodily sensations which constitutes *hypochondriasis*, superficial or careless observers confound these cases with the more simple and harmless forms of that disease. But experience shows that these patients are very dangerous to society.

552. Intellectual disorder, occasionally attended by violent acts,

is a result of the epileptic fit. Almost always after the convulsion is over the mind is heavy and confused, with great somnolency; but in a few cases this condition is absent or remains for only a short time, and is followed by bodily activity and a mental condition resembling that of acute mania. In this state the angry passions are sometimes highly excited, and the patient becomes extremely dangerous.

553. The form of mania known as *moral mania* consists in "a morbid perversion of the natural feelings, affections, inclinations, temper, habits, and moral dispositions, without any notable lesion of the intellect, or knowing and reasoning faculties, and particularly without any maniacal hallucination." When combined with a like affection of the intellect it becomes *general mania*. It usually precedes the intellectual form, the delusions of the intellect springing out of a morbid perversion of the feelings. Let this case be taken as an illustration. A solicitor, who, for many years, had conducted his business to the satisfaction of his partners and clients, had during the whole of that time tortured an unoffending wife by acts which no author would dare to commit to writing. At length he had an attack of acute mania, and claimed to be the Deity, the Saviour, the King of England, the heir apparent, and other dignitaries incompatible with each other. From this attack he recovered, had a speedy relapse, showed signs of softening of the brain, and died imbecile and paralytic.

554. Moral mania, like intellectual mania, may be either *general* or *partial*. Of *general moral mania* Frederick William of Prussia, father of Frederick the Great, affords an excellent example, combining drunkenness, household tyranny, religious austerity, disgusting personal habits, and repeated attempts at murder and suicide, with an intellect by no means wanting in power or culture.

555. *Partial moral mania* consists in the excitement of some one passion or propensity to a degree beyond the control of the higher faculties. In many cases the intellect and conscience remain intact, leading to struggles of which it is impossible to exaggerate the misery. The forms of this partial moral mania generally recognized are *kleptomania*, or a propensity to theft; *erotomania*, or amorous madness (in females, *nymphomania;* in males, *satyriasis*); *pyromania*, or a propensity to incendiarism; *dipsomania*, or a propensity to drunkenness; *homicidal monomania;* and *suicidal monomania;* to which might be properly added, an irresistible propensity to lying and begging, unconquerable pride, irrepressible vanity, unappeasable gluttony, and that most horrible form of it, *lycanthropy*, or wolf-mania. Of these, kleptomania and pyromania are most common in females; but cases of all the forms may occur in either sex.

556. Partial moral mania, whatever its form, is a disease of slow growth; but there is a class of cases known as *instinctive mania*, in which the disease manifests itself suddenly, and most frequently as *homicidal monomania*. The history of such cases is very remarkable.

The victim of the insane violence is either a perfect stranger, or an infant incapable of offence, or a near relation to whom the homicide is tenderly attached. After the fatal act no attempt is made to escape, the deed is openly confessed, and its legal punishment courted and desired. But this insane impulse may assume a less simple form; the thirst for blood may be a chronic passion, and, like the uneasy bodily sensations and mental states just referred to, may clothe itself in the fantastic garb of monstrous intellectual delusions, as happened in the parricide Dadd.

557. The forms of mania, general and partial, intellectual and moral, present infinite varieties, and occasion the greatest perplexity to medical men when they are called upon to examine patients suffering from them, to give evidence concerning them, or to sign certificates. This perplexity is increased by the very nature of the legal questions which the physician is expected to answer—questions framed by men without experience of madness, and reasonably apprehensive of the injury which society might sustain if those who seem to be criminals should escape direct and speedy punishment; but addressed to those who know what madness is, who think that the truth has higher claims upon them than the safety of the public, or the satisfaction of those ignorant and thoughtless persons whose ready assent to received doctrines constitutes what is falsely called public opinion.

558. Mania, then, consists not in the loss of the mind's faculties, but in their perversion: the senses are the sport of illusions of which the patient cannot detect the unreality, and the mind of delusions of which he cannot perceive the inconsistency or impossibility; real sensations become, as in sleep, the materials of imaginary scenes; the realities by which the patient is surrounded are blended with illusions, and real persons made to undergo strange transformations in obedience to his delusions: so that many of his strange antics and acts of violence are mixed results of his illusions and delusions. It also appears that the state of the patient's mind is subject to great variation from various external and internal causes; that the transition from one state to another is often as rapid as thought itself; that he is capable of exercising, for considerable intervals of time, complete self-control, so as to conceal his delusions; that, though sometimes easily imposed upon, he often evinces, in carrying out his insane purposes, all the forethought and preparation of a sane man; that in his wildest excitement he is often so far conscious of what he is doing as to recollect it many years afterwards, his statements being confirmed by sane persons having cognizance of the facts to which he refers; and that he may be conscious of his state, and of the legal relations in which it places him.

559. In treating of the unsound mind, we have spoken of its various forms without connecting them with the diseased states of the body, or of the brain, out of which they often spring, and with

which they are generally connected. To give a full account of all that is now known on this subject would occupy much space. Suffice it then to remark that as the undeveloped mind, in its forms of idiocy and imbecility, is rarely disconnected with a small and ill-formed brain, and the degenerate mind as rarely shows itself without a corresponding degeneracy of the brain tissue (often in the form of softening): so the disordered mind is sometimes to be traced to remote functional disorder or injury (*e.g.*, a loaded rectum, or a thorn pressing on a nerve in the foot), and almost always connects itself with, or springs out of, excited circulation through the brain, as in cerebral inflammation, and in fever.

CHAPTER IV.

SYMPTOMS AND SIGNS OF DISEASE.

560. The symptoms and signs of disease of general importance are, the urine, the pulse, the heart's beat, and the respiration. Others, as the tongue, the sputa, the evacuations from the bowels, the attitude of the body, and the expression of the countenance, are more special. The symptoms and signs first named will therefore be treated in separate sections, together with the examination of the abdominal and thoracic cavities; the remainder will be treated of collectively. The contents of the present chapter may therefore be conveniently arranged as follows:—1. The Urine; 2. The Abdomen: 3. The Chest, and the organs of Respiration and Circulation; 4. The Pulse; 5. The Respiration; 6. Other Symptoms and Signs of Disease.

1. THE URINE.

Properties of Healthy Urine.

561. *Physical Properties.*—Healthy urine, recently voided, has the temperature of the body, is perfectly transparent, and of a light amber colour, has a peculiar, but not unpleasant odour, which disappears on cooling, a salt taste, and a specific gravity ranging from 1005 to 1033.

562. *Chemical Properties.*—Reaction, slightly acid, due to the presence of acid phosphate of soda, and free lactic acid; remains unchanged when heated to the boiling point, and yields precipitates with the salts of baryta and silver, indicating the presence of sulphuric and phosphoric acids, and of chlorine. Hydrochloric, nitric, and acetic acids cause a separation of lithic acid. Oxalic acid produces a slight cloud of oxalate of lime, and the free alkalies throw down the earthy phosphates. Tannin produces a slight cloudiness.

563. *Decomposition.*—After standing some time, a slight cloud of mucus forms, and slowly sinks. An unpleasant odour is soon perceived, and the urine takes on an alkaline reaction, and effervesces with acids. Carbonate of ammonia is formed by decomposition of the urea, and ammonio-magnesian phosphate with phosphate of lime are thrown down. Part of these salts entangled by mucus form a scum. Decomposition continuing to advance, the odour becomes fœtid; a blue or grey mould forms on the surface; and prismatic and feathery crystals of triple phosphate, and amorphous phosphate of lime, collect at the bottom, or cling to the sides of the vessel.

564. *Constituents.*—The *organic* constituents consist of urea, uric (lithic) acid, hippuric and lactic acids, salts of ammonia, and extractive matters, with small quantities of kreatin and kreatinin, and a trace of sugar. The *inorganic* consist of carbonic, hydrochloric, sulphuric, and phosphoric acids, combined with soda, potash, magnesia, and lime, with traces of silica, iron, and fluorine. These matters are dissolved or suspended in a variable quantity of water.

565. The variation in the quantity of water, and of the solid constituents due to age, sex, time of day, character of food, and amount of exercise, renders it impossible to give more than an approximate analysis of urine. The following represents its average composition:—

Water	950		
Urea	...	24	
Uric Acid	...	0·3	
Kreatin	...	1·25	
Kreatinin	...	1·20	
Hippuric Acid	...	0·25	
Phosphates	...	9	
Sulphates	...	6	
Chlorides	...	8	
	950	50	
Total		—	1000

566. *Quantity.*—The quantity voided in twenty-four hours varies in different persons, and in the same person at different times. The following are estimates of authors:—Haller, 49 oz.; Simon, 45 oz.; Keill, 38 oz.; Christison, 35 oz.; Prout, 32 oz. (30 oz. summer and 40 oz. winter); Rayer, 21 to 57 oz.; Dalton's experiments on his own person, 48½ oz. (November), 51½ oz. (June). Average about 41 oz. It may, therefore, be stated at about two imperial pints.

567. The quantity of urine in health is chiefly determined by the liquid taken into the stomach; but it is affected by many other causes. It varies inversely as the pulmonary and cutaneous exhalation; and is greater in winter than in summer, on cold than on warm days, in moist than in dry air; during the day than during the same number of hours at night, and in the morning than in the evening. It is also increased by excitement and anxiety.

568. In disease, also, the urine is increased whenever the pulmonary and cutaneous transpiration is suppressed, excepting only those cases in which all the secretions are simultaneously diminished by high febrile action. In the cold stage of ague, under strong nervous excitement, and in hysterical paroxysms, an increased flow takes place. This increase, which may amount to 30 or 40 pints daily, is not accompanied by any change in the solid constituents. But in other cases the increase of water is attended by increase of solid contents, or by the introduction of an abnormal constituent, such as sugar or chyle.

569. On the other hand, the urine is diminished by increase of the cutaneous and pulmonary transpiration, by profuse diarrhœa, and in cholera; by hæmorrhage; in dropsy; in many forms of acute inflammation; and in the inflammatory stage of fever. It is suppressed, or greatly diminished, in inflammation of the kidney, and under the operation of active irritant poisons.

570. The quantity of the solid constituents is also subject to considerable differences in healthy persons. The most important constituents, urea and uric acid, are at a maximum in men in the prime of life, less abundant in females, and at a minimum in old age and childhood. They are increased by exercise and diminished by rest, increased by animal diet, and diminished when vegetable food only is taken.

571. *Density.*—This ranges from 1005 to 1033, and averages 1020 or 1025. Simon assigns it a range of 1005 to 1030, and an average of 1012; and Dr. J. C. Gregory a range for the adult of 1005 to 1033, the greatest range in the same individual being 21, and the ordinary range 15 degrees. The average deduced from 363 experiments on 50 individuals was 1022·5, and from 5 individuals, whose urine was examined between 20 and 50 times each, 1025·2.

572. The urine is more dense in males than females; and the density increases from childhood to manhood, to fall again in old age; it is increased by hot weather, much exercise, free perspiration, a dry diet, nitrogenous food, and during sleep. It is diminished by cold, sedentary habits, a watery diet, vegetable food, and acids; also by alcoholic fluids. It is at its average in the morning on waking; falls considerably after breakfast; rises gradually after mid-day; sinks immediately after dinner, but in a few hours rises higher than at any other time: and in the course of the night gradually returns to its average.

573. The urine secreted after the digestion of food differs widely from that formed after fluids have been taken. The former, the "urina chyli," contains, according to Nysten, thirteen times as much urea, sixteen times as much uric acid, and four times as much saline matter as the latter, the "urina potus." It has also an alkaline reaction.

574. The density of the urine in disease may vary from 1001 to 1065; and as the density in health does not appear to fall below 1005, nor rise above 1033, it follows that any number below 1005 and above 1033 should be regarded as a sign of disease, and any number approaching either limit should attract attention. A less density than 1005 indicates an increase of water, with a decrease of some of the solid constituents. A greater density than 1033 affords a strong presumption of diabetes, though 1030—1035 has been observed in cases of increased secretion with excess of urea.

575. The *solids* discharged in the urine in twenty-four hours average less than an ounce and a half. In a vigorous healthy adult

male they may be taken at 2 ounces, or nearly 1000 grains. In disease they have been known to rise as high as 36 ounces, and to fall as low as 11 grains.

576. The *colour* of healthy urine is inversely as its quantity; when scanty it is high-coloured; when abundant, pale. In the morning it is usually of a darker tint than later in the day. According to Schunck the colour of the urine is due to two syrupy deliquescent yellow pigments which he has called *urian* and *urianine*. In disease the colour bears some proportion to the quantity; but it is materially affected by diseased products which mostly render it turbid. It may be milky from the admixture of chyle, mucus, or pus, or of the earthy phosphates in excess; deep yellow, or greenish yellow, from bile or cystic oxide; dark red or purplish, from purpurin, as in inflammatory diseases; yellow-red, as in hectic and the sweating stage of ague; and brownish or cherry-red, from the admixture of the red particles of the blood. The normal pigments above mentioned are very easily decomposed by strong acids and alkalies, and give rise to brown or blackish deposits of melanic acid.

Several substances taken with the food, such as rhubarb, madder, beet-root, corn-poppy, and log-wood, are also said to tinge the urine red.

577. The ingestion of either phenic or benzoic acids under certain circumstances leads to the formation of indigo-blue, which is metameric with benzoyl-cyanide (C_7H_5OCN). The benzoates of the alkalies, when strongly heated, yield benzoyl and phenyl-benzoyl (C_6H_5,C_7H_5O) showing the intimate relation between the phenic and benzoic compounds. The "black" urine observed in cases of poisoning by carbolic (phenic) acid is a case in point.

578. *Indigin* is an occasional constituent of the urine, and this explains the presence of indigo in this secretion, for by decomposition it yields indigo-blue, indigo-red, and indigo-brown; each of which is occasionally deposited from the urine.

579. The natural *odour* of the urine, best perceived when it is scanty and high-coloured, disappears with dilution. Excessive acidity intensifies the odour, alkalinity renders it sweetish and aromatic. It is altered by some kinds of food, such as asparagus; is sweet in diabetes mellitus; and has the odour of sweetbriar when it contains cystin; and that of violets after inhalation or ingestion of oil of turpentine, or food containing ginger. When the urine is retained in spinal paralysis, or decomposed in cystitis it assumes an ammoniacal and more or less putrid odour.

Examination of the Urine.

580. For microscopic examination we require a few conical glasses and a pipette. The deposits are allowed to collect for several hours at the bottom of the glass, a portion is then drawn off by the pipette, and a drop transferred to a glass slide, and covered with a fragment of thin glass.

581. *The specific gravity* may be roughly taken by the urinometer. If accuracy be required, the urine must be weighed in a 1000 or 500 grain bottle, or if the quantity be small, one of the capacity of 250 grains of water.

582. *Reaction.*—This is determined by *litmus paper*, the reddened paper being changed to blue by alkaline urine, and the blue litmus to red by acid urine.

583. The urine submitted to examination should be either an average specimen of the entire day, or the first voided in the morning. It should be protected by a cover, and care should be taken to avoid the introduction of extraneous matters. Those likely to be found in the urine are depicted in Dr. Beale's "Use of the Microscope in Clinical Medicine Illustrated."

The principal reagents and their indications are as follows:—

584. *Heat* throws down albumen, and also excess of the earthy phosphates, but it dissolves the urates of soda and ammonia. *Nitric Acid* throws down a dead-white precipitate of albumen; it precipitates uric acid after some hours, but when the mixture is heated dissolves it with effervescence; it also dissolves the oxalate of lime and the alkaline and earthy phosphates; it precipitates the colouring matter of bile of a green colour, but if added in excess, it changes it quickly, first to a dingy red, and then to a brown; it also detects urea in excess, when added to an equal quantity of urine (sp. gr. 1020, and above, at 32° Fahr.), by the formation of crystals of the nitrate. Moreover, it produces a cloudiness in urine containing certain essential oils. *Hydrochloric acid* precipitates uric and hippuric acid, and throws down the colouring matter of the bile of a green colour, whatever the quantity added. It also dissolves the oxalate of lime, cystin and the phosphates. *Acetic acid* produces a cloudiness in urine containing mucus; it dissolves the alkaline phosphates, and the phosphate of lime sparingly. *Sulphuric acid* added to warm urine containing sugar or albumen causes a deposit of carbon. *Ammonia* throws down the earthy phosphates as a white precipitate, and dissolves cystin. *Oxalic acid in solution* throws down a characteristic oxalate of urea. *Oxalate of ammonia* is used to detect the presence of lime. *Caustic potash* dissolves uric acid and the urates of soda and ammonia, and with the aid of heat disengages ammonia from the urate; it also tinges saccharine urine a dark-brown, and thickens purulent deposits. A *solution of sulphate of copper*, with excess of caustic potash, when heated with saccharine urine, gives a deposit of the red oxide of copper.

Fig. 18.



The following are the chemical and microscopic characters of the principal constituents of the urine in health and disease.

585. *Urea.*—This in excess gives a high specific gravity to the urine (1·030—1.035). If abundant, it may be detected by adding to a little urine in a watch-glass an equal bulk of strong nitric acid. The mixture, if kept in a cool place, deposits crystals of nitrate of urea. When the quantity of urea is small, the crystals depicted in Fig. 18 may be obtained by evaporating urine over a water-bath to the consistency of syrup, and when cold, adding an equal quantity of nitric acid of sp. gr. 1·25. Glittering crystals soon form, and usually convert the mixture into a solid mass.

Fig. 19.



586. If we substitute a saturated aqueous solution of oxalic for nitric acid, we obtain crystals of the form shown in Fig. 19. Urea may easily be separated from the nitrate by the following process:—dissolve the crystals in a little water, and add an excess of barytic carbonate, evaporate to dryness over a water-bath, and dissolve out the urea by means of alcohol. The crystals are long colourless prisms, and have a cooling taste like saltpetre.

587. *Quantitative estimation of Urea.*—Both the chlorine and urea may be determined concurrently by the ingenious process devised by Liebig, in which mercuric nitrate is employed as an index to the quantities of both constituents. A solution of this salt precipitates urea from its solution, as an insoluble white precipitate composed of 1 equiv. of urea and 4 of mercuric protoxide. But when sodic chloride is present, no urea is precipitated, until the whole of the chloride is decomposed, corrosive sublimate and sodic nitrate being formed. As soon as the last trace of sodic chloride is thus decomposed, the urea begins to fall. In conducting the analysis four solutions are required. 1. Mercuric nitrate No. 1, for determining the amount of chloride. 2. Argentic nitrate, to precipitate the chlorine. 3. Mercuric nitrate No. 2, to precipitate the urea. These solutions are of such strength that 100 grain measures of each of the former two correspond to 1 grain of sodic chloride; and 100 gr. meas. of the latter to 1 grain of urea. 4. A solution of baryta, composed of 1 volume of cold saturated solution of baric nitrate, and 2 volumes of a cold saturated solution of baric hydrate. The first step in the process consists in precipitating the phosphates and sulphates, by adding to 2 fluid ounces of the urine 1 fluid ounce of the baryta solution and filtering from the abundant white precipitate. Next add two or three drops of nitric acid to the filtrate so as to give it an acid reaction. We now take 225 gr. meas. of the filtrate (=150 of the urine) and ascertain the quantity of sodic chloride contained in this quantity. This is effected by adding the sol. mercuric nit. No. 1, until the mixture becomes a little cloudy (*i.e.*, until urea begins to fall), the point of saturation of the sodic chloride. Say 65 gr. meas. have been required, then 150 gr. meas. of the urine contain

0·65 gr. sodic chloride. Next take 450 gr. meas. of the filtrate and add twice as much of the sol. of argentic nitrate as that used of mercuric nit. No. 1—viz., 130 gr. meas. Pass twice or thrice through a filter, so as to separate the argentic chloride: then take half of the filtrate, $\frac{450+130}{2}=290$ — 150 gr. meas. of urine; and from this, now deprived of phosphates, sulphates, and chlorides, precipitate the urea by the careful addition with constant stirring of sol. of mercuric nitrate No. 2. The first drop of the latter causes a precipitate, and this increases until the whole of the urea has combined with the mercury. If excess of the mercurial solution have been added, a drop of the milky fluid gives an orange precipitate with solution of sodic carbonate. We must avoid this and get an indication of the exact point of saturation thus: place a dozen large drops of the sol. sodic carbonate on a white plate, and from time to time convey on the end of the stirrer a drop of the mixture, and let it fall on the drop of sol. of sodic carbonate. As long as any uncombined urea remains in the mixture, a pure white precipitate is formed, but immediately the slightest trace of free mercuric nitrate is present, the precipitate assumes a primrose tinge. Here we must stop and read off the burette. Say 190 gr. meas. have been required, then 150 gr. meas. of the urine contain 1·9 gr. of urea and 1000 gr. meas. 12·7: for 150: 1000: 1·9: 12·7. For the analysis we shall want two or three burettes of about 500 grains capacity graduated into grain measures; a pipette to deliver 225 grains; and a second pipette graduated into 100 grain measures. These, and the standard solutions can be obtained from Mr. Griffin, Garrick Street, London.

588. *Uric Acid.*—There is sometimes so much uric or lithic acid in the urine that it separates on cooling, as a crystalline deposit. It is occasionally voided as gravel, and is a frequent constituent of urinary calculi, having every tint from light yellow to deep orange-red, or dark brown: hence the familiar names of "yellow and red sand." Occasionally it is quite colourless.

589. The urine which yields these deposits has generally a high colour, an acid reaction, and a specific gravity of 1·020 or more. The acid may be separated from urine which yields no deposit on cooling, by adding hydrochloric acid in the proportion of one or two drachms to six or eight ounces. The mixture, after standing in a covered vessel for twenty-four to forty-eight hours, yields a red or reddish brown deposit of uric acid.

590. The crystals also vary in size from grains visible to the naked eye, and known as *cayenne pepper grains*, to a fine sand, in which the characteristic forms of the crystal are only to be detected under high powers of the microscope.

591. Uric acid is insoluble in hot and cold water; is not redissolved when the urine is heated; is very soluble in caustic potash, and is precipitated colourless from this menstruum by the addition of an acid in excess; it is dissolved by nitric acid with effervescence,

and on evaporation to dryness yields a red or pink residue, which is changed to a rich purple (murexide) by vapour of ammonia. This is the appropriate test of its presence. Heated on platinum-foil uric acid burns with an odour of bitter almonds; when heated on porcelain it yields a crystalline sublimate to a superimposed disk of glass.

592. Under the microscope uric acid displays a great variety of forms. Its primary form is rhomboidal; but the angles are usually rounded off, forming lozenges; sometimes they are contracted, forming square plates or cubes; sometimes they are very acute, forming needle-like prisms (see Fig. 20). All these forms occur both separately and in stellate groups. The effect of albumin and other matters in modifying the form of these crystals has been carefully studied by Dr. Ord (St. Thomas's Hospital Reports, 1870, p. 335). The quantity of uric acid excreted varies from 3 to 15 grains and remains pretty constant under similar circumstances. Dr. Roberts ("Urinary and Renal Diseases," p. 63) found that the quantity secreted between the second and fifth hour after dinner is three times as great as at any other period. Mr. W. Vernon Harcourt gives the following as the best mode of estimating the quantity of uric acid: Neutralize a fourth part of the daily urine with hydrochloric acid, if alkaline; with carbonate of soda, if acid; and evaporate to 12 drachms: add a mixture of 12 drachms of alcohol and 3 drachms of hydrochloric acid. After the uric acid has been precipitated, pour off the clear fluid, throw the deposit on a weighed filter, and wash it, first with alcohol, and then with a mixture of equal parts of acetic acid and water; dry and weigh. Dr. Pavy has lately introduced a method which consists in the power which uric acid possesses of decolourizing a solution of ammonia—cupric sulphate. So much of a standard solution of the latter corresponding to a grain of the latter.

Fig. 20.



593. *Hippuric Acid.*—This, which abounds in the urine of herbivorous animals, exists also in human urine. It may be obtained by evaporating a few ounces of urine to the consistence of syrup, and adding hydrochloric acid in excess. A mixture of uric and hippuric acids is thrown down. This deposit having been washed in cold water, is boiled with alcohol, which dissolves

the hippuric acid. On evaporating the spirituous solution, the acid is deposited in long colourless prisms.

594. The *Urates* or *Lithates.*—These deposits are often very abundant, generally falling as the urine cools, but occasionally they are voided with it. They are rarely quite white, sometimes bright red, and they may assume any tint from light yellow to dark brown. They are soluble in warm water and in warm urine. Alkalies dissolve them, and acids in excess thrown down crystals of uric acid, which when treated successively with nitric acid and ammonia, yield the rich purple murexide.

595. *Urate of Ammonia.*—This salt is sometimes diffused through the urine, so as to give it the ropy appearance of muco-pus; in other cases it forms a whitish or a reddish-brown deposit, known as the *lateritious* or *brick-dust* sediment. Its microscopic form is shown in Fig. 21, the ultimate particles being mere molecules.

Fig. 21.



Urate of ammonia shares with the other urates the properties enumerated in § 594; but it has the characteristic property of giving out ammonia, when heated with liquor potassæ. The granular deposit known as urate of ammonia often consists of the mixed urates of soda, ammonia, lime, and magnesia.

596. *Urate of Soda.*—This is rare as an unmixed deposit, but is sometimes met with in gout, and in fever patients treated with carbonate of soda. It has the chemical properties common to the urates. It tinges the outer flame of the blowpipe yellow. Under the microscope it presents the form seen in Fig. 22 and in Fig. 23, *a*; *b* being a rare variety (Beale).

Fig. 22.



Fig. 23.



597. *Oxalate of Lime.*—This is rarely seen as a granular deposit, but is often diffused through the urine as minute octahedral crystals. It is a common constituent of urinary calculi, and the material of the "mulberry calculus." It is insoluble in water, liquor potassæ, and acetic acid; but soluble in nitric acid, and converted at a dull red heat into *carbonate of lime*, identified as such by dissolving with effervescence in acids.

598. The crystals of oxalate of lime assume three forms: as regular octahedra, appearing like a square plate with a cross of light (Fig. 24); as sharp elongated octahedra; and as dumb-bells

(Fig. 25). The first is the usual form. The crystals are commonly so minute as to require the higher powers of the microscope. Both octahedra and dumb-bells are sometimes found adhering to casts of the urinary tubes. Octahedra so adhering are shown in Fig. 39, p. 136.

Fig. 24.



Fig. 25.



599. The *Phosphates.*—Phosphoric acid exists in urine in combination with alkaline and earthy bases, as, 1. Ammonio-phosphate of magnesia, or the triple phosphate. 2. Amorphous phosphate of lime, or tribasic phosphate. And 3. Crystallized phosphate of lime. These deposits have the following properties in common. They generally occur in neutral or slightly-alkaline urine; are white unless tinged with blood, are not dissolved by heating the urine which contains them, but are, on the contrary, thrown down by heat; are soluble in weak acids, but insoluble in water, in ammonia, and in liquor potassæ. The phosphate of lime is less soluble in acids. Heated separately, they fuse with great difficulty; but when combined in nearly equal proportions, the phosphate of lime and the triple phosphate fuse readily, constituting the *fusible calculus.*

600. (1.) The *Ammonio-magnesian Phosphate*, or *triple phosphate.*—On adding a few drops of ammonia to healthy urine, it becomes turbid, and deposits the triple salt combined with phosphate of lime. The same result may happen from the development of ammonia or its carbonate when the urine is retained in the bladder for a long time, as in cases of paraplegia, or allowed to stand some hours out of the body. It is also common in diseased states of the mucous membrane of the bladder. The triple phosphate may present itself in any of the following forms:—*a.* As a white crystalline gravel. *b.* As a thin iridescent film on the surface of the urine. *c.* As a dense white deposit closely resembling mucus. *d.* In masses or ropes resembling muco-pus. The common form is

Fig. 26.



Fig. 27.



that of brilliant triangular or four-sided prisms with truncated ends (Fig. 26); as deposited from the urine by ammonia, it takes the stellar form (Fig. 27).

601. (2.) *Amorphous Phosphate of Lime* occurs as granules or molecules, like the amorphous lithates. They are sometimes found adhering to crystals of triple phosphate.

602. (3.) The *Crystalline* or *Bibasic Phosphate* was first recognized by Dr. Hassall. It occurs in the form of stellar clusters of long prisms with a square base (Fig. 28).

Fig. 28.



603. *Cystin.*—This curious substance is characterized by a large proportion of sulphur. It is not found in healthy urine, and is a rare product of disease. It constitutes a form of urinary calculus, but very seldom exists as a deposit. The urine which contains it is usually of a pale yellow tint, of low specific gravity, and of an odour resembling sweet briar. The deposit of cystin is white, or of a pale fawn colour, distinguished from white urate of ammonia by not disappearing on heating the urine which contains it; and from the earthy phosphates by its insolubility in dilute hydrochloric or strong acetic acid. It is at once distinguished from all other deposits by its ready solubility in ammonia. The crystals are hexagonal plates of variable thickness, but generally thin and often superimposed, as in Fig. 29. The ammoniacal solution yields, on evaporation, the same well-formed hexagonal plates or prisms, but sometimes clustered crystals, as delineated. Cystin is often found associated with uric acid and the urates.

Fig. 29.



Quantitative estimation of Phosphoric and Sulphuric Acids.

604. (1.) *Phosphoric Acid.*—This is wholly precipitated by uranic nitrate in the presence of sodic acetate and acetic acid as lemon coloured uranic phosphate, $2\ (Ur_2\ O_3)\ P_2\ O_5 + Aq.$* To effect the separation we require, 1. A solution of uranic nitrate, 100 gr. meas. of which are equivalent to 1 grain of $P_2\ O_5$; this is made by dissolving 709·9 grains of the pure fused salt in water to make up 10,000 grain measures. 2. A solution of sodic acetate with free acetic acid, made by dissolving 1000 grains of sodic acetate in 9000 grain meas. of water and making up 10,000 gr. meas. by the addition of acetic acid. Take 500 gr. meas. of the urine and mix with it 50 gr. meas. of the solution of sodic acetate; warm, and then slowly and with constant stirring add from the burette the uranium solution, removing a drop from time to time with a glass rod, and letting it fall into a drop of solution of potassic ferrocyanide.

---

* Neubauer and Sutton.

So long as any phosphoric acid remains in the solution, no brown colour appears; but it shows itself just as the point of saturation is overreached, when we stop and read off the burette.

605. (2.) *Sulphuric Acid.*—This is estimated as baric sulphate. To prepare the solution, take of powdered baric nitrate dried between folds of blotting paper 305 grains, and dissolve in water, making up the solution to 10,000 gr. meas. 100 gr. meas. are equivalent to 1 grain $S\,O_3$. Take 1000 gr. meas. of urine in a flask or beaker, add 12 drops of hydrochloric acid and boil, then let in the sol. baric chloride from a burette as long as the precipitate is seen to increase. The precipitate rapidly subsides and leaves a clear fluid, a drop of which must be taken from time to time and added to a solution of sodic sulphate. When the slightest excess of baryta has been added, a faint turbidity is produced in the latter. Then stop and read the burette.

606. *Chloride of Sodium.*—Common salt sometimes appears as crystals on evaporating a drop of urine on a glass slide. Their form is the cube, marked by lines or steps; but on hasty evaporation they have an irregular cruciform appearance.

607. *Chyle.*—Chylous urine, on cooling, gelatinizes spontaneously, assuming the appearance and consistence of *blanc-mangé.* It contains large quantities of albumin and fat.

608. *Fat*—Urine may contain fat in a separate form, or as a constituent of chyle or milk. It is also frequently met with in the shape of oil-globules attached to epithelial cells, or casts of tubes. (See § 371, Fig. 11 *b*, and § 627, Fig. 37.) The quantity of fat may be ascertained by evaporating a portion of the urine, dissolving the deposit in æther, evaporating the solution, and weighing the residue.

609. *Milk.*—Urine containing milk is turbid and pale, and contains fat globules and colostrum corpuscles. Milky urine does not coagulate by heat, unless the quantity of lactic acid be large, or unless it also contain albumin. On adding to a little urine moderately warmed a few drops of acetic, dilute sulphuric, or hydrochloric acid, flocculi of coagulated casein are formed. The quantity of casein may be determined by collecting these flocculi, washing and drying them, and dissolving out the oil-globules by æther.

610. *Sugar.*—This may sometimes be detected by the taste, especially if we first evaporate the urine to the consistence of a syrup; but this test is inconvenient in practice, and not to be depended on. The specific gravity of the urine affords certain evidence of the existence of sugar only when it exceeds 1·035, which is probably the highest figure for urine containing urea in excess. The specific gravity of diabetic urine ranges from 1·020 to 1·050. When the symptoms lead to a suspicion of the presence of sugar, it may be detected by one or more of the following tests:—

(1.) *Trommer's Test.*—Add to half an inch of urine in a test-tube, three drops of solution of sulphate of copper (twenty grains to the ounce), then add a quarter of an inch of liquor potassæ. Hydrated oxide of copper is thrown down, but dissolves in the excess of alkali. On boiling the liquid, if sugar be present, the red suboxide of copper, varying from a light orange to a deep crimson tint, is thrown down.

(2.) *Fehling's Test-solution.*—This may be conveniently substituted for the sulphate of copper and caustic potash of Trommer's test. It is prepared by dissolving 34·65 grains of sulphate of copper in a drachm or two of distilled water, and adding it to a solution of 173 grains of tartrate of potash, and 80 grains of caustic soda in about an ounce of distilled water; and making up the mixture to exactly 1000 grain measures. 100 grain measures of the solution are equivalent to half a grain of grape sugar. In order to ascertain the quantity of sugar in a given quantity of urine, take 100 grain measures of Fehling's solution in a 2 ounce flask or porcelain capsule, dilute with three or four times as much water, boil gently and continuously and deliver from a burette a little of the saccharine urine into it from time to time. In proportion as the sugar is added, the solution loses its blue colour, and red suboxide of copper falls and rapidly subsides. When the process is complete the supernatant fluid has a faint brown tinge. If there be any doubt of the existence of copper in the solution, remove a drop, neutralize it by acetic acid, and add a drop of solution of potassic ferrocyanide. A brown precipitate will occur if there be a trace of copper in the solution. If this prove to be the case, the mixture is to be again boiled, and a few grain measures more of the urine added. If the urine contain more than 1 per cent. of sugar, it should be diluted to half or one per cent., and the experiment repeated. Suppose 85 grain measures of the diluted urine have been required to precipitate the copper as suboxide, this quantity contains half a grain of sugar, 100 grain measures of the copper solution being equivalent to that quantity.

The following tests have been recommended, but are less free from objection than the foregoing:—

(3.) *Moore's Test,* with *liquor potassæ.*—Pour the urine supposed to contain sugar into a test-tube, add half its bulk of liquor potassæ, and boil for one or two minutes. The urine assumes an orange-brown tint, of depth proportioned to the quantity of sugar.

(4.) *Crystallization Test.*—Evaporate the urine to the consistence of a thick syrup, and digest in hot alcohol. Pour the cooled alcoholic solution into a large test-tube, and allow it to evaporate spontaneously. The sugar will crystallize on the sides in white granules.

(5.) *Fermentation Test.*—On adding yeast to diabetic urine, and raising the temperature to 80°, effervescence takes place, a brisk discharge of gas ensues, and a yellowish liquid is formed, which has the odour of beer, and yields alcohol by distillation. One part of sugar in 1000 parts of healthy urine of the density 1030 may be detected by this means.

(6.) *Torula Test.*—Expose the urine for a few hours to a temperature above 70°. A drop taken from the scum that covers the surface, and placed under the microscope, exhibits oval vesicles, which rapidly grow into a species of conferva, to which the term *torula* has been given. This formation, however, is not peculiar to diabetic urine. (Fig. 30.)

(7.) The *quantity* of sugar may be determined with a fair approach to accuracy by a modification of the fermentation test, which is thus performed. Fill a graduated tube with mercury, leaving space for little more than the requisite quantity of urine, which then introduce. Fill what remains of the space with yeast. Close the open end of the tube with the finger, reverse the tube in mercury, and expose it to a heat of 70° or 80° for twelve hours or more. Since the fluid thus introduced dissolves its own bulk of carbonic acid, the measure of the fermented liquid, added to that of the undissolved gas, gives the quantity of carbonic acid; from which the weight of sugar is inferred by allowing one grain for every cubic inch of gas.

Fig. 30.



611. *Bile.*—Urine containing bile is of a deep yellow-brown colour, and if the quantity be considerable, of a bitter taste. Its presence is readily detected.

(1.) By the gamboge colour on dilution with water.

(2.) By *nitric* and *sulphuric* acids, which produce in the liquid an iridescent play of colours. To apply this test, a drop of the bilious fluid and a drop of the acid are placed side by side on a porcelain plate, and joined by the touch of a glass rod.

(3.) *Pettenkofer's Test*—To a few drops of the urine on white porcelain add a drop of strong syrup, mix with a glass rod, and then place near it two-thirds of its bulk of pure sulphuric acid; gradually mix the two, spreading the fluid over a large surface of the cold porcelain so as to avoid the development of too much heat, which would cause a charring of the sugar. If bile be present a fine purple colour will be produced.

(4.) A fourth test has been proposed by Schwertfeger. It consists in throwing down the bile as a yellow precipitate, by acetate of lead, and dissolving the precipitate in alcohol acidulated with sulphuric acid. To the green solution thus obtained, Pettenkofer's test may be applied.

Tests 1 and 2 are most expeditious, and, therefore, to be preferred.

612. *Kyestein.*—This, though not peculiar to pregnant women, is occasionally found in pregnancy. It consists of a film of fat, a matter resembling casein, and crystals of ammonio-magnesian phosphate. It forms on the surface of the urine in periods varying from thirty hours to eight days, but usually on the third day. The urine is either neutral or ammoniacal at the time of its formation. After standing some time the pellicle breaks up and falls to the

bottom. The sediment has the disagreeable pungent odour of decayed cheese.

613. *Blood.*—Blood is sometimes voided with the urine in small defined clots, readily recognized; but, in other cases, it tinges the urine a bright red, brown, or bistre-red. Minute traces give to acid urine a smoky brownish appearance resembling weak tea. The colour alone is not conclusive, as other colouring matters produce similar appearances; but its nature is easily ascertained, either by the discovery of blood corpuscles under the microscope, or by the effect of heat and nitric acid, which throw down a dirty-brown coagulum, consisting of albumin blended with the colouring matter. The urine also assumes a bright red tint when treated with a strong solution of common salt.

614. *Blood Corpuscles.*—When not dissolved in the urine, the blood corpuscles form a dark brown-red sediment in which their forms may be detected by the microscope.

615. *Fibrin.*—This substance is voided in the form of casts of the tubes, or as a constituent of clots of blood. Coagula and flocculi of fibrin are readily distinguished from mucus by their amorphous appearance under the microscope, and the absence of epithelium.

616. *Albumin.*—This is very often found in the urine in quantities from 12 grains in a 1000 grain measures of the urine downwards. Its presence in acid urine is readily ascertained by boiling, which coagulates it. Boiling also precipitates any excess of phosphates. Hence it is always desirable to add a few drops of nitric acid, after boiling. Care must be taken to use a clean test-tube, for if the urine contain a trace of nitric acid previously, boiling does not precipitate the albumin. If the urine be alkaline, the albumin is best precipitated by the addition of a large quantity (one fourth) of nitric acid to the cold urine. Some essential oils, such as cubebs, and oleo-resins, as copaiba, are eliminated by the kidney, and render the urine turbid on the addition of an acid. They are, however, easily separated by shaking the turbid fluid with æther.

617. The *quantity* of albumin is readily estimated thus:—Counterpoise two filters and place one folded by the side of the other in a funnel. Take 1000 grain measures of the 24-hours acid urine; boil, throw hot on the filter, wash the filter with hot water, so as to get rid of all but a trace of urine, and then add fresh water and a few drops of nitric acid to dissolve any phosphates that may have been deposited with the albumin, and subsequently wash out every trace of acid and urine. Dry the filters and when the albumin is quite brittle, weigh, using the folded filter as a counterpoise.

618. *Mucus.*—A little mucus is present in healthy urine without affecting its transparency. In disease it may be blended with it in any proportion, from a slight cloud to a quantity sufficient to cause it to pour from one vessel to another as a viscid ropy fluid; and when the quantity is considerable, and the result of acute inflam-

mation of the mucous membrane, and especially when it is blended with an excess of phosphates, it may form a distinct deposit closely resembling pus. Urine containing mucus has generally an alkaline reaction, and is not coagulated by heat or nitric acid, unless albumin be also present; but acetic acid coagulates it.

619. *Pus.*—Urine containing pus is commonly either acid or neutral; and, on standing, deposits the pus as a distinct cream-coloured layer, readily diffused through the fluid by agitation. The deposit is not dissolved by acetic acid; it is rendered viscid and more consistent by liquor potassæ, and, when shaken with æther yields a quantity of fat. The urine, freed from its purulent deposit is coagulated by heat and nitric acid. In alkaline urine, pus has something of the viscidity of mucus.

Fig. 31.



Under the microscope pus presents a number of opaque spherical bodies, consisting of a cell-membrane inclosing nuclei, oil globules, and minute granules. The addition of acetic acid renders the envelope transparent and the nuclei more distinct, as in Fig. 31, in which *a* represents the ordinary appearance of the pus granule, and *b* of the same granule on the addition of acetic acid. Mucus presents similar microscopic appearances, but the particles are not so distinctly granular.

620. *Diagnosis of Pus and Mucus.*—Much stress was once laid on the importance of distinguishing pus from mucus, and many methods were devised for effecting that object. But it is now well understood that, though there is a great difference between pus and healthy mucus, there is very little between pus and the mucus of an inflamed membrane. Purulent urine contains albumin, but mucous urine, as such, is free from it.

Fig. 32.



621. *Semen.*—Occasionally the seminal fluid which lines the urethra after emission becomes washed away by the urine, and may be recognized in it by the spermatozoa (Fig. 32). The examination should be made soon after the urine is passed, with a quarter or an eighth power. The object must not be too strongly illuminated.

622. *Epithelium.*—This, as found in the urine, is of three kinds:—

(1.) *Renal.* (2.) From the urinary passages. (3.) *Vaginal.* Renal Epithelium (Fig. 33, *a*) is commonly present in acute nephritis. It is soon affected with fatty degeneration, in which condition the cells become opaque, and appear like spherules of dark aggregated granules. Epithelium from the bladder and ureter is represented at (*b*), that from the male urethra in Fig. 32: that from the vagina in Fig. 33, *c*.

623. Sometimes it is desirable to be able to recognize by inspection and the use of one or two simple tests, the character and composition of an urinary deposit. The most common deposits may be classed as follows:—

Fig. 33.



(1.) Red crystalline sediment—urine acid. Uric acid with colouring matter of the urine.

(2.) White crystalline sediment—urine neutral or alkaline. Triple phosphate.

(3.) White amorphous sediment—Phosphate of lime.

(4.) Pink sediments—urine acid. Urate and phosphate of ammonia.

(5.) Yellowish or nut-brown sediment—Urate of ammonia and soda, earthy phosphates, and colouring matter of urine.

(6.) Reddish-brown or lateritious sediment.— Alkaline urate (chiefly urate of soda), earthy phosphates (occasionally), colouring matter of urine, and alkaline purpurate.

(7.) Oxalate of lime. A scanty white powdery deposit, usually incumbent on a cloud of mucus.

(8.) Carbonate of lime. A heavy fawn-coloured deposit.

(9.) Cystic oxide. Very rare.

(10.) Red particles of blood entire, or disintegrated into chocolate-brown molecules, pus, mucus, &c.

624. The substances referred to in 2, 3, 4, 5, and 6, consist of colouring matter with alkaline urates and earthy phosphates in variable proportions. These are easily distinguished, both from each other and from certain secretions which resemble them, by shaking up the sediment and applying heat. If the sediment dissolve, it consists of alkaline urates, chiefly urate of ammonia; but if the fluid remain turbid, it consists of the earthy phosphates, or of pus or mucus. These may be readily distinguished by the addition of hydrochloric acid, which dissolves the phosphates, but not the pus or mucus. If urine containing urates also hold albumin in solution, the urine when heated first becomes clear, and then turbid.

625. *Casts of the Urinary Tubes.*—In diseases of the kidney considerable importance attaches to a microscopic examination of the urine, with a view especially to the discovery of casts of the urinary tubes. The casts, of which the chief varieties are represented in the figures, are best seen with a power magnifying about 200 diameters.

626. Fig. 34. *Epithelial cast*, composed of fibrin entangling epithelium and blood corpuscles, and indicating "acute desquamative nephritis," a form of disease not uncommon as a consequence of scarlatina, and which is analogous to the desquamation of the skin.

627. Fig. 35. *Granular cast*, composed of fibrin, with particles of disintegrated "epithelium, characteristic of chronic desquamative nephritis." These casts are common in the urine of men who have had numerous attacks of gout, and they may often be detected long before any other sign of renal disease, albumin appearing at a later stage.

Fig. 34.



Fig. 35.



Fig. 36.



Fig. 37.



Fig. 38.



Fig. 39.



628. Fig. 36. *Waxy or hyaline casts*, sometimes deposited in the advanced stage of chronic nephritis, but sometimes also in acute nephritis.

629. Fig. 37. *Oily casts*, composed of fibrin, entangling oil globules and epithelial cells gorged with oil. They indicate degeneration of the kidney, the most serious and incurable form of Bright's disease.

630. Fig. 38. *Purulent casts*, composed of fibrin entangling pus cells, and indicating suppurative nephritis ; a very serious and often rapidly fatal form of disease.

631. Fig. 39. *Blood casts*, such as occur in strangury and hæmaturia, after taking oil of turpentine. The blood is moulded in the kidney tubes, and affords unequivocal evidence that the hæmorrhage was renal. The crystals attached to the cast are oxalate of lime. (The wood-cuts are from the drawings of Dr. George Johnson.)

632. In diabetes, and in other morbid states in which the urine is loaded with matter in excess or foreign to its normal composition, we may wish to estimate the quantity of solid matter it contains. This may be done by multiplying the excess of the specific gravity of the urine above that of water by the weight of the urine, and the product by 0·00233. By referring to a table in which the weight of solids in given quantities of urine of different specific gravities is stated, the amount of solids in the specimen under examination may be directly calculated from the measured quantity, which should be the whole amount passed in twenty-four hours, or a measured fraction of it. The first of the two tables given below presents the quantity of solid matter contained in 1000 grains of urine of different densities : and the second the weight of one pint of urine. The mode of using these tables will be readily seen from a single example. Suppose a patient to pass, in twenty-four hours, three pints of urine of the specific gravity of 1·030, it is required to ascertain the weight of solid matter voided in this period. 1000 grains of urine, specific gravity 1·030, contain by Table I. 69·90 grains of solid matter, and a pint of urine of the same specific gravity weighs, by Table II., 9012 grains. Hence $\frac{69·9\times 9012}{1000}$ or 629·9 grains is the quantity of solid matter contained in each pint of urine ; and 629·9 × 3, or 1889·7 grains, is the total weight of solids voided in the twenty-four hours. This calculation gives us a sufficiently close approximation to the actual weight of saccharine matter in cases of diabetes mellitus.

TABLE I.

Solids in 1000 *Grains of Urine of different Densities.*

Specific Gravity.		Solids.	Specific Gravity.		Solids.
1·001	...	2·33	1·008	...	18·64
1·002	...	4·66	1·009	...	20·97
1·003	...	6·99	1·010	...	23·30
1·004	...	9·32	1·011	...	25·63
1·005	...	11·65	1·012	...	27·96
1·006	...	13·98	1·013	...	30·29
1·007	...	16·31	1·014	...	32·62

Specific Gravity.	Solids.	Specific Gravity.	Solids.
1·015	34·95	1·033	76·89
1·016	37·28	1·034	79·22
1·017	39·61	1·035	81·55
1·018	41·94	1·036	83·88
1·019	44·27	1·037	86·21
1·020	46·60	1·038	88·54
1·021	48·93	1·039	90·87
1·022	51·26	1·040	93·20
1·023	53·59	1·041	95·53
1·024	55·92	1·042	97·86
1·025	58·25	1·043	100·19
1·026	60·58	1·044	102·52
1·027	62·91	1·045	104·85
1·028	65·24	1·046	107·18
1·029	67·57	1·047	109·51
1·030	69·90	1·048	111·84
1·031	72·23	1·049	114·17
1·032	74·56	1·050	116·50

TABLE II.

Weight of a Pint of Urine of different Densities.

Specific Gravity.	Weight of one Pint.	Specific Gravity.	Weight of one Pint.
1·010	8837	1·031	9021
1·011	8846	1·032	9030
1·012	8855	1·033	9038
1·013	8863	1·034	9047
1·014	8872	1·035	9056
1·015	8881	1·036	9064
1·016	8890	1·037	9073
1·017	8898	1·038	9082
1·018	8907	1·039	9091
1·019	8916	1·040	9099
1·020	8925	1·041	9108
1·021	8933	1·042	9117
1·022	8942	1·043	9126
1·023	8951	1·044	9134
1·024	8960	1·045	9143
1·025	8968	1·046	9152
1·026	8977	1·047	9160
1·027	8986	1·048	9169
1·028	8995	1·049	9178
1·029	9003	1·050	9187
1·030	9012		

2. THE ABDOMEN AND ORGANS OF DIGESTION.

633. *The Abdomen.*—To facilitate description, the chest and abdomen are divided into a number of distinct parts or regions by imaginary lines drawn from fixed points, as in Figs. 40 and 41.

This division is made, in the first place, by four horizontal lines passing round the body—the first (*a a*) at the level of the clavicles, the second (*b b*) at the level of the point of the ensiform cartilage, the third (*c c*) at the level of the cartilages of the tenth ribs, and the fourth (*d d*) at the highest points of the crests of the ilia. The abdomen is further subdivided into seven regions (three central and four lateral) by two vertical lines (*e e*) arising from the middle point of each groin, and meeting the horizontal line (*b b*).

The three central regions thus formed are named in the order from above to below, the epigastric, the umbilical, and the hypogastric; the four lateral regions, taken in the same order, are the right and left hypochondriac, and the right and left iliac. The portion of the abdomen immediately above the line of Poupart's ligament is commonly known as the inguinal region.

Fig. 40.



Fig. 41.



634. The organs situate in each of these regions are as follow:— The *epigastric* contains the middle portion of the stomach and the pylorus, the left lobe of the liver, the lobulus Spigelii and hepatic vessels, and the head of the pancreas: and behind these, the cœliac axis, the semilunar ganglion, and part of the vena cava, aorta, vena azygos, and thoracic duct. The *umbilical* contains the omentum and mesentery, the transverse portions of the duodenum and colon, and some convolutions of the jejunum. The *hypogastric* is occupied by the bladder and part of the small intestines. Behind the bladder is the uterus in the female, and the rectum in the male. The *right hypochondriac* contains the right lobe of the liver and the gall-bladder, part of the duodenum and ascending colon, renal

capsule, and part of the right kidney; the *left* contains the large end of the stomach, the narrow extremity of the pancreas, the spleen, part of the colon, renal capsule, and upper part of the left kidney. The *right iliac* region contains the cæcum, the termination of the ileum and the commencement of the colon; the *left*, the sigmoid flexure and part of the descending colon.

635. The posterior regions, formed by continuing the horizontal lines *b b*, *c c*, and *d d*, are divided by a vertical line following the course of the spine into the four regions, the right and left dorsal, and the right and left lumbar. The *right and left dorsal* contain the upper portions of the kidneys.

The *right lumbar* contains the cæcum and lower part of the right kidney; the *left*, the sigmoid flexure of the colon, and lower portion of the left kindney.

636. When any of the organs are distended or enlarged, they encroach on surrounding parts, and occupy adjoining regions. Thus, the distended stomach or bladder may encroach on the umbilical region; the distended colon may rise into the epigastric; and the enlarged liver or spleen may descend into the right or left iliac.

637. The *size and shape* of the abdomen vary with age and sex. In the child the abdomen is large; in the spare adult, small; in the female it presents an enlargement in the hypogastric region. It varies in size, in the same person, with the full or empty state of the stomach, the quantity of gas in the intestines, and of urine in the bladder. Pregnancy, ascites, ovarian dropsy, tympanites, hydatids, enlargement of the liver or spleen, and various morbid growths attached to the several organs, may also increase the size and alter the shape of the abdomen.

638. In examining the abdomen, we employ three methods—*inspection*, *manual examination*, and *percussion*. In certain cases we resort to measurement, and in a few instances to auscultation.

639. By *inspection* we ascertain the size, form, and movements of the abdomen. The size is increased by any of the causes just specified; and the form is altered, either throughout the entire cavity, or in parts, according as the cause is extensive or limited. The history of changes of form is very important. Thus, the gradual, uniform, and central enlargement of pregnancy, the lateral enlargement in the first stage of ovarian dropsy, and the equal and gradual growth of ascites, form important means of diagnosis.

640. The movements of the abdominal parietes afford important indications, especially those of respiration. Thus, in peritoneal inflammation, as well as in painful affections of the abdominal muscles, respiration is performed by the chest alone. On the other hand, in pleurisy and in painful states of the muscles of the chest or of the diaphragm, the respiration is performed chiefly by the muscles of the abdomen. Again, when the abdomen is greatly distended, the action of its muscles is nearly suspended, and respiration is performed by the chest and diaphragm. In extreme cases, the viscera

are pressed against the diaphragm, and respiration is performed solely by the muscles of the chest.

641. By the *touch*, we gain further information as to the size, form, shape, tension, and movements of the abdomen, including those of respiration. The pulsations of the aorta are also perceptible to the touch in thin persons with lax abdominal walls, in cases of aneurism, of tumours situate over it, and of accumulations of fæces. We also ascertain by the touch the temperature and sensibility of the abdomen. The *temperature* should be compared with that of other parts. In acute peritonitis, and in severe febrile affections accompanied with abdominal inflammation, the surface has a peculiar pungent heat.

642. In testing the *sensibility* of the abdomen, pressure should first be made gently, and with the open hand. If this give pain, and there is inflammatory fever, the peritoneum is inflamed; but if there is no fever, the pain may be inferred to be in the muscular walls of the abdomen. If a slight touch produces no pain, we apply a deep and moderately strong pressure; and if this occasions rather a feeling of soreness than of acute pain, we may infer the presence of inflammation of the mucous membrane of the stomach or intestines. The pain due to inflammation of the peritoneum is best developed by a lateral pressure, causing it to slide over the intestines. In colic, strong pressure relieves pain, and forms an important means of diagnosis. Muscular pain, also, is relieved by gentle pressure, gradually increased; but on the sudden removal of the hand, the muscles are thrown into action, attended by acute suffering. Muscular pain, too, is rarely accompanied by constitutional disturbance, and, like neuralgia of the skin, is often dependent on, or associated with, an irritable state of the spinal cord. The contraction of the muscles in the act of expiration is another cause of pain which must be distinguished from the effect of pressure.

643. In applying pressure to the abdomen, we should always mark the expression of the countenance, as this is much more to be depended on than the patient's answers, especially when typhous symptoms are present, or the brain is affected. When the abdomen is very tender, the patient will throw the muscles into rigid tension, so as to shield its contents from pressure; and we have to suspend our examination till the patient's attention is diverted. When the tenderness is in the right hypochondriac region, and the cause disease of the liver, the right rectus muscle is generally found in a state of rigid contraction.

644. If, in examining the abdomen, we discover a tumour, or are anxious to ascertain the state of any of its contents more exactly, we relax the muscles by placing the patient on the back, with the head slightly raised and bent forward, the arms extended by the sides, the thighs bent nearly at right angles on the trunk, the knees apart and turned outwards, and the feet resting on the bed in contact

with each other. The patient must also be directed to use as little muscular effort as possible, and his attention must be diverted from the examination which is going on. In this relaxed state of the abdominal walls, the size and position of tumours, and the dimensions of the viscera, are readily ascertained. In women, a combination of abdominal swelling and tension with extreme tenderness is sometimes met with, under the name of *phantom tumours*. The pain or pressure is so great as to prevent a complete examination; but by the use of chloroform the pain ceases, the abdominal walls become supple, and the work of examination is rendered easy.

645. *Percussion* may be performed with the points of the fingers, or by the intervention of a plate of ivory or wood, or of a finger of the left hand. Applied in this latter manner over the site of the stomach, or over any part of the small or large intestines containing air, it elicits a clear sound. In the epigastric region, in ordinary states of the stomach, and over any part of the intestines largely distended with air, the sound is tympanitic. The clear sound is somewhat modified if the air be mixed with fluid. Percussion, on the other hand, elicits a dull sound when applied over solid viscera, over collections of fluid, over hollow viscera in their contracted state, over the intestines when containing only fæces, over the enlarged liver or spleen, and over solid tumours.

646. Percussion and the touch are employed together in detecting the presence of fluid. This is best done in the upright posture. The palm of one hand is placed on one side of the abdomen with a firm but gentle pressure, while the fingers of the other hand tap lightly and quickly on the part directly opposite to it. If fluid be present, a peculiar and characteristic vibrating shock is experienced.

647. Direct percussion with the points of the fingers is used to distinguish muscular pains of the abdomen. A slight quick touch throws the muscles into action, and so causes pain. This, together with the absence of pain on firm pressure gradually applied, its recurrence on the sudden removal of the pressure, the acute pain produced by every movement of the affected muscles, and the absence of urgent constitutional symptoms, combine to distinguish muscular pains from those due to disease of deep-seated parts.

648. *Measurement* of the abdomen is sometimes resorted to. A common tape graduated to eighths of an inch answers the purpose. No precautions are necessary beyond noting whether the measure is taken during inspiration or expiration. When the abdomen is uniformly enlarged by a tumour or by fluid, and especially when successive measurements are required, the tape should be applied at the level of the umbilicus.

649. *Auscultation* is occasionally resorted to in examining the abdomen, to confirm by means of the friction-sound, the diagnosis of peritoneal inflammation. This sound is caused by the rubbing together of two surfaces roughened by deposits of lymph. By using the stethoscope, we may also hear the pulsations of the aorta in

spare persons, and may detect the placental murmur and the pulsations of the fœtal heart. The first is a blowing sound, synchronous with the pulse of the mother, and best heard in the iliac regions near the groins. The second is not unlike the ticking of a watch, occurring from 120 to 160 times in a minute, and best heard about the centre of the left iliac region. It is rarely audible till the end of the fifth month.

650. In taking notes of cases of abdominal tumours or enlargement of viscera, their size and extent, as indicated by percussion, may be conveniently figured on outlines kept for the purpose. The figures annexed will serve to illustrate the use of such outlines. Fig. 42 shows the regions of dull and clear sound in the healthy subject, in which *a* shows the dull region of the liver, and *b* that of the spleen; while *c* indicates the region of clear sound over the stomach moderately distended, and *d* that of the colon similarly distended. The fainter shadow (*e*) indicates the parts of the abdomen which, when empty, yield a moderately dull sound, when filled with flatus a clear (tympanitic) sound, and when filled with solid matters (as with fæces) a full dull sound. Fig. 43 shows the dull region of the liver (*a'*) extended, as in organic disease, with enlargement; (*b'*) a similar enlargement of the spleen, and the regions of dulness, corresponding with a distended descending colon and rectum (*f*); a loaded cæcum (*g*); and a distended bladder (*h*). The use of the shaded outlines, as applied to the heart and lungs, will be noticed in another place.

Fig. 42.



Fig. 43.



3. THE CHEST AND THE ORGANS OF RESPIRATION AND CIRCULATION.

651. An examination of the external conformation of the chest must precede all inquiries into the diseases of the parts contained within it. To facilitate such examination, the chest, like the abdomen, is divided into regions, by lines drawn from fixed points. (See Figs. p. 139.) The two horizontal lines (*a a* in the line of the clavicles, and *b b* on the level of the ensiform cartilage), joined by a vertical line bisecting the sternum, divide each side of the chest in front into two principal regions designated by characteristic names. Those corresponding to the first horizontal line are the *clavicular;* those above the clavicles are the *supra-claviculars*; those beneath them the *intra-clavicular*. The parts marked by the nipples are known as the *mammary* regions, and the armpits as the *axillary* regions.

On the back of the chest the *supra-scapular*, the *scapular*, *inter-scapular*, and *infra-scapular*, correspond—the first to the root of the neck and shoulders behind limited below by the upper border of the blade-bone, the second to the blade-bone itself, the third to the space between the two blade-bones, and the fourth to that part of the chest immediately below the angles of those bones.

652. The size, shape, and movements of the chest may be ascertained by *inspection*, *manual examination*, and *measurement*.

Inspection.—A well-formed chest is large in all its dimensions, and round in its outlines. The spine is straight, or, in very strong men, and those who use the right arm much, curved almost imperceptibly towards the right. The chest appears symmetrical; but when measured, the right side is found larger than the left by about half an inch; and there is naturally somewhat more fulness above and immediately beneath the clavicle on the left than on the right side, on account of the greater prominence of the right clavicle. The chest is wider and longer in men, but deeper in women. Women are also more subject to distortions of the chest and spine

653. A glance at the chest enables us to judge of its size. Closer examination is required to detect deviations from its usual form. The chief distortions affecting both sides alike, are those arising from constrained posture and the use of stays. Of the former, the most remarkable is the flattened chest of the shoemaker. Alterations in the shape of both sides of the chest also arise from diseases affecting equally both lungs; such as tubercle, leading to contraction, especially in the subclavian region, and dilatation of the pulmonary cells (emphysema), causing a notable convexity of the front of the chest. Alterations in the shape of a side, or of a limited portion of a side, may arise from more than one disease of the corresponding lung. Acute pleurisy causes enlargement of the affected side but in certain chronic cases there is contraction. In hydrothorax, also, and in pneumothorax, the affected side is enlarged. In extreme cases the intercostal spaces are raised to a level with

the ribs. More partial changes arise from circumscribed pleurisy and limited adhesions. In advanced phthisis, the position of a cavity is often indicated by the falling in of one of the intercostal spaces. Other changes in the size and shape of the chest arise from diseases of the heart and large vessels.

654. Inspection also enables us to ascertain the character of the respiration; whether tranquil or hurried, easy or difficult; abdominal as in acute pleurisy or acute pleurodyne; or thoracic, as in acute diseases of the abdomen and severe rheumatism of the abdominal muscles or diaphragm. The character of the heart's impulse may also be ascertained by inspection.

655. *Manual Examination.*—By this, as by inspection, we ascertain the development of the muscles, the thickness of the walls of the chest, the presence of œdema or emphysema of the integuments, heat and soreness of the skin, local tenderness, or muscular pain. The extent and character of the heart's impulses may also be ascertained by the hand, and it is usual to apply the two hands to corresponding parts of the chest when we wish to compare the respiration on the two sides.

656. Firm pressure in the intercostal spaces often causes pain when the pleura is inflamed, either generally or partially. This partial tenderness occurs in consumption, when the pleura covering a cavity is inflamed, or when a collection of pus is making its way externally.

657. The chest is a common seat of muscular pains. Pain in the side (pleurodyne) is a consequence of violent efforts in coughing; and pain in the left side a very frequent occurrence in weak and delicate females. These muscular pains, which are apt to be mistaken for pleurisy, are developed by slight percussion with the points of the fingers, by the movements of the arms or trunk, and by a deep inspiration. The absence of pain on firm and gradual pressure, with its recurrence when the support is suddenly removed, is also a good diagnostic of muscular pain. Percussion with the fingers throws the muscles visibly into action through the whole length of their fibres, and causes remarkable partial and transverse contractions, which are best seen in emaciated persons, and especially in advanced phthisis.

658. *Measurement.*—This may have to be resorted to in disease as a means of diagnosis; in health, as a measure of strength and vigour.

In disease we may wish to ascertain the size of the chest, or of certain portions of it, or to determine the degree of expansion and enlargement which the whole, or parts of it, undergo during inspiration. The progressive enlargement or diminution in its size which accompanies certain forms of disease, may also be ascertained by repeated measurements made with great care, in the same position, and in the same state of the cavity. A graduated tape may be used for this purpose. To measure the size of the chest the tape should be carried horizontally round it, passing over the two nipples, or at an equal distance above or below them. When the expansion due to the movements of inspiration is to be ascertained, one end of the tape should be firmly held by one hand to the spine, while the other is allowed to slide freely through the other held over the centre of the sternum. The chest should first be measured after a full expiration, then after a deep inspiration; by shifting the tape we may measure the degree of expansion of both sides. In making these measurements, the fact that the right side is naturally larger than the left by half an inch, must be borne in mind. The expansion of the chest in ordinary inspiration does not exceed an inch and a half, and it is somewhat greater on the right than on the left side.

659. In examining the chest with a view to test the strength and vigour of healthy persons, as in recruiting for the army, we must be provided with certain standards of comparison, and also make allowance for the different degrees in which the muscles are developed, and covered with fat. In these examinations the expansion of the chest should be performed with evident ease and freedom; and the tape drawn tightly across the nipples should show a movement of not less than an inch.

660. The greatest circumference of the chest in robust men varies from 39 to 42 inches; and in spare men of medium height ought not to fall much short of 35 inches. In robust men it bears to the height the proportion of about 1 to 1·75. If in a man of 5 feet 4 inches, the average circumference is taken at 38 inches, an allowance should be made of half an inch in the chest-measurement for every inch added to the stature.

Stature.	Circumference of Chest.	Stature.	Circumference of Chest.
64 inches.	... 38 inches.	69 inches.	... 40½ inches.
65 „	... 38½ „	70 „	... 41 „
66 „	... 39 „	71 „	... 41½ „
67 „	... 39½ „	72 „	... 42 „
68 „	... 40 „	73 „	... 42½ „

661. It ought, however, to be understood, that the chests of very tall men are not so large in proportion to their height as those of men of medium stature; tall men do not bear fatigue so well as those of shorter stature.

662. Various stethometers, or instruments for measuring inspirations, have been invented. Dr. Quain's consists of a string passing round the chest, adjusted in the act of expiration, and as the chest expands by inspiration, it indicates the enlargement by a hand moving on a dial-plate. Dr. Sibson employed a similar instrument, especially for measuring the movements of particular portions of the chest.

THE LUNGS.

663. The cavity of the chest is a hollow cone, of which the apex *is cut* off by a horizontal plane, corresponding with its upper open-

ing, and the base by an oblique plane, looking forwards and downwards, constituting the lower opening. The first is filled by the trachea, œsophagus, and large blood vessels: the second is closed by the diaphragm. This conical cavity is flattened before where the cartilages of the ribs join the sternum, and behind, where the ribs unite with the spine; but rounded at the sides where it is formed by the ribs and their cartilages.

664. The principal organs contained within the chest are the lungs and the heart. The size of the chest corresponds closely with that of the lungs, and is liable to various deformities from diseases affecting those organs. The size and shape of the chest are also altered in certain diseases of the heart and large vessels.

Fig. 44.



665. The lungs are in close contact with the walls of the chest in every part, with the exception of a small space (2, Fig. 44) to the left of the sternum, where they leave part of the middle mediastinum containing the heart uncovered, and a narrow space (1) behind the sternum corresponding to the position of the large vessels.

666. The apices of the lungs are contained in the supra-clavicular regions, rising from 1½ to 2 inches above the clavicles.

667. Of the two lungs the right is the larger, but the left the longer. The right lung reaches to the level of the sixth rib in front, of the eighth rib at the side, and still lower behind. The left lung extends to the level of the seventh rib in front, it reaches the eighth rib at the side, and descends still lower behind. Both lungs applying themselves closely to the diaphragm, descend much lower behind than before, being there prolonged into thin wedges. The diaphragm separates them from the liver on the right side, from the stomach in the centre, and from the spleen and colon on the left side posteriorly. (Figs. 44, 45, and 46.) The weight of the right lung averages 22 ounces, that of the left 20.

Fig. 45.



The right bronchus enters the lung on a line with the second intercostal space, and is wider, more horizontal, and more superficial than the left.

668. The chest is subjected to several kinds of examination, having special reference to the condition and functions of the lungs; our object being to ascertain, 1. The number and character of the respirations; 2. The capacity of the lungs; and, 3. The true condition of their texture.

669. *Number and Character of the Respirations.*—We may *count the* respirations in one of two ways: by observing the motions

of the trunk or of some article of clothing which moves as it moves, or by placing the hand on the chest or abdomen. The first method is best adapted to the sitting or erect, the last to the recumbent, posture. The most convenient plan is to cause the patient to lie down, to rest the hand on the abdomen, and then to grasp the wrist as if feeling the pulse. But whether we count the respirations by sight or by touch, the patient's attention should be withdrawn from the breathing, as the muscles of respiration are partially under the control of the will. The character of the respirations, whether natural, slow or quick, easy or laboured, sighing, catching, or gasping, may be ascertained in either of these ways.

Fig. 46.



670. The character of the respiratory movements differs in the two sexes and at different ages. In very young children they are performed chiefly by the abdomen; in adults of both sexes mainly by the chest. In men the lower part of the chest, in women the upper part, is brought mostly into play, both in easy and in difficult breathing.

671. In very tranquil breathing inspiration is performed by the descent of the diaphragm, marked by a gradual protrusion of the abdomen; and expiration by contraction of the abdominal walls. In ordinary breathing, however, the ribs are raised and tilted out-

wards during inspiration, to recover themselves by their own elastic reaction during expiration. In violent inspiration, not only the diaphragm and intercostals are called into play, but the scapulæ are raised and fixed. In violent expiration, as in coughing and sneezing, the abdominal muscles are brought into action, by which the viscera of the abdomen are compressed and the diaphragm forced upwards into the chest. Yawning and sighing are forms of deep inspiration; coughing and sneezing of violent expiration. Deep inspirations relieve the circulation by leaving greater space for the admission of blood into the heart, whilst violent expirations free the lungs, nostrils, and air-passages from irritating substances.

672. *Number of Respirations.*—These may be registered by an appropriate instrument. That which I devised resembles a large watch with a dial-plate graduated to 10,000, and furnished with two hands, one of which is set in motion by a string attached to a short chain. The instrument is fastened over the pit of the stomach by a band passing round the abdomen, and the string is made tense in the act of expiration, by fastening the free end to a fixed point at a short distance from the body. Every inspiration accordingly, by bringing the two fixed points nearer together, relaxes the string, while every expiration tightens it and sets the hand in motion, causing it to traverse one space on the dial-plate. The experiments, of which the results are given under the head of THE RESPIRATION, were performed by means of this instrument. (G.)

673. *Capacity of the Lungs.*—Several plans have been proposed for ascertaining the capacity of the lungs.

674. Dr. Lyon's method consists in noting the time required to empty the chest after a complete inspiration, by counting aloud. To render the expiration continuous and complete, the patient is directed to count from "one" upwards, as far as he can, slowly and audibly; and the number of seconds is noted by the watch. The time so occupied is a measure of the capacity of the lungs. Dr. Lyons fixed its limit for perfectly healthy persons at thirty-five seconds; but this is too low; for in more than one trial I have myself continued to count for forty seconds. In confirmed phthisis, Dr. Lyons stated the limit at eight, and often at less than six seconds; and, in pleurisy and pneumonia, from four to nine. This method, though open to obvious objections, admits of useful application.

675. Dr. Hutchinson employed a gasometer properly poised and accurately adjusted.

This instrument consists of a cylindrical vessel, *c*, holding several pints of water, filled by a spout at the top, and emptied by a stop-cock, *f*, at the bottom. Into this vessel a cylinder, *c*', of smaller size, counterpoised with the weights, *w w*, is inverted. The cover has an opening, *e*' and *e*, in the centre, which may be closed at will by the plug, *d*' and *d*. An elastic tube, *a*, with a glass mouthpiece, and furnished with a stop-cock, *b*, communicates with the lower vessel, *c*. The bent glass tube, *g* also communicates with the lower vessel, as does the glazed space, *i*. A graduated scale, *s'* and *s*, attached to, and moving with, the upper vessel *c'*, and an index, *h*, complete the instrument. If we suppose the gasometer, *c'*, to be filled with air, so as to occupy the position indicated by the dotted lines, the instrument is prepared for use by taking out the plug, *d*, and lowering the gasometer till the coloured spirit in the two legs of the syphon, *g*, stands at the same level. The index, *h*, is then placed at the level of the water in the glazed space, *i*, which, communicating with the reservoir, *e*, shows the height of the water within, and at the zero of the scale. The plug, *d*, is now replaced, the stop-cock, *b*, being supposed to remain closed. The subject of the experiment then fills his chest completely, and applying his mouth to the mouth-piece, and at the same time opening the stop-cock, *b*, discharges the air from his lungs. The gasometer rises, the stop-cock, *b*, is again turned so as to close the passage for air, the coloured liquid in the syphon, *g*, is again brought to the level in the two legs, and the height of the scale above the index marks the number of cubic inches, and measures, if the experiment has been properly performed, "the quantity of air which an individual can force out of his chest by the greatest voluntary expiration, after the greatest voluntary inspiration."

Fig. 47.



676. By numerous observations made with this instrument, Dr. Hutchinson established certain averages for the healthy chest, which he then used as standards of comparison for the chests of consumptive patients. He found the limits of capacity in health to be 80 cubic inches in a dwarf measuring 3 feet 9 inches, and 464 cubic

inches in a giant measuring 6 feet 11½ inches. He also ascertained that the capacity was 40 or 50 cubic inches below the mean in very fat persons; that it was reduced from 4 to 6 inches by a moderate meal, and from 9 to 14 by a full meal, that it is greatest in the erect posture; that it diminishes after 55 years of age; that it bears a remarkable relation to the stature; and that it is much diminished in pulmonary consumption.

677. The following table presents in the first column the ascertained or calculated capacity of the lungs in healthy persons between the ages of 15 and 55, of different statures, from 5 to 6 feet; and in the second and third columns the capacity of the lungs of persons of the same stature, suffering from the early and advanced stages of pulmonary consumption. (The table is taken from Dr. Hutchinson's work on the Spirometer.)

Stature.		*Capacity. Healthy Males.*	*Early Stage of Consumption.*	*Advanced Stage of Consumption.*
Feet.	Inches.	Cubic Inches.	Cubic Inches.	Cubic Inches.
5	1	174	117	82
5	2	182	122	86
5	3	190	127	89
5	4	198	133	93
5	5	206	138	97
5	6	214	143	100
5	7	222	149	104
5	8	230	154	108
5	9	238	159	112
5	10	246	165	116
5	11	254	170	119
6	0	262	176	123

678. The disparity between the capacity of the lungs in healthy persons, and in persons of the same stature under incipient and advanced consumption, is so considerable as to prove the utility of this instrument. But it must be borne in mind that emphysema and bronchitis, as well as diseases of the heart encroaching on the lungs, would give rise to the same results. In making practical application of the figures it would probably be unsafe to set down to the account of disease a moderate diminution of capacity; though Dr. Hutchinson thought that if a man between 5 feet 7 and 3 feet 8 inches, who ought to expel about 220 cubic inches of air, can expel no more than 185, or a 6-foot man, who ought to expel about 260 cubic inches, no more than 200 or 220 cubic inches, disease may be suspected. When we bear in mind the modifications in the capacity of the lungs due to the causes specified in § 691, and especially that, according to Dr. Hutchinson's statement, "very fat men, of any stature, may blow 40 or 50 cubic inches less than the mean, and yet not be diseased in the chest," it is reasonable to suppose that other causes compatible with health may lessen its capacity. The figures in the second column are, however, so much

below those belonging to the healthy chest, as to furnish a very strong presumption of disease.

679. In using Dr. Hutchinson's instrument, the patient should be in the erect posture, and be narrowly watched to see that he performs the operation of expanding his chest and expelling the air carefully and properly. Allowance must also be made for advance in age above 55.

680. *The Texture of the Lungs.*—To ascertain the state of the texture of the lungs, we use the two methods known as *percussion* and *auscultation*. In percussion the ear discriminates the variations of sound elicited by striking the walls of the chest; and in auscultation those caused by the passage of the air into and out of the lungs in the act of breathing, and also those which, in morbid states, are produced by the movements between the lungs and walls of the chest.

681. *Percussion.*—If the chest were full of air, it would yield, when struck, a sound like that of an empty barrel or drum; if, on the contrary, it were filled with solid animal substance, it would sound as dull as the arm or thigh. But containing, as it does, a spongy organ, the lung, including in its tissue a large quantity of air, it is less resonant when struck than if it contained only air. The more air it contains, the more resonant it is; hence it is more resonant during inspiration than during expiration. If, again, the texture of the lung be so altered as to admit a larger quantity of air, as in emphysema, the chest yields a clearer sound. On the other hand, if the lung admits less air than usual, the sound is duller. This happens in congestion, in inflammation, in tubercular deposit; when solid tumours form in the lung itself, or occupy its place; as also when the lung is compressed by fluids in the sac of the pleura (hydrothorax and empyema). But if, instead of fluid, there is air in the cavity of the pleura (pneumothorax), the sound is more hollow than if the healthy lung were in contact with the walls of the chest.

682. But the nature of the sound is also influenced by the thickness of the walls of the chest itself. If two chests contain exactly the same quantity of air, that will give the clearest sound which has the thinnest walls. Those parts, too, which are padded with muscle or fat, yield a duller sound than those which are less covered. Thus, the sound is dull over the pectoral muscles and over the shoulders; but clear above and below the clavicles, in the arm-pits, and below the angles of the scapulæ. In the healthy chest, then, the clearness of the sound will vary directly as the quantity of lung beneath the part struck, and inversely as the thickness of the walls.

683. Again, wherever the substance of the lung is thin, the sound on percussion is modified by the parts lying immediately behind it: thus, below the fourth rib, the layer of lung in front of the liver on the right side is thin; and the sound is less clear than in the upper

part of the chest. The thin layer of lung which overlays the heart, so as to leave only a small portion of it uncovered (2, Fig. 44), has the same effect. In all such cases, gentle percussion elicits the clear sound of the healthy lung, strong percussion that of the solid substance behind it. The limits of the clear sound are somewhat extended by a deep inspiration, which stretches and expands the lungs; and diminished by a forcible expiration, which contracts them. Tumours in the deeper seated parts of the lung, or consolidation of the lung itself, have the same effect as a solid viscus. Gentle percussion elicits the clear sound of the healthy lung, and strong percussion the dull sound of the tumour or condensed lung beneath. The clearer sound of the healthy lung is exaggerated in the parts of the chest near the stomach by the air which it contains.

684. When the chest is being examined, the patient should be in the erect or sitting posture, and, if possible, in an open room, for curtains and bed-clothes dull the sound. The chest should be bare, or only covered by a single layer of clothing. Each part under examination should be rendered as tense as possible; the anterior part by stretching the neck and throwing back the shoulders; the supraclavicular space by turning the neck to the opposite side; the axillæ, by raising the arms above the head; and the back part by causing the patient to fold his arms and stoop. In comparing opposite and corresponding points, the position of both sides must be the same. If we are examining the front of the chest, the hands must fall loosely; if the sides, they must be raised equally above the head; if the back, they must be equally folded.

685. There are different ways of eliciting the sounds of the chest by percussion. We may strike with the points of the fingers, the flat of the hand, or the fist; or we may interpose the fingers of the opposite hand, a pad of indiarubber, or a plate of wood or ivory. Such things are called "plessimeters," and percussion by their aid is named "mediate percussion." When dealing with slight differences of sound, a plessimeter combined with a hammer may be so used as always to strike with the same force. Dr. Sibson made use of this combination under the name of a "spring plessimeter," consisting of a round pad of india-rubber fixed to the end of an axis, and striking on a plate of ivory. The axis works through a collar, and, being raised, is made to fall each time with equal force by means of elastic springs.

686. Direct percussion with the points of the fingers should only be employed to set the muscles in action, for in many cases, especially in advanced phthisis pulmonalis, the skin and muscles are so sensitive that the slightest touch occasions pain. Percussion with the open hand, or closed fist, is little used, except when we wish to contrast the two sides of the chest over their whole extent at once.

687. Mediate percussion is always to be preferred, and the readiest plessimeter is a finger of the left hand applied to the

surface with a firm pressure, by which the skin and flesh are condensed, and made better conductors of sound. This is especially necessary in stout, flabby, dropsical, or emphysematous subjects. The finger should then be sharply struck by the three middle fingers of the right hand, taking care that the stroke falls directly and not obliquely. In comparing the two sides of the chest, care should be taken to strike the same point, with the same force, and in the same state of the chest, whether full of air in inspiration, or partly emptied by expiration, or motionless as when the breath is held.

688. The chief indications given by percussion in disease, by clear and dull sounds respectively, are shown in the following table:—

	In the Lungs.	*External to the Lungs.*
Resonant or clear.	Healthy condition.	
Hyper-resonant Tympanitic Amphoric	Emphysema. Tubercular excavation.	Very thin chest walls. Pneumothorax.
Dull sound on percussion.	Congestion, hepatization, and condensation. Pulmonary apoplexy. Œdema. Tubercular deposit. Other morbid degenerations.	Pleuritic effusion. Hydrothorax. Hæmothorax. Tumours in pleura or mediastinum. Diseases of heart or arteries, with enlargement.

689. From the part of the chest in which the clear or dull sound occurs, we may often infer the cause which produces it. Thus, emphysema, though it may be confined to one side, and to a limited spot, commonly occurs on both sides, and over a large extent of lung; pneumothorax, on the contrary, is usually confined to one side and, tubercular excavations generally to the upper part of the lungs. Congestion and hepatization occupy chiefly the lower lobes, generally on one side, but sometimes on both; œdema commonly exists in both lungs at the same time, tubercular deposit is found chiefly in the upper lobes; whilst other morbid degenerations occupy all parts of the lungs indifferently. Of causes external to the lungs, effusion of serum, blood or pus into the cavity of the pleura is commonly confined to one side; tumours in the pleura and mediastina may occupy any position; diseases of the heart affect the neighbouring parts; and aneurismal tumours chiefly the upper and anterior part of the chest.

690. *Auscultation.*—The passage of air through the structures of the lungs, in inspiration and expiration, causes certain sounds, which are heard on applying the ear or the stethoscope to the chest, and are found to vary in different situations. In the neck, and at the upper part of the sternum during inspiration, a hollow, blowing sound is heard—this is tracheal respiration; on each side of the upper part of the sternum, between the scapulæ, and sometimes in the axillæ, a whiffing tubular sound—this is bron-

chial respiration; on most other parts of the chest a sound which has been compared to that of a sleeper breathing gently through the nostrils, or to the sighing of a gentle breeze—this is called vesicular, from its presumed seat, the air-cells. This sound is heard both in inspiration and expiration; but the expiratory murmur is usually almost inaudible or very faint. When this breezy murmur is very distinct, as in children, it is termed *puerile respiration.*

691. The intensity of this respiratory murmur varies in different healthy persons, and in the same person at different times. It is more intense, as has just been stated, in young children and in females. It is also augmented by deep inspiration, and, therefore, may be increased by causing the patient to breathe quick, to draw a deep breath, or to cough, whereby the lungs are emptied, and a full inspiration secured. The respiratory murmur also becomes more intense, or *puerile*, in one part of the lung by consolidation of the remainder, and in one lung by consolidation of the other; also by partial impediments to free action of the lung, such as tight stays.

692. The respiratory murmur is sometimes scarcely audible; but in the absence of other morbid sounds, and of dulness on percussion, this indistinctness does not indicate disease.

693. The respiratory murmur may also be absent in limited portions of the chest, through the bronchial tubes being obstructed by tenacious mucus; but here percussion will give a clear sound. When the air-cells are filled with fluid from within, or compressed from without, the chest will sound dull on percussion, unless the pressure be occasioned by air in the pleura.

694. The *bronchial* respiration in health is heard along the track of the large bronchial tubes; but if the lung be condensed, it not only loses its proper respiratory murmur, but, being a better conductor, conveys to the ear the sound produced in the tubes. Hence bronchial respiration heard with unusual distinctness near the site of these tubes, or heard on one side and not on the other, or with widely-differing intensity on the two sides, or in parts where it is not heard in health, is an indication of consolidation by disease or pressure.

695. The bronchial respiration, as thus heard, resembles intense puerile respiration; or the noise made by drawing the breath through the closed hand; or that occasioned by blowing into a quill; or, lastly, the short puff used in blowing out a candle.

696. To the same class of sounds belongs the *cavernous* respiration, which, in its most marked form, produces the illusion that air is drawn through the stethoscope in inspiration, and puffed into the ear in expiration. It generally arises from a cavity in the substance of the lung—but occasionally from a dilated bronchus.

697. The *amphoric* respiration is a sound like that produced by blowing into a bottle, and is caused by the passage of air into or out of a cavity in condensed lung tissue.

698. Besides the respiratory sounds produced in the tubes and air-cells of the lungs, when those parts are moistened by their natural secretions in their usual quantity, there are other sounds due to the increased resistance offered to the passage of air by constriction of the parts themselves, or by fluids of various degrees of consistence.

699. The variation in character and intensity of these sounds is indicated by the terms *râle* (rattling), *rhonchus* (snoring), *crepitation* (crackling), and *sibilus* (hissing, wheezing, or whistling). *Crepitation* is further distinguished as *dry* and *moist*—the dry being due to swollen mucous membrane, constriction of the tubes, or obstruction with viscid phlegm; the moist to fluids of less consistence in the tubes or cells.

700. *Râles* are limited to the larynx, trachea, and bronchial tubes; *Rhonchus* and *Sibilus* to the largest and medium-sized tubes; and *Crepitation* to the fine-air tubes and the air-cells.

701. *Crepitation* is of two kinds—*fine* and *coarse*. Fine crepitation has its seat in the air-cells and smallest air tubes; it is a very delicate sound, resembling that caused by rolling a lock of hair between the thumb and finger. Coarse crepitation is heard in the finer and medium-sized tubes, and is nothing more than fine mucous râle.

702. Crepitation is further subdivided into *moist* and *dry*. *Moist* crepitation (*râle crepitant* of Laennec) is a rapid succession of crackles, such as are produced by throwing salt on a hot iron plate. The sensation may be *felt* by compressing healthy lung tissue, or emphysematous integument. It exists whenever the finer bronchi and air-cells, partially filled with viscid fluid, still admit the passage of air. Hence it is present in œdema and apoplexy of the lungs: occasionally in pulmonary catarrh and bronchitis; often in the first stage of phthisis; and in the first stage of pneumonia, as its most constant and characteristic sign. It disappears when hepatization comes on, and reappears when the inflammation is subsiding. In the first and last of these stages the moist crepitant rhonchus obscures the respiratary sound, but does not completely mask it: in the stage of hepatization, both sounds are absent.

703. *Dry* crepitation. (*Râle crepitant sec à grosses Bulles*, or *craquement* of Laennec.)—This is the sound produced by blowing into a dry bladder. It occurs during inspiration in emphysema, and most distinctly in interlobular emphysema.

704. *Rhonchus* and *Sibilus*.—These sounds indicate a dry state of the mucous membrane. They generally occur together as *sibilant rhonchus*, which resembles a prolonged whistle, the chirping of birds, or the sound emitted on the separation of two smooth oiled

surfaces. The *sonorous* resembles the snore of sleep, the bass note of a violoncello or the cooing of a pigeon. When intense it may be perceived by the hand placed on the chest. All these varieties of sound arise from contraction of a portion of bronchial tube, by swelling of the mucous membrane, by pressure of consolidated lung, or by a plug of tenacious mucus; the sibilant rhonchus existing in the smaller, and the sonorous in the larger tubes. A *click* is also sometimes heard, either during inspiration or expiration, from the sudden displacement of viscid mucus.

705. The *moist* bronchial rhonchus is called the *mucous râle* (*râle muqueux* of Laennec). It is due to the passage of air through tubes containing a fluid, as when we blow through a pipe into soap and water. It is present in pulmonary catarrh, bronchitis, and hæmoptysis; and in all diseases accompanied with much expectoration, as in the third stage of pneumonia, and in phthisis. The *tracheal* râle is a modification of this sound, existing in the trachea when filled with fluid. It has been compared by Laennec to the rolling of a distant drum, or the noise of a carriage in a paved street. The *cavernous rhonchus* is extremely rare. It is caused by the bubbling or gurgling of a fluid in a *circumscribed* space, and is, therefore, a sure sign of a cavity in the lungs, which, in ninety-nine cases out of a hundred, is of tuberculous origin.

706. *Vocal Sounds.*—In a healthy chest there is commonly a diffused resonance, most distinct between the scapulæ, in the situation of the bronchial tubes. If we rest the hand on the chest in the act of speaking, especially if the voice be a bass, we perceive a vibration, or *fremitus*. If we place the stethoscope over the larynx or trachea, the voice seems to pass through the tube, being much more clearly perceived by the ear applied to the stethoscope than by the other. This is *laryngophony*. A similar sound is heard when the lungs between the bronchial tubes and the walls of the chest are condensed, and especially if the bronchi are at the same time enlarged. This is *bronchophony*. If in the cavity of the pleura, outside a condensed lung, there is a thin layer of fluid, as happens in recent cases of pleurisy, a sound is heard like the bleating of a goat, or the squeaking of Punch. This is *ægophony*. Again, in cases of pulmonary excavation, the voice passes through the tube to the ear, as it does in laryngophony, and is called *pectoriloquy*. Lastly, when there is a large cavity communicating with the bronchi, containing fluid and filled with air, a sound is produced during respiration, by speaking, or in coughing, which resembles the falling of a pin into a cup; or the expiratory sound is exaggerated and resembles the faint vibration of a metallic tube. The first is called *metallic tinkling*, the second *metallic breathing*. These sounds occur in large abscesses of the lungs, but most distinctly in pneumothorax, in very rare cases of which disease this metallic tinkling has been produced by each beat of the heart.

707. There is one sound which, though due to an external cause, may be confounded with sounds originating within the chest—the

muscular sound (*bruit musculaire*). It is due to muscular contraction and is very distinct in patients shivering with cold, or in whom the muscles are put on the stretch, as when the shoulders are forcibly thrown back, the hands forcibly raised above the head, or the arms strongly folded across the chest. It is an extremely rapid vibrating sound, closely resembling, when strongly marked, the distant rumbling of carriages over a paved street. The pupil should make himself familiar with it, by placing his ear on the pillow, and contracting the muscles of the jaw with different degrees of force and quickness, taking care, at the same time, to avoid grating the teeth. When he closes the jaw gently, he will hear the rapid vibration just mentioned; a stronger contraction will render the vibration more rapid; a strong and abrupt contraction closely imitates the first sound of the heart. The continuity of the "bruit musculaire" distinguishes it at once from all respiratory and vocal sounds.

708. It only remains to mention two sounds which have their source external to the lungs, in the sac of the pleura. The one is a *friction* or *to-and-fro* sound, occurring both in inspiration and expiration when the pleuræ are dry and rough with deposits; the other a *splashing* sound, distinctly heard by the ear applied to the chest, when there is a mixed collection of air and fluid in the pleural cavity, and a sudden jerk (*succussion*) is given to the chest. This sound is sometimes heard in very large tubercular cavities.

709. The young auscultator may consult with advantage the following table, which presents at one view the chief points just stated :—

SOUNDS PRODUCED BY THE PASSAGE OF THE AIR IN RESPIRATION.

NATURAL.

Tracheal; in the neck and at the top of the sternum.
Bronchial; near the top of the sternum, and between the scapulæ.
Vesicular; on most other parts of the chest.

MORBID.

Bronchial respiration; from condensed lung.
Cavernous; } in cavities communicating with the bronchi.
Amphoric; }

Rales and Rhonchi.
- *Moist*
  - *Mucous;* liquid in bronchi.
  - *Crepitation;* viscid liquid in small tubes and air-cells.
  - *Gurgling;* liquid in cavity.
- *Dry.*
  - *Dry crepitation;* in emphysema.
  - *Cavernous rhonchus;* in cavity destitute of fluid.
  - *Sibilant and Sonorous rhonchus.* Contraction of bronchi, by swelling of mucous membrane, pressure, or tenacious secretion.

SOUNDS OF THE VOICE TRANSMITTED THROUGH THE CHEST.

Healthy.
Laryngophony; over larynx.
Tracheophony; over neck and upper part of sternum.
Bronchophony; near top of sternum, between the scapulæ, &c.
(*Fremitus*, or *vocal vibration;* felt by hand in many parts of chest.)

Morbid.
Bronchophony; sound of voice through condensed lung.
Ægophony; the same, vibrating through a thin layer of fluid.
Pectoriloquy; the same in a cavity of the lungs.
Tinkling, &c.; a changed echo of voice or cough in a large cavity containing air and liquid.

SOUNDS PRODUCED BY THE MOTIONS OF THE LUNGS.

Friction-sounds, when the pleuræ are dry or rough from deposit.

SOUND PRODUCED BY SUCCUSSION.

A splashing sound, when the cavity of the pleura or a large tubercular excavation contains fluid mixed with air.

SOUNDS PRODUCED BY THE CONTRACTION OF THE MUSCLES.

Vibratory sounds of varying intensity.

THE HEART.

710. The position of the heart and large vessels, with their relation to the walls of the chest, and to the lungs, will be best understood by referring to Figs. 44 and 45. It will be seen that the lungs, which fill so large a part of the chest, leave an irregular space (1 and 2, Fig. 44) in the anterior part of the chest unoccupied. That part of this space (1) which lies behind the upper half of the sternum, has a nearly uniform width of two inches, the anterior edges of the two lungs being here nearly parallel. The lower portion of this space (2), on the other hand, being formed by the wide separation of the left lung from the right, approaches the triangular form. The upper part corresponds to the large vessels, the lower to the heart. This space, however, does not represent the size and shape of the heart and large vessels, but merely of such portions of them as are not concealed from view by the thin edges of the lungs; nor can the heart and large vessels be fully seen until the pericardium has been opened, the cellular membrane connected with it dissected away, and the lungs turned aside to right and left. Posteriorly (Fig. 45), the inner edges of the two lungs are nearly parallel, leaving a centre space (1 and 2) about two inches wide, occupied by the trachea and œsophagus above, and by the œsophagus and descending aorta below. In consequence of the great thickness of the spine and muscles of the back, this space is not favourable to stethoscopic examination.

711. The pericardium, which surrounds the heart, is firmly attached above to the large vessels connected with its base, and to the diaphragm below; so that the heart within this fibro-serous sac descends with the diaphragm in inspiration, and ascends with it in expiration.

712. The large vessels at the base of the heart form a sort of fixed point on which it moves. From this point it is tilted and twisted forward during contraction of the ventricles; towards this point it is raised with the diaphragm, during expiration; and from this point it is pulled downwards during inspiration. These changes of place are exaggerated by the ribs moving in directions opposite the diaphragm.

713. In tranquil breathing, the vertical movement of the heart is scarcely perceptible, but the variation of the height of the apex during full inspiration and expiration is so great, that, during a deep inspiration, the apex instead of beating in the fifth intercostal space, may be felt in the sixth, but indistinctly, from the lung being drawn in front of it. By a forced expiration, on the other hand, the ribs are drawn down and brought closer into contact with the heart, so that it may be felt beating in the fourth intercostal space, and even as high as the third rib.

714. The same act of inspiration which depresses the diaphragm and tilts the ribs outwards expands the lungs, so that their anterior edges slide over the pericardium; and the same act of expiration which forces the diaphragm upwards, and pulls the ribs downwards, causes the lungs to collapse, and their anterior edges to slide back again, thus leaving more of the pericardium exposed. A distended stomach, or a general enlargement of the abdomen, has the same effect on the position of the heart as an act of expiration.

715. In consequence of the free motion which the heart enjoys, it is affected by the posture of the body, receding a little from the anterior walls of the chest when we lie on the back, and moving somewhat to the right or left, as we lie on the sides.

716. The heart, then, occupies an oblique position within the chest, so that, when we stand or sit, the base, fixed by the attachments of the large vessels, is directed upwards, backwards, and to the right; the apex downwards, forwards, and to the left; the base separated from the fifth, sixth, and seventh dorsal vertebræ by the descending aorta and œsophagus; the apex, when the ventricles are contracted, and the respiration tranquil, corresponding to the space between the fifth and sixth ribs—a point about one and a half inch below, and one inch to the inside of the left nipple, or two inches and a half from the left border of the base of the ensiform cartilage. One half the heart, consisting of a small part of the left auricle and the whole of the left ventricle, and the left vertical half of the right ventricle, lies to the left of the sternum, behind the cartilages of the fourth and fifth, and the sternal articulations of the fifth, sixth, and seventh ribs, and the fourth fifth, and sixth inter-

costal spaces: the other half of the organ, consisting of nearly all the rest of the right ventricle, lies behind the lower half of the sternum, a small part only of the ventricle and the right auricle being behind the sternal articulations of the third, fourth, and fifth ribs, and the fourth and fifth right intercostal spaces. The flat under and posterior surface of the left ventricle lies upon the diaphragm, which separates it from the left lobe of the liver; the rounded right ventricle is turned upwards and forwards, separated from the sternum and thin anterior edges of the lungs by the pericardium and loose cellular membrane connected with it.

717. The orifices and valves, which are the seat of the sounds heard on applying the ear or the stethoscope over the heart, are very close to each other, the orifice of the aorta (1, Fig. 48) lying directly behind that of the pulmonary artery (2), while the right and left auriculo-ventricular orifices (3 and 4) are only a third of an inch apart, and just below those of the arteries. The diagram (Fig. 48) shows, in horizontal section, both the relative positions of the semilunar valves and the relative thickness of the walls of the right (5) and left ventricle (6).

Fig. 48.



718. The position of these valves in the healthy subject, relatively to the bones and walls of the chest, has been determined by transfixing them with needles. In the recumbent posture, the bulging part of the pulmonary artery corresponds to the space between the second and third ribs of the left side, close to the sternum; so that a line, *b b*, Fig. 49, drawn across the sternum to the lower margin of the third ribs, passes over the valves of the pulmonary artery, a little to the left of the mesial line (at *v*), and about half an inch above the valves of the aorta, which lie (in the erect *position* of the body) behind the pulmonic valves. The auriculo-

ventricular orifices correspond to a line drawn across the sternum at a somewhat lower level in the third interspace, the valves themselves being situate to the right and left of those of the aorta and pulmonary artery respectively.

719. As a knowledge of the exact relation of the heart, and of its several parts, to the bones and walls of the chest is very conducive to a sound diagnosis of its diseases, the facts already stated will be briefly recapitulated, reference being made to the annexed engraving.

Fig. 49.



720. (1.) *Parts of the Heart and Large Vessels not covered by the Lungs, and separated from the walls of the Chest only by the Pericardium and loose Cellular Tissue.*—The root of the pulmonary artery; the ascending aorta; the anterior surface of the right ventricle; a small portion of the appendix of the right auricle, with the apex and anterior margin of the left ventricle. See 1 and 2, Fig. 44, and the unshaded portion of the heart in Fig. 49.

(2.) *Pulmonary Artery.*—Close to the sternum, in the interspace of the second and third ribs of the left side.

(3.) *Aorta.*—The ascending aorta lies behind the mesial line of the sternum; it makes its first bend behind the manubrium, and is then directed obliquely backwards to the left, forming the arch, the crown of which is on a level with the first intercostal space. The descending aorta commences on the left of the third dorsal vertebra.

(4.) *Valves of the Pulmonary artery and Aorta.*—The first of these is situate immediately to the left of the intersection of a line, *b b*, drawn across the sternum to the inferior margins of the third ribs, with the mesial line, *a a.* The latter lie immediately behind those of the pulmonary artery on a level with the body of the fifth dorsal vertebra.

(5.) *Auriculo-Ventricular Valves.*—To the right and left of the valves of the aorta and pulmonary artery respectively, about a third of an inch apart, the tricuspid being somewhat lower than the mitral.

(6.) *Apex of the Heart.*—When the body is erect and the breathing tranquil, this is felt beating between the fifth and sixth ribs of the left side, an inch and a half below, and an inch to the inside, of the left nipple.

721. In examining the heart, three points demand attention—its *position and size*, its *motions*, its *sounds.*

722. *Position and Size of the Heart.*—These are determined chiefly by percussion, and, in some cases, though with less accuracy, by the touch. In healthy and well-formed persons percussion elicits a dull sound over an area of about two inches in diameter, extending from the point where the heart's beat is felt to the left side of the lower half of the sternum as high as the 3rd costal cartilage. This space, which corresponds to the part of the heart uncovered by the lungs, yields a dull sound, both on strong and slight percussion. Beyond this space the sound is gradually softened off, in proportion as the thickness of the overlapping lung increases; but on strong and sharp percussion, the dull sound is heard through the intervening portion of lung. When the heart is enlarged, or the pericardium filled with fluid, the region of dulness is increased. The same effect is produced by consolidation of the surrounding lung, by tumours between the pericardium and walls of the chest, by partial pleuritic effusions confined by false membranes, or even by enlargement of the left lobe of the liver. It is only in the ascertained absence of such diseased conditions that the extent of dulness on percussion may be taken as the measure of the heart's size. (See Figs. 42 and 43, in which the area of dulness in health and its extension in disease are compared.)

723. On the other hand, the absence of dulness on percussion does not afford certain evidence of non-enlargement of the heart; for emphysema of the lung, pneumothorax, or even distension of the stomach with gas, may give rise to so clear a sound on percussion as to mask the heart-affection. The dulness also ceases, even in healthy persons, on lying down, or taking a deep breath. The *persistence* of a dull sound under these circumstances affords evi-

lence either of adhesions of the heart or lungs, or of such an nlargement of the heart, or distension of the pericardium, as prevents the heart from receding.

724. *Motions and rhythm of the Heart.*—The auricles and ventricles contract alternately, the systole of the one being synchronous with the diastole of the other. The auricles first contract, then he ventricles. The contraction of the ventricles is followed by heir silent diastole, causing a short pause. During the diastole of he ventricles, and the accompanying short pause, the blood flows from the auricles into the ventricles, and the contraction of the auricular appendices, which immediately succeeds the pause, excites he ventricles to new contraction. The order, therefore (or *rhythm*), of the heart's movements is as follows:—systole of ventricles and diastole of auricles; diastole of ventricles, and systole of auricles; corresponding to the interval of no sound or pause. Of the *whole* ime consumed, the systole of the ventricles occupies one half; the ystole of the auricles and the diastole of the ventricles with the pause the other half.

725. The *impulse* of the heart is synchronous with the contraction of the ventricles and the pulse in the large arteries. It is due to he contraction of the ventricles, which are at the same time pressed more closely against the chest wall. The effect is felt chiefly at he apex; for a thick mass of spongy lung absorbs and neutralises he force of the impulse over the rest of the heart's surface. A full xpiration, or the bending of the body forward, by lessening the ntervening portion of lung, extends the limits of the impulse.

726. The strength of the impulse, and the extent of surface over which it is felt, vary greatly in disease. When the walls are hickened at the expense of the cavities (concentric hypertrophy), he impulse is little increased in extent, but greatly augmented in orce; but when the walls are thin and the cavities large, the mpulse is less forcible, but of greater extent. If thickening of the walls is accompanied by increased size of the cavities (in which ase the heart will be greatly enlarged), the impulse is stronger and more extensive, and perceptible over a space of five or six square nches.

727. Fluid in the pericardium renders the impulse indistinct, and ts place variable. Adhesions of the heart and pericardium, on the contrary, confine the impulse to one spot, so that neither change of posture, nor the movements of inspiration and expiration, have any sensible effect upon it. Congenital transposition of the heart s rare. Tumours within the chest and diseases of the lungs may displace the heart, and shift the spot in which the impulse is felt. This will be more distinctly felt, *cæteris paribus*, when the contraction of the ventricle is abrupt.

728. When the heart beats strongly, and especially in emaciated subjects, its movements may be seen as well as felt, and their force, extent, and nature furnish useful indications. When the

heart is enlarged, these movements are perceptible in the epigastric region.

729. The heart is also subject to irregularities of action; such as double and triple impulse, depending generally on spasmodic and partial contraction of the ventricles, and on irregular transmission of blood from the auricles; to intermittence, inequality, and increased or diminished force. As these produce appreciable changes in the pulse, they will be considered under that head.

730. *Sounds of the Heart.*—The natural sounds of the heart are two—a dull, prolonged sound, synchronous with the contraction of the ventricles, the heart's impulse, and the pulse in the larger arteries; and an abrupt, clear sound immediately succeeding the first, and followed by a silent interval. The first sound is loudest over the middle of the ventricles, the last over the site of the semi-lunar valves, and for a short distance upwards along the sternum. Both sounds are most distinct when the pulse is slow, and more so in thin than in stout persons. We hear them in our own persons when lying on the left side; and in disease they may sometimes be heard at a short distance from the patient. The intensity of the sound diminishes as the distance from the præcordia increases.

731. In stout persons, the sounds are limited to the region of the heart itself; in narrow-chested persons, and in children, they may be heard all over the chest, before as well as behind. Any cause which increases the conducting power of the contents of the chest, such as consolidation of the lungs in pneumonia and phthisis, extends the limits within which the sounds are audible. When consolidation is confined to the right side, the sounds of the heart are heard more distinctly on that side, both before and behind, than on the left.

732. *Cause of the Sounds.*—The dull, heavy, prolonged first sound is caused by the contraction of the ventricles and their *musculi papillares*, stretching the cordæ tendineæ and the membranous valves (tricuspid and bicuspid) into which they are inserted. The second sound is due to the sudden expansion and flapping together of the semi-lunar valves.

733. The heart sounds may be changed in intensity or in kind. An increased loudness is often heard during nervous palpitation, both by the patient and his attendants; it may also be produced by dilatation of the ventricles. In the former case, the impulse is increased; in the latter, diminished. On the other hand, the sounds may be so feeble as to be heard with difficulty; as happens in general debility, in obstructed pulmonary circulation, when the heart is overloaded with blood, in softening of its fibres, and in excessive hypertrophy. In the latter case, there will be strong impulse with weak sounds.

734. During nervous palpitation, and after strong exercise, both sounds of the heart are unusually distinct; the contor action being strong and abrupt, and the valves of the aorta closing with a jerk.

735. Of the sounds present in unusual or diseased conditions of the circulation, some belong to the heart, others to the blood vessels. They are the following:—The *bellows sound* (bruit de soufflet), the *simple blowing sound*, the *hissing sound*, the *sawing sound* (bruit de scie), the *rasping sound* (bruit de râpe), a *humming sound* (bruit de diable), a *buzzing sound* (bruit de mouche), a *whizzing sound*, and peculiar musical sounds, such as cooing, whistling, &c.

736. The sounds heard over the region of the heart, or in the large vessels that spring from it, are chiefly the bellows sound and its modifications—the sawing or rasping sound; and the musical sounds.

737. The *bellows* sound is always produced when there is a marked disproportion between the force of the heart's contractions and the size of the tubes or orifices through which the blood has to pass. It may arise—1. In healthy persons, during very strong contraction of the heart, the arteries retaining their normal size; in nervous persons, during violent palpitations, the heart contracting both quickly and forcibly; in chlorotic females, from, as is thought, a thin condition of the blood; and in cases of great debility from sudden hæmorrhage. In these cases the sound is not constant. When present, it bears a close resemblance to the panting noise of a locomotive engine. 2. From narrowing of the orifices, the heart contracting as usual or with increased force: as when the orifice of the aorta or pulmonary artery is contracted, with or without enlargement and hypertrophy of the corresponding ventricle. 3. From narrowing of the orifices by deposits, incrustations, or thickening of the valves. 4. From adhesion of the aortic or auriculo-ventricular valves to the adjacent walls.

738. The student must be cautioned against confounding a rapid tubular respiration with a *bruit de soufflet*. When the cause of the sound is doubtful, the patient should be made to hold his breath.

The place in which abnormal sounds are heard, and the sound of the heart which they accompany, often enable us to fix on their precise seat and cause. Thus, sounds heard only in the region of the heart or over the valves, becoming indistinct when the ear follows the course of the aorta, but more distinct as the ear approaches the apex, may be ascribed to disease of the auriculo-ventricular valves; or to external causes having the pericardium for their seat. On the other hand, sounds heard in the site of the valves, and remaining equally distinct or becoming more distinct as the ear follows the course of the large vessels, may be referred to disease of the coats or valves of the aorta or pulmonary artery. Of the two auriculo-ventricular valves, the mitral is much the more liable to disease. Of the two arteries, the coats and valves of the aorta are by far the most liable to morbid change.

739. If the abnormal sounds accompany the first sound of the heart, they are probably due to disease of the auriculo-ventricular orifices, or of the valves or coats of the arteries. When they

acccompany the second sound, they probably arise from disease of the aortic valves. Double sounds are commonly due to disease simultaneously affecting both the auriculo-ventricular and the semilunar valves.

740. A more exact diagnosis of the causes of abnormal valvular sounds may be arrived at by taking together the position of the valves and the direction in which the sounds are most distinctly conducted. In the case of the tricuspid the valvular sound conducted by the walls of the right ventricle would be most distinctly perceived on the right side, and towards the base of the heart; while abnormal sounds due to disease of the mitral valve would be most distinctly heard on the left side, and towards the apex. So also with abnormal sounds due to disease of the two great arteries; the sounds will continue distinctly audible along the track of the respective vessels, but become less and less distinct as the ear travels in a direction from the base to the apex of the heart. Aortic murmurs, therefore, will continue distinct behind the middle of the sternum, and in the direction of the right shoulder; while pulmonic murmurs, becoming indistinct in that direction, will be best heard at the left of the sternum, between the second and third ribs, and continue distinct in the track of the left pulmonary artery, or for a short distance in the direction of the left sub-clavicular space.

741. The following diagnosis of valvular sounds is in accordance with these statements:—

(1.) A murmur with the *first* sound of the heart heard over the site of the semilunar valves, and most distinct at *c* (Fig. 49, p. 163), is *aortic*.

(2.) A murmur with the *first* sound heard in the same situation, but most distinct at *d*, is *pulmonic*.

(3.) A prolonged murmur with the *second* sound, loudest over the semilunar valves, is due to regurgitation through those valves,—of the aorta, if the sound is loudest in the direction *c e*; of the pulmonary artery, if loudest in the direction *d f*; but in either case becoming less intense, as the ear travels towards the apex of the heart.

(4.) A murmur with the *first* sound, loudest at *f*, is from tricuspid regurgitation.

(5.) A murmur with the *first* sound, loudest at *e*, is from mitral regurgitation.

(6.) A murmur with the *second* sound, loudest at *e*, is from contraction of the mitral; if loudest at *f*, from contraction of the tricuspid.

Lastly, as a general rule, a murmur with either sound distinct at *c* and *d* is semilunar; if distinct at *e* and *f*, it is tricuspid or mitral. And it must be remembered that murmurs originating in the right side of the heart are extremely rare.

742. The indication afforded by abnormal sounds over the heart and large vessels may often be confirmed or corrected by placing the

hand on the wrist, while the ear is applied to the chest. In the case of disease of the auriculo-ventricular valves, when the sound precedes the pulse, it has been attributed to the entry of the blood into the ventricle; but since the contraction of the auricle is too feeble to induce vibration in a stiffened valve, the so-called "præsystolic" murmur requires some other explanation. When the sound is synchronous with the pulse it is caused by reflux of the blood. The indications may also be confirmed or corrected by attending to the pulse. For instance, an irregular, unequal, and feeble pulse is common in disease of the mitral valve, but a full, hard, regular, thrilling pulse in disease of the aorta.

743. The sounds heard in the region of the heart, from causes external to it, are superficial friction sounds, generally double, and in rare cases triple or fourfold. They arise from deposits of fibrin or other morbid formations on the pericardium. They are of limited extent, and are not heard in the course of the large vessels; and they differ from endocardial sounds, by their to-and-fro brushing or rubbing character; they are more superficial, and vary much in intensity, according as the effusion is rough and dry, or smooth and moist.

744. The hand applied to the spot where an abnormal sound is heard often perceives a peculiar *thrill*, like that felt on touching the back of a purring cat. This is called the purring tremor (*frémissement cataire*). A similar thrill is sometimes felt under strong pressure in the healthy arteries themselves, after profuse loss of blood, and in anæmia. It is also present over aneurismal tumours, in aortic dilatations, in arterial varix.

745. The most common sound in the vessels remote from the heart is the bellows murmur. This may always be produced, both in arteries and veins, by the firm pressure of the stethoscope, but is most distinctly heard in chlorotic females, and after hæmorrhages. It is heard in the veins of the uterus during pregnancy, but may be produced by pressure of the stethoscope transmitted to the iliac veins, or aorta.

746. The humming sound (*bruit de diable*) and the buzzing sound (*bruit de mouche*) are also heard under the pressure of the stethoscope in different states of the vessels, and in the large veins. They may be heard in most anæmic females by placing the stethoscope with a firm pressure in the supra-clavicular space; but they are not peculiar to anæmia. They are generally most distinct on the left side, but, in rare instances, are perceptible only on the right or only on the left.

747. This humming or buzzing sound is known from sounds due to the motion of the blood in the arteries by being continuous. Sometimes, as above the clavicles in extreme cases of anæmia, a humming sound, due to the motion of the blood through the veins, is heard at the same time with a bellows sound caused by its motion through the arteries.

748. The peculiar whizzing or grating sound of aneurism, and of aneurismal varix (an accidental opening from an artery into a vein), completes the history of valvular sounds.

4. The Pulse.

749. By the ear or hand applied to the region of the heart, we count the number, force, quickness, regularity, and degree of equality of its beats; but the pulse teaches us this and something more. It is a measure not only of the number, force, quickness, regularity, and degree of equality of the heart's contractions, but also of the quantity of blood sent forth at each beat. Hence it is a better measure of the circulation. It would be a perfect one were it not that the coats of the arteries vary in their contractility. But this circumstance gives the pulse an additional claim to attention; for it serves as an index of the state of the nervous system, by which the contractility of the arteries is determined.

750. Some precautions are necessary in examining the pulse and some directions are required. The first precaution is, to wait till the emotion occasioned by the presence of the medical attendant has subsided. For the purpose of counting the number of beats, a single finger may be used; but in order to observe the more minute changes of the pulse, the four fingers of the opposite hand should be applied in the course of the radial artery, with a moderately firm and equal pressure. By compressing the artery with the ring or little finger, we can ascertain by the forefinger the degree of compressibility. In infants and very young children, it is often difficult to count the pulse at the wrist, and in these cases the beat of the heart should be preferred. The pulse should, if possible, be counted while they are asleep.

751. Of all the characters of the pulse, its frequency is the one most easily ascertained. This usually corresponds with the number of the heart's contractions: it can never exceed, though it may fall short of it. In certain diseases of the heart the ventricles receive so little blood that no impression is made on the mass of the circulating fluid, and the impulse does not reach the radial artery: or the heart contracts without having any blood in it; or some pressure, temporary or permanent, exists in the course of the artery: in all these cases, the pulse is imperceptible, and we miss some of its beats. In syncope, all the beats of the heart are so feeble that no pulse can be felt at the wrist.

752. The number of the pulse in health varies with age, sex, and temperament; with posture, time of day, sleep, exercise, food: with mental emotions; with temperature and density of the air: with the quantity of blood in the body; and with the strength and vigour. Our principal information on this subject is condensed in the following pages:—

753. Age.—*Infancy.*—The number of the pulse is very variable in infants. In the healthy infant asleep on the day of its birth, *Heberden* found it to be between 130 and 140; and according to

Quetelet, the numbers immediately after birth, both for males and females, are as follow :—

Maximum, 165; Minimum, 104; Mean, 135; Range, 61.

The following numbers are from Billard; the averages are approximations :—

	Max.	Min.	Mean.	Range.
1 to 10 days	180;	less than 80 (in 18)	106;	more than 100
1 to 2 months	150;	70	103;	80
1 to 3 months	100;	70	87;	30

The pulse of the infant at birth, and for some time after, is, therefore, very variable, and is little to be depended on as an indication of health.

754. From infancy till towards the middle of life, the number of the pulse progressively diminishes, to increase again slightly towards its decline. The following table, founded on an aggregate of about 700 observations, most of which were made by myself, shows, for the first 25 years of life, the average and extreme numbers of the pulse, without distinction of sex, time of day, or posture of the body. The table shows an uninterrupted fall from 128 to 90, in the first seven years of life, aud a further fall (with irregularities due to the small number of observations) during the 18 years that follow; also a range, for the whole period of 25 years, varying from 56 to 29, and displaying a progressive decrease with fluctuations dependent on the same cause.

Age.	Max.	Min.	Mean.	Range.
1	158	108	128	50
2	136	84	107	52
3	124	84	106	40
4	124	80	105	44
5	133	80	101	53
6	124	70	95	54
7	128	72	90	56
8	112	72	92	40
9	114	65	87	49
10	120	76	91	44
11	100	56	84	44
12	120	70	94	50
13	112	70	84	42
14	114	68	86	46
15	112	60	84	52
16	104	66	83	38
17	102	54	76	48
18	104	58	74	46
19	108	60	76	48
20	106	52	72	54
21	99	59	74	40
22	96	41	68	55
23	100	60	74	40
24	84	52	71	32
25	88	59	73	29

755. The following table shows the number of the pulse at different ages, based on twenty-five observations at each age, all in apparently healthy persons, fasting, at rest, in the middle of the day, and in a sitting posture:—

AGE.	MALES.				FEMALES.			
	Max.	Min.	Mean.	Range.	Max.	Min.	Mean.	Range.
1 week,	160	104	128	56	160	104	128	56
2 to 7 years,	128	72	97	56	128	70	98	58
7—14	108	70	84	38	120	70	94	50
14—21	108	60	76	48	124	56	82	68
21—28	100	53	73	47	114	54	80	60
28—35	92	56	70	36	94	62	78	32
35—42	90	48	68	42	100	56	78	44
42—49	96	50	70	46	106	64	77	42
49—56	92	46	67	46	96	64	76	32
56—63	84	56	68	28	108	60	77	48
63—70	96	54	70	42	100	52	78	48
70—77	94	54	67	40	104	54	81	50
77—84	97	50	71	47	105	64	82	41

756. The pulse of the adult male, then, may be stated at 70, that of the adult female at 80: the highest number is somewhat less than 100 in the male, and somewhat more than 110 in the female; the least number in each is about 50. The range (difference between the highest and lowest numbers) extends from 28 to 56 in the male, average 43; and from 32 to 68 in the female, average 48; The lowest number in the table is 46: the lowest observed by Floyer was 55.

757. Much lower numbers have, however, been met with in healthy persons. Heberden records, 42, 30, and even 26 beats in a man whose "chief distemper" was the age of fourscore; and Fordyce, 26, in an old man in the Charter-house. In a young man whose pulse is not included in the table (he suffered from slight dyspepsia, and has since died of phthisis), I have repeatedly counted as few as 38 beats; and in a medical man reduced to extreme weakness by a succession of exhausting maladies, and who had slowly recovered health and strength, I have counted as few as 30 beats; which, or a near approach to it, continues to be the usual number at an interval of some years from the date of his recovery. Pulses as low as 16 or even 14 are on record, but it is doubtful whether the persons examined were healthy. Falconer has observed pulses of 36 and 24 in women, and Dr. Graves one of 38.

758. In disease, extraordinarily small numbers have been counted; one case is reported by M. Piorry, in which there were 17 beats in

a minute; in a case of epilepsy (Sir W. Burnett) the number was 14; Heberden was told of a pulse of 12 or 16; and in a remarkable case of injury to the upper part of the spine, followed after an interval by fits of syncope with convulsions, the pulse was usually about 33, but fell during the fits to 12, 10, 8, "and at three or four different times, when the patient was quite insensible, and not in a fit," 7½ in a minute. (Mr. Holberton, in "Med.-Chir. Trans." 1841.) These low frequencies of pulse are generally little affected by stimuli, and, as in the case reported by Dr. Graves, remain unaltered by febrile attacks.

The pulse often falls very low during convalesence from fevers and other exhausting maladies; and a very infrequent pulse has been specially noted among the anomalous symptoms of diphtheria.

759. On the other hand, there may be exceptions of an opposite kind—that is, cases of great frequency of pulse; but I have no well-authenticated instances to report. But in disease the pulse sometimes runs very high. Floyer thought that the greatest number which could be counted was 140; but Heberden met with a pulse of 180. Dr. Joy counted 200 in a case of acute hydrocephalus; and a medical man, as well as a medical friend of his, assured me that during occasional violent fits of palpitation he counted in his own person 250 beats in the minute; I have myself counted upwards of 170 in pulmonary consumption; and during the rapid formation of diffused abscess of the arm, in a boy ten years old suffering from a fatal attack of enteric fever, I distinctly counted 264 beats in the minute, being nearly nine in two seconds. Twice, when suffering from attacks of indigestion, I have counted in my own person, without the watch, what must have been at least 250 beats. (G.)

760. *Sex.*—On comparing the two columns of the last table, it will be seen that the pulse of the female has nearly the same number as that of the male up to seven years, but that at more advanced ages the female pulse is in excess by from 6 to 14 beats, the average excess being 9. The pulse, too, has a greater range in the female; that is to say, there is a greater difference between its highest and lowest numbers; the pulse of women being often much more frequent than that of men, while in other instances it falls nearly as low.

761. As it is not easy to bear in mind the number of the pulse in the two sexes for the several periods specified in the tables, the following approximate figures may assist the memory:—

1. At birth	140
2. Infancy	120
3. Childhood	100
4. Youth	90
5. Adult age	75
6. Old age	70
7. Decrepitude	75–80

An addition of about 10 beats will have to be made to 4, 5, and 6, in order to give the numbers in the female.

762. *Temperament.*—Nothing is certainly known of the influence of temperament. The pulse is probably more frequent in the sanguine and nervous than in the lymphatic and bilious; but I have counted 50 beats in a youth under 20, with every mark of the sanguine temperament.

763. *Posture.*—In the healthy adult male the mean frequency of the pulse in the different postures is as follows:—

Standing, 79; sitting, 70; lying, 67; including all exceptions.
Standing, 81; sitting, 71; lying, 66; excluding all exceptions.

In the adult female of the same mean age the numbers are—

Standing, 89; sitting, 82; lying, 80; including all exceptions.
Standing, 91; sitting 84; lying, 80; excluding all exceptions.

764. The extremes are very remote from these mean numbers. Thus, in men, the difference between standing and sitting may be as high as 26, and as low as 0; that between sitting and lying as high as 18, and as low as 0; and that between standing and lying as high as 44, and as low as 0. In women, differences scarcely less marked have been observed. Numerous exceptions also exist to the rule that the pulse is more frequent sitting than lying, and standing than sitting. The effect of change of posture on the same number of the pulse is nearly twice as great in males as in females, and nearly three times as great in adults as in early youth.

765. The effect of change of posture increases with the frequency of the pulse, as is seen in the following tables:—

MALES.

	51–70	71–90	99-110	111-130
Standing	61	81	101	120
Sitting	55	68	82	93
Lying	52	67	74	81
Difference between standing and lying	9	14	27	39

FEMALES.

	61–80	81–100	101-120
Standing	71	92	108
Sitting	67	85	97
Lying	68	83	90
Difference between standing and lying	8	9	18

766. The exceptions to the rule decrease as the frequency of the pulse increases, and for the higher numbers disappear. The effect of change of posture on the same number is greater in the morning than in the evening. When the head is placed lower than the body the pulse falls.

767. The number of the pulse in the different postures is determined by the muscular effort required to support the body in those postures.

768. The effect of change of position is much increased by debility, but diminished in phthisis pulmonalis, and, according to Dr. Graves, is reduced to zero in hypertrophy of the heart.

769. *Period of the Day.*—The pulse of the healthy male is, as a general rule, more frequent in the morning than in the evening, to diminish as the day advances. To this rule there are many exceptions in men, and still more in women. The fall is also more rapid and uniform in the evening than in the morning. It is also a general rule that all exciting causes act more powerfully on the pulse in the morning than in the evening.

770. In experiments on the pulse in my own person, I found that the effect of the same food on the same number of the pulse was, taking one experiment with another, nearly twice as great, and lasted more than three times as long, in the morning; while in more than one instance the same food which in the morning raised the pulse from 5 to 12 beats, and kept it raised for one or two hours, had no effect whatever in the evening.

771. *Sleep.*—The pulse falls considerably in sleep. Quetelet found a difference of 10 beats in an adult female, the same difference in a girl from three to four years old, and in a boy from four to five years a difference of 16 beats. Sleeplessness excites the circulation.

772. *Exercise.*—This excites the pulse more than any other cause. It may raise it to more than three times its natural number. Change of posture is but a particular case of this. After severe and continued exertion the pulse suffers the same collapse as the other functions, and falls much below its natural number. Passive exercise also excites the pulse.

773. *Food.* The pulse is little affected by vegetable food, more by animal substances, most of all by warm drinks. Spirituous liquors and tobacco, even though used habitually, raise it; cold liquids lower it.

774. *Mental Emotions.*—These have a marked effect on the pulse, the exciting passions raising it, the depressing passions lowering it. The apprehension which patients feel in the presence of their physician is well known to excite the pulse, and the caution not to count it till the excitement has ceased is as old as Celsus.

775. *Temperature of the Air.*—Cold air lowers the pulse, warm air raises it. When Sir C. Blagden remained eight minutes in air heated to 260°, the pulse rose to 144, double its natural number.

776. *Density of the Air.*—De Saussure found the pulses that beat 49, 66, and 72 times respectively at Chamouni, raised to 98, 112, 100, on the summit of Mont Blanc. Dr. Frankland's pulse after six hours' perfect rest and sleep, at the top of Mont Blanc was 120, on descending to the corridor it fell to 108, at the Grand Mulets it was 88, and at Chamouni, 56. His normal pulse was 60. (Kirke's "Physiology.")

777. *Quantity of Blood in the Body.*—The pulse is more frequent in that degree of plethora which falls short of overloading the heart; its frequency is but little increased when the heart is oppressed. Compression of the arteries raises the pulse by producing the first degree of plethora. A slight decrease in the quantity of blood lowers the pulse; a considerable decrease raises it.

778. *Debility.*—In debility without disease the pulse falls; it rises in extreme weakness, or when debility is complicated with irritation.

779. The common causes of increased frequency of pulse in healthy persons, therefore, are the following: Muscular exertion, active and passive exercise, a change from a posture requiring less effort to one requiring more, food (especially warm drinks, spirituous liquors, and tobacco), heat, diminished pressure of air, extreme debility, sleeplessness, the first degree of plethora, and exciting passions and emotions.

780. The chief causes of diminished frequency, on the other hand, are sleep, fatigue (provided it be not carried to excess), change of posture from one requiring greater effort to one requiring less, the inverted position of the body, continued rest, debility without disease (provided it be not extreme), cold applied externally or taken internally, increased atmospheric pressure, and depressing passions.

781. Other characters of the pulse, besides its frequency, deserve notice. The pulse of healthy men may be described as regular, moderately full, compressible, and rising slowly under the finger; that of healthy women and children as smaller and quicker in the beat. The pulse in the sanguine temperament is full, hard, and quick; in the lymphatic temperament, slower in the beat. In old age the pulse is often rendered hard by the increased firmness of the arteries.

782. Exceptions also occur to the regularity of the pulse; instances having been observed in which the pulse was irregular or even intermittent in health, and regular in disease, resuming its intermittent character on recovery. Heberden records two cases in which the pulse that was both irregular and unequal in health, *became regular* during illness. In some persons this irregularity

occurs on every slight attack of indigestion, especially where much flatulence is present. In other cases, where no other obvious cause exists, a severe attack of indigestion may raise the pulse to as many as 250 beats.

783. The number of the pulse, then, though a point of much importance, is not the only one that demands attention: it has other characters of at least equal value. The following description and explanation of them will be found useful:—

784. The impression made on the finger by the pulse is compounded (*a*) of the beat of the heart, (*b*) of the reaction of the aorta and large vessels, (*c*) of the condition of the coats of the artery, (*d*) of the consistence of the blood, and (*e*) of the state of the aortic valves.

785. (*a*) The characters of the pulse which depend upon the degree and mode of the heart's contraction are the following:—

Number of the heart's contractions.—Pulse, *frequent*, *infrequent*.

Regularity of the heart's contractions.—Pulse, *regular*, *irregular*: (intervals unequal), *intermittent* (intervals equal).

Quantity of blood expelled by the heart.—Pulse *large* (full), *small:* quantity at each beat the same, pulse *equal;* different, *unequal*.

Time occupied by each beat of the heart—Pulse *slow* (labouring), *quick* (sharp), *very quick* (jerking or bounding).

786. (*b*) A healthy tone of the arterial wall produces a *steady* pulse; the absence of this occasions the peculiar *thrilling* pulse of aortic disease and of aneurism. The following modifications are due to this cause:—

Contractility of the arteries increased.—Pulse *hard* (strong, sharp, wiry, incompressible).

Contractility of the arteries diminished.—Pulse *soft* (weak, yielding, compressible).

Elasticity lost in the large arterial trunks.—Pulse *jerking, thrilling, vibrating.*

787. (*c*) The character of the pulse is further modified by the degree of contractility or *tone* of the muscular fibres in the coats of the smaller arteries. It exists in every degree from the tense state of high nervous excitement or rude robust health, down to the flabby condition of collapse, shock, or extreme debility.

788. (*d*) The influence which the consistence of the blood has in modifying the pulse is best seen in extreme cases of anæmia, in which an important element being deficient, the pulse assumes the *thrill* that in other cases is due to a loss of elasticity in the arteries.

789. (*e*) The state of the aortic valves has a marked effect on the pulse. In health their prompt closure keeps the arterial system full, and conduces to steadiness in the pulse. But when

the valves are diseased and patent so as to allow regurgitation into the left ventricle, each pulse is peculiarly distinct, the wave caused by each contraction being felt as if the blood were "shot under the finger," the vessel in the interval being unusually empty. This is an exaggeration of the *jerking* pulse of anæmia.

790. The foregoing characters of the pulse are rarely, if ever, met with separately, but admit of various combinations, of which the following are the most important:—

Pulse *frequent, large, soft.*—(Compounded of a frequent beat of the heart, a large quantity of blood sent out by each contraction, and an artery wanting in elasticity and tone.) This pulse accompanies the premonitory stage of many febrile and exanthematous diseases, and it is present in dilatation of the left ventricle.

Pulse *frequent, large, hard.*—(Compounded of a frequent beat of the heart, a large quantity of blood sent out at each beat, and an artery full of elasticity and tone.) The pulse of the first degree of plethora and of hypertrophy with dilatation.

Pulse, *rather frequent, large, slow* (labouring).—(Compounded of a rather frequent and slow beat of the heart, and a large quantity of blood sent out at each contraction.) The pulse of a greater degree of plethora, the heart overloaded with blood.

Pulse *frequent, large, hard, quick.*—(Compounded of a frequent and quick beat, a large circulation of blood, and an artery full of elasticity and tone.) The pulse of inflammatory fever.

Pulse *frequent, large, hard, thrilling.*—(Compounded of a frequent beat, a large quantity of blood, the artery at the wrist elastic and full of tone, with a loss of elasticity in the larger arteries.) The pulse of aneurism; and of dilated aorta, without obstruction to the flow of blood.

Pulse *frequent, small, quick.*.—(Compounded of a frequent beat, a quick contraction, and a small quantity of blood sent out at each beat.) This is the characteristic pulse of phthisis in males, and of anæmia in females. In a moderate degree, indeed, it is the character that marks the female pulse, and is present in an exaggerated form in all the less severe disorders of women. With the addition of extreme hardness, it is the pulse of hypertrophy with contraction of the heart.

Pulse *unequal* and *irregular, frequent* or *infrequent.*—(Compounded of a variable quantity of blood sent out at each contraction, and of contractions performed in unequal times.) As the quantity of blood sent forth by the heart may depend upon one of two causes,—diminished supply from the auricle, or want of power in the heart,—this pulse may indicate mitral valve disease, or atrophy or softening of the heart. It may depend, also, on causes which render the supply of blood to the left auricle variable. Hence it occurs in some diseases of the lungs. A similar pulse may occur suddenly as the consequence of the formation of a large polypus in the left ventricle, or from pressure on the heart by effusion into the pericardium.

Pulse, *infrequent, large, hard.*—(Compounded of an infrequent beat, a full supply of blood, and an artery in a state of elasticity and tone.) A pulse met with in apoplexy before depletion has been practised, in hydrocephalus, in compression of the brain, narcotism, and in simple hypertrophy of the left ventricle.

Pulse *infrequent, quick.*—(Compounded of an infrequent and a quick beat of the heart.) A pulse sometimes met with in the hysteric female, and in very rare cases of phthisis in the male.

791. These are the leading combinations of the chief elements of the pulse. They are given partly as examples of the use of terms, partly as hints to those who may wish to follow out the study of the pulse.

792. Taken in combination with other symptoms, the pulse furnishes important indications in all diseases; while in pulmonary consumption and diseases of the heart and arteries, it often gives the earliest clue to the existence of an obscure and lurking malady. Hence its importance to the medical examiners of insurance offices.

793. It must not, however, be supposed that the pulse is free from the uncertainties that attach to all other symptoms of disease. On the contrary, we encounter, from time to time, remarkable exceptions to general rules. There are no characters of the pulse, for instance, more generally present than those just indicated as occurring in pulmonary consumption, especially in men; but among some hundreds of cases conforming to the rule of increased frequency, we meet with a single case in which the number falls short even of the average in health. In one case I counted a pulse of 64 in the erect posture. The dyspeptic patient referred to at § 757, as having a pulse of 38, died several years afterwards of pulmonary consumption. In other diseases and states of system usually characterized by great frequency of pulse, very curious exceptions do occasionally take place. There have been epidemics of continued fever characterized by a very low frequency; and cases of all the more severe febrile disorders marked by the same curious exceptions to the rule. Thus, Dr. Wells counted a pulse of 58 in a boy eight years of age, suffering from anasarca after scarlatina. Of the striking difference of frequency that may exist in two persons suffering from the same disease, Heberden gives a good illustration. Two young women were ill of the same infectious fever, and the pulse of the one was never above 84, while the pulse of the other was counted as high as 180. Both recovered. The low frequency in the first case was thought to be due to the state of the brain, "which was affected comatosely."

794. The pulse in disease is also subject to great variations in the same persons, either within short intervals of time, or in states of system in other respects apparently the same. Thus, it is not uncommon in typhus fever to find the pulse varying in a few hours from 40 or 50 beats to 120 or 130; and in a case of phthisis, the pulse, which was 64 in one attack, was 120 in a second, not distinguishable from the first by any other symptom.

Changes in the frequency of the pulse in either direction afford very important indications in disease. Thus, Heberden remarks, "that before some critical swelling or deposit of matter begins to show itself in fevers, the pulse will be so rapid and indistinct as hardly to admit of being counted," a statement confirmed by the case cited § 759. The same accurate observer tells us that if, in an illness, a pulse of feverish quickness all at once becomes quiet, while all the other bad signs are aggravated, we are to suspect a translation of the diseased condition to the brain, and to apprehend apoplexy, palsy, or death: and, again, that if the pulse of a child be 15 or 20 below the healthy standard, with signs of considerable illness, the brain is certainly affected.

795. Besides the simple characters of the pulse already described, others less common and more obscure have been mentioned by authors, of which the following are examples:—The redoubled pulse (*dicrotus, bisferiens, bisiliens*), when two strokes follow each other rapidly, and are separated from the two succeeding ones by a pause —a pulse said to indicate approaching hæmorrhage; the *incident* pulse (*incidens, inciduus*), when the second pulsation is weaker than the first, the third than the fourth, after which there is a stroke as strong as the first: this is the critical pulse of the old writers; the *pulsus caprisans*, admirably named, but rarely felt; it consists in a small pulse, succeeded after a short interval by a large one, conveying the impression of an unsuccessful effort, followed by the overcoming of an obstacle.

Fig. 50.



Much light has been already thrown on the variations of the pulse in health and disease, and more may be confidently expected, by the use of the sphygmograph invented by M. Marey, and improved in some minor details by Dr. Sanderson. This ingenious instrument, may be described as a skilful combination of springs and levers, by which all the changes that occur in the radial artery in a short period of time can be correctly exaggerated and traced on paper, or on an oblong fragment of smoked glass.

It may be well to show by examples the striking differences that have been ascertained to exist between the pulse in health and in one or two diseased conditions. The curves in Fig. 50 show—1. The firm long pulse of vigorous health. 2. The soft pulse of ordinary health. 3. The hard pulse of chronic Bright's disease. 4. The undulatory pulse of typhus. It will be seen that the number of the pulse is indicated as well as its character. Thus, the pulse in 1, is 50; in 2, 56; in 3, 70; in 4, 160. These outlines are selected from the plates given by Dr. Sanderson in his excellent "Handbook of the Sphygmograph," to which the reader is referred for fuller information.

5. The Respiration.

796. The number and character of the respiratory movements, and the relation they bear to the circulation, frequently engage attention at the bedside. In order to appreciate rightly their value as signs of disease, it must be borne in mind that the muscles of respiration are under the control both of voluntary and involuntary nerves, and that their subordination to the will renders them liable to all those affections of the voluntary muscles in which volition is suspended, lost, or interfered with, such as chorea, tetanus, and hysteria.

797. As respiration may be in part a voluntary act, it is necessary in experimental inquiries to eliminate the disturbing element of the will. This is best done by means of such an instrument as will register the number of respirations during a considerable interval without requiring the attention of the experimenter. (See § 672.)

798. At the bedside, this object may be secured by placing the hand of the patient on the abdomen, as if to count the pulse. By relaxing the grasp on the wrist, and allowing the hand to rise and fall with the movements of the abdomen, the respirations may be counted, without attracting attention to the breathing, and the pulse and breathing counted in succession, and compared. This precaution of holding the wrist should be observed even when, the respirations being audible, we prefer to count them by the ear.

799.—*Number of the Respirations.*—This is subject to as much variety as that of the pulse. It is usually stated at 18 in the minute, or about one to every four beats of the pulse. For the adult male the estimates of authors vary from 14 to 26 in a minute.

800. The respiration, like the pulse, varies in frequency with age sex, posture, and time of day—with exercise, rest, and sleep.

801. *Age and Sex.*—Quetelet got the following results from about three hundred observations on males, and fewer on females:—

	Number of the Respirations.	
Age.	Male.	Female.
At birth	23 to 70	27 to 68
5 years	32	—
15—20	16 to 24	19
20—25	14 to 24	17
25—30	15 to 21	—
30—50	11 to 23	19

802. The range of my own respiration, from my twenty-eighth to my thirtieth year, as founded on numerous experiments with the self-registering instrument, in different postures and circumstances, was 12 to 22. (G.)

803. Vierordt obtained, as the result of observations on his own person, in the *sitting* posture, a maximum of 15, a minimum of 9, and an average of 12. Hutchinson, in rough and inexact experiments on 1714 healthy males in the same posture, found a minimum of 6, and a maximum of 41; while the greater number were found to breathe 20 times in the minute, and a very large proportion between 16 and 24 times. The recorded frequency of respiration in the persons of the principal experimenters on that function ranges from 14 to 27.

804. *Posture.*—The results of a large number of observations, made on my own person, by the self-registering instrument, were as follows:—For a pulse of 64 the respirations were, standing, 22; sitting, 19; and lying, 13. Hence the rule of the pulse—that the difference between standing and sitting is greater than that between standing and lying—is inverted in the case of the respiration. The respiration in the sitting posture, for different frequencies of pulse, ranged from 15 to 21. (G.)

805. *Period of the Day.*—The pulse becomes less frequent as the day advances, but the respiration becomes more frequent. For the same number of the pulse, there are about 18 respirations in the evening for 17 in the morning. The same rule obtains in disease in both sexes.

806. *Sleep.*—In a woman, ætat. 27, Quetelet found the respirations to be, awake, 27; asleep, 21. In two young children the differences were 5 and 8 respectively. In his experiments the respiration was more affected by sleep than the pulse.

807. The other causes which in health affect the frequency of the pulse, produce a like effect on the breathing. Thus, all causes which increase the frequency of the pulse and the force of the circulation, also augment the number of respirations, and the reverse. Exercise increases the number of respirations, rest diminishes

them: heat increases and cold diminishes the frequency both of the pulse and breathing. Sleep, which lowers the pulse, lowers still more the breathing. The only exception to the rule is that of debility; for weakness without disease, if not extreme, is attended by an infrequent pulse, while the number of respirations is increased in every degree of debility.

808. *Proportion of the Respiration to the Pulse.*—This has been variously estimated by authors, at 1 to 4, 1 to 4½, and 1 to 5. But these estimates were formed in ignorance of the effect of posture on the breathing. In experiments on my own person, made with the self-registering instrument, the proportion has varied between 1 to 2·60 and 1 to 5·23; and in the sitting posture from 1 to 2·61 to 1 to 5·00. (G.)

The chief causes of the different ratios of pulse and respiration are posture, time of day, and number of the pulse itself.

809. *Posture.*—For a pulse of 64, the proportion, standing, was 1 to 2·95; sitting, 1 to 3·35; and lying, 1 to 4·97.

810. *Time of day.*—The proportions morning and evening for the same frequency of pulse are about 1 to 3·60 and 1 to 3·40.

811. *Number of the Pulse.*—The ratio of the respiration to the pulse decreases as the pulse increases; for a pulse of 54, being 1 to to 3; for a pulse of 72, 1 to 4. As a general rule, the number of respirations increases with that of the pulse, but in a less rapid ratio, the proportion decreasing as the pulse increases. It is believed that these statements, founded on my own observations will be found in the main correct. (G.)

812. In disease the number of respirations varies within much wider limits than that of the pulse. The smallest number I have counted is 6 in a female in a deep sleep, but not comatose, after attempting suicide by laudanum; and I have counted as few as 10 respirations in a case of paralysis. On the other hand, I have reckoned as many as 44 in a case of phthisis, 73 in a case of paralysis agitans, and 140 in a case of hysteric asthma. (G.) Floyer met with 60 respirations in a case of suffocative catarrh, and in a case of inflammation of the lungs in a child; on the other hand, he counted as few as 7 in more than one attack of asthma. Dr. Graves has recorded as few as 12, and as many as 50, in cases of fever.

813. *Ratio of the Respiration to the Pulse in Disease.*—Floyer found it as high as 1 to 2 in a case of suffocative catarrh, and as low as as 1 to 14 in one of asthma: Dr. Graves as high as 1 to 2 in one case of fever, and as low as 1 to 20 in another. In the case of paralysis agitans already referred to, I counted a pulse of 72 and 73 respirations: in a case of hysteric asthma, 144 pulses and 140 respirations; in a case of transposition of the heart, 32 respirations to 46 pulses; and in a case of paralysis, 1 respiration to 6¼ pulses. In a case of aneurism of the heart, there were 34 respirations to 33 pulses. (G.)

814. These variations in the number of respirations as compared with that of the pulse are readily explained, if we reflect that the respiration is influenced by many causes besides the quantity of blood sent to the lungs by the heart. Some of these are internal, some external. The principal internal causes are the state of the lungs themselves, and of their investing membrane. Among external causes are mechanical obstructions, such as the pressure of tumours on the air passages, constriction of the chest, increased or diminished action of the muscles of respiration, &c. All these obstructions to the free play of the lungs quicken the breathing; and this, whether accompanied by a feeling of uneasiness or not, has been called *dyspnœa*. As this is the chief symptom of all diseases of the lungs, and a concomitant of a great majority of diseases of the heart, its chief causes are here presented in a tabular form.*

CAUSES OF INCREASED FREQUENCY OF RESPIRATION, OR DYSPNŒA.

	I. *Quantity of blood in lungs increased.*	
	a. With quickened circulation.	Exercise, repletion, plethora (1st degree), inflammatory fevers, hypertrophy of the right side of the heart.
	b. With obstacle to return of blood to the heart.	Diseases of the mitral valve, pressure on the pulmonary veins, &c.
	II. *Quality of the blood altered.*	
	a. More venous than usual.	Morbus cœruleus, &c.
	b. Red particles deficient.	Anæmia, chlorosis.
	III. *Deficiency of oxygen.*	
	a. Air pure, but small in quantity.	Air rarefied by high temperature, or diminished atmospheric pressure.
	b. Air defective in quality.	Non-poisonous gases, as nitrogen and hydrogen.
	IV. *Mechanical obstructions.*	
Internal.	a. Of the air tubes.	Diminished size from thickening of walls, from pressure, and from accumulations of mucus.
	b. In lungs themselves.	Congestion, hepatization, œdema, tubercle, &c.; emphysema, dilated bronchi, vomicæ, &c.
	c. In pleural sac.	Hydrothorax and pneumothorax, pleuritic affections and adhesions.
	d. Caused by other organs.	Enlargement of the heart or large vessels, aneurismal tumours.
External.	a. In parietes of chest.	Malformations and distortions, ossification of cartilages, &c.
	b. In abdomen.	Enlarged viscera, tumours or dropsical effusions.
	V. *State of the muscles of respiration.*	
	a. Paralysis (partial).	Injuries of the spinal marrow, in the neck, &c.
	b. Debility.	From fatigue, from exhaustion, after severe febrile affections, and at the approach of death.

---

* A similar table is given by Dr. Williams in Lib. Pr. Med., vol. iii. p. 25.

c. Pain.	1. In muscles.	In intercostals, diaphragm, or abdominal muscles, those acting which are free from pain.
	2. In surrounding parts.	In the abdomen in peritonitis, in the chest in pleurisy, the muscles that cause least pain acting alone.
d. Spasm.		Tetanus, hydrophobia, &c.
e. Other forms of augmented innervation.		Strong mental emotions: hysteria, asthma.

815. The chief causes of diminished frequency of respiration are sleep and coma, whether produced by narcotics or by cerebral pressure. Hence the breathing is slow in apoplexy, and in narcotic poisoning.

816. Other characters of the respiration, besides increase of number, merit attention; as the full or deep, the small or feeble, the equal or unequal; the regular or irregular; the short, quick and catching; the long, the labouring; the thoracic, the abdominal, and diaphragmatic.

817. A peculiar respiration associated with fatty degeneration of the heart has been described by Drs. Cheyne, Stokes, and Sibson. The patient, after being in a state of apnœa for a quarter of a minute or more, has a feeble respiration followed by a succession of breathings, increasing up to a maximum of strength, and then as gradually diminishing.

818. The number of respirations taken by itself is of little value; but when combined with observations on the pulse, or examinations of the chest by percussion and auscultation, it may be significant. Thus, a frequent respiration, taken alone, may arise from any one of the many causes specified in the table; but coupled with an infrequent pulse, in the ascertained absence of visceral disease, it indicates great debility; or, in its absence, hysteria. On the other hand, an infrequent pulse and respiration combined would as probably arise from some disease or injury of the brain, or of the upper part of the spinal cord. Again, a frequent and quick respiration, without visceral disease, but attended by acute pain of the chest or abdomen, is explained by the existence of that pain, whether its seat be the muscles or the peritoneum.

819. Important indications may also be obtained by noting the number of respirations day by day in acute diseases. In pneumonia, for instance, a daily diminution in the number, with or without a similar change in the pulse, gives good hope of recovery; in apoplexy or in narcotic poisoning, on the contrary, a rise in the number, especially if attended by increased frequency of pulse, may be considered a good symptom. So in convalescence from fever, or other exhausting malady, a falling respiration, with a rising pulse, is a sure sign of returning strength.

820. In using these, as well as the less important symptoms and signs of disease, the observer should be on his guard against the common error of trusting implicitly to any one sign, however valu-

able, to the neglect of others capable of affording useful information. In diseases of the chest, for instance, neither stethoscopic signs, nor respiration, nor pulse alone, can furnish the practitioner with all the information which he wants; but if, knowing the exact value of each of these signs and the fallacies attaching to each, he uses all of them at the same time, there are few difficulties in diagnosis which he will not be able to overcome.

6. Other Symptoms and Signs of Disease.

821. Besides the signs and symptoms examined in the first five divisions of this chapter, there are many others of which it is easier to recognize the importance than to arrange them in a manner free from objection. Some of them, as the expression of the countenance, the appearance of the tongue, and the presence or absence of pain, are subjects of observation and inquiry in every case without exception; while others, as the appearance of the sputa, or of the discharges from the bowels are noted only, or chiefly, in diseases of the lungs, or of the primæ viæ. Yet these symptoms of larger import often associate themselves very naturally with others of very limited application—*e.g.*, the appearance of the tongue with that of the lips and gums in anæmia; so that it seems reasonable to group them together, and to treat them in connection with each other. Accordingly the remaining symptoms and signs will be examined in this section under the distinct heads of—1. The organs of digestion. 2. The organs of circulation. 3. The organs of respiration. 4. The urinary and genital organs. 5. The nervous system. 6. The temperature of the body. 7. The expression of the countenance, and the condition and attitude of the body.

822. (1.) The Organs of Digestion.—The condition of the alimentary canal is revealed to us in part by the state of the tongue; in part by alterations in the functions of the stomach and intestines, such as nausea, vomiting, and purging; and in part by the character of the matters voided from the stomach and bowels.

823. The value of the *tongue* as a symptom or sign of disease, and an aid in diagnosis and prognosis, will be understood if it is borne in mind that it consists of a dense mass of muscular fibre, largely supplied with blood, covered with a secreting membrane, and lying in a bath formed of the secretions of the mouth and salivary glands. It may, therefore, be expected to indicate the state of the muscular and nervous systems, of the circulation, of the secretions generally and especially of those of the alimentary canal, to which it belongs by continuity of membranous covering, and as subserving the function of mastication.

824. The tongue has not the same appearance in all healthy persons. In some it is habitually clean, in others slightly furred; in some florid, in others pale; in some compact and firm, in others flaccid and indented by the teeth; in some it is broad and flabby when protruded, in others strongly contracted and drawn to a point.

Even in the most healthy persons it is covered with a thin white fur in the morning before taking food, and those who sleep with the mouth open, awake with a perceptible dryness of tongue.

825. In disease, the tongue presents a variety of appearances. As to *size*, it is swollen in inflammation of the organ itself, in severe diseases of the adjacent parts, in salivation from mercury, and in malignant disease; on the other hand, its size is diminished when there is much emaciation. The swollen tongue is often indented by the teeth, an appearance which it also wears in that relaxed and flabby state that often accompanies great weakness. Its *form* varies with the mode in which it is protruded; but as a general rule, it is small and pointed in "irritation" broad and flabby in exhaustion. The *temperature* of the tongue is low in syncope, apnœa, and, in common with the breath, very low in cholera. Its *colour* coincides, to some extent, with that of the general surface, being florid in plethora; pale after profuse discharges, in anæmia and allied states of system, and in many chronic wasting maladies; and livid in apnœna and in diseases of the heart and lungs which greatly impede respiration. Its colour also depends on the state of the digestive organs; being universally red, or red at the tip, or at the edges, or both, in some cases of acute inflammation of the mucous membrane of the stomach and bowels. It is also very red and tender in some cases of scarlatina, and in continued fevers after the disappearance of the fur. A smooth red tongue, sometimes known as a "glazed" tongue, is often present in fever attended by great irritation of the stomach and bowels, and in idiopathic affections of those organs. The tongue is also red in acute inflammation of the throat. In poisoning by the mineral acids it is stained of characteristic colours, and has its epithelial covering partially or wholly removed.

826. Much importance attaches to the state of the tongue in respect of *moisture*. As the tongue of a healthy person is kept moist by the secretions of the mouth, and by the saliva, it becomes dry when those secretions fall short of the quantity required to supply the loss by evaporation and that which from time to time passes down the gullet in the act of swallowing. It is obvious, therefore, that the tongue must afford a valuable index of the state of the secreting organs, and of the condition of the circulation, as promoting or retarding their proper functions. Accordingly a dry tongue, such as exists in inflammatory and febrile states of system, indicates a state of circulation unfavourable to secretion in other organs as well as in the tongue and mouth. On the other hand, a moist tongue indicates a favourable state of the secretions generally, and the absence of any high degree of inflammation or fever; and it is obvious that a transition from a dry to a moist tongue must always be a favourable sign. Hence, in cases of fever, the physician carefully inspects the tongue, examines it by the touch, and hails a moisture appearing at the edges, and gradually extending to the centre, as the sign of a freer state of all the secretions, and a mark

of approaching convalescence. Again, a moist and flabby tongue, indented by the teeth, is justly regarded as a sign of want of tone and vigour.

827. A *fur* collects on the tongue in almost all severe diseases:—a white creamy fur in the first stage of fever, in catarrh, in quinsy, in most severe inflammations, and in acute rheumatism; a thick brown or black coating in more advanced stages of fever; or the tongue is dry, parched, and tender. A thick, black, dry fur, with black *sordes* about the teeth, is seen in the typhous stage of fever, and in low typhous conditions of the system, coinciding with a highly impure state of the blood, with unhealthy secretions, and fœtid discharges from the bowels. A brown dry fur exists in cases of local irritation, the tongue becoming moist as the irritation subsides. In jaundice, the fur is sometimes tinged with bile,, and in scurvy it is blackened by effused blood. In dyspepsia, the appearance of the tongue is very variable. A thick fur may collect at the base, while the tip and edges are bright red; or the fur extends over the whole surface, and is accompanied by indentations of the teeth, by partial abrasions of the epithelium, and by deep cracks, which are often strongly marked in spirit drinkers. Deep foul ulcers of the tongue, with hard borders, are common consequences of syphilis. In constipation the tongue is sometimes covered with a brown fur; but it may present no unusual appearance.

828. The tongue has usually a characteristic appearance in scarlatina. The elongated florid papillæ protrude through a white coating of fur; or, the tongue, being bright red and free from fur, the papillæ appear distinct on the red ground. In the first case the tongne resembles a white, in the second a red, strawberry.

829. In common with the lining of the mouth and throat, the tongue may be the seat of small superficial ulcers, known as *aphthæ*. These are common in infancy, when they constitute the "thrush;" also in the last stage of pulmonary consumption, and towards the fatal termination of other chronic visceral diseases.

830. The mode in which the tongue is *protruded* is often characteristic. Sometimes it is tremulous in extreme weakness, in cases of idiopathic fever with debility, and under the influence of fear. It is protruded with difficulty when dry; slowly and hesitatingly in diseases accompanied by stupor, in which case it is withdrawn after an interval, and as if in consequence of deliberation. In partial paralysis the tongue is protruded either towards the sound or the affected side of the face.

831. The *gums* afford signs of the state of the circulation, not of the digestive organs. They are florid in plethora; pale in anæmia; livid when respiration is much impeded; swollen and dark, and apt to bleed on the slightest touch, in sea and land scurvy; swollen with a red line in mercurial salivation; marked with a blue line in lead poisoning.

832. The *lips* and membrane of the mouth, like the gums, indicate

the state of the circulation. They are pale in anæmia; dry and parched when the tongue is similarly affected, the seat of aphthous ulcers in young children, in consumption, and towards the close of febrile and inflammatory affections. An herpetic rash on the lips is a common and characteristic accompaniment of severe catarrh.

833. The *teeth* afford some useful indications. During the first dentition they are sometimes the source of much suffering, of severe febrile symptoms, of marked disturbance of the functions of the alimentary canal, of convulsions, and of eruptive diseases. In later life, sound teeth are an indication of vigour, and their early decay is one of the marks of a feeble or scrofulous constitution. They are wrinkled and imperfectly developed as the result of syphilitic taint, or of illness during dentition. Caries of the teeth may, however, be induced by habitual indigestion, by the excessive use of sweets and acids, and by the abuse of mercury. Workmen who handle mercury are subject to chipping of the teeth. The teeth grow loose in scurvy, and during salivation with mercury. They are covered with dark brown or black sordes in continued fevers and in typhous states of system. *Grinding* of the teeth in sleep is common in children suffering from worms or other intestinal irritation; and *chattering* of the teeth accompanies the severe shiverings that usher in many febrile disorders, and form part of the ague fit, as well as a prelude to the formation of matter.

834. The *fauces* and *tonsils* are subject to chronic inflammation and swelling, and the *uvula* to relaxation, indicating a want of constitutional vigour. The same parts are the seat of inflammation in scarlet fever, diphtheria, and severe catarrh; and of ulceration in secondary syphilis. The tonsils are liable to intense inflammation and great enlargement in quinsy, and they are the seat of a painful chronic irritation in public speakers who use the organs of speech unskilfully.

835. *The Saliva.*—An increased flow of saliva may occur as the result of irritation of the salivary glands, in inflammation of the mouth and parts adjacent, or as the consequence of dentition in children, and of unsound teeth in the adult; sometimes, again, as an effect of certain active medicines, such as mercury, iodine, antimony, and their preparations, of prussic acid and digitalis. An increased flow of saliva is not uncommon in pregnancy. Mercurial salivation is distinguished by soreness of the gums, a brassy taste, and a peculiar fœtor. Frothing at the mouth, due in part to increase of saliva, and in part to increased mucous discharge from the air-passages, is a common symptom of epilepsy and hydrophobia, in the first of which the froth is, as it were, churned out of the mouth by convulsive movements of the muscles of the tongue, mouth, and lips; while in the second it is ejected between the closed teeth. Salivation attends one form of paralysis.

836. *The Taste.*—The sense of taste is impaired in all diseases in which the nostrils are swollen or obstructed, as in catarrh; or

in which the tongue becomes dry or furred. When the lingual and glossopharyngeal nerves are diseased; and occasionally in apoplexy. A bitter taste is often present in jaundice, and on waking in the morning in persons suffering from feverish attacks or from severe dyspepsia; and it may be caused instantaneously by strong mental emotion. Consumptive patients often complain of the salt taste of their sputa, and a putrid taste is present in diseases in and about the mouth attended by decomposition. Some dyspeptics also complain of a taste like rotten eggs; and a brassy taste is one of the signs of mercurial salivation. It is probable that the sense of taste is subject to illusion in madmen who swallow their vomited matters, urine, and fæces.

837. *The Appetite.*—Loss of appetite (anorexia) and distaste for food (nausea) are among the earliest symptoms of indisposition and the most constant attendants of severe illness; on the other, hand, a restored appetite is among the earliest indications of convalescence. A failing appetite, again, is an unfavourable symptom in chronic maladies, and in advanced age; but it may be caused in persons not suffering from disease by want of exercise and fresh air, and by depressing passions. A voracious appetite is an occasional result of irritation of the stomach, or of intestinal worms; and it is somtimes a disease of itself, not easily traced to its true cause. It is often present in the mesenteric disease of children, in whom that part of the food which should have nourished the body is prevented from entering the lacteals. A voracious appetite is also common during established convalescence, obviously as a means of repairing the wasted body. Intense hunger is one of the after-effects of Indian Hemp. In some cases it is associated with frequent vomiting of food, as in inflammation attacking the stomach near the pylorus. A depraved appetite (pseudorexia) occurs in pregnant females, in chlorosis, and in hysteria, and in some forms of insanity.

838. *Thirst* is a common symptom of disease. It is present in active inflammations, and in violent febrile attacks, in consequence, probably, of the tongue, mouth, and throat partaking of the vascular fulness of the whole system, and suffering from a distressing dryness. It also occurs in accidents and diseases attended by sudden loss of blood, or rapid outpouring of some important secretion, as in diarrhœa, dysentery, and cholera; in diabetes; in some forms of dropsy; and in cases of phthisis attended with profuse perspiration. In healthy persons it always follows strong exercise, and it is the most [illegible] the soldier on the march, and of the [illegible] battle. It is also a consequen[illegible] matters, as in the sailor fed [illegible] of condiments [illegible] and is a leadin[illegible]

839. T[illegible] *pecul*[illegible]

mixed, pass [illegible] being [illegible] spirits, due [illegible] distinguish the [illegible]. A foul breath is among [illegible] healthy condition [illegible] advanced stages [illegible] in and about the [illegible] by gangrene. [illegible] the mouth, and [illegible] honey in saccharine [illegible].

840. Vomiting is a [illegible] appreciated [illegible] the chief organ [illegible] the brain, heart, and [illegible] symptom of [illegible] consequence of [illegible] organs of the body [illegible] among the causes affecting [illegible] simple overloading [illegible] of its mucous membrane [illegible] to the passage of the [illegible] stomach: permanent [illegible] through the intestines [illegible] inflammation of the entire [illegible] Asiatic cholera. Vomiting is also a common [illegible] narcotico-acrid poisons, and sometimes [illegible] pure narcotics, especially [illegible] of chloroform. To the more [illegible] and [illegible] belong concussion of the brain, the [illegible] an apoplectic seizure, and inflammation [illegible] membranes. Vomiting, again, [illegible] gallstones, and of renal calculi, and [illegible] heart, and of the womb. It is [illegible] females, and is one of the most [illegible] Lastly, vomiting is often [illegible] symptoms of severe attacks of the [illegible] small-pox.

In vomiting [illegible] is important [illegible] general rule, [illegible] to inflamma[illegible] ulcers of [illegible]

[illegible]d
[illegible]ass
[illegible]art
[illegible]llow
[illegible]ght to
[illegible]age in
[illegible]its of in-
[illegible]no skin of
[illegible]rk-red on a
[illegible]en and land
[illegible]ent fevers,
[illegible] into the

returned nearly unchanged in irritation, inflammation, ulceration, or obstructive disease of the stomach itself, in pregnant women, in vomiting due to remote constitutional causes and nervous shocks, and under the operation of many irritant poisons. Clear acid liquids are vomited after an interval of from half an hour to two hours or more in the disease known as gastralgia or gastrodynia. Bile regurgitates from the duodenum, and is discharged by vomiting, in functional and organic diseases of the liver. Blood is often discharged in very large quantities in the disease known as hæmatemesis; generally of a dark colour, clotted, and mixed with food; rarely of the florid hue of hæmoptysis. The blood so discharged may flow from the general surface of the stomach, or from one or more ulcers in the mucous membrane; or it may regurgitate through the pylorus from the duodenum. A discharge of a large quantity of florid blood may be the result of an aneurism bursting into the stomach. A brown grumous matter, often mixed with blood, is rejected from the stomach in poisoning by the corrosives. Vomiting of purulent or muco-purulent matter points to the rupture of an abscess of some neighbouring viscus. Fæculent vomiting is a symptom of mechanical obstruction of the lower portion of the intestinal canal, or of a fistulous communication between the stomach or upper part of the small intestines and the colon. In a highly acid state of the contents of the stomach, a clear acid liquid with a brown frothy scum, abounding in small round black flakes, is sometimes vomited. These, when placed under the microscope, are found to contain the vegetable growths described by Goodsir as *Sarcina ventriculi.* (Fig. 51.)

Fig. 51.



842. The *bowels* are variously disordered; sometimes confined from torpor, from the absence of their natural stimulus, from mechanical obstruction, or from the operation of the poison of lead; sometimes relaxed, from inflammation of the mucous membrane, whether caused by previous constipation, unwholesome food, purgative medicines, or irritant poisons. Diarrhœa is also the usual result of ulceration of the intestines in enteric fever and in phthisis; it is frequently present in advanced stages of tabes mesenterica, and very prevalent during the heats of summer. It is an occasional consequence of a change of residence from cold to hot climates, and from low situations to elevated ones. Strong mental emotions also sometimes give rise to diarrhœa. Associated with vomiting it constitutes cholera, and is a leading symptom of irritant poisoning. Frequent and scanty discharges of watery stools with mucus, pus, or blood, accompanied by tenesmus, mark the disease known as dysentery.

843. The alvine discharges may consist of mucus, tenacious lymph, or pus, as in inflammations of the mucous membrane of the canal, the nature of the secretion depending on the degree of inflammation; or they may consist of blood poured out by the vessels

of the intestines generally, by those of the large intestines exclusively, or by the enlarged veins of the rectum (piles). In tabes mesenterica they consist chiefly of ill-digested food, and in disease of the pancreas they contain an unusual quantity of fat.

844. The fæces may be white from the absence of bile; unusually yellow from its excess; green, as often happens in children; dark and offensive, from the long retention of fæculent matter, or from morbid secretions of the liver; dry and in rounded masses (*scybala*), sinking, instead of floating, in water, from long retention. They assume a light yellow colour under the use of mercurial preparations; a green colour from the mineral acids in large doses; preparations of iron, bismuth and copper turn them black, as does also the admixture of blood in large quantity.

It is important to distinguish those discharges which flow from the general surface of the intestines from such as are the product of disease in the rectum. When, therefore, pus or blood is discharged with the motions, and the symptom is not promptly relieved by proper aperient medicines, the rectum should be examined for piles or fistula, or (if florid blood is poured out in considerable quantity) for a bleeding artery laid bare by ulceration.

845. We are often assisted in our diagnosis by comparing the discharges from the stomach with those from the bowels. Thus, obstinate constipation, with vomiting of fæculent matter, implies mechanical obstruction, as in strangulated hernia; while vomiting, of fæculent matter, mixed with imperfectly digested food (*lientery*) goes far to justify the inference that a fistulous opening exists between the stomach or beginning of the small intestines and the colon (ileo-colic fistula).

846. (2.)—THE ORGANS OF CIRCULATION.—The most important symptom and sign of disease connected with the circulation is the pulse, which has been minutely examined in a former division (4) of this chapter; and some indications of the state of the *capillary circulation* have also been considered when speaking of the gums, lips, and lining membrane of the mouth. Similar indications of the state of the circulation through the small vessels, and of the full or empty state of the vessels generally, are afforded by the appearance of the skin, which is pale after losses of blood in anæmia, in leucocythæmia, and in analogous states of system, universally florid in plethora, of a brighter or duskier red, in patches of greater or less extent, in the febrile exanthemata, livid in diseases of the heart and lungs attended with imperfect aëration of the blood, and yellow in jaundice, from the retention in the blood of bile which ought to be eliminated by the liver. The languid circulation of old age is marked by dark discoloration of the skin of the legs; and habits of intemperance often betray themselves by the appearance of the skin of the face, permanently mottled with streaks and spots of dark-red on a yellow ground. In extreme debility, such as occurs in sea and land scurvy, and in the typhous stage of continued and remittent fevers, the small vessels often give way, and the blood is shed into the

surrounding tissues. When the effusion is large, it is called an *extravasation;* when it forms small round spots in the skin, these are called *petechiæ*. Extravasations and petechiæ do not disappear on pressure; but the redness due to plethora, inflammation, or congestion, readily disappears on pressure, but quickly returns on its removal.

847. The *veins*, by their distended and swollen state, sometimes supply useful aids to diagnosis. When, for example, the sounds heard over the region of the heart lead us to infer valvular disease, but leave us in doubt as to the particular valve affected, a visible pulsation in the jugular veins accompanying each beat of the heart indicates regurgitation of the blood through the imperfectly closed *tricuspid* valve. This is called the *venous pulse*. When the pulsations are very distinct, we infer that the walls of the right ventricle are thickened. This true venous pulse must be distinguished from the lifting of a vein by the force of the artery lying beneath it. The superficial veins sometimes become greatly distended and varicose from closure, by pressure or disease, of some deeper-seated venous trunk.

848. (3.) THE ORGANS OF RESPIRATION.—Though the number of the respirations, and the proportion they bear to the pulse, as well as the respiratory movements generally, have been minutely examined in a former part (5) of this chapter, several symptoms and signs of disease, due to disturbance in the functions of the lungs, remain to be considered. The respiratory movements, for instance, of sighing, yawning, sneezing, and coughing, to which may be added the noisy inspiration known as stertor, deserve notice, as well as the changes the pulmonary secretions undergo in disease, and the odour and temperature of the breath. The signs derived from the altered character of the respiratory movements may be treated under the two heads of *noisy inspiration* and *noisy expiration.*

849. *Noisy Inspiration.*—In healthy persons the air passes into and out of the chest noiselessly; but there are diseases which are accompanied and characterized by peculiar inspiratory sounds. A long loud *whooping* inspiration following the complete emptying of the lungs by a succession of violent expirations, or coughs, is the familiar indication of whooping cough; laryngismus stridulus is recognized by the peculiar *crowing* character of the inspirations; and croup by a similar inspiratory sound compared to the crowing of a cock. Attacks of spasmodic and humoral asthma, again, are marked by the loud wheezing or whistling which accompanies each drawing in of the breath. *Stertor, stertorous breathing*, or snoring, is another form of noisy inspiration, occasioned by the flapping of the soft palate when inactive, as in sound sleep, or paralyzed, as in cerebral congestion. Accordingly it is present in apoplexy, and in compression and concussion of the brain; and is one of the group of symptoms known as *coma*. *Sighing* and *yawning* again are forms of deep and audible inspiration, which, as a general rule, indicate the previous imperfect performance of the function of *respiration*, from deficient nervous power, congestion of the

lungs; or a slight mechanical impediment to the complete expansion of the chest. As a general rule, sighing is expressive of emotion or intense occupation of the mind, and yawning of bodily fatigue. Yawning is also present in apoplexy, and in many nervous affections falling short of well-defined disease, and it attends the accumulation of urea in the blood. In the congestion of the lungs which follows recovery from asphyxia, after fainting fits, and during hysterical attacks, sighing and yawning are common occurrences. Among mechanical impediments inducing yawning or sighing as supplementary to the ordinary movements of respiration, tight-lacing and the accumulation of flatus in the stomach hindering the downward movements of the diaphragm may be specified. Another form of noisy inspiration is *hiccough*. This is due to slight spasm of the diaphragm, and is nearly allied in character to that common expression of grief, *sobbing*. Hiccough is often experienced to a painful degree in the act of eating, when the food is swallowed hastily. It occasionally accompanies inflammation of the diaphragm, or of those viscera, or parts of viscera (such as the liver, pancreas, duodenum, or cardiac extremity of the stomach,) which are in contact with, or lie adjacent to it; and it is common in diseases of the kidney. It accompanies the fæculent vomiting of strangulated hernia, and often occurs towards the termination of many acute maladies, when it must be looked upon in a very unfavourable light.

850. *Noisy Expiration.*—Sneezing and coughing are the two forms of noisy expiration, requiring notice as symptoms and signs of disease. *Sneezing* is a violent expulsion of air through the nostrils, following a deep and full inspiration. It either serves to clear the nostrils of some cause of irritation, or it marks the irritable state of the lining membrane which precedes catarrh and measles. It is a symptom of longer continuance in hay-asthma. It often attends the action of iodide of potassium. In common with other violent movements of the muscles of respiration, it may occur in hysteria. *Coughing* is a violent expiratory effort by which the air-passages are freed from offending matters, as the nostrils by sneezing. The contents of the air-tubes thus expelled are said to be *expectorated*, and the act of expulsion is called *expectoration*. The matters themselves are known as *sputa*.

851. There are many different kinds of cough. A cough may be *dry*, or unattended by expectoration; or *moist*, being accompanied by *sputa*. The dry cough may be due to irritation of the pulmonary branches of the pneumo-gastric nerve, or to the pressure of tumours and morbid growths on some part of the air-passages. Hence a dry persistent ringing cough will sometimes indicate aneurism of the aorta. A dry cough is also present in the early stage of inflammation of the air-tubes, when the blood-vessels are in a state of fulness unfavourable to secretion. This happens at the onset of attacks of catarrh, influenza, and croup, and in the first stage of humoral asthma. A dry cough is also one of the results of dyspepsia,

of obstinate constipation, and of intestinal worms; and a loud dry, barking cough is recognized as a symptom of hysteria. The cough in incipient phthisis is either dry or attended with scanty expectoration. An inflamed state of the fauces with enlarged tonsils and relaxed uvula, is another cause of a dry cough. Inflammation or ulceration of the larynx and trachea also gives rise to a troublesome dry cough, or one attended with very scanty expectoration. When the seat of the disease is the upper part of the larynx, the dry cough is accompanied by a hoarse voice. A short, dry cough, attended with acute pain' in the side, is one of the symptoms of pleurisy. A dry cough coming on in paroxysms is called a *spasmodic* cough, and may be often traced to inflammation of the liver, to biliary obstruction, or to disease of some viscus situate near the diaphragm. But coughs accompanied by free expectoration, when occurring in paroxysms, are also termed spasmodic. A *moist* cough is more common than a dry cough. Such a cough is present in catarrh, in bronchitis, in advanced phthisis, in whooping-cough, in pneumonia and in gangrene of the lungs.

852. The *Expectoration*, or *Sputa*.—The matters coughed up from the lungs often furnish important information; but to interpret them aright, we must bear in mind that substances spit out, or otherwise voided from the mouth, may consist of the secretions of the mouth and throat, or of the nostrils, or lungs, as well as of the secretions and contents of the stomach; and it is not always easy to determine, from the description of a patient, which of these parts has supplied the matters submitted to inspection. When, for instance, the fluid consists wholly or chiefly of blood in large quantity, it is not always easy to ascertain whether it came from the lungs by an almost imperceptible cough, or from the stomach by an easy act of vomiting; when, on the contrary, the quantity of blood in the sputa is small, it may be difficult to determine whether it was hawked from the throat or coughed from the lungs. Young children generally swallow expectorated matters.

853. Having ascertained that the matters submitted to examination come from the lungs, we should consider their quantity, both absolutely, and relatively to the time occupied in their discharge, as well as their quality. As a general rule, a continuous and abundant expectoration, especially if coughed up with ease, may be regarded as favourable, as far, at least, as the present state of the patient is concerned. Such an expectoration exists in the moist stage of common colds, in chronic bronchitis, in confirmed phthisis, and in whooping-cough.

854. On the other hand, a scanty expectoration ushers in all acute attacks of disease of the lungs, though it also exists in the first stage of a common cold, and throughout the incipient state of pulmonary consumption. It marks the first onset of a fit of humoral asthma, and the first stage of pneumonia. Again, a transition from a scanty to a more abundant secretion may be looked upon as a favourable symptom, just as the reverse indicates a relapse or in-

crease of disease. When a scanty secretion, coughed up with difficulty, is streaked with blood, it may be taken as evidence of great congestion, or active inflammation of the lungs. Again, a copious sputum brought up in one act or fit of coughing has a significance of its own. It shows either a previous accumulation of the discharged matter in some cavity of the lungs, or in some neighbouring viscus, or a very rapid outpouring of the same from a considerable extent of mucous membrane of the lung itself.

855. The character of the sputa often supplies an important aid to diagnosis; the changes which occur in the course of the same illness being specially deserving of attention. The sputa may consist of unmixed mucus of various degrees of consistence (as in catarrh, bronchitis, and pneumonia); of a thin watery mucus (in some cases of early phthisis); of a tenacious, gelatinous mucus, mottled with small round brown or black spots, and full of air-bubbles (in humoral asthma immediately following the dry stage); of a stringy tenacious brown or rust-coloured mucus (in the first stage of pneumonia); of mucus tinged or streaked with dark blood (in the acme of a fit of humoral asthma, in acute pneumonia, and in some cases of phthisis pulmonalis); of mucus blended with pus (in fully developed catarrh, in bronchitis, and in confirmed phthisis). Again, the expectorated matters may be wholly or chiefly *purulent*, the contents of a cavity suddenly or gradually discharged, or of the sac of the pleura communicating with the lung by a fistulous opening; or of an abscess in the liver, in this case deeply tinged with bile. The sputa have sometimes an extremely offensive odour, arising from the decomposition of the retained secretions, or from gangrenous destruction of the lung tissue. Expectoration of *blood*, often in large quantity, is a common occurrence in disease of the heart and lungs.

856. *Spitting of Blood.*—There are few cases of pulmonary consumption in which this symptom does not happen; and it always furnishes a strong presumption in favour of the existence of that disease. A scanty expectoration of blood may, however, occur in pneumonia, in acute bronchitis, and in the fit of asthma; and a copious and rapid discharge of blood by coughing in the rare disease known as fibrous bronchitis, and in aneurismal tumours communicating with the air-passages, as well as in phthisis. The colour of the blood, the matters with which, if not pure, it is mixed, and the mode of its discharge should always be carefully inquired into, as it may be of great importance to distinguish copious hæmorrhage from the lungs, in hæmoptysis, from equally copious discharges of blood in hæmatemesis.

857. A microscopical examination of the sputa may aid the diagnosis in cases where the symptoms are obscure. When the sputa are of such consistence as to allow of it, they should be washed lightly in water, to remove extraneous matters coming from the mouth. Small portions of the mass may then be covered by thin

glass and examined. In this way we may recognize the fibres of the elastic tissue of the air-cells (Fig. 52), indicating a destruction of the substance of the lung, as in phthisis and gangrene; casts of the minute air-tubes, as in pneumonia and fibrous bronchitis; and the small granular matter of tubercle in phthisis. The sputa in this disease are frequently found to be made up of semi-transparent round, oval, or triangular spots, consisting of small granular cells (*tubercle corpuscles*), mixed with free granules and oil-globules. Sometimes, also, they contain fragments of mixed phosphate and carbonate of lime, which effervesce on the addition of an acid.

Fig. 52.



858. (4.) The Urinary and Genital Organs.—The urine itself has been minutely examined in a previous section of this chapter. The indications afforded by the mode of passing the urine remain to be considered. It may be voided with difficulty (dysuria), and the difficulty may be attended by acute suffering at the neck of the bladder (strangury). The slighter degrees of dysuria are sometimes caused by pressure, or by irritation, propagated from a neighbouring organ, the rectum, when loaded with fæces, or worms. Enlargement of the womb, as in advanced pregnancy, or irritation of the vagina, as in acute gonorrhœa, may cause the same symptoms in the female. Inflammatory affections of the rectum, such as dysentery, will also occasion it; and the irritant poisons cause it, partly by the inflammation set up in the rectum, partly by the irritating quality imparted to the urine. Two poisons especially, cantharides and turpentine, possess the property of inflaming the whole urinary system, and exciting strangury, with painful erections of the penis in the male, and excitement of the genital organs in the female. Frequent and painful micturition may also be occasioned by a highly acid state of the urine, and by gravel. Affections of the bladder itself, such as inflammation (the offspring sometimes of catarrh sometimes of gonorrhœa extending from the urethra), ulceration, spasm, and fungous growths, may give rise to the same symptom; or it may be traced to similar affections of the urethra, to stricture, to enlargement of the prostate, or to the passage of calculi.

859. *Retention of urine*, from an obstacle to the discharge of the urine actually secreted, must be distinguished from *suppression of urine* (ischuria), the effect of disease of the kidney arresting the secretion. Retention of urine may result from continued over-distention of the bladder, exhausting the power of the muscular coat; from disease of the spinal cord paralyzing it; or from loss of sensibility through cerebral disease, or extreme functional disorder of the nervous centres, as in continued fever and in typhous states of the system. Spasm of the neck of the bladder is another cause of retention. It sometimes occurs in hysteria. In many cases the

cause of retention is mechanical. The seat of the obstruction may be in the ureter (as in the passage of a calculus from the kidney), in the bladder itself, or in the canal of the urethra, from enlargement of the middle lobe of the prostate, or from the pressure of a tumour external to the canal.

860. *Suppression of urine* (Ischuria renalis) means a cessation of the secretion of the kidneys. This may occur in idiopathic inflammation of the kidney, or as the result of inflammation produced by irritant poisons, especially cantharides and corrosive sublimate. It may also occur after scarlet fever; and it is a symptom of Asiatic cholera. Extreme congestion of the kidney may also occasion it. The effect of prolonged suppression is great drowsiness, passing gradually into coma.

861. The *sexual organs of the male* occasionally furnish useful indications. A troublesome irritation of the glans penis and prepuce, with frequent erections (priapism), characterizes stone in the bladder. Erections, without irritation of the extremity of the organ, also occur from congestion of the kidney, from irritation at the neck of the bladder, and from inflammation of the canal of the urethra. Painful erections, with curvature of the organ, constitute the most troublesome symptom of gonorrhœa. Priapism is also a leading symptom of poisoning by cantharides and turpentine, and of other active poisons of the irritant class. Erection of the penis, with discharge of urine or other fluid, and expulsion of fæces, is also a not uncommon occurrence in death by hanging and decapitation; in poisoning by prussic acid; in other forms of violent and sudden death; and in the epileptic fit.

862. The *sexual organs of the female* are subject to many diseases, some of which deserve notice as symptoms or concomitants of other disorders. Anæmia, for instance, is often accompanied by amenorrhœa, as is the opposite state of plethora, though less frequently. Certain mental disorders, again, especially some forms of mania, and some varieties of monomania, are found associated with amenorrhœa, dysmenorrhœa, or the change of life. The importance attached to the menstrual function by patients, and the occasional association of disorders of menstruation with constitutional disturbance, and especially with hysteria, render it expedient for the medical man to inquire into the state of this function in all cases that come under his care. The suppression of the menstrual discharge, the enlargement of the breasts, with the darkened and otherwise altered appearance of the areola, the change in the shape and size of the abdomen, and certain changes in the uterus itself, have great importance as signs of pregnancy.

863. (5.) THE NERVOUS SYSTEM.—The symptoms and signs of disease which have to be treated under this head consist of, *a*, altered sensation; *b*, altered muscular action; and *c*, altered mental phenomena.

864. (*a.*) *Altered Sensation.*—All the organs of sense may suffer in three ways; the sensation of which they are the seat may be blunted or lost, heightened, or perverted. The muscles also, and those viscera which are not organs of sense, and in health perform their functions unconsciously, may become, through disease, highly sensitive, and the seats of acute pain. Again, all parts of the body, whether endowed with sensibility or not, may manifest pain on pressure, or forcible extension.

865. *Pain*—In estimating the value of pain as a symptom of disease, we have to consider its degree, its character, its seat, its extent, its duration, its persistence or otherwise, and its concomitants. In estimating the *degree* of pain, it is necessary to bear in mind the difference of expression used by patients in describing it, according as they have more or less general sensibility, more or less fortitude, and more or less honesty. The lesser degrees of pain are usually spoken of as slight, moderate, bearable; the greater degrees as acute, intense, severe, violent, excruciating, agonising, distracting, intolerable. The only general principle of practical importance which can be laid down in respect of degrees of pain is, that the most acute is often occasioned by causes that entail the least danger to life; while the lesser degrees are often present in diseases of far more formidable character. It should also be borne in mind that there are states of system, such as hysteria, which exaggerate pain, and others, such as lethargy and the typhous state, which blunt it.

866. The *character*, like the degree, of pain is subject to considerable variety, and assists us in tracing it to its source, and assigning its true cause. A *dull*, *obtuse*, *aching* pain is common in congestions and sub-acute inflammations, and even in acute inflammations of soft and yielding parts. There is a dull, aching pain in the right side in congestion of the liver, in the loins in congestion of the kidney, and in the head, back, and limbs, at the onset of severe febrile attacks. A higher degree of this pain is present in periostitis, rheumatism, gout, and the milder forms of neuralgia, when it is distinguished as a *gnawing* pain. A *burning* pain is often present in severe inflammation, as a combined result of heat and tension. A *throbbing* pain is present in inflamed parts subject to pressure, as in whitlow, and also in all abscesses similarly circumstanced. Pain in parts of the intestinal canal is commonly described as *griping* or *twisting*. In scirrhous tumours, and in neuralgia, the pain is designated as *shooting*, *cutting*, *darting*, *lancinating*.

867. The *seat* of pain may afford useful indications by corresponding with the diseased part or organ which occasions it, or by the part affected with pain being in connection with the immediate seat of the disease by the intervention of nerves more or less directly traceable from the one to the other. Thus, disease of the hip-joint occasions pain in the knee; stone in the bladder, pain in the glans penis (in the female, pain at the meatus urinarius); inflammation of the kidney, and calculus in the ureter, cause pain in the groin,

thigh, and testicle; disease of the womb, pain in the loins; constipation, pain down the back of the thigh; inflammation of the liver, pain in the right shoulder; and disease of the heart, pain in the left arm, or down to the bend of both arms. Leucorrhœal discharges, and all causes of debility in nervous and irritable females, give rise to pain in the left side; to a tender state of the spinal cord; to superficial thoracic and abdominal pains: and irritation at the root of a sensitive nerve, to pain in all the parts to which its branches are distributed. Some of these pains are called *sympathetic*.

868. Of the *extent* of pain it may be said (as a general rule) that pain limited to one spot is more likely to indicate severe disease than pain of greater extent. The pains of muscular rheumatism are generally extensive, as are those which attack hysteric females. But, on the other hand, neuralgic pains are often limited to small spots, as the brow, or to single organs, as the testicle or mamma.

869. The *duration* of pain is a point of importance, especially when taken in connection with the general health. Pain of long continuance, not materially affecting the health, would probably be neuralgic; and in the female would probably be connected with other symptoms of hysteria. The *persistence*, or otherwise, of pain is also well worth attention. As a general rule, the pain in important local diseases is *continuous*, though liable to exacerbations, and, under treatment, to abatement. In less important cases pains are *fugitive*, *wandering*, *shifting*. In one disease—brow-ague—the pain is *intermittent* or *remittent*.

870. The *concomitants* of pain are also highly important. As a rule, the pain of inflammation is increased by pressure, and muscular pain by motion, or by brisk percussion with the points of the fingers, while neuralgic pains are independent of these causes. The pains of colic are relieved by pressure. Neuralgic, rheumatic, and gouty pains are usually compatible with health, or with slight departures from it, while most other pains are associated with marked deviations from it.

871. *Diminished Sensation.*—All the organs of sense may have their function blunted or lost; and as this condition sometimes furnishes important indications, it will have to be considered as it affects touch, sight, hearing, smell, and taste.

872. The *sense of touch* may be so impaired as to give rise to numbness, which may be brought about by cold, by pressure on the trunks of the nerves, or by the local action of narcotic poisons. Long-continued numbness would probably arise from pressure on the trunk of a nerve, or of some disease of the nerve itself, impairing but not destroying its function. Total loss of sensation in any part of the body would follow stronger pressure, or severe disease of the nerve or nervous centres. Loss of sensation in the arms or legs, or in the whole body, is an occasional accompaniment of muscular paralysis of the same parts. A loss of sensibility is occasionally present in hysteric females, and may be brought about

by narcotics and by mesmeric manipulations. In examining patients with a view to determine the presence or absence of sensibility, it should be borne in mind that strong muscular contractions may follow irritation of the skin from reflex action, in the absence of sensation.

873. The *sense of sight* is variously effected, not merely from local causes attacking the organ itself, but also from disordered and diseased conditions of brain. Slight and transient affections of the sight are common in dyspepsia, and in slight febrile and other disturbances of the circulation. These affections consist in dark spots (muscæ volitantes), bright spots, sparks, or brilliant colours (as seen by persons drowning or hanging), or in simple indistinctness of vision, in a flickering motion, in a double vision, as in the drunkard, or in a half-vision of objects.

Illusions have already been considered at p. 105. A heightened sensibility of the retina, accompanied by a dread of light (photophobia), is a common symptom of acute inflammations of the eye itself, and of inflammatory affections of the brain. It may also be present in acute anæmia from loss of blood, and in the hysteria of weak and delicate females. The opposite state of permanently diminished sensibility of the retina is usually connected with disease of the optic nerve, or of that part of the base of the brain from which the nerve arises. Transient dimness of vision, or actual blindness, sometimes occurs from loss of blood, from excessive lactation, or from other exhausting discharges, and it commonly precedes the fainting state.

874. *Squinting*, when not permanent, is often due to affections of the brain, and is an unfavourable symptom. It is common in children with disease of the brain attended by convulsions; and the permanent squint of the adult is often traceable to this cause.

875. The state of the *pupil* is highly deserving of attention. As a general rule it is contracted in irritation of the brain, whether due to inflammation of the organ or not, and the contraction is extreme in poisoning by opium and the Calabar bean. On the other hand, the pupil is apt to be dilated in congestion of the brain without irritation, in hydrocephalus, in epilepsy, in some cases and stages of apoplexy, and in functional disorders due to remote causes, such as constipation and intestinal worms. It is also dilated in poisoning by belladonna, hyoscyamus, and stramonium, and by some other poisons belonging to the class of narcotico-acrids, as well as by the local application of the more active members of this class. The condition of the pupil is also an indication of the state of the retina. If it contracts freely under the stimulus of light, the retina has not lost its sensibility; if not, there is a loss of sensibility in the nerve, and, in certain cases, in the entire nervous system. When, in the absence of disease of the eye itself, the pupil of one eye is dilated while that of the other is contracted, cerebral disease may be presumed to be present. The *state of* the surface of the eye is used as a test of the condition of

the nervous system. If insensible to the touch, the nervous system generally may be assumed to be in the same state. It is so under the full influence of chloroform, and in epilepsy, but in the malingerer it, of course, responds to the touch.

876. The *sense of hearing* is subject to analogous affections with the sense of sight—to ringing sounds (tinnitus aurium), to distinct musical notes, and to puffing sounds like the noise of a locomotive. These may occur from slight and transient causes, and need not excite apprehension. But they may also usher in chronic or acute diseases of the brain. Of more marked illusions of the sense of hearing, something has been said at p. 105. The sense of hearing is generally acutely painful in inflammation of the brain; and, in common with the sight, in the opposite state of the cerebral circulation; also in some cases of hysteria. *Deafness* is common in fever and in the febrile exanthemata. In some instances it is associated with cerebral disease, and forms one of the group of symptoms by which it may be recognized.

877. The *sense of smell* is subject to illusions similar to those that affect the eye and ear; but the disorders of this sense have little significance as signs of disease.

The *sense of taste* has been already considered in § 495.

878. (*b.*) *Altered Muscular Action.*—The muscles are subject to paralysis, to convulsion, and to spasm. *Paralysis* may be local or general, of greater or less extent. It may affect the muscles of the tongue, or the muscles of the upper eyelid (causing ptosis), or several of the muscles of the eyeball (causing strabismus), or the muscles supplied by the facial nerve (causing palsy of one side of the face), or the muscles of one arm or one leg, or the muscles of one side of the body (hemiplegia), or the muscles of the lower half of the body (paraplegia). The loss of power may also vary in degree, being complete or incomplete. The cause of local paralysis may be either pressure in the course of the nerve supplying the palsied part, or disease of the spinal cord. As a general rule, paraplegia may be traced to injury or disease of the spinal cord, and hemiplegia to disease of one hemisphere of the brain. A local and limited palsy, traced to a nerve issuing from the base of the skull, becomes an important indication of cerebral disease, if accompanied by palsy of some part supplied by a nerve issuing from another foramen.

879. In reference to *convulsive actions*, some distinctions worth bearing in mind are referred to at § 444. The most important to observe at the bedside are the twitchings (*subsultus tendinum*), the picking at the bedclothes (*floccitatio*), and the tremulous protrusion of the tongue in low fever. These symptoms only occur in cases which combine prostration with excitement of the nervous system; and they are highly unfavourable. Convulsions are also common in infancy and childhood, and may be brought on by the irritation of teething, constipation, or worms; and they are present in

hydrocephalus, in uræmia, and in poisoning by strychnia and other substances. In children they show themselves in the form of chorea or epilepsy; in adults in epilepsy, hysteria, and delirium tremens. They may occur on one side of the body, while the other is palsied. In sudden death from violence, or from active poisons, such as prussic acid, general convulsions, attended, as in epileptic fits, by expulsion of urine and fæces, precede the event.

880. *Spasms of the muscles*, or prolonged and rigid contraction, occur in tetanus and hydrophobia; and in some forms of hysteria. They are characteristic of poisoning by strychnia, are produced by some of the opium-alkaloids, and are occasionally observed in poisoning by all the more active poisons, both organic and inorganic. Rigid contractions of single muscles, or of groups of muscles, of long continuance, attend organic disease of the brain, and constitute a very formidable symptom. Strabismus is the result of contraction of a single muscle.

881. (*c.*) *Altered Mental Phenomena.*—These have been already treated of in a former chapter (p. 111); it only remains in this place to speak of that condition known as coma. *Coma* is a state of complete insensibility and loss of motive power. It may arise from several causes: from apoplexy; from such poisons as opium and carbonic acid gas; from drunkenness; from the operation of intense cold; from poisoning of the blood, as in uræmia; and from accumulation of serum in or on the brain. In distinguishing the coma of drunkenness from that of apoplexy we are assisted by the odour of the breath.

882. (6.) THE TEMPERATURE OF THE BODY.—The use of the thermometer from day to day may furnish useful indications, both by coinciding, with, and by somewhat anticipating, changes in the circulation as indicated by the pulse. The main facts relating to this topic are stated at p. 97.

882*. In the course of an attack, either of fever or severe local inflammation of any part of the body, the physician who used to be satisfied with judging of the heat of the body by his sense of touch, now seeks for more accurate information by the aid of the thermometer, and by its means follows from day to day, from morning to night, or even, in critical cases, at shorter intervals, the rising or falling temperature.

882**. For this purpose he makes use of a small and delicate instrument requiring preliminary adjustment and careful noting of results. He begins by bringing the register into contact with the surface of the mercury, and then places the instrument under the tongue, causing the patient's mouth to be closed upon it; or, what is better, and has the advantage of being more readily applied in all cases, he makes use of the armpit. Having first caused the body to be well covered by the bed-clothes, he places the thermometer in the axilla, and draws the arm of the patient across the chest, so as to keep the bulb on both sides in close contact with the skin. This should be quickly done under the bed-clothes, or with the shortest possible exposure to cold. After an interval of five minutes, during which the examination of the patient may be continued, the result may be ascertained. Unless an inconveniently long instrument be used, there is some difficulty in reading the register, and it may be well to employ an instrument in which arrangements are made for magnifying the figures: or a pocket lens should be carried for the purpose.

883. (7.) THE EXPRESSION OF THE FACE AND CONDITION AND ATTITUDE OF THE BODY.—*The expression and aspect of the countenance* often afford great assistance in diagnosis, but it is not easy to convey by words a just idea of the physiognomy of disease. The varieties of mental disease are strongly marked in the face. The wild excitement of mania, the deep despondency of melancholia, the vacant look of the idiot, imbecile, and demented, are familiar to all observers. Patients with delirium tremens have often an air of extreme suspicion, and the habitual epileptic has a physiognomy of his own. Again phthisis, emphysema, organic disease of the heart, diabetes, and Bright's disease, betray themselves to the experienced physician by the expression of the countenance; cancerous disorders often reveal themselves by the peculiar colour of the skin, as does the disease to which Dr. Addison's name has been given; and hysteria is often detected by rapid transitions from tears to smiles, and by an appearance of health inconsistent with the complaints of the patient.

884.—The *condition of the body* in respect of nutrition always claims the attention of the physician. Rapid loss of flesh, or sudden corpulency, should equally excite attention. The one is common in such maladies as pulmonary consumption, diabetes, and organic disease of the stomach, as well as in diseases attended by profuse discharges; also in the decay of aged persons; the other may follow recovery from pulmonary consumption, or precede attacks of apoplexy. But corpulency in the healthy may be due to inactivity or indolence. The moist or dry state of the skin is a symptom of some importance. The conditions which determine it are set forth at p. 49.

885. The *posture of the body* is often highly characteristic. It betrays loss of power in the paralytic, and weakness in the exhausted. The last stage of fever and of all exhausting maladies is marked by the helpless posture on the back; and lying on the side, as in healthy sleep, often affords an early and most welcome sign of commencing recovery from fever. The sitting or semi-recumbent posture, with the head raised by pillows, is highly characteristic of diseases directly or indirectly affecting the breathing, such as severe diseases of the lungs, and advanced diseases of the heart. The recumbent posture, with the legs drawn up, is equally characteristic of painful diseases of the abdominal viscera. In diseases of the chest we should note on which side the patient lies with most ease and comfort. As a general rule he lies

on the diseased side; but the choice of position is determined in one case by a sense of pressure, in another by a sense of dragging, in a third by the ease with which the fluids gravitate to the air tubes, and in many cases by several conditions combined. In painful diseases of the abdominal viscera, the patient, as a general rule, lies easiest on the side of the disease. The inferences to be drawn from posture are less satisfactory than could be wished.

CHAPTER V.

HYGIÈNE.

886. In a large proportion of the cases that come under the care of the physician, it is necessary to pay attention to those circumstances which affect the general health of the patient, and to lay down rules for his guidance in matters that belong rather to the province of Hygiène than to the Practice of Physic. Indeed, it often happens that the only remedial measures which he feels called upon to prescribe consist of a change from bad to good habits of life, from an unhealthy residence or locality to a healthy one, from intense application to study or business to repose of mind and complete change of scene and occupation. In a certain class of cases, again, change of climate is the appropriate remedy, and a locality has to be chosen suited to the disease or state of health of the patient.

With this regulation of the habits and residence of their patients, the hygienic duties of the greater number of medical men terminate; but there are duties of a larger and more comprehensive character in the right performance of which many medical men are directly interested—some as officers to such public institutions as workhouses, prisons, schools, hospitals, and lunatic asylums; others as officers in the army and navy, in charge of camps, barracks, ships of war, and merchant and emigrant vessels; others, again, as district officers of health.

The subject of this chapter may, therefore, be properly treated under the two distinct heads of *private* and *public* hygiène.

1. PRIVATE HYGIÈNE.

887. The principal matters which require to be regulated, with a view either to the preservation of health, or its restoration, are diet, exercise, clothing, condition of dwelling, place of residence, and habits of life. *Diet*, as appropriate to persons of different ages, and as applicable to particular maladies and states of system, will be treated in the next chapter.

888. *Exercise*, regulated according to the state of the patient, is an important therapeutic agent. It may be of two kinds—*active* and *passive;* in the one the patient moves about by his own muscular effort; in the other he is borne from place to place. Walking, running, dancing, riding, rowing, fencing, boxing, wrestling, drilling, and all gymnastic exercises and active games, are of the first class;

riding at foot-pace, carriage exercise, sailing, rocking, and swinging, of the second. Both kinds call the muscles into play, and promote the circulation of the blood; but in the passive form the muscles are only employed in maintaining the posture, while the circulation is quickened only by slight displacements of blood.

889. Besides the advantage of quickening the circulation, active exercises, by calling the abdominal muscles into play, promote the action of the bowels. Those exercises, too, whether active or passive, which are carried on in the open air, have the incidental advantage of supplying a purer air for respiration; and they imply a change of scene and occupation, which reacts favourably on the mind.

890. In prescribing the kind and amount of exercise, the physician must be guided by the circumstances of each particular case. In the absence of organic disease, and when the patient suffers merely from general debility brought on by overwork, intense study, or too close attention to business, the choice of an appropriate exercise must be mainly determined by his circumstances and tastes. If practicable, change of air and scene, with the exercise which travelling implies, should be insisted on; and, where the strength allows of it, walking exercise. A sea voyage is in these cases to be preferred to carriage exercise. When the patient is unable to quit the scene of his studies or business, horse exercise in the morning or evening of the day will be found most suitable; and this is especially the case with the inhabitants of large cities, who cannot readily reach the country on foot. Fencing, rowing, quoit-playing, archery, tennis, and cricket have the double advantage of bringing all the muscles of the body into play, and of compressing a great amount of exercise into a small compass of time. Archery and lawn-tennis deserve encouragement as open air exercise, suited to persons of either sex.

891. For growing children of delicate health, exercise is of the utmost importance, and the active games of childhood may be combined with equestrian exercise and instruction in the graceful accomplishments of dancing and fencing. In these cases much anxiety is often felt respecting the development of the chest, especially where a tendency to consumption is supposed to exist. With a view to promote this object, drilling, and the manly exercise of fencing, is strongly to be commended for young men, and the nearest approach to it for young women. It is greatly to be preferred to dumb-bells, to the clubs, or to those gymnastic exercises which consist of tedious repetitions of the same movements. Reading aloud, much insisted on by ancient medical authorities, might be revived with great advantage; but to guard against the formation of habits injurious to the free play of the lungs, a judicious teacher should be engaged. Singing, properly taught, has the same recommendation.

892. In organic disease of the lungs or heart, all strong exersion, whether active or passive, is inadmissible, and walking on level ground is the strongest exercise that can be safely prescribed. It is to be preferred to any form of passive exercise except that of the carriage or garden chair. Violent exercises, especially rowing in races, often give rise to heart-disease in persons having every appearance of strength and vigour. Such gymnastic exercises as require prolonged and violent action of the muscles are open to the same objection.

893. On the subject of *clothing* much misapprehension exists. There is a strong tendency towards over-clothing, especially of the chest, with a view to guard against pulmonary disorders. A delicate patient is often made to wear, in the very height of summer, as many flannels and skins as would be a sufficient protection in a polar winter, and in this way the very risk of catching cold, which it is deemed so important to avoid, is incurred. The same error is committed at night when, in addition to a load of bed-clothes much exceeding what is required to preserve the proper temperature of the body, flannel is worn next the skin.

894. An opposite error is sometimes committed in very young children, under the erroneous notion of hardening them. At the other extreme of life warm clothing is highly necessary, especially in patients suffering from pulmonary affections; and great care should be taken in severe weather to keep up the temperature of the sleeping apartment throughout the night.

895. Young men who persist in wearing no covering to the chest throughout the year but the linen shirt, and refuse to wear cotton or flannel next the skin in the winter, are also in error. A thin cotton vest should be worn even in summer, especially by those who perspire freely. In hot climates cotton, in cold climates flannel, is the proper material for body-clothing. The importance of an immediate change after active exercise, or when the clothes are wet, need not be insisted on.

896. The *condition of his dwelling* is of great importance to the invalid. The points to be attended to in choosing a house, or in planning a residence, are chiefly the following:—

Site and soil.—Where there is a free choice, a gravelly or chalky soil and sloping ground are to be preferred to a clay soil and low level site. A tenacious clay soil, a rich alluvium, or a dry surface soil with water at a short distance beneath, should be avoided, but especially the flat banks of rivers or streams, or the flat base of hills, as well as marshy spots, and the neighbourhood of stagnant water. The worst combination of site and soil is a flat alluvial deposit receiving the drainage of sloping grounds. Such spots are favourite haunts of continued fevers, as marshes are of agues; and good ground has been lately assigned for tracing many cases of consumption to the same cause.

Aspect.—In England a south aspect is to be preferred, especially for invalids, as being free from the extremes of heat and cold. A north aspect lacks both light and warmth; an east aspect has the advantage of the light and warmth of the morning sun, but is exposed to the cold drying winds of winter; a west aspect is open to the objection of being too hot in the after part of the day. In houses which can have only two opposite aspects, a south-east and a north-west are to be preferred. When there is perfect freedom of choice, a morning-room to the east, the principal sitting-room to the south, with bed-rooms to the south for invalids and aged persons, and to the east for young and healthy ones, is a desirable combination. Dairies, larders, and store-rooms should be to the north.

Shelter.—Houses require shelter from the north and east; and when such shelter is not afforded by nature, it should be secured by plantations, which ought in no case to be so near the house as to obstruct the free movement of air, or to endanger its foundations by the growth of roots. To the south and west the house should be open; but large trees at a moderate distance to the west, afford a grateful shade from the heat in summer.

Water-supply.—A well, yielding clear, colourless water, and free from drainage contamination, and a tank to hold a supply of rain-water from the roof, amounting to at least ten gallons per head per diem for a month or six weeks, are great desiderata. In deep wells the water may be said to have been filtered by the strata through which it passes; but shallow wells, especially when they are sunk in compact clay soil, are little better than recipients of surface water; and when, as often happens, they are near the cesspools or drains of the house, they are liable to be contaminated. The water-supply from shallow wells is also liable to contamination from running brooks which have received sewage. Typhoid fever is sometimes the direct result of drinking this impure water, sometimes the indirect consequence of using it in such a way as to become blended with the milk supply.

Drainage.—The soil on which the house stands should be thoroughly drained, and all offensive refuse promptly removed by impervious pipes properly trapped. Water-closets should be so placed that the drains may not pass under the house; and the sewage (in the case of detached houses in the country) should be led off to a spot remote from the house, and at regular and short intervals be applied to the land. Care should also be taken to so arrange the outlet for sewage that the foul air of the drains may not be shut up or driven back into the house, and, in some cases the drains should be supplied with ventilating pipes. In erecting places of convenience out of doors, the spots chosen should not be too near the dwelling, and the barbarous custom of digging deep cesspools should be avoided, especially in light soils, and near wells and *springs.* The proper construction is that adopted in many northern towns. A piece of ground is rendered impervious to moisture by ramming or paving; on this the offensive matters and slops from the house are received, and the dust, with the sifted ashes from the fires, is thrown on them, through a hopper in the side. At short intervals of a fortnight, or month, the accumulated matters are removed and thrown on a compost-heap. These simple arrangements have the advantage of being both wholesome and economical. If the dust and ashes of the house prove insufficient, dry earth may be added; or the arrangement now known as the "earth closet" may be adopted from the first.

897. The preservation of dwellings from dampness is of the first importance. To accomplish this it is not sufficient to make the roof proof against the weather; the basement also must be attended to. The floor or pavement should be raised on dwarf walls, supplied with air-bricks, and the house should be surrounded by an area or air drain, so that the walls may be kept from contact with the soil. These precautions are especially necessary in clay and rich alluvial soils, difficult of drainage.

898. *Light and Air.*—Rooms should be lofty and spacious, and have open fire-places, and windows opening above and below. Staircases well lighted and aired by windows opening on them, are preferable to those lighted by sky-lights, even when the lights admit of being opened. Pure air, especially in the bedroom of the invalid, should be guaranteed by the open fire-place. When the rooms are spacious, no special provision for ventilation is required beyond the facility of opening doors and windows; but small sleeping-rooms require a constant provision for the renewal of the air by means of ventilators so constructed as to prevent drafts.

899. In order to preserve the health of delicate children, it is essential to provide for the free ventilation of their sleeping apartments. Overcrowding and consequent impurity of the air in such apartments is a common cause of disease in the children even of affluent persons, and a principal source of the high mortality of the children of the poor. In addition to the precautions for insuring thorough ventilation, a certain amount of space, approaching the thousand cubic feet insisted on in § 219, should be allotted to each child.

900. In cities, and even in rural districts, the external air admitted into our houses is often very far from being sweet and pure. In the country the causes of impurity are few in number, being chiefly the gases from stagnant pools, ponds, or marshes, or the effluvia from cesspools, farm-yards, stables, pig-sties, or heaps of manure. The sources of impurity should always be placed at a distance from dwelling-houses; and in no case in contact with them. In large cities the sources of aërial impurity are much more numerous, and become doubly objectionable from narrow space and imperfect movement of the air. They consist in emanations from

manufactures peculiar to towns, from the necessity of heaping up, at least for a short time, the dust and ashes of our houses, from the difficulty of consuming the smoke of our chimneys, and from the defects inherent in a large and complicated system of sewerage.

901. *Warming.*—This should be so effected as not to interfere with ventilation. Close stoves should, therefore, be banished from living or sleeping apartments; their use being restricted to entrance halls. staircases, and large rooms only occasionally occupied. For living and sleeping rooms the best combination is an open fire-place of sufficient size and good radiating surface, with double windows, double panes of glass, or thick plate glass. In this way (especially when the walls of the house are thick, or double) any temperature that may be desired can be economically combined with complete ventilation. This mode of insuring a supply of warm pure air is of great importance in pulmonary diseases, especially in the bronchitis of old persons.

902. Among the *habits of life* which militate most against health, and tend to counteract the best medical treatment, the chief are sloth, luxury, dissipation, indulgence in the pleasures of the table, the abuse of spirituous liquors, opium, and tobacco, irregularity in the time of taking meals and rest, and want of personal cleanliness.

903. For those whose constitutions have been undermined by sloth, luxury, and dissipation (Chap. I. § 83), travelling, and the wholesome observances of fashionable baths and watering-places—early rising, regular hours for meals and exercise, the frequent use of baths, and cheerful and congenial society—are the only remedies which we have it in our power to prescribe. As intemperance and indulgence in the pleasures of the table are the besetting temptations of the same persons, there is, perhaps, no better way of guarding against them than by prescribing foreign travel, or a residence at well-chosen baths or watering-places.

904. When the abuse of spirituous liquors, opium, or tobacco is recognized as a cause of disease, steps should be taken to abolish these practices slowly and gradually, both on account of the greater safety of this procedure, and of the greater ease with which the patient may thus be made to lay his bad habits aside.

905. Irregularity in the time of taking meals and rest is an evil incident to the busy life of large cities, and one which we are often called upon to remedy by prescribing such improved habits as are compatible with the exigencies of the patient's business.

906. A want of personal cleanliness is more often chargeable against persons of education than might be expected. The practice of daily ablution of the whole body is observed by comparatively few; but it is one to be commended as an excellent tonic, as tending to guard against the catching of cold, and as keeping the pores of the skin open. The warm bath should be *occasionally* employed to insure a more perfect cleansing of the skin.

The practice of daily ablution with cold water, followed by friction with a rough towel, hair gloves, or the flesh-brush, is often of great benefit to those who have an hereditary predisposition to consumption, or who have already manifested a tendency to it.

907. *Change of air or climate* is generally esteemed a most important means of preserving, improving, and restoring health. There are two classes of persons to whom it is usual to recommend the change. The one consists of invalids who suffer from no defined disease, but whose general health has been impaired by exposure to one or other of the many unwholesome influences which attend a residence in large towns (see § 69 *et seq.*); the other comprises persons suffering from some well-defined malady, such as chronic dyspepsia, chronic rheumatism, scrofula, pulmonary consumption, chronic bronchitis, and asthma.

908. To the mere invalid, who has suffered from the cares and anxieties of business, the dissipation of a town life, or the *ennui* of an idle and useless existence, change of climate is chiefly valuable as affording facilities for change of habits, scene, and occupation. In advising such persons, little more is required than to avoid climates positively unhealthy, and to make choice of countries or places which offer the greatest facilities for change of habits and occupation; and in the case of the victim of *ennui*, the greatest inducements to exertion of mind and body.

909. In advising patients suffering from actual disease, a more exact knowledge of climate is needed, at the same time that considerations of personal convenience will have to be carefully weighed. Assuming that there are no circumstances peculiar to the patient to render a change inexpedient, the medical man will have first to consider the kind of climate best adapted to his disease, and then to select from a number of places having the required climate the one which is, on the whole, to be preferred.

910. In making choice of a climate, we may either consider the state of the patient's system, without reference to his disease, or we may be guided solely by the nature of his malady. The state of system may be either one of relaxation, characterized, if the disease affect any of the mucous membranes, by excessive secretion; if the glandular system, by indolent swellings or ulcers; if the skin, by chronic cutaneous affections; if the locomotive system, by chronic rheumatism and atonic gout. A cold skin, and weak, perhaps infrequent, pulse, with general languor of all the functions, characterize this state. On the other hand, the state of system may be one of irritation, with a dry state of the mucous membranes, a harsh dry skin, and a frequent quick pulse, with a tendency to more acute forms of inflammation. In the state of relaxation, a dry bracing climate is indicated; in the state of irritation, a mild moist one. In both, it is important to avoid a great increase of temperature, as tending to exhaustion; sudden changes, as giving rise to cold and slight febrile attacks, and the east and north-east winds,

as shown by experience to be peculiarly trying to the invalid. In chronic rheumatism, gout, and calculous disorders, a higher temperature appears to be advantageous. The climate of the East and West Indies, of the Cape of Good Hope, and of Egypt and Algiers, is deemed suitable to this class of invalids.

911. As a general rule, the bracing spots adapted to a state of relaxation are those which are elevated, scantily wooded, exposed to the prevailing winds, and consisting of a gravelly or chalky soil; on the other hand, the mild moist climates are to be found in low situations, on clay soils, wooded, and partially or wholly uncultivated, and sheltered from the prevailing winds. As a general rule, too, the climate of the sea-shore is milder and more uniform than that of the interior, being warmer in winter and cooler in summer. Watering-places have also the two-fold advantages of pure sea-breezes and of sea-bathing.

912. Bearing these considerations in mind, it will be easy to point out among the common resorts of the invalid, the places in England and abroad best adapted to the two opposite states of relaxation and irritation.

913. The mild sheltered places most resorted to on the English coast, are Undercliff, in the Isle of Wight; Hastings, Worthing, and Bournemouth, on the south coast; Dawlish, Sidmouth, Exmouth, and Salcombe, on the coast of Devon. The sheltered spots in the islands of Guernsey and Jersey; Pau in the south-west, and Hyères and Nice in the south-east of France; Mentone, Rome and Pisa in Italy; and Malaga in the south of Spain, offer the like advantages abroad. The islands of the Northern Atlantic (Madeira, the Canaries, and the Azores) and those of the Western Atlantic (the Bermudas and Bahamas) have the same mild relaxing climate.

914. On the other hand, the mild bracing spots adapted to a state of debility and relaxation without irritation, are, in England, Brighton, on the south coast; Torquay, on the coast of Devonshire; Clifton, on the western coast; in France, Montpellier; in Italy, Naples. These places must be understood to be intended chiefly for winter residence, the summer being spent at Yarmouth, Lowestoft or Scarborough, or inland in such spots as Malvern, Cheltenham, Leamington, Tunbridge Wells, Matlock, and Buxton, in England; among the higher Pyrenees in France; or at the better situated spas of Germany.

915. The climate best adapted for residence during the entire year is perhaps that of Madeira, which to moderate fluctuations of a temperature little exceeding that of the milder parts of England, adds the advantage of a drier atmosphere, except during the autumnal rains.

916. The diseases in which change of climate may be expected to be most beneficial are emphysema, chronic bronchitis, asthma, and all those affections of the air passages and lungs in which *previous* experience has shown that the patient suffers severely in

winter and is comparatively well in summer. The efficacy of change of climate in pulmonary consumpton is not so well established; but in the state known as tubercular cachexia (the presumed forerunner of tubercular deposit) as in other forms of cachexia, change of climate is advantageous. Whether a mild bracing or a mild relaxing climate is to be chosen must depend on the state of the system, whether it be one of languor and torpid action, or one of feverish excitement.

917. There are certain states of system in which it is well to combine with change of climate the alterative effects of minute doses of saline or other substances in a state of solution; in other words, to select as the scene of the required change of climate, regimen, and occupation, some spot where access can be had to mineral waters. Such places abound both in England and on the Continent.

918. The *mineral waters* most in repute may be divided into four classes—*the saline*, *chalybeate*, *sulphureous*, and *acidulous*—to which may be added the *hot springs*. A short description of each of these classes, with the principal watering-places where they are found, will assist the physician in his choice.

(1.) *Saline Mineral Waters.*—These consist of variable quantities of the chlorides, sulphates, carbonates, and nitrates of potash, soda, lime, magnesia, and alumina, to which may be added, as of rare occurrence, free nitrogen and free carbonic or sulphuretted hydrogen gas, the salts of iron in small quantity, with traces of phosphoric acid, iodine, and bromine. Sea-water is a concentrated form of this class of mineral waters. These waters act as gentle aperients, and are suitable for patients suffering from dyspepsia, habitual constipation, and functional derangement of the liver. The waters of Cheltenham, Leamington, Purton near Swindon, and Scarborough, in England; of Spital-on-Tweed, Pitkaithly, Airthrey, Dunblane, and Innerleithen, in Scotland; and of Ems, Carlsbad, Homburg, Seidschutz, Kreuznach, Friedrichshall, and Pülna, in Germany, belong to this class. Some of these waters contain minute quantities of iodine and bromine, and are therefore indicated in scrofulous disorders, especially when attended by glandular enlargements. The waters of Kissengen and Kreuznach contain bromide of sodium in sufficient quantity (about a fourth of a grain in a pound of water) to have some effect if taken freely and continuously. The Woodhall spa, near Horncastle, is very much richer both in iodine and in bromine. The strongest aperient waters belonging to this class are, in England, those of Cheltenham and Leamington; in Scotland, those of Airthrey; in Germany those of Pülna, Seidschutz, Homburg, Kreuznach, Kissengen, and Marienbad.

(2.) *Chalybeate Waters.*—These contain variable quantities of the sulphate and carbonate of iron, and are, therefore, tonics specially adapted to the treatment of anæmia, and of functional disorders of the uterus. They are slightly stimulating, and require to be combined with aperient medicines. The waters of Tunbridge Wells and Harrogate in England, of Hartfell Spa and Vicar's Brig in Scotland, of Spa and Tongres in Belgium and the Low Countries, of Passy near Paris, and of Rennes in the South of France, belong to this class.

(3.) *Sulphureous Waters.*—These abound in free sulphuretted hydrogen gas, and are prescribed in several skin diseases. The waters of Harrogate in England, of Moffat, Strathpeffer, and Rothsay in Scotland, of Enghein near Paris, of Barèges in the higher Pyrenees, of Aix and Leuk in Switzerland, and of Aix-la-Chapelle in Prussia, belong to this class.

(4.) *Acidulous Waters.*—These are characterized by the quantity of free carbonic acid they contain. They are more or less rich in saline ingredients; so that they might be placed with almost equal propriety in Class 1. They are applicable in the cases in which saline waters are found useful, but, being more stimulant, are better adapted to those that are characterized by great debility. The chief waters belonging to this class are those of Ilkeston, in Derbyshire, of Kissengen, Marienbad, Auschowitz, Eger, Pyrmont, Spa, Fachingen, Geilnau, Seltzer, and Homburg in Germany; of Pougues, Mont d'Or, and Vichy in France; and the Saratoga Congress Spring in America. The waters of Carlsbad and Ems contain comparatively small quantities of free carbonic acid. The chief acidulous waters of Germany, classed according to the quantity of carbonic acid they contain, beginning with the richest, are—Geilnau, Pyrmont, Eger, Auschowitz, Spa, Fachingen, Homburg, and Seltzer. The waters of Homburg rank first among the waters of Germany for combined richness in salts and free carbonic acid.

(5.) *Hot Springs.*—These are useful both as baths and as internal remedies. As baths they have the advantage of containing, like sea-water, but in smaller quantity, certain saline ingredients, which act as stimulants to the surface; also, in some cases, free carbonic acid and nitrogen. Taken internally they have, according to their strength, the properties of saline waters. The principal members of this class are the waters of Matlock, Buxton, Bath, and Bristol in England; of Carlsbad, Ems, and Wiesbaden, in Germany; of Baden in Switzerland; of Plombières and St. Nectaire in France.

919. The contents of some springs are such as to give them a place in more than one class, and to entitle them to compound appellations, such as *saline chalybeates*, named from their combining saline and chalybeate properties. At some favourite watering-places, both in England and on the Continent, several classes of mineral waters are found. Both Cheltenham and Leamington, for instance, have saline, chalybeate, and sulphureous waters; and Harrogate, in addition to strong and mild sulphur-waters, has its pure and its saline chalybeates.

920. There is no way in which most of the bad habits already referred to (§ 80) can be more effectually broken through than by *residence* at the least frequented of watering-places. Those most

resorted to are unsuitable, as they combine the luxuries and temptations of large towns with the absence of those natural beauties which offer so wholesome an inducement to walking and other exercises.

2. Public Hygiène.

921. The saddest pages in the history of all nations are those that treat of the wholesale sacrifice of human life through ignorance or neglect of the simplest means of preserving health and averting disease. Such sacrifices have occurred in lying-in hospitals from insufficient space and neglect of ventilation; in foundling hospitals from the same causes, combined with absence of the mother's care and want of the infant's proper nutriment; in schools from want of space, neglect of cleanliness, and insufficient and improper food; in workhouses and prisons from the same causes, added to idleness, listlessness, and depression; in civil hospitals chiefly through want of space; in military hospitals from the same cause, added to the want of proper medical attention and nursing, and sometimes of proper food and medicine; in emigrant and transport ships, and men-of-war, from narrow space, foul air, bad water, and bad food; in armies in the field from ill-chosen encampments, bad provisions, overcrowding, neglect of cleanliness, and intemperance. Convulsions, infantile tetanus, and gangrene of the mouth; marasmus; puerperal fever; Asiatic cholera; jail fever; typhus, relapsing fever, "parish infection," and "the sickness of the house"; scurvy; diarrhœa and dysentery; ophthalmia; malignant ulcer and hospital gangrene—have all been traced to such causes; while smallpox, plague, sweating sickness, black death, and cholera, have committed their worst ravages among men, women, and children overcrowded, and wanting one or more of the simple requisities of pure air and water, cleanliness, due shelter, efficient drainage, appropriate clothing, and wholesome and suitable food.

922. It is no disparagement to the art of healing to say that more lives have been sacrificed to neglect of the simplest means of preserving health than can have been saved by the most skilful medical and surgical treatment. It is of the first importance, therefore, that the physician should be able to recommend with authority the measures to be adopted to preserve the health of men, women, and children when of necessity congregated in large numbers. These measures might, indeed, be inferred from what has been said in this chapter on diet, exercise, clothing, condition of dwelling, place of residence, and habits of life, and, in the earlier chapters of this work, on the causes of disease; but the precepts thus laid down for individuals require to be modified in order to meet the cases of men, women, and children in the aggregate.

923. Of foundling hospitals, for the reception of infants, it is unnecessary to say more than that they are as indefensible on physical as on moral grounds, and that it would be waste of time to point

out the means of reducing the mortality to which they must be subject. The same observation applies, though not with equal force, to lying-in hospitals. The danger of congregating large numbers of puerperal women within their walls can only be averted by a largeness of space and freedom of ventilation to which expense must always be a serious obstacle.

924. Of schools, it will suffice to remark that the contagious maladies to which children are subject render an observance of all the rules of health presently to be laid down for adults doubly necessary.

925. To prisons attaches the necessary drawback of confinement at an age when the desire for active employment is at its height. The same is true of the younger inmates of workhouses; and it is not to be doubted that when, to the evils of confinement in the case of the healthy, are added those of sick wards with inadequate accommodation, limited space, and a scale of expense necessarily adapted rather to the means of poorer ratepayers than to the strict necessities of the case, workhouses have always been, and must continue to be, highly destructive of life.

926. Sailors and soldiers on duty are exposed to special disadvantages; sailors, to confined quarters, and close confinement in rough weather, often combined with bad water, scanty and unwholesome food, and great exposure and fatigue; soldiers, to the same evils, in nearly the same degree, and the superadded disadvantage of equal exposure to the weather, with less shelter, encampment on unhealthy spots, and prolonged occupation of badly-selected sites for barracks and hospitals.

927. In treating of the means of preserving health and preventing disease among bodies of men there will have to be considered: 1. The case of persons confined within such buildings as prisons, workhouses, and barracks. 2. The case of the sick in hospitals. 3. The special case of persons living for a time on board ship, as sailors or emigrants. 4. The case of sailors and soldiers in actual warfare.

928. (1.) The means of preserving the health of persons confined within such buildings as prisons and workhouses are those already described as applicable to individuals and families, with a few obvious modifications. The buildings should combine a healthy site and suitable aspect with good water-supply, thorough drainage, spacious living and sleeping rooms, facilities for oversight and inspection, and ground for exercise and wholesome labour. The parts of the structure requiring drainage should be placed on the skirts of the building, so that the drains need not be carried under the building itself; and the earth-closet may be used with advantage. The walls should be surrounded by air-drains; the lower story of the building should be raised so that the floor is not in contact with the soil; the space in living and sleeping rooms should not fall far short of the dimensions prescribed by John Howard (10 × 10 × 10 feet) and warmth and ventilation should be conjointly secured, by open fire-*places*, and windows glazed with thick glass, or with double panes

of common glass, and opening above and below. In prisons, warming by hot air, hot water, or steam, and ventilation by mechanical aids, cannot well be dispensed with. In all other buildings these methods are highly objectionable, except for passages and halls, and for rooms occupied only occasionally, and for short periods of time. Scrupulous cleanliness is to be insisted on, not merely for its own sake, but for the occupation it gives; facilities for exercise have not merely to be provided, but exercise itself to be organized and superintended. The diet of the inmates should consist of a due proportion of animal and vegetable substances, from which vegetables or cheap fruits containing a vegetable acid, or such an acid in combination with an alkali, should on no account be omitted. This precaution requires to be specially borne in mind when the potatoe, which answers this description, falls short.

929. (2.) Hospitals, in common with buildings tenanted by bodies of healthy persons, should combine a well-selected site, a dry soil, thorough drainage, a suitable aspect, a compact arrangement of rooms and passages favourable to efficient oversight and easy communication, and an economic system of warming and ventilation. The remarks already made on site, soil, and drainage, as applicable to houses, apply equally to hospitals, and a few additional words on the subject of aspect will supply all that is required on this head.

The best aspects for the wards of an hospital are north and south, or north-west and south-east. The east and west aspects have the advantage of greater cheerfulness with the drawback of the sun's glare; and the west aspect is open in summer to the objection of great heat in the after part of the day. The south aspect is the best for consumptive patients, for those suffering from diseases of the lungs, for weak and delicate persons, and for the aged. In hospitals restricted to two aspects, direct north and south are preferable to direct east and west. In general hospitals with a north and south aspect, the southern wards are most suitable for diseases of the chest, for aged persons, and for the weak and delicate; the northern wards for febrile and inflammatory disorders. For convalescent hospitals, the greater cheerfulness of the east and west aspects is a recommendation. The airing-grounds should have a southern exposure. Dispensaries and rooms for the examination of patients should face north and south, and larders and provision-stores north.

The most economical arrangement of an hospital is one which devotes the basement to the out-patient department, the dispensary, the living and sleeping rooms of nurses and subordinate officers, the kitchen and stores.

A compact arrangement of rooms and passages is best obtained in a lofty building with a large central staircase: and the most economical, as well as the least objectionable, arrangement for warming and ventilating by a combination of open fire-places with thick walls, and windows glazed with thick glass, or double panes of thin glass, and opening above and below, or tilting inwards in three or more sections. The air of the central staircase should be warmed by open fires, and be available in bad weather for the ventilation of the wards.

As the wards of an hospital are occupied by sick persons day and night, the cubic contents per bed should be much larger than in prisons, workhouses, and barracks. For adult males, and in the case of hospitals in London and the large towns, it should not fall far short of 1500 cubic feet; and in fever hospitals and lying-in wards should approach 2000. In St. Thomas's Hospital it is upwards of 1800 cubic feet per bed in the ordinary wards, and about 2500 in the block for infectious diseases. A considerable reduction may be made in the case of women and children, and of hospitals in open situations in small towns.

The wards of an hospital should be lofty as well as spacious, should have a height of 14, 15, or 16 feet, and such length and width as to give ample space round the beds. The beds arranged along the outer walls should stand each between two windows, and those of inner walls opposite to them, and the corner beds should not touch the end walls. The windows should rise to within a short distance of the ceiling, and open above and below. The number of beds in a ward may vary with the kind of cases admitted. In civil hospitals, thirteen or fifteen beds in a ward are convenient numbers, especially as admitting of symmetrical arrangement; in military hospitals, thirty beds is the number usually preferred. For an equal number of nurses or attendants, the number of beds in a ward will decrease with the severity of the cases, and *vice versâ.*

The same principles of arrangement and construction apply to military as to civil hospitals. For soldiers in actual service, it is important to observe that the roughest weatherproof shed, provided it be spacious, is better than the most substantial building if overcrowded. This truth, firmly established by Dr. Brocklesby, is one that ought never to be absent from the mind of the army surgeon. (See Dr. Guy's "Public Health," p. 312).

930. (3.) A ship on the open sea has the solitary advantage of being surrounded by air free from injurious terrestrial emanations. In all other respects it is placed under unfavourable circumstances; for it combines the drawbacks of inadequate space for passengers and crew, and stowage of water and provisions; of ventilation liable to frequent interruptions; of a moist atmosphere acting on vegetable matters subject to decomposition. A ship in harbour, though in other respects better circumstanced, is often exposed to the most deleterious emanations from low swampy lands and rich alluvial soils. A seafaring life, moreover, is exposed to great and continuous fatigues under circumstances otherwise unfavourable to health, and to a certain extent, and often for long periods of time, to the evils of a monotonous existence. Hence the health of seamen and passengers by sea can only be preserved by the most watchful care and attention to the cleanliness, dryness, and ventilation of the ship, the supply of fresh water, and of sound provisions embracing all the

elements of a wholesome diet, with suitable clothes, and proper change of clothing, with fitting exercise, occupation, and recreation, and facilities for separating the sick from the healthy. The precise means to be adopted to insure these ends can only be fitly described by those who add to a general knowledge of the principles of hygiène a special acquaintance with the construction and internal economy of ships.

931. (4.) The preservation of the health of soldiers and sailors in actual warfare is a subject which can only be adequately treated in works specially devoted to it. Men engaged in offensive wars are exposed at the same time, or in quick succession, to every cause of disease except inactivity of mind and body; and even from this they are not always exempt. They are often called on to serve in unhealthy climates and pestilential places, in inclement seasons, with inadequate shelter, or with no shelter at all, with short supplies of provisions, rarely of the best quality, and from which some important elements of a wholesome diet are almost necessarily omitted; exposed to every species of hardship and privation, to fatigue and want of rest, and they are sometimes tempted to dangerous excesses of riot and intemperance. When serving at a distance from home, they often enter on a campaign with health impaired by the confinement of a long sea voyage, and may have to occupy garrisons and encampments combining the most unwholesome sites with the most imperfect sanitary arrangements. Under such circumstances a close attention to all the known means of preserving health and preventing disease becomes imperatively necessary. Some of the leading precautious and provisions applicable to the soldier in service may be briefly stated.

In transporting troops from place to place the same watchful care is required on board ship as in the case of sailors and passengers; and when it is possible to chose the time of year, that should be selected which will enable the soldier to arrive at his destination at the healthiest season, and one bearing the nearest resemblance to his native climate. His *clothing* should be suited to the climate and season, being of close-fitting woollen materials in cold climates and in winter; of cotton, sitting loose, and with protection for the head, in hot climates and in summer. In winter, flannel should be worn next the skin; in summer, cotton. A warm waterproof cloak for wet weather and night use, and strong thick shoes well-fitted to the feet, with thick woollen socks, complete the necessary clothing of the soldier. In all places, and at all times, mere soldierly appearance and bearing should give place to comfort and practical efficiency. The best *bedding* for the soldier is a mattress stuffed with cork, covered beneath with waterproof cloth, and having a double flap of the same material to draw over the body. The soldier's *diet* should be as carefully adapted to the climate as his dress. In cold climates a full supply of animal food should be provided, and spirituous liquors are least injurious; in warm climates an excess of vegetable food, and an abstinence from spirituous liquors, should be enjoined; in both, vegetables and ripe fruits, or their nearest substitutes, ought on no account to be omitted. The soldier on the *march* should be in motion during the hours most suitable for exercise and for avoiding the intense heat of warm climates. He might always advantageously walk one or two miles before taking his first meal; then, after rest and refreshment, enter on the principal portion of the day's march. The best food for the first meal is warm nutritious soup, or hot coffee with bread; and tea is always a grateful refreshment. The ground chosen for *encampments* should, if possible, be sloping, so as to allow of natural drainage, protected from cold winds, and, in hot climates, affording the shelter of trees. Places for the deposit of offensive matters should be chosen in reference to the prevailing direction of the wind. They are best placed on a sloping bank, upon which dry earth should be thrown day by day; the mixed soil being removed at short intervals to a convenient distance. Soldiers should not remain on the same spot for any length of time, but the site of the camp should be changed at short intervals. Proper arrangements should always be made for separating the sick from the healthy; and, in providing tents, or huts, or more substantial buildings for hospitals, the principle already laid down should be constantly borne in mind, that the roughest shelter, with plenty of space, is preferable to the most substantial building without it.

Soldiers in *cantonments* or *barracks* often suffer through the selection of an improper site. Instead of being stationed on high sloping ground, some low-lying swamp at the mouth of a river is chosen, with the certain result of excessive sickness and a high mortality. If to this first fatal error there be added a similar neglect of other hygienic precautions, the results are lamentable. If, on the other hand, a good choice of site is followed up by careful attention to all the simple rules of health, the soldier's life may be preserved even in the unhealthiest climates.

In cantonments and barracks, and on the march, as far as the exigencies of actual warfare will permit, the following precautions should be carefully observed. The soldier should be sheltered, as much as possible, from the heat of the day, and from the cold and dews of the night; dry, healthy spots should be chosen for military exercises; military duties should be so timed that the soldier may be deprived as rarely as possible of his natural sleep; in mounting guard arrangements should be made to employ as few fatigue-parties as possible; the messes should be so ordered that the soldier may begin the duties of the day with a comfortable warm breakfast; the diet should always comprise a due supply of vegetables and, if possible, of ripe fruits, and the canteen should be placed under stringent regulations; the means of personal cleanliness provided, and daily washing of the feet and frequent bathing insisted on; flannel waitcoats or cotton shirts should be worn next the skin, and a flannel belt round the loins; and a change of clothing provided and ordered after every exposure to rain. The soldier should also be subject to frequent medical inspection, especially during the prevalence of epidemics; be encouraged to engage in manly sports, and employed to the utmost in useful and cheerful labours and studies.

The subject of Public Hygiène would be incomplete if some notice were not taken of the *dietaries* adapted to preserve the health of men, women, and children when brought together in large numbers. A separate section may also be advantageously devoted to the subject of purification of air, water, and animal excreta; to deodorants, disinfectants, and antiseptics.

3. Dietaries.

932. The great pestilences of former days were always preceded or attended by famine or scarcity: and a deficiency of food, or a failure of some important crop, such as the potato, has proved the immediate forerunner of the most fatal outbreaks of fever in more recent times. Moreover, the relation which scarcity of food bears to one form of fever is so marked as to have led the best modern authorities to speak of it as "Relapsing, or Famine Fever."

933. Scarcity of food, or the lack of some important element of a wholesome diet, has also given rise to many fatal maladies among soldiers in active service, and especially those engaged in the attack or defence of besieged places, as well as among seamen.

934. The same cause has also been in occasional operation in all establishments for the reception of healthy and sick persons—in schools, prisons, and workhouses, in barracks, and in hospitals; and some notable and instructive examples of the danger attending large reductions in existing dietaries, and the omission from the diet-roll of such an important element as the potato and its vegetable equivalents, have been afforded within the present century. One of the most painfully instructive of these cases occurred at Millbank prison in 1822; and some instances on a smaller scale in other prisons still more recently.

935. The principal diseases which have been traced to scarcity of food, or to food of an improper character, are scurvy (purpura nautica and purpura hæmorrhagica), dysentery, and diarrhœa, continued fever, and scrofula; in infants, the diseases known as tetanus neonatorum; and in children, marasmus. All those maladies, bodily and mental, which follow upon gradual exhaustion of strength, and impairment of constitution, are also promoted by the same cause.

936. Of the diseases just specified the one which is most certainly produced by an insufficient diet, but especially by one from which vegetables are excluded, is scurvy—a disease which fortunately marks its presence not merely by extreme weakness, but by the characteristic swollen, spongy, and bleeding gums, the pouring out of blood in circular spots (petechiæ), or in irregular blotches beneath the skin, and bleeding from the mucous surfaces.

937. In devising suitable dietaries for the inmates of public establishments, or for other bodies of persons, the following general principles applicable to all persons alike, and subject to modifications in accordance with age and sex, health and sickness, and the demands made on the strength by different conditions and occupations, may be usefully laid down, relating to:—1. The constituents of a wholesome dietary. 2. The proportions in which those constituents should be given. 3. The quantities required by adults of either sex, and by children of different ages. And 4. The variations in quantity necessitated by condition and occupation.

938. (1.) *The constituents of a wholesome dietary.*—Experience has taught us the necessity of blending in the same dietary more than one kind of food; and has warned us, in language not to be mistaken, of the danger of omitting from any dietary for any length of time that vegetable element of which, in consequence partly of its abundance and partly of the convenience with which it may be stored and kept, the potato is the best representative. By chemical analysis of the blood and animal structures, we have been taught that the body cannot be built up, nourished, and maintained in health and vigour without such mixed food as shall supply it with the nitrogenous elements of muscle and skin, the carbonaceous element of fat, and the several mineral matters which enter so largely into the composition of bone, and furnish an essential element of the nervous tissue. Chemistry has also taught us that of the excretions, some (as the exhalation from the lungs) abound in carbon, others (as the urine) in nitrogen and saline matters. On the other hand, we have been taught, by the same science, that all the elementary constituents of the blood and tissues, and all the solid and gaseous elements of the excretions, exist in the food which we consume and the air we breathe, and can be traced to them; and, further, that it is possible to arrange all the varieties of food in two great classes, according as they contain or do not contain nitrogen (§ 167), the non-nitrogenous class subserving the function of respiration, and contributing largely to the production of heat; the nitrogenous or plastic class employed in building up, maintaining, and repairing the tissues of the body.

939. The composition of the milk by which young animals are nourished, and of the egg, which performs the same office for birds, confirms the information derived from the sources just indicated; for the solid matter of milk consists of more than a third of its weight of the nitrogenous element, casein; somewhat more than a fourth of the carbonaceous material, oil or butter; and less than half of another carbonaceous element, sugar: these, with about a hundredth of its weight of mineral substances, of which by far the larger portion is phosphate of lime, being held dissolved or supended in about eight times their weight of water. Here we have a nitrogenous or plastic element (casein), combined with carbonaceous elements in the proportion of about one to three. In the egg,

again, the nitrogenous element, albumin, in the proportion of about seven parts, is blended with oily matter (a small quantity of sugar only being present), in the proportion of five parts, these matters being mixed with about three times their weight of water.

940. It follows, then, from the teachings of experience, and the researches of the chemist, that a dietary to be *wholesome* and *nutritious* must contain a combination of nitrogenous or plastic, and non-nitrogenous or respiratory, elements, together with vegetables known to contain a free acid, or such an acid in combination with potash.

941. Now, some articles of food in common use are rich in nitrogen, others in carbon, and others, again, contain both elements blended in proportions approximating more or less closely to the actual requirements of the frame. So that it is quite possible to construct wholesome and nutritious dietaries by very different combinations of food. One diet may have milk for its chief element, another the flour of wheat or other cereal, another meat, another fish, another the potato. In India rice is the staple of diet, in Ireland the potato, in Scotland oatmeal, in England the flour of wheat, in Greenland blubber, the main constituent of which is oil.

942. For practical purposes the substances most used in the dietaries of this country may be classed as nitrogenous, carbonaceous, and mixed—the first group consisting of meat, cheese, and peas; the second of suet, bones, and molasses, rice, and the potato; and the third of milk, and the flour and meal of wheat, oats, barley, and maize. The common vegetables which contain a free acid, or an acid in union with potash, are potatoes, turnips, and carrots. Cabbage and onions have the same antiscorbutic property, but with a nitrogenous element.

943. The cheapest articles which may be readily and abundantly procured in this country are:—among the nitrogenous group, shins of beef (meat and bone together for soup), butter-milk and skimmed milk, and peas; among the carbonaceous group, bones, suet, molasses, potatoes, and rice; and among the mixed group, Indian meal, barley meal, oatmeal and wheaten flour.

944. This grouping has no pretence to scientific accuracy; for, with the exception of suet and molasses, the rest consist of combinations of the nitrogenous and carbonaceous elements in different proportions, the nitrogenous group having a larger proportion of nitrogen, the carbonaceous group of carbon, and the mixed group the two elements in proportions which peculiarly fit them to become the substantial centre or basis of a wholesome and nutritious dietary.

945. These elements of a cheap dietary are variously combined in actual practice:—oatmeal mixed with water or milk into porridge; Indian corn with milk, and suet with wheaten flour, into puddings; shin of beef with onions, carrots, and pearl-barley, into a nutritious soup; bread is eaten with cheese; and the potato, in the best dietaries, forms a part of every dinner.

946. (2.) The proportions in which these, the chief constituents of a wholesome dietary, ought to be blended, have been ascertained with some approach to accuracy by a chemical comparison of the food consumed and the excreta discharged, by adult males. If Dr. Dalton's experiments on himself might be taken as a standard, it would follow that an adult healthy male ought to be supplied with articles of food containing about eleven and a half ounces of carbon and an ounce and a half of nitrogen (§ 243 et seq.). The nitrogen should, therefore, bear to the carbon the proportion of about one to seven, or one to eight. Vierordt expresses the wants of the adult frame somewhat differently. He says that an adult male, to keep in good condition, requires about four ounces of albuminous matter, nearly three of fat, and about ten and a half of amylaceous food daily. One pound of wheaten bread, one pound of potatoes, and about four ounces of meat, or its equivalent in nutritious meat soup or cheese, per diem, would fairly meet this requirement. If it were deemed expedient to exclude the meat element, one pound of bread, half a pound of potatoes, half a pound of oatmeal, and seven pints of milk per diem, would similarly meet the theorectical requirements of the German physiologist.

947. By very general assent it has become the practice in England to supply to paupers and prisoners a dietary consisting chiefly of bread, potatoes, and meat, soup containing meat, and gruel for breakfast. A liberal, but not excessive, diet for men not at hard work might be roughly stated to consist of about 275 ounces per week of food served in the solid form, and about fourteen pints in the liquid form; while for men at hard labour the quantity of solid food is generally found to exceed 300 ounces per week, the liquid food being still about fourteen pints.

948. The quantities of food required by adult men and women, and by children respectively, are not easily ascertained. One obvious consideration arises out of the weight of the classes to be provided for. Thus, the weight of an adult woman being about a sixth less than that of an adult man, it would be reasonable, if all other things were equal, to deduct a sixth from the dietaries of adult males, in order to adapt them to the use of adult females. But as the wear and tear of the system is less in women, the deduction may perhaps be roughly represented by a fourth of the food served in the solid form. So also, as the weight of men or women at sixty-five or seventy years of age is about a twentieth less than the weight of adults, and their functions much less active, it would not be unreasonable to reduce the dietary of aged persons by at least a tenth.

949. The case of children offers greater difficulty; but here, too, the element of weight cannot be disregarded. A child five years old will weigh about a fourth, a child of seven about a third, and one of fourteen not much more than the half of an adult of the same sex; but as the child is growing, it is obvious that it requires a quantity of food not to be measured by the weight alone. Hence, instead of a fourth, a child of five years might require a third of the

food given to the adult, a child of seven might require a half, and a young person of fourteen as much as two-thirds. Assuming the weekly diet of an adult to be 300 ounces of solid food, consisting chiefly of bread, potatoes, and meat, the solid constituents of the dietary of the Foundling hospital, as given by Pereira, would amount for children under nine years to about five-twelfths, and above nine to about seven-fifteenths. The liquid portion of the food in these dietaries for children consists very properly of milk. In adult dietaries it is used exceptionally.

950. (3.) As to the quantity of food rendered necessary by condition of life and occupation, it may suffice to observe that, *cæteris paribus*, it should be in proportion to the activity of the individual, inaction of mind and body implying a moderate allowance, and activity of mind and body a liberal supply. A liberal supply of the vegetable element, of which the potato is the most convenient representative, is specially needed in men or women who lead an inactive life within doors. It is believed, too, that convicts, in consequence partly of long confinement, and partly of the depressing effect of imprisonment, require a more liberal diet than paupers; and that convicts with long sentences must be better fed than prisoners whose term of retention is shorter. It is probable that as the depression produced by imprisonment has been over-estimated, so also has the need of a more sustaining diet; and it is quite possible that an increase of the vegetable (potato) element would meet this exceptional case better than an absolute increase in the quantity of the food.

What the proper tests of a sufficient diet in the case of men, women, or children congregated in workhouses, prisons, schools, &c., should be, is a question not yet satisfactorily answered. In reference to one test—the gain or loss of weight—recent inquiries have shown that it is both fallacious and misleading, especially in the case of prisoners at hard labour, in which a very considerable loss of weight (such as 20 or 30lbs.) has been shown to be quite consistent with a full capacity for work. For prisoners not at hard labour the test of weight may perhaps be applied with more confidence, a dietary under which, on an average, the prisoners maintain their initial weight commending itself as probably sufficient. Under the dietaries in force at our separate convict prisons, the inmates, on an average, gain somewhat in weight.

4. Deodorants, Disinfectants, and Antiseptics.

951. The medical man may have to give advice as to the choice and use of these agents in the sick-room, when it is not possible to resort to a thorough draft of air to sweep away the offensive odours emanating from the patient or his *excreta*, and in cases of fever or the febrile exanthemata, in order to render inert or harmless the contagious matters which float in the air, or attach themselves to clothing, bedding, and furniture. He will also naturally be consulted

respecting the purification of air, water, and offensive refuse matters; and, if officially engaged in the prevention of disease, the direction of such works of purification will constitute no inconsiderable part of his duties.

952. In treating this subject, the chief deodorants, disinfectants, and antiseptics will first be named and classified, and then those among them which are best adapted for special purposes will be pointed out.

953. (1.) *Deodorants*, or agents, which remove, or destroy, odours. These are—1, dry solid matters, such as charcoal, lime, earth, or ashes, which act by absorbing, or combining with, the water and gases of the odoriferous material; inodorous saline solutions, of which the acid, the base, or both, combine with some element of the gas or gases to which the material owes its offensive properties (such as permanganate of potash, chloride of zinc, perchloride of iron, nitrate of lead, sulphate of iron, and the mixed sulphates of zinc and copper); 3, chlorides of lime, potash, and soda, which yield chlorine when mixed with acids; 4, liquids giving off acid vapours which combine with the ammonia of the sulphide and other ammoniacal compounds (such as vinegar and pyroligneous acid); 5, gases, as chlorine, iodine, bromine, ozone, nitrous, and sulphurous acids, and ammonia; 6, kreasote and carbolic acid. The smoke of tobacco, of coarse brown paper, of cascarilla bark, of benzoin, of juniper berries, of pastilles, &c., can only conceal offensive odours, and should not, therefore, be regarded as deodorants. 7. The vapours of burning tar or pitch, and those perhaps of the resins generally, and the smoke of burning paper saturated with nitrate of potash, may be said to occupy an intermediate position between deodorants and disinfectants.

954. (2.) *Disinfectants*, or agents which destroy infectious matter. This class is smaller than the foregoing, and comprises only a few of its more active members; and the efficiency of some of them is rather inferred from their known chemical activity than proved experimentally; for the exact nature of infectious germs is as yet unknown. The most approved disinfectants are—*Heat.* (A temperature of 212° Fahr., applied as hot air, steam, or water, during the space of from half an hour to an hour, effectually destroys infectious matters.)—*Chemical vapours.* Among deodorants those that are most likely to answer the purpose of disinfectants also, are chlorine, bromine, and iodine, ozone, and nitrous, hydrochloric, and sulphurous acid gases.—The tar acids (carbolic, cresylic, and kreasote), of which *Carbolic acid* is the most available. Sulphurous acid gas, generated by burning sulphur, and carbolic acid more or less diluted with water, are among the best of our disinfectants.

955. (3.) *Antiseptics*, or agents which arrest or prevent fermentation and putrefaction. The most efficient members of this class are—a high or low temperature (212° and 32° Fahr.).—Sulphur-fumes and Carbolic acid, Kreasote, Iodine, Ammonia, Perchloride of Mercury, Boracic and Salicylic acids.

956. In making choice of one or other of these agents in special cases, we must be guided by the character of the material to be cleansed or purified. In empty rooms or buildings, or for the cleansing of floors or walls, burning sulphur, strong solutions of carbolic acid, and the several substances which give off bleaching or corrosive acid fumes, may be freely employed: they are less applicable to rooms containing furniture. The dry deodorants—charcoal, lime, earth, ashes, and sulphate of iron,—are specially applicable to fæculent discharges, as is also the permanganate of potash in solution. Water containing animal matter may be treated with a dilute solution of permanganate of potash, and water which owes its hardness to bicarbonate of lime held in solution, may be softened by the use of milk of lime. The air of sick-rooms may be purified by the vapours from moist chloride of lime, or by solutions of the permanganate of potash or carbolic acid freely exposed on cloths moistened with it. The odour of fæculent matters diffused through the sick-room quickly disappears on burning coarse brown paper saturated with nitrate of potash.

On the subject of the preceding chapter, especially in what relates to Military Hygiène, the reader may consult with advantage Dr. Parkes' "Manual of Practical Hygiène." Dr. Guy's work on Public Health, referred to at p. 220, contains many illustrations from the past History of disease in England, which may be consulted with advantage by those who desire to promote a knowledge of hygienic truths and principles.

CHAPTER VI.

GENERAL THERAPEUTICS.

957. The Science of Therapeutics treats, as the name implies, of the cure and palliation of diseases. In its widest sense, it comprises all information bearing on the knowledge of disease, and of remedies. The application of this knowledge constitutes the *Art* of healing.

958. The art of healing is beset by the same difficulties that attach to the study of disease, and by others peculiar to itself. As our imperfect acquaintance with the phenomena of health limits our knowledge of disease, so our scanty knowledge of the action of remedies on the healthy frame is an obstacle to the successful treatment of disease. But still greater obstacles result from the difficulty of instituting comparative trials of different modes of treatment in the same disease, and our ignorance of the extent to which the body, if left to itself, would repair the injuries it sustains. We cannot always leave disease to itself; hence we are ignorant to a great extent of the value of the "vis medicatrix naturæ," and we are reluctant to employ a new remedy in a disease in which an old one is used by general consent, lest an unsuccessful or fatal result should be laid to our charge.

959. To form an exact classification of remedies, or to establish broad principles of treatment, is therefore a work of great difficulty. What we know on the subject will be best explained by taking the principal functions of the body, as described in a former chapter, and showing the effect of remedies on each of them in turn. In pursuance of this plan, the following arrangement will be adopted:—

(1.) Remedies applicable to disorders of the alimentary canal, including the treatment of those of the liver, pancreas, and spleen. (§§ 142 to 187.)

(2.) Remedies which modify the composition of the blood. (§§ 188 to 215.)

(3.) Remedies which affect the organs of circulation. (§§ 256 to 353.)

(4.) Remedies which act on the tissues. (§§ 354 to 393.)

(5.) Remedies which act on the nervous system. (§§ 394 to 454.)

(6.) The duties of the nurse and the management of the sick-room.

1. General Treatment of Diseases of the Alimentary Canal.

960. *Diet.*—Disorders of the stomach require regulation as to *food and* the time and mode of taking it. The most common

functional disorder is anorexia, or loss of appetite, attendant on almost all severe diseases, especially those of an inflammatory or febrile character. It always indicates a loss of digestive power, and necessitates either entire abstinence, or a bland unirritating diet, such as barley-water, toast-water, milk-and-water, and weak tea; acidulated drinks, such as lemonade and effervescing water; and ripe juicy fruits, especially the orange and grape.

961. The *acute* form of functional disorder of the stomach requires a diet free from all matter which can irritate its tender membrane, such as gruel, arrow-root, or sago, made with or without milk, to the entire exclusion of solid matters, whether animal or vegetable. The *chronic* form requires a close attention to the time and mode of taking food, the quantity and quality of the food itself, and the state of other parts of the alimentary canal, especially the large intestines, as well as that of the liver. Complete mastication, a moderate quantity of liquid and of solid food, a sparing use of condiments, and moderate intervals between meals, are points always to be insisted on. The diet suitable to each patient is, to a certain extent, a matter of experience, and distressing symptoms (such as palpitation with an irregular or intermitting pulse) have sometimes been removed by omitting some article, such as tea, or by substituting unfermented for fermented bread.

962. In organic diseases of the stomach, nutritious unirritating food, such as strong broths, soups, and jellies, must be prescribed. When the stomach is unable to retain food, life may be prolonged by nourishing enemata; by friction of the skin with oily matters; or by local baths of warm nutritious liquids.

963. Young children require a strict regulation of the diet, an abstinence from solid food, and, in extreme cases, a recurrence to the diet of the infant at the breast, substituting for the milk of the mother, asses' milk or new milk from the cow, and administering it, if necessary, in small quantities, and at long intervals. This simple treatment, aided by the steady use of aperients when required, is often attended with the best effects, after nourishing and stimulating food, given with a view of imparting strength, has wholly failed.

964. In diabetes, saccharine and starchy food and articles which are readily converted into sugar are to be avoided. The diet therefore is made to consist chiefly of albuminous and oleaginous elements by the substitution of gluten bread for common bread, and the use of eggs, milk, vermicelli, macaroni, and lean flesh. But restriction of the diet in diabetes is dictated by a theory of doubtful soundness, that when we cannot attack the cause or source of the disease, we ought to render difficult or impossible the development of its leading symptom.

965. In the subjects of the oxalic diathesis, we shall have to ascertain what articles of diet aggravate the disorder, and generally it will be necessary to interdict the use of sugar, acid fruits, and fermented liquors.

966. Strict dietetic rules have sometimes to be enforced as means of inducing certain states of the system. The strength and power of endurance developed during training for the ring, are partly due to the diet prescribed; and the reduction of weight in the jockey is effected in part by an opposite dietetic treatment. Mr. Banting reduced his weight in one year from 202 to 156 pounds by abstinence from bread, butter, milk, sugar, potatoes, and beer; and the diet of Millbank effected a like reduction of weight in the "Claimant," without any injury to his health.

In the practice of medicine diet plays an important part. Thus we allow a nourishing diet to the convalescent, and restrict a patient with a severe inflammatory or febrile attack to substances containing little or no nutriment; the *antiphlogistic* diet or regimen being more or less strict, according to the severity of the disease. In the most severe cases total abstinence from food may be necessary, liquids alone being allowed to allay thirst: in less severe cases, the patient may be restricted to a vegetable diet, as having little effect on the circulation.

967. During convalesence from acute diseases strict attention must be paid to the digestion. When the appetite returns it is apt to be voracious, and then we must carefully avoid overtaxing the digestive power, cautiously passing from sloppy food to fish and then to meat, selecting the most digestible (see § 164). It is better that the patient should hunger than that he should overfeed. As the appetite returns, the regular action of the bowels must be secured. The greatest care is required during convalesence from enteric fever.

968. In prescribing an appropriate diet, it should be borne in mind that vegetable food has little or no effect on the circulation, but that animal food acts as a stimulant; that warm liquids excite, while cold liquids act as sedatives; and that food affects the circulation most in the early part of the day. It is in cases of slow and unsteady convalesence, when there are some remains of local affection, when the appetite is variable, and that condition of the general system exists known as "irritation," that these facts must be applied in practice. When the patient, though weak, is free from disease, when the appetite is good, and the circulation tranquil, food may be given with less caution.

969. But there are cases in which a nourishing and even stimulating diet is necessary, though local inflammation and constitutional irritation be present, and the appetite for food is almost wanting. To this class belong exhausting discharges, and extensive injuries in course of reparation, for which we prescribe solid food of the stronger and more stimulating kind, with the nutritious and stimulant liquids, wine, ale, porter, &c. In such cases, too, the previous habits must be attended to, and the drunkard must be supplied with his accustomed stimulant.

970. Many substances which increase the appetite and stimulate the stomach are in common use as *condiments*. Of these, common salt is the only one absolutely required; for experiment has shown that animals deprived of it soon perish, however nourishing their food in other respects; and one of the severest punishments to which man has ever been subjected, is a diet without salt. But when the diet consists principally of vegetables, spices are to be commended, as promoting digestion.

971. Every substance possessed of irritant properties increases the vascularity of the mucous membrane, and the flow of its secretion, and stimulates the muscular coat to contraction. The rubefacients which inflame the skin, inflame the mucous membrane of the stomach too; and many substances which cannot act on the skin through the cuticle, affect the more delicate and less protected lining of the stomach. In small doses these substances increase the appetite and strengthen digestion; but in large doses they act as emetics. Thus, common salt, which in moderation is the best and safest of condiments, in large doses produces sickness, and in still larger ones is an irritant poison.

972. Medicines having a similar action on the bowels, are given as adjuncts to counteract the unpleasant effects of other drugs. Thus, we combine mint, ginger, or cloves with saline purgatives, ammoniacum with squills, galbanum with aloes, the essential oils with aperient pills.

973. The aromatics, stomachics, carminatives, or cordials, are the remedies most frequently employed with a view of increasing the appetite, or causing the fibres of the stomach to contract. Ginger, mint, and cardamoms alone, or combined with bitters, are among the best remedies of this class.

974. *Emetics.*—Those in common use are mustard, common salt, ipecacuanha, tartar-emetic, and zinc. It is usual to promote the action of these substances by copious draughts of warm water, and by tickling the throat with a feather. Emetics are commonly prescribed merely with a view to unload the stomach; for this purpose they are often given at the outset of febrile affections. But they are also administered at intervals, with good effect, in incipient cases of phthisis pulmonalis, and in bronchitis accompanied with profuse expectoration. Emetics of common salt (three table-spoonfuls to a quart of water) have been prescribed with a view of producing reaction in the collapse of cholera.

975. The stomach becomes less sensitive to stimulants often repeated: while a more gentle stimulant loses its effect entirely by repetition. The first few doses of tartar-emetic often cause sickness; but the stomach becomes accustomed to its use, and then it no longer induces vomiting; and this is true of other irritant medicines, and of tobacco also.

976. Both condiments and emetics cause a flow of blood to the mucous membrane; cold liquids and ice have the opposite effect,

and are therefore useful in acute inflammation of the stomach, or active hæmorrhage from its surface.

977. The *Liver.*—The functional disorders of the *liver*, which consist in a diminished secretion of bile, are most effectually treated by small doses of mercury, or by nitro-muriatic acid. Taraxacum and podophyllin are also given to increase the biliary secretion, for which purpose the remedy last named is extremely effective. Such remedies are termed *cholagogues.*

978. The *Spleen* and *Pancreas.*—Congestion of these organs are readily relieved by abstinence, and brisk aperients. Quinine has a specific action on ague, in which disease of the spleen frequently originates.

979. *Simple Diarrhœa*, like dyspepsia, may often be removed by a farinaceous diet, from which all solid and irritating matters are excluded; and it will generally yield to a single full dose of castor-oil.

980. *Constipation*, as it arises from many causes, requires many remedies. The substances which naturally promote the action of the bowels are those innutritious matters that escape the action of the stomach; such as the cuticle and spiral vessels of vegetables, the hard covering of seeds; and the tendons and gristle of meat. When these are carefully removed in the process of cookery, constipation is apt to arise, and may often be removed by restoring some of them to the food. Thus, brown or whole-meal bread often proves an effectual laxative. Constipation also occurs in persons of sedentary habits, and disappears under active exercise.

981. The medicines that cause vomiting when taken into the stomach, as tartar-emetic, tobacco, sulphate of zinc, ipecacuanha, squills, &c., and the whole class of irritant poisons, act as purgatives when they pass into the bowels; but many of the substances which act as violent purgatives have little or no effect on the stomach.

982. Purgatives act in two ways—by promoting the secretion of the mucous membrane, and by increasing the peristaltic action of the intestines; but some act slightly in one of these ways and energetically in the other. Those that excite abundant watery discharges are called *drastic* or *hydragogue cathartics.*

983. Medicines that act on the bowels may be divided into groups or classes. There are the *laxatives* (manna, cassia pulp, tamarinds, prunes, honey, bitartrate of potash, castor, almond, and olive oils); the *saline* or antiphlogistic aperients (sulphates of soda, potash, and magnesia); the *milder acrid* aperients (senna, rhubarb, and aloes); the *strong acrid* purgatives (as jalap, scammony, black hellebore, camboge, croton oil, colocynth, and elaterium); and, lastly, the *hepatic* purgatives (hydrargyrum c. cretâ, pilula hydrargyri, calomel, and podophyllin).

984. We choose one or other of these remedies, according to *the object* we have in view. If we wish simply to relieve the

bowels, we prefer the compound rhubarb or colocynth pills, or a combination of aloes with rhubarb or ipecacuanha; if to promote the secretions of the whole course of the intestinal canal, we use the gentle laxative; if to reduce inflammation, the saline; if to overcome obstinate constipation, the stronger purgatives; if to remove dropsical effusions, the drastic or hydragogue cathartics; and if to promote the secretion of the liver, we combine the hepatic purgatives with those adapted to fulfil other indications.

985. The choice of purgatives is not more important, however, than the mode of administration. When the bowels have been long overloaded, and especially when the local irritation has affected the nervous centres, it is important to remove the load from the intestines without increasing the mischief already existing; in other words, hypercatharsis must be carefully avoided. Here we must not only select such purgatives as effectually remove the fæculent matter, but watch their operation from day to day; and as soon as any signs of intestinal irritation make their appearance, we must withdraw our purgative, and treat the hypercatharsis by a farinaceous diet, as if it were ordinary diarrhœa.

986. In cases of extreme irritability of the stomach or bowels, we may relieve the intestines by enemata, consisting of warm water, or gruel with or without an admixture of common salt; or we may employ, in the same way, any of the ordinary aperient remedies. The shock of cold water to the abdomen, sometimes employed with advantage in cases of obstinate constipation, or the electric spark, will also produce a purgative effect.

987. Enemata containing turpentine or an essential oil, such as the oil of rue, are advantageous in the painful flatulent distension of the abdomen that occurs in many cases of fever as well as in other states of system. They are most effective when thrown into the bowels by the long elastic tube. Enemata of salt dissolved in gruel are also often administered for the removal of worms, especially of the thread-worm.

2. Remedies which Modify the Composition of the Blood.

988. All articles of food, and all poisons and medicines (even the least soluble), find their way into the blood. Those substances which enter naturally into its composition, when taken in quantities proportioned to the wants of the frame, are used in building up the fabric of the body and in the production of animal heat; but when taken in excess, they are imperfectly assimilated, and cause disturbance of the internal organs in the process of elimination. Poisons and medicines in like manner, mixing with the blood, circulate with it; and after having been thus brought into contact with the textures of the body, pass out more or less quickly with the excretions.

989. In the treatment of disordered states of system, and of diseases properly so called, we sometimes administer such articles

of diet or medicine as will supply some defective element of the blood; but sometimes we purposely introduce a substance foreign to its composition, in order to destroy or counteract some injurious or poisonous material to which the diseased condition owed its origin. The substances of the first order are termed *Restoratives*; those of the second order *Catalytics* or *Alteratives*.

990. *Restoratives*—This class may be distributed into two kinds. (1) Water and every description of wholesome food, when the body is suffering from the want of them. Thus water has the virtues of a medicine after long marches, in starved and wounded persons; in some forms of poisoning; in profuse discharges of blood, and in diseases accompanied by excessive secretion; and there are cases in which we limit the supply of water with advantage. A nutritious animal and vegetable diet is as medicine to the convalescent; a spare diet, chiefly vegetable, to the plethoric and gouty patient. Fresh food is curative in scurvy; fatty and oily substances of some service in phthisis; animal and vegetable matters not containing sugar, or easily converted into it, are preferred in diabetes; sugar in a crystallized form is forbidden in the oxalic acid diathesis, and fatty matters are contra-indicated in disease of the pancreas. (2) Those medicines, properly so called, which supply an element wanting to the blood. Such are iron and its preparations in anæmia and its allied conditions; such are alkalies and acids respectively, when the acid or alkaline reaction of the urine indicates an excess of acid or of alkali in the blood. The whole class of vegetable tonics and quinine are especially believed (see Headland on the "Action of Medicines") to act favourably in states of debility by supplying to the blood an element closely allied in composition to the *taurin* of the bile.

991. *Catalytics*, or *Alteratives*.—The medicines of this class are believed to be able to destroy or neutralize certain morbid poisons existing in the blood. Mercury and iodide of potassium act thus on the syphilitic poison. Again, mercury, in an eminent degree, and the fixed alkalies in a less marked manner, possess the power of checking inflammation—a power attributed, at least in part, to their well-known property of rendering the fibrin of the blood more soluble. The nature of the change which arsenic produces in the blood is less obvious, though its efficacy is undoubted; and the same observation applies to iodine and antimony.

3. Medicines which act on the Organs of Circulation.

992. We recognize four states of circulation in healthy persons, in disease, and under the operation of medicines, of which states the character of the pulse is the best indication. 1. Increased frequency of pulse with increased force and fulness; 2. Increased frequency with diminished force and fulness; 3. Diminished frequency with increased force and fulness; 4. Diminished frequency with lessened force and fulness.

993. In health, the first state of circulation is brought about by violent exercise, by spirituous liquors, and by other stimulants; the second, by those strong mental emotions and impressions which, in excess, give rise to syncope; the third attends exhaustion and sleep; and the fourth is commonly observed in the less healthy inhabitants of large towns, and in those who lead sedentary lives.

994. In disease, the first state is present in acute inflammation or high inflammatory fever; the second, in diseases attended with extreme debility; the third, in some cases of hysteria, and in some cases and certain stages of apoplexy; and the fourth, in persons predisposed to, but not actually suffering from, pulmonary consumption, as well as in those who are recovering from fever, diphtheria, and other exhausting maladies, and exceptionally in some epidemics of fever and of the febrile exanthemata.

995. The same conditions follow the operation of remedies; the frequent, full, and strong pulse is produced by spirituous liquors, by ammonia, and by other diffusible stimulants; the frequent, small, and weak pulse by tartar-emetic, tobacco, lobelia inflata, and aconite; and the infrequent pulse, of varying size and force, by opium, digitalis, henbane, stramonium, and other allied remedies.

996. In the cases specified—that is to say, in health, in disease, and under the operation of remedies—supposing the several states to be produced in the same person, with the same quantity of circulating fluid in his body, it is obvious that in a given time more blood will traverse each organ in the first case; less in the second; a variable quantity, sometimes more, sometimes less, in the third; and a smaller quantity in the fourth case.

997. In the first case, the quantity of blood traversing each organ is increased in two ways; by the greater frequency of the heart's beat and the larger quantity of blood sent out at each beat: in the second, the blood traversing each organ is diminished, because the quantity sent from the heart is lessened more than the number of beats is increased; and in the third and fourth, the heart sends forth in the one more, in the other less, blood than compensates the lesser number of its beats.

998. The remedies which augment the frequency as well as the force of the heart's contractions are called *stimulants;* those which augment their frequency and diminish their force *depressents;* those which produce diminished frequency with increased or diminished force *narcotics* and *sedatives.*

999. *Stimulants.*—The state of the circulation, as indicated by the pulse, being the test and measure of the effect of remedies, those are stimulants which increase the frequency and force of the heart's contractions. In exceptional cases, however, stimulants have the reverse effect.

1000. This excited state of circulation is effected by the nervous system, whatever the part to which the stimulant is applied; the change in the nervous centres being reflected back on the heart and blood vessels. For instance, if brandy be taken into the stomach, the impression on its nerves is conveyed direct to the heart through the branches of the solar plexus, or to the brain and spinal cord, whence it is reflected upon the heart; or being absorbed into the circulation, it may be applied directly to the nervous centres, or to the nerves supplying the lining membrane of the heart and blood vessels. In the simple case of exercise, the most powerful stimulant of the healthy frame, the effect on the circulation is partly mechanical, and partly reflex.

1001. The local effects of stimulants on the healthy body are due to the increased flow of blood to all its organs. The free and rapid circulation through the lungs leads to more complete decarbonization of the blood; the increased flow of arterial blood to the brain excites all its functions; the impressions on the senses are more acute, the flow of ideas more rapid, volition stronger and more prompt, the passions excited, the feelings joyous; the capillary circulation is increased; the glandular structures pour forth their secretions; and the functions of digestion and defæcation are performed with increased vigour.

1002. But stimulants in excess paralyze the nervous system, and thus act as depressents or narcotics. Thus excess of spirituous liquors lowers the heat of the body, and induces languor with a slow and feeble pulse. Still larger doses produce narcotism. Similar effects are produced by chloroform and the æthers. The action of belladonna and ammonia is more purely stimulant than that of either alcohol or æther.

1003. It was stated (§ 999) that increased frequency, fulness, and force of pulse is the test of the action of stimulants; but there is one case in which the test fails. It is the case of debility, without local disease, characterized by a small and frequent pulse which loses frequency and gains force under the use of stimulants. The effect of stimulants on the infrequent pulse of debility without local disease is also much less than that produced on the pulse in health, —a fact easily explained by the nervous exhaustion that attends debility, and renders it dead to all impressions from within or from without. If stimulants administered in this state lower the pulse, they act favourably as tonics; if they raise it much, they do harm, imparting momentary strength, to be followed by proportionate depression.

1004. As the question whether we shall or shall not administer stimulants in certain diseased conditions is important, it may be well to describe the signs which indicate the expediency or necessity of resorting to them, as well as those which prove that we were justified in giving them. The conditions of systems which especially demand the exhibition of stimulants, are:—1. The *fainting state.* 2. The continuous exhaustion brought on by loss of blood, profuse discharges, prolonged abstinence, an innutritious diet, and mental or bodily fatigue. 3. The exhaustion which occurs when febrile disorders assume the typhous or adynamic type. And 4. The exhaustion that ushers in many severe diseases.

(1.) The fainting state, whether produced by sudden loss of blood, by violent or prolonged exertion; by exposure to a hot and impure atmosphere; by intense mental emotion; by the cessation of the heart's action from organic disease, or by poison, such as prussic acid, and the vapour of æther and choloroform, demands the same treatment; namely, the shock of cold water, and the diffusible stimulants, ammonia, brandy, &c.

(2.) The exhaustion brought on by loss of blood, by continuous discharges, or by any of the causes just specified—a state indicated by extreme pallor of face, skin, gums, and tongue; small, quick, and frequent, or small, frequent, and irregular pulse; hurried respiration, with frequent sighing; great nervous irritability; and, in some cases, delirium—demands the continued and persevering use of those less diffusible stimulants which combine alcohol in variable proportion with a certain quantity of nourishment, such as porter, ale, wine, and brandy, proportioned to the degree of exhaustion. It is generally expedient to combine a narcotic with the stimulant, and opium is the one usually indicated.

(3.) The exhaustion which attends continued fevers and inflammations also requires the use of stimulants. In the extreme degree of this state, marked by the position on the back, the sinking of the body towards the foot of the bed, the picking of the bed-clothes, the low muttering delirium, and the involuntary discharges, such remedies are obviously necessary. But long anterior to this stage of extreme exhaustion and collapse, stimulants may be given with the greatest advantage, though some of the symptoms may be such as to excite a doubt of the propriety of administering them: the skin may be hot and dry, the tongue coated with a dry fur, the breathing quickened, the pulse frequent and sharp with some fulness, the countenance dusky, the eye injected with dark blood, the patient restless and delirious, his movements indicating considerable muscular strength. In this state it may become a grave practical question whether stimulants ought or ought not to be given, and our doubts can only be decided by actual experiment, and careful observation of the patient before and after the use of the stimulant. If the temperature be raised and the pulse become more frequent, harder, and sharper, the stimulant is unsuitable; but if the reverse be the result, we shall be justified in the use of the stimulant, and may repeat it. If, after an interval of a few hours, during which we have presevered in the use of stimulants, we find the pulse less frequent, slower, and softer, the tongue becoming moist, the skin cooler and moist with perspiration, the breathing deeper and slower, the countenance less dusky, the eye more clear, and the restlessness and the delirium abated, we have every reason to continue our treatment. A sign much insisted on by Dr. Stokes, as decisive of the necessity for stimulants, is the state of the heart.

t partakes of the weakness which affects the entire muscular em, its pulsations become extremely feeble, and the first sound ost imperceptible. The beneficial operation of stimulants is erefore indicated by a stronger impulse, and renewed distinctness sound. The one condition indicates the necessity for stimuli, he other justifies their use.

(4.) The exhaustion which commonly supervenes in the advanced stages of continued fever, and in other diseases which have put on the typhous type, is sometimes present in the early stages of the same maladies. The first effect of the poison of the several infectious and contagious disorders is sometimes nearly allied to collapse. The patient is extremely weak, and faints on the slightest exertion, the countenance is pale, the surface cold, the pulse frequent, full, quick, and extremely compressible, and the respiration hurried. In this state also it may be a question whether stimulants ought to be employed, and actual experiment alone can decide the question. If the stimulant lowers the pulse and renders the breathing less frequent, we are justified in prescribing its repetition, at the same time looking out for the reaction which in most cases follows this state of depression.

1005. *Tonics.*—These remedies, as the name implies, are given in states of debility, and specially in convalescence from exhausting maladies, with a view of restoring firmness, strength, and *tone* to the entire frame. In extreme weakness, stimulants impart real strength; in other words, they become tonics. In less degrees of debility, they produce less obvious effect than on the robust and healthy. Again, stimulants in large doses become tonics in small ones. But the class of remedies to which the term *tonics* is commonly and properly applied gradually restore the strength without stimulating the system. One class of tonics, the preparations of iron, owes its virtues to its power of supplying a deficient element of the blood. The good effects of other tonics (such as bark, and its active principle quinine) are not so readily explained.

1006. *Depressents.*—This name distinguishes a class of remedies which render the pulse frequent, small and weak, being the exact reverse of the action of stimulants. This change in the circulation is accompanied by great prostration of strength, nausea, cold sweats, and all those symptoms which characterize approaching syncope; and it is brought about by the abstraction of blood, b the preparations of antimony, by tobacco, aconite, and the lobel inflata, and by the less active remedies, ipecacuanha and squills.

1007. The loss of a large quantity of blood, or the rapid remo of a smaller quantity, occasions syncope, or a state approaching s and as during this state the heart sends out a comparatively s quantity of blood, and propels it with little force, that part flammation which is due to increased action of the heart is re letting.

metic, which, next to bleeding, is most p about the same state as is prod bleeding, and may be occasionally employed, either alone or in combination with it, in the treatment of *acute* inflammations.

1009. As there is an exception to the rule that stimulants increase the number and force of the pulse, so is there an exception to the rule that depressents increase its number while they lessen its force. Thus, blood-letting, which belongs to the order of depressents, renders the pulse full and strong, and even increases its frequency, in certain cases of plethora, when the circulation is oppressed, and in pneumonia, when the pulmonary circulation is impeded. Again, in cases of acute inflammation with high inflammatory fever, bleeding or tartar-emetic will lessen the frequency and force of the pulse at the same time. In all these cases, the *modus operandi* is the same; it appears to be different only because the circumstances vary.

1010. *Sedatives.*—These remedies differ from stimulants and depressents, inasmuch as, in lieu of increasing the frequency of the pulse, they diminish it. The true sedatives differ from the pure narcotics inasmuch as in large doses they cause delirium, while the narcotics in large doses occasion coma and apoplexy. Sleep, also, is an occasional, not a constant, effect of sedatives.

1011. Hydrocyanic acid, digitalis, and aconite, the principal remedies of this class, commonly lower the pulse. But there are states of system in which these remedies increase its frequency, just as there are states in which the effect of stimulants and depressents on the circulation is reversed. Digitalis, for example, which, in diseases accompanied by a frequent pulse, lowers it in a remarkable degree, and often much below the healthy standard, in some healthy persons, and in some conditions has the reverse action. The effects of hydrocyanic acid are more constant; but exceptions doubtless exist to the rule of its operation.

1012. *Cold* is a most powerful sedative. A moderate degree of cold applied to the surface acts as a stimulant; but when the skin is hot and dry it reduces the temperature, lowers the circulation, soothes the nervous system, and disposes to sleep. Applied to the head, in the form of cold lotion or of ice, it is a most valuable remedy in inflammatory affections of the brain; and it is of the greatest service in all inflammations and hæmorrhages. Ice may be swallowed with advantage in bad cases of quinsy and scarlatina, and in hydrophobia with great relief to the symptoms. Applied locally, in the form of *douche*, cold restores the contractility of the capillary vessels, and by preventing further effusion, allows the absorbents to remove any fluid that may have been thrown out. Intense cold is also a valuable anæsthetic, and may be employed in painful operations on superficial parts. It also acts as a narcotic, and may produce states of system difficult to distinguish from the effects of alcohol.

1013. *Narcotics.*—The action of these remedies belongs so completely to the fourth head (the action of remedies on the nervous system) that nothing need be said in this place except that their effect on the circulation is the opposite of that produced by stimulants and depressents. They lessen the frequency of the heart's action, and, to a greater extent, the respiratory movements.

1014. The remedies just examined affect the circulation primarily by their influence on the nervous centres; and secondarily, through the reflection of that influence on the heart. It remains to speak of the

1015. *Remedies which affect the Smaller Vessels: Treatment of Inflammation.*—It has been already stated that in inflammation there is diminished action (that is, diminished contractility) of the small arteries, with increased action of the heart, and that the two together keep up that dilated state of the small vessels which is the essence of inflammation. It is obvious that there are two ways in which these minute vessels may be restored to their healthy state: the first is by lessening the quantity of blood passing through them; the second, by increasing their contractility. In most acute inflammations, both changes have to be brought about. If the inflammation be recent, the small vessels may recover themselves on being relieved from the undue quantity of blood sent to them by the heart; and in this case the abstraction of blood, or the use of depressing remedies, will suffice. But if the inflammation be chronic, the small vessels may not recover their contractility, though the blood circulates through them in diminished quantity; and in this case we must use such remedies as restore the lost contractility of the vessels. The same treatment is required in the analogous state of congestion.

1016. *Blood-letting.*—Venæsection may be necessary in the earliest stage of pneumonia, in plethoric subjects, as a means of direct relief. Acute pleurisy and other local inflammations rarely require more than local depletion, by means of leeches, or cupping instruments. A high temperature, rapid throbbing pulse, severe orthopnœa or dyspnœa, and acute pain are indications which will lead us to select this remedy.

1017. The strong action of the heart which attends acute inflammation is absent in inflammation of the mucous membranes, unless it take on the most acute character, as in croup, or in irritant poisoning.

1018. When inflammation of the mucous membranes is very severe, especially if the affected membrane line some narrow passage apt to be filled with the secretion poured out from its surface, as in acute capillary bronchitis, and in acute nephritis, local depletion may be necessary.

1019. When the seat of inflammation is an organ of extreme delicacy, we are obliged to employ general remedies, though the disease does not affect the circulation or threaten life. Thus, in inflammation of the internal parts of the eye, the most active measures are necessary to save the organ from destruction.

1020. As a rule, then, blood-letting is only required in the earliest stage of inflammation, attacking robust and plethoric persons, when it is attended by increased action of the heart; when some function essential to life is impeded; or when some delicate organ is threatened with destruction.

1021. The second indication—that of causing contraction of the small vessels—may be accomplished in various ways: *locally*, by pressure, cold, astringent applications, and the cautious use of substances which themselves cause inflammation, but act as stimulants when applied in small quantity, and for a short period; and *generally*, by remedies which, by emptying the blood vessels, promote their contraction—such are purgatives: and another very distinct class which stimulate the muscular walls of the blood-vessels to contract. This latter class of remedies contains two kinds. The first are those like digitalis and ergot, which act directly upon involuntary muscular fibres; the second act more or less indirectly, and usually in a reflex manner. Such are astringent stimulants and irritants, as tannin, copaiba, cubebs, pepper, cantharides, turpentine, the salts of zinc, copper, and silver.

The salts of antimony, mercury, arsenic, and iodine have a three-fold action; by increasing the secretions they diminish the volume of the blood, by their irritant action they promote contraction of the bloodvessels, and by a depressent influence on the sympathetic nerve, they lower the force of the heart's action.

1022. Combinations of these remedies are used with great advantage. Thus, depletion, either general or local, may be followed by purgatives, and these, again, by such general remedies as digitalis, tartar-emetic, or saline diaphoretics.

1023. If the vessels are much distended, local depletion is indicated as a preparatory measure. When the small vessels have been partially emptied, we may apply the remedies just mentioned according to the nature of the inflamed part. Pressure, properly applied, lends support to the vessels; cold acts on all the tissues of the part, on its vessels and nerves; astringent applications cause all the textures to contract, at the same time that they gently irritate the vessels, and excite them to the performance of their proper function; while such irritants as nitrate of silver, and sulphate of zinc or copper, prove beneficial by their stimulating property.

1024. The cases in which one of these remedies is more applicable than another have been determined by long experience. Tartar-emetic is to be preferred in common, mercury and iodine in specific, inflammation. Mercury is to be preferred in cases of great urgency (such as iritis and croup), when our object is not merely to subdue inflammation, but to suspend the specific disease of which it is a part.

1025. Uva ursi, copaiba, cubebs, and black pepper are employed with advantage in inflammation of the mucous membrane of the urinary passages. They act as direct stimulants through the urine. Uva ursi is used chiefly in inflammation of the mucous membrane of the bladder; copaiba and cubebs in gonorrhœa (in which disease pepper has also been employed), and black pepper in hæmorrhoids. Copaiba has been prescribed with advantage in cases of bronchitis.

1026. *Hæmorrhage.*—Active hæmorrhage may require the same remedies as acute inflammation; and passive hæmorrhage those which are useful in some forms of chronic inflammation—viz., cold, the preparations of lead, and vegetable astringents.

1027. The treatment of *febrile affections* is governed by the same general principles as the treatment of inflammation. When free from the complication of local disease, and attended by a frequent, full, and hard pulse, depressing remedies, such as a brisk purge followed by tartar-emetic, are indicated: but in cases attended by great prostration, with a small and frequent pulse, stimulant diaphoretics are beneficial. Local disease must be treated by general or local remedies, according to the patient's strength.

1028. The process of *secretion* is one over which medicine exerts much power, directly and indirectly. The most important secretions are those of the lungs, skin, kidneys, and bowels. The aerial secretions of the lungs are not usually subjects of observation or measurement.

1029. The influence of remedies on the secretions will be best understood by selecting that of the skin as an example. When the skin is red, hot, and dry, we can excite perspiration by the application of cold; when it is pale, cold, and dry, by heat. In the one case, we diminish the size of the small vessels, and lessen the quantity of blood they contain; in the other, we increase both. In the same conditions of skin, and in the same states of system, we produce the same results by depressents and stimulants, so that, in the case of this secretion, we can produce the same effect by a local application and by an internal remedy. In both cases, the temperature favourable to sweating is intermediate between the two extremes of temperature.

1030. In extreme debility it is well known that cold sweats take place from mere relaxation of the vessels, when the temperature of the body is extremely low.

1031. Blood-letting itself in a case of inflammatory fever, will promote the flow of all the secretions, by relieving that congestion of the vessels which is the chief impediment to secretion.

1032. When, therefore, we wish to promote the secretions, and especially that from the skin, we strive to bring the circulation into that state in which secretion is possible. When the skin is hot and dry, we select a depressent, when cold, a stimulant diaphoretic. in languid states of circulation, again, we prescribe a stimulating *diuretic,* and a depressing one when there is strong febrile action.

1033. The remedies which promote the *absorption* of fluids thrown out into the cavities of the body, act for the most part through the general system. Of these the most powerful is blood-letting, which acts by diminishing the quantity of the circulating fluid, and when the cause of dropsy is inflammatory, by removing the inflammation. The other remedies in common use are employed with the same view. They are directed to the secreting organs, the bowels, kidneys, and skin. The increased secretion from these parts has the twofold effect of blood-letting—it lessens the quantity of the circulating fluid, and it subdues inflammation.

1034. The local means best adapted to promote absorption, are those which stimulate the parts affected, such as friction with the hand or with stimulant liniments, tincture of iodine, a jet of cold water, or electricity. These act favourably either by restoring the capillaries to their healthy state, or by stimulating the absorbents. (See § 335.)

4. REMEDIES ADAPTED TO THE REMOVAL OF THE SOLID STRUCTURES OF THE BODY.

1035. Morbid growths, due to effusion into the cysts or meshes of an organ, as in bronchocele, or deposits of solid matter, as in gout and secondary syphilis, are more or less amenable to remedial treatment (see Alteratives). But others, such as cancer, fibrous tumours, and exostosis, are wholly unaffected by the action of medicine, and require surgical interference.

1036. Atrophy and hypertrophy are, to a great extent, under the control of medicine. The remedies applicable to a state of atrophy are exercise, friction, electricity, and, in short, all those means which increase the flow of blood to the part and promote its natural actions. Those, on the other hand, which are of use in hypertrophy are, rest, pressure, cold, local abstraction of blood, and preparations of mercury and iodine.

5. REMEDIES WHICH ACT ON THE NERVOUS SYSTEM.

1037. As all the functions of the body are dependent on nervous influence, all active remedies must affect the nervous system. Stimulants, depressents, sedatives, narcotics, and some medicines, at least, which belong to the class of tonics, affect the circulation through the nerves; and even those remedies, of which the action is strictly local, act locally on the nerves, and, through them, on the vessels to which they are distributed. But there are some substances which exert so peculiar an influence on the nervous system as to demand a separate notice. In this action we recognize three marked varieties. Some produce a state of excitement in all the functions of the nervous system; others soothe the nerves, tranquillize the mind, and procure sleep; a third class act chiefly on the organs of circulation and respiration, while they derange the functions of the brain, and occasion delirium; and a fourth class depress the nervous power and lower either the pulse and temperature, or the motor activity. The first class are known as *stimulants*, the second as *hypnotics*, the third as *narcotics*, the fourth as *sedatives*.

1038. (1.) *Stimulants.*—The mode in which these remedies affect the body, and the cases in which they may be used with advantage, have already been pointed out (§ 407 *et seq.*). But they not only affect the circulation in the manner described, but also all the functions of the brain, spinal cord, and nerves. The most active and efficient stimulants are ammonia and its carbonate, phosphorus, musk, mustard, and turpentine; to which may be added the more active and diffusible among the narcotic medicines, belladonna, alcohol, æther, and chloroform, and camphor when given in large doses, the first effect of which is stimulation. To these may be added, as special stimulants to the spinal cord and nerves of voluntary motion, the alkaloids strychnia and brucia, and the plants that contain them.

1039. (2.) *Hypnotics* or *soporifics.*—Of these opium, and its alkaloid morphia, and chloral hydrate, are the chief, and bromide of potassium, henbane, lactucarium, the hop, and the nutmeg, the less important. These are used to relieve pain (*anodynes*); to soothe irritation (*paregorics*); or, lastly to procure sleep (*hypnotics* or *soporifics*). Opium is both stimulant and hypnotic; hence it is admirably adapted to the state of irritation accompanied by much debility, the hypnotic principle soothing the excitement, the stimulant counteracting the debility. Sulphuretted hydrogen, carbonic acid, carbonic oxide, and cyanogen gas, act also as hypnotics and sedatives.

1040. (3.) *Narcotics.*—These remedies, which occasion the mixed effects of sleep, stupor, and delirium, as their leading symptom, are sometimes subdivided into the smaller groups of *inebriants, soporifics* and *deliriants.* Alcoholic liquors, chloroform and the æthers, camphor, and Indian hemp, are usually regarded as "inebriants," but in excessive doses they produce more or less delirium. Henbane, belladonna, and stramonium cause delirium as an early and prominent symptom, and these are therefore regarded as typical "deliriants."

1041. (4.) *Sedatives.*—This class comprises many substances allied in some of their properties to the narcotics. They exert a depressent action on the heart, and lower the temperature; they differ from narcotics in not producing sleep. Henbane, when given in large doses, produces delirium; black hellebore, veratria, and colchicum are cathartic; ipecacuanha and squill are emetic; aconite, tobacco, lobelia, digitalis, and hydrocyanic acid are the simplest and most powerful sedatives of the whole class, causing extreme general prostration; conium, physostigma, and gelsemium have a simple sedative action on the centres of the voluntary, and ultimately of the involuntary, muscular system.

1042. Cold has already been mentioned more than once, as a remedy of great power (§ 1012). It may produce a marked sedative effect on the nervous system, without any corresponding effect on the circulating organs. It blunts sensibility and subdues pain, and in cases of violent nervous excitement allays the irritation of the nervous system, reduces the number of the pulse, subdues the most acute pain, and infallibly procures sleep. It is also of great efficacy in the most violent paroxysms of mania.

Having indicated the chief remedies which affect the nervous system, it will be useful to speak more particularly of their action on the special functions of sensation and voluntary motion.

1043. Of the remedies which act on the *nerves of sensation*, aconite is the most powerful. It produces numbness and a tingling sensation in the parts to which it is applied. Strong hydrocyanic acid, locally applied, also causes numbness; opium and belladonna, too, act locally on the nerves of sensation; and chloroform is a powerful local anæsthetic, after producing, as its first effect, redness and heat of surface. But the best sedative is cold. It is sure and manageable, and, with proper precautions, may be applied whenever a sedative is indicated.

1044. Belladonna shares with hyoscyamus and stramonium the power of dilating the pupil, whether given internally or applied directly to or near the eye. Calabar bean has the opposite effect.

1045. The *nerves of voluntary motion*, and through them the muscular system, are powerfully affected by remedies in three different ways—with *paralysis convulsions* and *tonic spasms.*

1046. Extreme muscular debility is the familiar effect of all depressing remedies. This effect is produced by tartar-emetic among mineral, and tobacco and lobelia inflata among vegetable, poisons. Paralysis, or the extreme of muscular weakness, is produced by various poisons, as the strychnos toxifera (wooraly or woorara), and by large doses of aconite and conium, and by one metallic poison—lead.

1047. Convulsions are produced by almost all active poisons. They precede the fatal event in quick poisoning by hydrocyanic acid, and occasionally occur in poisoning by opium, arsenic, and the stronger mineral poisons.

1048. Tetanic spasms are produced by nux vomica, by St. Ignatius' bean, by the strychnos tieuté, and by the active principles strychnia and brucia. They are an occasional effect of monkshood and of ergot taken in poisonous doses, and they are sometimes present in poisoning by the more active irritants.

1049. The muscular contractions of the uterus caused by ergot furnish an example of local action on the muscular fibres, of which advantage is taken in the practice of midwifery.

1050. The treatment of diseases dependent on, or accompanied by, local affections, with reflex action of the muscles is of much importance, especially in such diseases as tetanus and hydrophobia. In the latter disease ice has often given great relief.

1051. Many of the metallic salts, such as those of arsenic, copper, iron, silver, and zinc, appear to exert an influence on the nervous system. They act locally as irritants, and when administered in small doses, and during a considerable period, as tonics; as such they have been used with advantage in chorea and epilepsy.

6. Nursing.

1052. In nursing, attention must be given to the following particulars:—Situation of the sick-room; the room itself—its arrangements, temperature, ventilation, light, refreshment; administration of medicine and food; condition and personal comfort of the patient; his intercourse with his attendants; precautions required in cases of contagious disease.

1053. *Situation of the Sick-Room.*—When we can exercise a choice, a south, south-west, or west aspect should be preferred. In acute inflammation of the brain or eye a north aspect is best. But, in the early stage of the disease, at least, aspect must be sacrificed, if need be, to quiet.

The *room* should be spacious, lofty, lightsome, and have a chimney with a good draught. In some cases the carpet may be retained; but superfluous furniture, hangings, and articles of clothing, should be removed.

1054. *The patient's bed* should be placed with its head out of direct currents of air from door and windows, and with ready access to either side of it; it should be furnished with rollers that it may be wheeled to any part of the room, and, as a rule, should be without curtains. A calico screen may be used to intercept draughts and shut out the view of the door, and of the nurse while she is preparing food or medicine.

1055. *Temperature.*—This may range from 60° to 70° Fahr., according to the feelings of the patient, and should be kept as constant as possible. If the patient complain of cold, a hot water bottle, or cushion, or an additional blanket, or eider-down quilt, may be used.

1056. *Ventilation.*—In cold and moderately warm weather a fire should be kept constantly burning. If the external air be very cold, the fresh air may be derived through the door from the lower parts of the house; if temperate, the landing window and the bedroom door, or one of the bedroom windows, should be opened. In summer, when it is too warm for a fire, the windows should be wide open during the day and at night be partially opened. The door may be kept ajar and occasionally fanned to and fro to cause a freer circulation of air. Vitiation of the atmosphere of the sick-room by visitors and too many attendants must be avoided. The free combustion of gas, too, must be prohibited. Growing plants may be introduced into the sick-room, as they serve both to purify and to moisten the atmosphere.

1057. *Light* should be moderated according to the feelings of the patient. If he be watchful it should occasionally be excluded during the day, advantage being taken of the times when the vigilance is least. It must be constantly excluded in cases of active inflammation of the brain or eye. Direct sunlight is rarely tolerated in acute disease, but in some chronic diseases it is both pleasing and refreshing.

1058. *Refreshment.*—Offensive odours diffused through the air may be counteracted by burning a few lavender flowers or a pastille, sprinkling eau de Cologne, or burning coarse brown paper saturated with a strong solution of nitrate of potash, dried, and kept for use. But as more effectual means, the carpet being removed, the floor should be sprinkled several times a day with a weak aqueous solution of kreasote or carbolic acid; or rags wetted with the same should be suspended near the bed. In cases of infectious disease, such as fever, diphtheria, gangrene of the lungs, &c., baskets of wood charcoal should be placed under the bed and in the corners of the room, and the evacuations should be received into water containing powdered carbolated lime, or a solution of carbolic acid, sulphate of iron; or a mixture of dry earth, ashes, or powdered wood charcoal, with sulphate of iron (℔j to ℥j).

1059. *Administration of Medicine.*—Pungent medicines should be given well diluted with water, to obviate coughing and nausea. Doses should be carefully measured in a graduated medicine glass, and given without delay, especially when they contain volatile ingredients. Deposits, if any, should be well shaken up. In the intervals the bottle should be kept closely corked. As a rule, medicine should be given an hour before food. But if nutriment has to be administered frequently, the medicine must be so given as least to interfere with it; stimulants may be taken with stimulants, and tonics with food; purgatives should be given before food; hypnotics at any time.

Medicines should never for a moment be allowed to stand side by side with applications for external use, and the two ought to be kept in different places. It is best to regard liniments and lotions as poisons, and to keep them out of the way in grooved bottles, so that they may be recognized as such by the touch.

1060. *Administration of Food.*—If a patient has a distaste for food, very small quantities should be offered at a time. He may thus be induced to partake of it again and again when a larger quantity presented at once would be refused. In irritable conditions of the stomach a tablespoonful of nourishment may excite vomiting, while a teaspoonful repeated often would be retained. Strong tea and jelly may be both suitable and harmless, but together, we must remember, they form indigestible leather. The juice of oranges and grapes is generally harmless, but few things are more indigestible than the pulp, skins, and seeds. In the typhous condition, food or stimulants are needed every hour; and as the patient is well-nigh insensible to his wants, his life depends on the close attention of the nurse.

1061. *The nurse* should be quiet, circumspect, and firm, and possess the tact only to be acquired by experience. Good eyesight is indispensable. She should set aside out of reach sedative draughts, liniments, and other external applications, keeping within easy reach only such mixtures or draughts as are required at short intervals. She should be provided with oiled silk, oiled cloth, &c., so as to prevent discomfort in the use of poultices and moist applications. She should be allowed as little discretion as possible; written directions as to the nature and quantity of food and medicine, and the times of its administration, should be given to her, and she should be directed to make a written report accordingly, noting down the number of hours the patient has slept, the time at which any new symptom, such as pain, dyspnœa, vomiting, fits, &c., occurred; and whether, and when, the bowels or bladder have acted. She should be directed in certain cases—such as constipation, diarrhœa, enteric fever, dysentery, hepatic disease—to set aside the evacuations in the-water-closet. In severe disease a bed-pan and glass urinal should be provided for the patient's use. The urine should be occasionally preserved for examination.

She should look to the general condition of the patient, and note the temperature of the body, and especially of the feet. In the typhous condition these parts may be found cold and purple, and when it may be too late to recover them from this incipient stage of gangrene. In spinal and cerebral diseases, as well as in the typhous condition, the integument over the sacrum and trochanters must be daily looked to; and if it appear congested, lead plasters spread upon amadou or wash-leather must be applied, and the pressure obviated by a water-pillow or water bed. The medical attendant must occasionally verify the statements of the nurse, and himself examine the condition of the hypogastric region. When a patient is placed on a water bed, the water should be warm, and a thick layer of blankets be put between the bed and body, to allow of free exit of perspiration, and prevent chilling. If the patient complain of cold we must replace some of the cold water by hot.

1062. *Personal Comfort.*—If the patient's condition allow of it, his bed should be made every day, a couch being at hand to receive him. In cases of protracted illness it is well to provide two beds. The linen should be changed as often as it can be done without undue fatigue, and advantage should be taken of this change to administer a bath, or to sponge the skin with warm water. A bath is a very important adjunct to a sick-room, for we have no more efficient means of provoking sweat and of soothing nervous excitability than the warm bath. In some cases (suppression of urine, convulsions) it is indispensable. A thermometer should be at hand to regulate the temperature. For a tepid bath we may prescribe 85°; for a warm 95°; for a hot 105°.

If it can be done without fatigue, the teeth and mouth should be cleansed occasionally, and the hair brushed.

1063. *Thirst* may be allayed by toast-water, thin gruel, or barley-water, and by soda-water, lemonade, or iced water slightly acidulated, if need be, with sulphuric or phosphoric acids, and sweetened. In the typhous condition spirit or wine may be added to these drinks.

When the tongue is parched, hard, and cracked, a little olive oil should be frequently smeared over it. When sordes tend to accumulate, the mouth should be occasionally cleansed with the finger covered with soft rag moistened with warm water or oil.

1064. *General Management of the Sick-room.*—All should be quiet and yet cheerful here. If the patient be unduly apprehensive, anxious looks and tones must be avoided in his presence. When he is awake to impressions, there should be no whisperings in his presence or hearing. In the sick-room all our communications should be *with* the patient, either directly or openly through the nurse. We must inspire confidence and hope by a plain, easy, and decided manner. There must be no mystery or ambiguity about our acts and words. We must answer the solicitous inquiries of the patient as simply and straightforwardly as possible, so as leave no doubt in his mind. "You are better by this little indication." "You are worse because of this complication against which I am going to direct remedies such as we may reasonably hope will cause it to yield sooner or later." "What you want is sleep, and this we will secure for you to-night." Such must be the language of the medical attendant.

1065. The sensations and ideas are so perverted in delirium that patients labouring under mental disease, whether primary or secondary, are best treated by assuming a cheerful indifference. When homicidal and suicidal tendencies exist, cutting instruments must be removed, and windows secured. If the patient obstinately refuse food, do not press it—put it from time to time before him, and let others eat in his presence. Loud, strange, or uncertain noises should be prevented. The influence of music may be brought to bear in certain cases.

1066. In protracted illness, when the intellect is clear, we should vary the position of the bed, and change from time to time the pictures, ornaments, and furniture of the room, and distribute about it Wardian cases, aquaria, growing plants, and cut flowers of various hue; for anxiety and gloom are inseparable companions of severe illness, and we should not neglect any means, however trifling, of dispelling them.

1067. When a case of contagious fever occurs in a house, and the patient cannot be removed, strict precautions are necessary to prevent the spread of the disease. The younger members of the family should be sent away at once, or, if this be impracticable, they should live and sleep on the ground-floor. The patient should be placed in the airiest and most secluded room in the highest part of the house, and only those in attendance should have access to that story. If possible, he should be under the care of a single nurse, and an adjoining room should be devoted to her use, with ready means of communication with the people below. Her food and that of the patient should be brought to the landing on the floor below, where she should receive it. She should go downstairs as seldom, and keep aloof from other persons as much, as possible. Before leaving her room she should be careful to wash her hands, using a little carbolic acid, or carbolic acid soap. A fire and a large kettle of boiling water should be constantly at hand. A separate set of articles should be devoted to the patient's and the nurse's use, and before they are sent away they should have boiling water poured from the kettle upon them. Linen should be treated in the same way, and then wrung out and put aside. It should be allowed to accumulate to the end of the illness, and after a second exposure to the action of boiling water, be sent to the laundress. The patient's room must be thoroughly ventilated. Disinfectants should always be mixed with the dejections, and they should be conveyed to the water-closet in a tightly-covered vessel. The water-closet pan should be well-flushed, and if other conveniences be near, the rest of the household should not use this one during, and for some time after the illness.

1068. After convalescence the sick-room must be thoroughly cleansed. Clothes which cannot be washed must be burned. The bed, mattress, and carpets must be baked in a hot oven; oil paint scoured, the ceiling whitewashed, the walls re-papered, the floor scalded, and afterwards scrubbed. The door should be kept shut, and the windows open, and a large fire should be kept up during, and for some days after, the cleansing. Boiling water is a thorough disinfectant. We may use such disinfectants as charcoal, chloride of lime, chloride of zinc (Burnett's fluid), and carbolic acid, in addition, but we must not trust to these alone. Burning sulphur is an efficient, but from its destructiveness an objectionable disinfectant, excepting in a completely bare room.

PART II.

PRACTICE OF MEDICINE.

CONTENTS.

GENERAL DISEASES.

CHAPTER 1. States of the system.
2. Local diseases, affecting all or several of the organs or textures of the body.
3. Febrile diseases without essential local complication.
4. Febrile diseases with essential local complication.
5. Febrile diseases arising from local causes.
6. General diseases (not febrile), with essential local complication.

SPECIAL DISEASES.

CHAPTER 1. Diseases of the nervous system.
2. Diseases of the organs of circulation.
3. Diseases of the organs of respiration.
4. Diseases of the organs of digestion, and abdominal viscera.
5. Diseases of the urinary organs.
6. Diseases of the organs of generation.
7. Diseases of the organs of sense.
8. Diseases of the skin and its appendages.
9. Parasitic animals.
10. Poisons and their antidotes.

---

1. Classification of remedies, and formulæ.
2. Glossarial index.

GENERAL DISEASES.

CHAPTER I.

STATES OF THE SYSTEM.

Plethora	The Plethoric State.
Anæmia	The Anæmic State.
Cachexia	The Cachectic State.
Mimosis Inquieta	The Nervous State.
Febricula	The Febrile State.

The subjects treated in this chapter have peculiarities which entitle them to a place by themselves. They are rather disorders than diseases properly so-called. They consist in a departure from health, more or less permanent, not necessarily complicated with any local affection, and are often present and cognizable in combination with specific and well-defined maladies. A plethoric, an anæmic, or a cachectic patient, one suffering from extreme debility, or from a group of nervous symptoms, may become the subject of a disease, such as fever or small-pox, which will be materially influenced in its character, progress, and termination by that pre-existent *state of system*. The treatment of a disease will also be materially influenced, and in some cases altogether determined, by the state of system on which it has supervened. Again, in all those diseases in which the symptoms are obscure, or the appropriate remedy not yet discovered, the only course open to the physician is to direct his prescriptions to the states of system. Nor ought it to be forgotten that these states of system may be themselves brought on by several analogous local or general causes, and that to recognize them is to possess a clue to the often obscure, and little-suspected, origin of the existing disorder. For these reasons they are treated in a chapter by themselves, and take precedence of diseases properly so-called.

PLETHORA.—THE PLETHORIC STATE.

Synonyms.—General Hyperæmia.—Polyæmia.—Fulness of blood.—A full habit of body.

Definition.—A state of system characterized by an excessive *quantity of blood*, or by an excess of its more solid constituents.

Symptoms.—The complexion florid; the capillaries of the surface injected; the redness of the skin momentarily removed by pressure; the lips red; the eyes bright, and the conjunctiva injected; the tongue clean and red, or slightly furred; the appetite generally good; the bowels usually confined; the skin dry, but perspiring profusely on exertion; the pulse frequent, full, firm, and bounding. In strongly-marked cases, the pulse is infrequent, and labouring, or irregular in force and frequency, according to the degree in which the heart is oppressed. The extremities are cold; the patient is weak, listless, and easily fatigued on exertion, suffers from palpitation, shortness of breath, and frequent sighing; and complains of giddiness, noises in the ears, bright or dark spots before the eyes, and a dull heavy pain in the head.

Terminations.—In local congestions, inflammations, and hæmorrhages; in apoplexy, especially in persons with large chests and short necks; in hypertrophy of the heart; in gout.

Pathology.—An excessive quantity of blood, or superabundance of red particles and fibrine; urine with excess of urea.

Causes—*Predisposing:* A peculiar habit of body, with large chest and short neck. *Exciting:* A highly nutritious diet; beer and spirituous liquors; sedentary habits; too much sleep; inadequate exercise. In females, suppression of the catamenia.

Diagnosis.—By the fulness of the whole capillary system, and the rapid filling of the vessels of the surface on the removal of pressure.

Treatment.—*Indications:* I. To lessen the quantity of blood. II. To increase the actions of the excreting organs.

The first indication is best fulfilled by a spare diet, abstinence from malt and spirituous liquors, early rising, and regular exercise; and the second by the frequent use of saline aperients.

In extreme cases, and where there is a threatening of local congestion, abstraction of blood by venæsection, cupping, or leeches may be necessary. But, as a rule, it is better to avoid the letting of blood, and to trust to the prolonged use of abstinence, exercise, early rising, and saline aperients. If amenorrhœa be present, four or six leeches may be applied to the groin at the menstrual periods. If apoplexy or gout impend, the treatment must be modified accordingly.

Prophylaxis.—The diet should be spare and moderately nutritious, with abstinence from malt or spirituous liquors; perspiration should be promoted by brisk exercise; and the bowels kept free by suitable aperients.

ANÆMIA.—THE ANÆMIC STATE.

Definition.—A state of system characterized by a diminution in the quantity of the blood, or of the red particles and other solids.

Varieties.—1. Anæmia from loss of blood. 2. Chronic anæmia. 3. Cachectic anæmia, or chlorosis.

1. Anæmia from Loss of Blood.

Symptoms.—The most familiar effect of loss of blood (or of profuse discharges rapidly poured out) is *syncope* (see p. 239). The fainting state is followed by reaction, and is apt to recur on slight exertion, or change of posture; but in *fatal cases* the symptoms become gradually and progressively worse; the countenance paler and more sunken; the extremities colder and colder; the breathing hurried and interrupted by deep sighs or yawns, panting, gasping, or stertorous; the pulse imperceptible; restlessness and jactitation are followed by coma, or convulsions; at length the strength is exhausted, and the patient gasps and expires. In states of extreme weakness, death sometimes occurs on suddenly assuming the sitting or standing posture.

The state of *reaction* is characterized by peculiar and strongly-marked symptoms; by forcible beating of the carotids, with a sense of throbbing and tension in the head; palpitation of the heart, throbbing at the pit of the stomach, and in the course of the aorta, and a frequent, bounding, and often irregular sharp pulse; a hurried panting, sighing respiration; restlessness, jactitation, and mental agitation; intolerance of light and sound; the sleep disturbed by fearful dreams; the waking hurried and perplexed. Violent delirium, mania, coma, amaurosis, and deafness are among the concomitants of this state.

Post-mortem Appearances.—An empty state of the cavities of the heart, and general pallor of the viscera, most marked in the lungs.

Diagnosis.—By the extreme pallor of the face, skin, lips, and gums.

Treatment.—*Indications.* I. To stimulate the brain with the blood that still remains. II. To maintain the action of the heart by external and internal stimulants. III. To subdue abnormal nervous action. IV. To promote the formation of new blood.

The first indication is effected by placing the head on a level with the chest; the second, by the free exhibition of ammonia, wine, or brandy, and the application of cloths wrung out of hot water, or of sinapisms to the region of the heart; the third, by a full dose of tincture of opium, which is obviously preferable to the solid preparations of the drug. If violent delirium or acute mania be present, as a consequence of the loss of blood, we may repeat the dose at intervals of three or four hours, according to the effect produced. Convulsions declare the most imminent danger, and if the means were at hand we might resort to the transfusion of blood, or to galvanism and artificial respiration. The formation of new blood will be promoted by administering beef-tea, or egg beat up with milk, wine, or brandy, or, if the power of deglutition fail, introducing these into the rectum. Having re-established the circulation, the subsequent treatment will be that of chronic anæmia. For a time the erect or sitting posture must be strictly interdicted.

2. Chronic Anæmia.

Definition.—A state of system coming on gradually, continuing generally for some weeks or months, and dependent on a decrease in the red particles and solid constituents of the blood.

Symptoms.—Universal pallor, extending to the conjunctiva, gums, and membrane of the mouth: dead whiteness of the tongue; cold extremities; debility; fainting fits; palpitation and dyspnœa on the slightest exertion, with violent pulsation of the carotid arteries; headache, consisting generally in a fixed pain over the eyebrows or on the top of the head; pain under the left breast, or a sense of fulness in the chest; pulse frequent, small, and quick (in extreme cases *jerking*), increased by exertion and emotion. The patient is easily agitated by slight noises or unexpected events, and suffers from depression, and, in some cases, from hysteria; the secretions and excretions are generally scanty, and the bowels often torpid.

Physical Signs.—On applying the stethoscope above the clavicles, especially on the right side, a humming sound (*bruit de diable*—humming-top sound, or venous murmur) is heard. Slight pressure of the stethoscope on the larger arteries produces a *bruit de soufflet*, resembling the soft sound caused by blowing across the mouth of a bottle; or the puffing of a locomotive engine. A soft blowing sound is also often heard at the *base* of the heart. In the space above the clavicle the venous murmur and the arterial bellows sound may be heard at the same time These are indications of a flaccid condition of the arteries and veins. They are not, however, peculiar to anæmia, nor always present in this condition.

Complications.—Often, but not always, associated in women with amenorrhœa, or with scanty menstruation.

Causes.—*Predisposing.* The female sex, especially about the age of puberty. It is rare in males. *Exciting.* In females obscure, but connected with the function of menstruation. In males occasioned by overwork; as with compositors, bakers, and others, who spend much of their time in dark, hot, and ill-ventilated rooms. For other exciting causes, see Cachexia.

Prognosis.—Favourable; but recovery sometimes slow and tedious.

Diagnosis.—From chlorosis, by the absence of disorder in the functions of the alimentary canal. The soft basal bellows murmur must not be attributed to *organic* heart disease.

Treatment.—*Indication.* To promote the formation of the red particles and solid constituents of the blood. This will be effected by the use of the preparations of iron in full doses, together with a nourishing diet. The best preparation of iron is the dried sulphate, of which five grains may be taken three times a day. (Form. 137.) The pilula aloes et myrrhæ may be given, if required, but mercurials should be given with caution, as salivation is readily induced in anæmic patients.

I have often given the dried sulphate of iron, combined with extract of gentian, in ten-grain doses; and an anæmic female, who takes these pills as others take stimulants, swallowed on one occasion twelve pills, containing half a drachm of sulphate of iron, in one day. The same preparation, in the same liberal doses, may be given with like advantage in the few cases of anæmia that occur in the male subject. (G.)

A generous diet, with a moderate allowance of wine, is indicated in cases of anæmia attended with marked debility; and exercise in the fresh air, proportioned to the strength of the patient. For mental depression, change of air and scene, and the use of chalybeate waters, may be recommended; or sea-air with sea-bathing. The shower-bath is a useful tonic.

3. Cachectic Anæmia, or Chlorosis (Green Sickness).

Definition.—A state of system combining the characters of anæmia with those of cachexia; an altered state of the blood with unhealthy secretions.

Symptoms.—A greenish-yellow pallor of the skin, puffiness, and often œdema of the integument; heaviness; listlessness; fatigue on the least exertion; palpitation; throbbing of the carotid arteries; a small, quick, and frequent pulse; shortness of breath; pains in the back, loins, and hips; indigestion with flatulency and acidity; foul breath, and offensive evacuations from the bowels. The appetite is often singularly depraved; such things as chalk being greedily eaten, and the accustomed food rejected.

Causes.—Those of anæmia and cachexia combined. Amenorrhœa is a general, though not a constant, accompaniment.

Treatment.—*Indications.* I. To restore the normal character of the blood by the means recommended in chronic anæmia. II. To correct the depraved secretions.

The second indication may be fulfilled by gentle aloetic aperients combined with myrrh and a little blue pill.

For the treatment of uterine complications, see amenorrhœa, dysmenorrhœa, &c.

CACHEXIA.—THE CACHECTIC STATE.

Definition.—A disorder allied to anæmia caused by an alteration in the blood from morbid processes arising within the body, or the absorption of some deleterious agent from without.

VARIETIES.—Syphilitic Cachexia. Alcoholic Cachexia. Marsh Cachexia. Tubercular Cachexia (Tuberculosis). Carcinomatous Cachexia. Cachexia of hot climates. Leucocythæmia. Supra-renal Cachexia.

SYMPTOMS.—A sallow, dusky, or muddy complexion, often tinged with yellow; a dry and harsh skin; a small, frequent, and compressible pulse; the tongue sometimes clean, moist and red, sometimes pale, but more commonly furred or cracked; the appetite capricious, often craving and voracious; dyspeptic symptoms; the bowels either costive or loose, with dark, slimy, and offensive stools; the urine generally high coloured, of a strong odour, and depositing lithates; the perspiration and breath offensive. Enlarged tonsils, aphthæ, and cutaneous eruptions, are frequent concomitants of this state, as are also obscure and wandering pains of the body and limbs.

TERMINATIONS.—In recovery, or in tubercular or other organic diseases of the viscera.

CAUSES.—*Predisposing.* An ailing infancy, and hereditary defect of constitution. *Exciting.* Unwholesome diet; insufficient exercise; intemperance; continued exposure to marsh miasma, to a cold, damp atmosphere, or to unhealthy climates; the impure air of crowded cities; the gradual operation of mineral poisons, as mercury, lead, copper, arsenic; and of animal poisons, especially the syphilitic.

PROGNOSIS.—*Favourable,* if there be no organic disease, and the patient can be removed from the influence of the ascertained cause. *Unfavourable,* when complicated with visceral disease.

TREATMENT.—*Indications.* I. To remove the exciting cause. II. To improve the state of the blood. The exciting cause may be removed, in the several cases specified, by proper diet, exercise, change of air, ventilation of apartments in which unhealthy occupations are carried on, and change from unwholesome employments to healthy ones. In syphilitic cachexy preparations of mercury or iodine will be required. The quality of the blood may be improved by a wholesome mixed diet of animal and vegetable food. The condition of the digestive, cutaneous, urinary, and uterine functions must be carefully inquired into, and the nature of the secretions determined. If the bile be vitiated and defective, alkalies combined with tonics, and mercurial purgatives, should be given. If the urine be loaded with phosphates or oxalates, the mineral acids may be given in combination with quinine; and if lithates be present, alkalies, with tonic and stimulant infusions. The skin must be cleansed and stimulated by daily shower or sponge baths, followed by friction with a coarse towel. Change of air and of scene, and chalybeates or saline waters, may be prescribed with advantage.

Of the varieties of cachexia specified above, some are described under the diseases which produce them; others, as leucocythæmia and supra-renal cachexia, require separate notice.

LEUCOCYTHÆMIA, LEUKÆMIA, LYMPHÆMIA, is a form of cachetic anæmia, first described by Dr. Bennett of Edinburgh. It derives its name from an excess of white corpuscles in the blood, and is characterized by great pallor, accompanied in some cases by œdema, or by dropsical effusions. The functions of the stomach and bowels are generally deranged, and jaundice is sometimes present. There is great weakness and emaciation, shortness of breath, and in cases of long standing, hectic fever. The blood is found to contain white corpuscles in great excess. It is generally a disease of adults, and is commonly associated with disease of the spleen, which is often greatly enlarged, and of the liver. The lymphatic glands are also often implicated. The disease is chronic, and the prognosis unfavourable, except in the rare cases in which the viscera are not seriously affected. This state sometimes follows severe attacks of remittent or intermittent fevers, which have left behind them disease of the liver and spleen. The treatment consists in the use of preparations of iron, and of the remedies indicated for the concomitant visceral disease.

Virchow distinguishes two forms of leukæmia, the *splenic* and the *lymphatic;* the spleen being the starting-point of the disease in the one, and some portion of the lymphatic glands in the other; in the splenic form the white corpuscles are comparatively large and well-developed, with one or more nuclei closely resembling the cells of the spleen. In the lymphatic form the white corpuscles are small, and have a single somewhat granular nucleus, attached to the cell-wall. "In many instances it looks as if perfectly free nuclei were contained in the blood."

CACHEXIA OF HOT CLIMATES.—This is common among Europeans resident in hot climates: either as the consequence of disease of the abdominal viscera brought on by attacks of intermittent or remittent fever; or as the mere result of a prolonged residence in unhealthy localities, or again, as the sequel of febrile attacks, not followed by organic mischief. It may also be induced by the injudicious use of the lancet or of mercury, or by attacks of diarrhœa, cholera, dysentery, scurvy, or hepatitis. The leading symptoms are, a pale and sallow countenance, a cold and shrivelled skin, a pearly whiteness of the eye, a dilated pupil, a dull and languid expression, peevishness, and despondency. The belly is generally swollen, and the extremities often œdematous, the digestion weak, the bowels torpid, the tongue pale, and coated with a white fur, the pulse feeble, and the respiration quickened by exertion. The treatment proper for this state consists in the use of the preparations of iron, with aloetic aperients, if needed in the local treatment of visceral complications, and strict attention to all the means of preserving health. A dry and bracing air, mental rest, and suitable bodily exercise, must be particularly insisted on. Preparations of mercury and all lowering remedies are contraindicated.

I have, in one or two instances, seen this state of system following service in hot climates and attacks of intermittent or remittent fever, but without serious disease of the liver or spleen, speedily and entirely cured by the use of preparations of steel. (G.)

SUPRA-RENAL CACHEXIA.—*Supra-renal Melasma, Morbus Addisonii.* This form of cachexia is characterised, like leucocythæmia, by great pallor of surface, pearly whiteness of the conjunctiva, great languor and debility, loss of appetite, an uneasy feeling at the pit of the stomach, and sometimes vomiting of food, feeble pulse, and some loss of flesh; accompanied by a peculiar and characteristic discoloration of the skin over the whole surface, but particularly on the face and under the eyes, on the neck, on the penis and scrotum, the arm and armpit, the navel and epigastrium. The skin has a smoky look, and presents every shade of colour from amber to dark chestnut, or even chocolate; sometimes blended with spots or patches of morbid whiteness. The discoloration may also affect the lips, and inside of the cheeks, exactly resembling the dark blotchy condition of the dog's mouth. Cases in which the discoloration is extensive and strongly marked, end fatally.

CAUSE.—Disease of the supra-renal capsules. We are indebted to Dr. Greenhow for an analysis of all the published cases of so-called Addison's disease. The following are the results at which he has arrived:—There were 10 cases of bronzed skin in which the supra-renal capsules were healthy; 24 in which they were in part or wholly destroyed by cancerous deposit, but in 8 only of which was there any cutaneous discoloration approaching to bronzing; 34 cases of miscellaneous affections of the capsules, in only 16 of which was there any decided bronzing; 59 cases in which the degeneration of the capsules was associated with tubercular and vertebral disease; 23 in which the capsular disease was associated with phthisis and other serious diseases; 5 in which the state of the other organs was not reported; 13 in which the supra-renal disease was complicated with disease of the mesenteric and intestinal glands, or of the lungs or pleura; and only 28 cases in which the disease of the capsules was absolutely unaccompanied by constitutional disease. In some even of these latter, death may have been due to general fatty degeneration and asthænia, for some of the subjects were overladen with fat. Dr. Greenhow rejects the first sixty-four cases in this enumeration as spurious examples of Addison's disease.

MIMOSIS INQUIETA.—THE NERVOUS STATE.

SYMPTOMS.—Flushings, tremblings, palpitations, dyspnœa, pain in the left side, giddiness, loss of memory, low spirits, anxiety, and timidity. In extreme cases the patient is startled by the slightest noise; is in constant apprehension of death, or of some great evil about to befall him; imagines that he has done something wrong; or is in constant fear that he may commit some great crime. The sleep is often disturbed by frightful dreams. Neuralgic pains, with extreme weakness of the hands and forearms, are of common occurrence, and give rise to an unfounded alarm of paralysis. There is often indigestion, and the bowels are flatulent and costive. In other respects the health does not greatly suffer; the patient looks well, does not lose flesh, and may even be of a full habit of body. In women, faintings and hysterical paroxysms are sometimes superadded, and the disease occasionally terminates in mania.

Causes.—*Predisposing.* A nervous temperament. Excessive discharges, such as hyperlactation, leucorrhœa, menorrhagia, diarrhœa, and repeated loss of blood; the change of life. *Exciting.* In either sex, fright, grief, anxiety, overwork, scanty nourishment, or fatigue. In men, excessive study, anxiety, dissipation, and sexual abuse.

Diagnosis.—From serious nervous diseases, such as delirium tremens and mania, by the absence of delirium, and of obstinate delusions.

Prognosis.—Favourable, but recovery generally slow and tedious.

Treatment.—I. Support the patient's strength by the use of astringent tonics (Form. 130), a generous diet, a moderate amount of wine, fresh air, and exercise. II. Allay the nervous irritation by the use of sedatives, such as opium, hyoscyamus, and digitalis.

FEBRICULA.—THE FEBRILE STATE.

Synonyms.—Febris ephemera. Simple fever. Feverishness.

Definition.—A continued fever, of slight degree and short duration, which often runs its course in twenty-four hours.

Symptoms.—Increased heat of skin, sometimes as much as 5° or 6°, and frequency of pulse, flushed face, slightly furred tongue, thirst, loss of appetite, restlessness, lassitude, headache, and general muscular pains. These symptoms are sometimes preceded by shivering, and generally pass off by perspiration.

Causes.—Fatigue; exposure to cold; heated rooms; intemperance in eating or drinking; slight local inflammation. The poison of typhus fever acting on a strong constitution, or that of any of the exanthemata acting on a person who has already had the disease.

Diagnosis.—From the severer forms of continued fever by the mildness of the symptoms. Caution, however, is necessary in giving an opinion, as the onset of severe cases of continued fever, or of the febrile exanthemata is often not more strongly marked.

Prognosis.—Favourable, but guarded, for the reason just stated.

Treatment.—I. If the febrile attack have originated in intemperance in eating or drinking, an emetic should be given.

II. The feverish symptoms will generally yield to a saline aperient (Form. 242), and low diet. In more severe cases, ten grains of Dover's powder may be given at bed-time, followed by a saline aperient in the morning. The patient should keep his bed, and be restricted to tea, farinaceous food, and cooling drinks, until the temperature remains normal.

CHAPTER II.

PHLOGOSIS	Inflammation.
CONGESTIO	Congestion.
HÆMORRHAGIA	Hæmorrhage.
HYDROPS	Dropsy.
ERYSIPELAS	St. Anthony's Fire.

PHLOGOSIS.—INFLAMMATION.

Varieties.—1. Acute. 2. Chronic.

1. ACUTE INFLAMMATION.

SYMPTOMS.—1. Local. 2. General or Constitutional.

1.) *Local Symptoms. When External.* Redness, swelling, t, and pain. The *redness* arises from the increased quantity of ›d contained in the vessels of the part; the *swelling* from the ıe cause, with the exsudation of serum, albumin, or lymph; the *t* exceeds that of other superficial parts, but never rises higher n that of the blood; the *pain* is caused by tension and pressure the nerves of the part. It is accordingly most severe when the rounding textures are most unyielding, as in whitlow; comatively slight, or only produced by external pressure, in the lax cous membranes. *When internal.* There is pain and disbance of function. The pain, in parts which can be submitted to ssure, is increased by that pressure, and this forms an important ans of diagnosis; and, in the less severe forms of inflammation, n not existing before is sometimes brought out by it. The *turbance of function* in secreting organs consists in alteration, ıinution, or total suppression of their appropriate secretions, ording to the degree of the inflammation; in other organs, of ious degrees of excitement—in the brain, rapid succession of as, restlessness, delirium; in the eye and ear, intolerance of light l sound, or false sensations, such as flashes of light, musical es, &c.; in the lungs, dyspnœa; in the heart, palpitation.

2.) *General* or *Constitutional Symptoms.* In healthy persons, group of symptoms commonly known as *Inflammatory Fever;* nely, rigors, succeeded by pains in the head, back, and limbs; ıitude; nausea, and loss of appetite; increased heat of surface; rst; furred tongue; frequent, full, hard pulse; a dry skin; scanty l high coloured urine; and constipation or diarrhœa. There is light aggravation of the symptoms towards evening, and a slight ıission in the morning. The sleep is disturbed, and the patient ıomewhat delirious. If blood be drawn it will be found cupped l buffed.

In severe and extensive inflammation, or in unhealthy persons, the symptoms are those of *Constitutional Irritation:*—extreme anxiety and restlessness; hurried respiration; rigors; a frequent, quick, sharp pulse; low muttering delirium; and, in fatal cases, death by exhaustion.

In the very weak, hectic fever usually shows itself as soon as pus is formed.

TERMINATIONS.—1. Resolution. 2. Increased secretion. 3. Hæmorrhage. 4. Adhesion. 5. Softening. 6. Induration. 7. Suppuration. 8. Gangrene.

CAUSES.—*Predisposing.* Sanguine temperament; full habit of body; and exhausted, cachectic, and febrile states of system. *Exciting.* 1. Mechanical injury- 2. Chemical irritants. 3. Cold and heat. 4. An altered or poisoned blood. 5. Local congestion from imperfect elimination of effete matters.

CAUSES WHICH MODIFY THE CHARACTER OF INFLAMMATION.

1. Texture. 2. Condition of system. (1.) *Texture.* The *serous* membranes when acutely inflamed take on the adhesive inflammation, very rarely the suppurative; when less inflamed, they pour out serum. The *mucous* membranes secrete mucus, pus, and, in rare cases, coagulable lymph, and are prone to suppuration and to softening, but not to adhesion of opposed surfaces. Inflammation of the *cellular* tissue causes a secretion of serum, and, when very severe, of coagulable lymph and pus. The common termination of inflammation is by *abscess.* Inflammation of the cellular tissues is called *phlegmonous* inflammation. The *parenchymatous* substance of organs is apt to be softened by acute, and hardened by chronic, inflammation; it is also liable to abscess and gangrene. Of the *fibrous* tissues, tendon and ligament are prone to gangrene, cartilage to ulceration. *Osseous* inflammation terminates in gangrene (caries and necrosis). The *skin* resembles the mucous membranes in being prone to suppuration. It is also the seat of diffused redness, pimples, vesicles, pustules, and spots of ulceration and gangrene. Hence the great variety of skin diseases.

The general and constitutional symptoms of inflammation also vary greatly with the tissue affected. In inflammation of the *serous membranes,* there is little heat of surface, little muscular debility, little tendency to delirium (unless the serous membranes of the brain be affected); the pulse is hard; there is acute pain, great tolerance of loss of blood, excess of fibrin, and a cupped and buffed appearance in the blood itself. In inflammation of the *mucous membranes,* on the other hand, there is little pain, little tolerance of loss of blood, no increase of fibrin, and the absence of the cupped and buffed appearance.

(2.) The plethoric are liable to boils, carbuncles, and adhesive inflammation of the serous membranes. In the anæmic there is *but little* tendency to inflammation, and when it occurs, it is sub-acute, and generally results in serous effusion and acute œdema. The cachectic are liable to those low forms of inflammation which result in the deposit of croupy or diphtheritic exsudation upon the mucous membranes; to the formation of tubercle in the lungs and lymphatic glands; or the outpouring of sero-purulent fluid into the serous cavities.

The constitutional symptoms which mark the several terminations of inflammation are of great practical importance. *Acute adhesive inflammation* is accompanied by a full, strong, and hard, or small, wiry pulse, somewhat increased in frequency; little or no heat of skin, little or no headache, vertigo, or delirium; no muscular tremor or debility, slight change in the character of the urine, and great tolerance of blood-letting. *Suppuration* is announced by burning, throbbing pain, by severe and often by repeated rigor, occurring in some cases almost with the regularity of ague, and followed by heat and sweating—the symptoms, in fact, of hectic fever. *Gangrene* is indicated by a sudden cessation of pain, by general collapse, pallor, cold clammy sweat, sunken features, sometimes low delirium, sometimes peculiar self-possession. A dry, brown tongue, sordes, a small, frequent, feeble pulse, and the other symptoms of the typhous state, usually precede the fatal ending of extensive or long continued inflammations.

TREATMENT.—The remedies against *acute* inflammation are either general or local. The *general remedies* are blood-letting by venæsection or arteriotomy, tartar-emetic, in full doses of a fourth of a grain or more, and after free purgation, the use of calomel and blue pill, combined with opium, in repeated doses, so as to produce slight constitutional effects. In slighter inflammations the use of strong saline aperients will be sufficient. In internal inflammations, diaphoretics and the warm bath are of great service. The *local remedies* are depletion by leeches, cupping, or scarification, incisions, cold, cataplasms and fomentations, and counter-irritants. Inflammation of exposed mucous surfaces require strong irritants, such as nitrate of silver, which have the effect of promoting the contraction of the dilated vessels. Another effective local remedy is pressure, which has been applied with advantage in orchitis and in anthrax.

2. CHRONIC INFLAMMATION.

SYMPTOMS.—Those of the acute form, but less intense, and of longer duration. The redness is of a more dusky hue; the heat little, if at all, above the natural standard, and the pain very slight, or only produced by pressure. The functions of internal parts when thus inflamed are generally languid, and their secretions are diminished. In chronic inflammation of the cellular tissue, serum usually takes the place of the more solid products of acute inflammation.

TREATMENT.—This chiefly consists in the use of local remedies, such as moderate depletion by leeches or cupping; friction and stimulants (nitrate of silver, iodine), which cause the capillaries to contract; and counter-irritants. The cold douche, and the interrupted or continuous current are also great aids in promoting the contraction of the capillaries. In chronic inflammation of the lower extremities support, by means of bandages or elastic stockings, is very beneficial. Iodine and its preparations, given internally, promote the absorption of effused matters.

CONGESTIO.—CONGESTION.

Varieties.—1. Active. 2. Passive.

1.—**Active Congestion.**—Sthenic or active Hyperæmia.

Characters.—A local fulness of the small vessels, analogous to that general fulness which constitutes plethora; accompanied by a more rapid flow of blood, and the florid redness which is present in inflammation.

Terminations.—In inflammation; active hæmorrhage; passive congestion; dropsy.

Treatment.—When congestion threatens to pass into inflammation, the moderate abstraction of blood by leeches or cupping, a position favourable to the return of blood to the heart, the use of cold, counter-irritants, and the administration of saline aperients and tonic stimulants, are indicated.

2. **Passive Congestion.**—Passive or Asthenic Hyperæmia.

Characters.—Distension of the capillaries and small veins, a languid circulation of blood through the part, and a dusky hue.

Terminations.—In active congestion, in oppressed and sluggish function. In dropsy. In passive hæmorrhages. In chronic ulcers of the legs.

Causes.—Mechanical pressure. Obstruction to the flow of blood through the lungs, the heart, or the liver. Postures unfavourable to the free return of blood to the heart. Constitutional debility. Cold. Imperfect action of secreting and excreting organs.

Treatment.—Must vary with the cause. In congestion of the mucous membranes, and in congestion or chronic ulceration of the integuments, stimulant and astringent applications. The moderate use of aperient medicines, to relieve the general circulation; of stimulants to excite it; and of tonics to support it. Leeching, dry cupping, and friction are also useful remedies in this state.

HÆMORRHAGIA.—HÆMORRHAGE.

When hæmorrhage occurs from excitement of the circulatory organs it is called *active;* when from a congested state of capillaries, *passive.*

1. ACTIVE HÆMORRHAGE.

CHARACTER.—A sudden discharge of bright-coloured blood. It is an accident which may happen to almost anyone, epistaxis (nose-bleeding) being the usual form. Certain individuals and even families, however, inherit a hæmorrhagic diathesis (Hœmophilia, "bleeder disease"). From Immerman's statistics, it appears that this condition is about twice as common in Germany as it is in England, while in France and North America it is about half as frequent as in England. According to Grandidier, the comparative frequency of the source of the bleeding in 308 recorded cases was as follows: From the nose, 152 times; the gums, 38; intestines, 35; the respiratory tract (hæmoptysis), 17; the urinary tract (hæmaturia), 16; the stomach (hæmatemesis), 14; female genitalia, 10; tongue, 6; ear, 5; tips of fingers, 4; scalp, 4; other parts, 7.

In these subjects, trifling operations, such as circumcision, leeching, the extraction of a tooth, occasion profuse and sometimes fatal hæmorrhage.

CAUSES.—*Predisposing.* Youth and vigour. Plethora. *Exciting.* Strong exertion; spirituous liquors in excess; violent passions and emotions. The *immediate* cause may be severe wounds; the rupture of a large artery, or of an aneurismal sac; active congestion of a mucous surface; or the laying bare of an artery by ulceration. In hæmophilia there appears to be a congenital defect in the development of the blood-vessels, the largest arteries being in some cases abnormally narrow, while the intima (inner coat) of both larger and smaller arteries is remarkably thin and transparent. Hypertrophy of the left ventricle of the heart has been frequently observed. On the other hand, in the few cases in which careful examination has been made, the blood appears to be unusually rich in red corpuscles and fibrin, while the white corpuscles are notably few. The condition, therefore, approaches plethora, rather than that of anæmia.

TREATMENT.—Brisk saline aperients, and a low diet; a posture unfavourable to the flow of blood towards the seat of the hæmorrhage; rest of the part affected; cool air and cold drinks; ice and cold applications; styptics; Digitalis (Form. 77); Ergot, Turpentine; Sulphuric acid (Form. 146). Tannic or gallic acid; acetate of lead. In all cases of extreme debility brought on by excessive hæmorrhage, and marked by great pallor of surface, opium and its preparations in full doses are indicated, either alone or combined with astringents, and a liberal supply of port wine.

2. PASSIVE HÆMORRHAGE.

CHARACTER.—A slow discharge of dark-coloured blood by extravasation from mucous or other surfaces in a state of passive congestion.

TREATMENT.—That of passive congestion, supra.

HYDROPS.—DROPSY OR ANASARCA.

Definition.—An effusion of serum into the areolar tissue, with or without effusion into serous cavities.

Œdema is the term given to local effusions into the areolar tissue. Those that take place into the several cavities are known as *hydrocephalus*, *hydrorachis*, *hydrothorax*, *hydropericardium*, *ascites*, *ovarian dropsy*, *hydrocele*, *&c.*

Varieties.—(1) mechanical dropsy, (2) dropsy from debility, (3) febrile dropsy, (4) cardiac, pulmonary, hepatic and renal dropsy.

Symptoms.—Dropsy generally first shows itself towards evening by swelling of the feet and ankles, which disappears on lying down. By degrees the swelling becomes permanent, ascends, and successively affects the thighs, the integuments of the trunk, the external genitalia. In extreme cases the dropsical effusion extends to the upper extremities—to the chest, neck, and face; and is almost always attended by effusion into one or more of the serous cavities. The parts affected *pit* on pressure with the finger. The skin is pallid like marble, cold and dry, and when the effusion is great, it becomes tense and shining. At length it gives way at several points, the water oozes out, and the contiguous skin becomes red and excoriated; sometimes it is raised up into small blisters, sometimes it sloughs. Except in renal dropsy, the urine is scanty, high-coloured, and deposits lithates. Dyspnœa, palpitation, flatulence, and drowsiness are commonly associated with dropsy.

Causes.—With a view to prognosis and treatment it is of the utmost importance to ascertain the cause of the dropsy. The following are the chief points to attend to:—1. If the dropsy be purely local or limited to one side of the body, it depends on *mechanical obstruction* of a large vein—*e.g.*, œdema of head, neck and upper extremities may be due to an aneurismal or other tumour compressing the descending cava. Œdema of the leg may arise from the pressure on the iliac vein of a cancerous mass in the pelvis, or enlargement of the gland at the femoral opening. 2. *Dropsy from debility* will be recognized by attention to the previous history of the patient. If there have been neither rheumatism nor scarlet fever, and there are no symptoms of organic disease of any great organ, though there be a soft bruit at the base of the heart, we shall have no difficulty in assigning this to its proper cause—anæmia. 3. *Acute or febrile dropsy* is known by its suddenly following exposure to cold; as when a person, after violent exercise and in a profuse perspiration, falls asleep on the cold damp ground; or when, during recovery from scarlatina, the action of the skin is checked by exposure to cold, wind, or rain. This variety has its origin in severe congestion of the kidneys, indicated by the scanty, albuminous, bloody, or coffee-coloured urine. *Chronic forms of renal dropsy* will also be indicated by the absence of *severe* cardiac and pulmonary symptoms, and by the state of the urine, which is pale like whey, highly albuminous, and usually deposits a slight cloud composed of casts of the uriniferous tubules. (See Acute and Chronic Nephritis.) 4. *Pulmonary dropsy* generally follows an acute attack of general bronchitis in one who has long suffered from emphysema. The lungs themselves may also be œdematous from local debility of their structure; or they may be the seat of cancer or tubercle. 5. *Cardiac dropsy* is commonly due to disease of the valves of the heart allowing of regurgitation, obstructing the entrance of venous blood into the lungs, and so inducing congestion of the venous system. Occasionally the cause lies in a fatty heart. Abnormal heart-sounds, and a feeble, intermittent pulse, attend these diseased conditions. 6. *Hepatic dropsy* is readily inferred from the history of the patient, the presence of ascites before swelling of the legs, the condition of the liver, the absence of swelling from the upper parts of the body, and scanty bilious urine loaded with lithates and usually free from albumen. (See Cirrhosis and Cancer of the Liver.)

PROGNOSIS.—Favourable, if not dependent on organic disease of long standing, and great severity.

TREATMENT.—*Indications*. I. To remove the cause. II. To lessen the quantity of the fluid. III. To relieve distress by its discharge.

(I.) In dropsy associated with febrile action, the remedies for inflammation are indicated; in dropsy dependent on debility, tonics or stimulants according to the degree of the debility; in dropsy from venous congestion, moderate depletion to relieve the vessels, and regulated pressure to afford support; in congestive dropsy dependent on organic disease, medicines directed to relieve the disease; and if the disease has impoverished the blood, tonics and alteratives.

(II.) The effusion may be lessened by increasing the secretions of the skin, kidneys, and bowels—by sudorifics, diuretics, and purgatives adapted to the state of the patient. As sudorifics we may occasionally use the hot-air bath, salines, such as nitrate of potash, acetate of ammonia, &c.; as diuretics, the salts of potash or soda, in combination with digitalis, broom, buchu, turpentine, and copaiba, are often beneficial; as purgatives, the saline aperients, compound jalap powder (gr. xx. to gr. lx.) and elaterium (gr. ¼ to gr. 1). The doses and strength of the several remedies must be regulated by the state of the patient, the sudorifics and diuretics belonging to the class of depressents being preferred in inflammatory and febrile dropsy, and in comparatively vigorous states of the system; and sudorifics and diuretics belonging to the class of stimulants in states of debility. Saline purgatives will be more appropriate in the latter form, and drastic purgatives in the former. Cardiac, hepatic, and renal dropsy require modifications of treatment, and remedies adapted to the primary disease. (See Diseases of the Heart, Liver, and Kidney.)

(III.) When the collection of fluid interferes mechanically with the functions of surrounding parts, we may have to resort to the operation of acupuncture, in anasarca threatening to discharge itself by vesication, or ulceration; paracentesis abdominis, in ascites; in hydrothorax, to paracentesis thoracis; in hydrocele, to tapping, followed by stimulant injections to effect a radical cure.

ERYSIPELAS.—ST. ANTHONY'S FIRE.

Definition.—A contagious malady, epidemic at certain seasons, consisting in an inflammation of the skin, or of the skin and cellular tissue, spreading from a single centre over a greater or less extent of surface, and subsiding, or disappearing in one part as it extends to another.

Varieties.—1. Idiopathic erysipelas. 2. Traumatic erysipelas.

1. Idiopathic Erysipelas.

Symptoms.—The disease usually sets in with rigors, quickly followed by pyrexia, confusion of intellect, and sometimes delirium or coma. There is nausea, and in some cases vomiting; in others, diarrhœa; the tongue is moist and covered with a uniform white fur; and the pulse is frequent, quick, full, and compressible. After a variable interval of a few hours, or of one or two days, a red spot, accompanied by more or less swelling, appears on the skin. From this centre an inflammatory blush of a rosy, bright scarlet or dusky red colour spreads more or less rapidly, fading away into the healthy skin. The inflammatory area rapidly extends, and the affected and contiguous portions of the integuments become more or less œdematous. As the redness extends, it disappears from, or gradually subsides in the parts first occupied. After a longer or shorter time the inflammation usually terminates in desquamation of the cuticle, or in the formation of vesicles of variable size, containing a yellowish serum or lymph. The fever is in proportion to the extent of the disease, and only declines after it has ceased to spread, when, in favourable cases, the patient rapidly regains appetite and strength. In unfavourable cases, the fever assumes the typhous character, passes through the several stages, and displays many of the symptoms described under "Typhus Fever" and the patient sinks comatose or exhausted from the fifth to the tenth day; rarely so late as the fourteenth or twenty-first.

Terminations.— 1. Resolution (*erysipelas mitius*). 2. Vesication and desquamation of the cuticle. 3. Œdema (*erysipelas œdematodes*). 4. Suppuration of the areolar tissue (*erysipelas phlegmonodes*), or gangrene (*erysipelas gangrænosum*). 5. Pyæmia. 6. The disease sometimes suddenly leaves one part of the surface, and attacks a distant part (*erysipelas erraticum*). 7. Inflammation of the brain and its membranes. 8. Inflammation and suppuration of the mucous membrane of portions of the intestinal canal. 9. Inflammatory œdema of the glottis producing suffocation.

Erysipelas of the face (*erysipelas faciei*) is by far the most common form. It usually begins on the nose, and thence gradually extends over the entire face, causing great swelling of the nose and eyelids, and, in severe cases, giving rise to horrible disfiguration. Sometimes it descends and spreads over the neck and trunk, but more commonly attacks the scalp. In its passage over the head, the membranes of the brain are often more or less affected, and there is acute headache, sometimes delirium, violent or muttering, and occasionally coma. From the head it generally extends down the back, and sometimes affects the membranes of the spinal cord. In severe cases, the affection of the membranes of the brain and cord remain for some time, and show themselves by mental excitement, and by numbness and spasmodic twitchings of the extremities. In erysipelas of the head and face there is generally more or less inflammation of the throat, and in rare instances it proves fatal by inducing serous effusion into the submucous tissue of the glottis and epiglottis.

PATHOLOGY.—A special inflammation of the blood vessels and lymphatics of the skin, which may terminate in resolution, or in the formation of pus attended by symptoms of pyæmia.

MORBID ANATOMY.—Inflammatory or purulent deposits may be found in the viscera, especially the lungs; and upon the serous and mucous membranes.

CAUSES.—*Predisposing.* A full plethoric habit; constitutional peculiarity; previous affections of the same nature. The adult age; exhausting diseases, such as dropsy, especially renal dropsy, fever, or the febrile exanthemata. *Exciting.* Contagion; cold; excessive heat, or vicissitudes of temperature; exposure to the sun; abuse of fermented liquors; suppressed evacuations; the presence of irritating matter in the alimentary canal; wounds or local inflammation of the common kind occurring in certain constitutions, in certain seasons, and in places where the disease already exists. It is often epidemic during spring and autumn, frequently prevailing in hospitals, gaols, and other crowded situations; and it is a frequent concomitant of puerperal fever.

DIAGNOSIS.—From *erythema* by the duskier blush, pain, and swelling, and by the presence of severe pyrexia. *Erythema nodosum* does not spread, and is never accompanied by pyrexia. *Acute eczema* is distinguished by the presence of a minute vesicular eruption.

PROGNOSIS.—*Favourable.* Moderate pyrexia, a rosy or bright scarlet colour; not extending over a large surface; no vesications; the febrile symptoms diminishing with the disappearance of the blush; and this, soon after, assuming a yellowish hue, with an abatement of the swelling. The adult age. *Unfavourable.* Typhous symptoms: the inflamed skin becoming a dark rose-colour; sudden recession of the inflammation from the surface, and invasion of an internal part; its extension over a large surface without leaving the part it first occupied; livid vesications; weak, rapid, irregular pulse; great prostration of strength; early appearance of coma; original or acquired debility; complication with dropsy, jaundice, or other affections originating in organic disease. Infancy and old age.

CONTAGION.—The disease may spread by contact, or be inoculated and conveyed by fomites. It may attack the same person several times, and may co-exist with other severe diseases. In some years it is epidemic, and may rage with extreme violence.

MORTALITY.—The deaths in London, in a million persons of all ages, vary from 110 to 260, and average 160. The *rate* of mortality in persons attacked varies from less than one in three to one in ten.

TREATMENT.—*Indications.* I. To subdue inflammation, and promote salutary changes in the part affected. II. To support the strength. III. To prevent spreading to other parts.

(I.) The pyrexia may be subdued by free action of the bowels, kidneys, and skin. A full dose of compound jalap powder may be given once or oftener, and followed by repeated doses (℥ss) of acetate of ammonia, combined with gr. v. to gr. x. of the carbonate. The local treatment will consist in the use of warm fomentations, such as decoction of poppy heads. If the inflammation be limited, the part may be first rubbed over with solid nitrate of silver. Light bandaging is of great service where it can be applied. In every case the inflamed skin should be carefully protected from the air by fine flour, starch powder, carbonate of zinc, or cotton wool. A mixture of two parts of collodion and one of castor oil forms a complete protection. It is elastic, and by its contraction gives the required support to the swollen parts. It should be thickly painted with a camel's-hair brush.

(II.) As the disease is adynamic, stimulants, such as wine, brandy and ammonia are often needed, more especially in those accustomed to their use. A full dose of opium is often very serviceable. The presence of delirium does not contraindicate the use of stimulants or opiates when they are required.

Tincture of perchloride of iron (♏x—♏xl) alone, or combined with quinine, every three or four hours, is a valuable tonic in erysipelas.

If the disease assume a typhous character, we must depend upon stimulants chiefly. A pint, or more, of wine or brandy may be needed in the twenty-four hours; it may be given in the form of the Mistura Vini Gallici. The diet should consist of egg emulsion, milk, gruel, and beef-tea. The iron may be continued during convalescence, or quinine and acid may be substituted.

(III.) If coma and delirium arise, hot bottles or sinapisms must be applied to the feet. Evaporating lotions or ice may be simultaneously applied to the head. If the patient become noisy and restless, a full dose (gr. i—ii) of opium will be required.

In phlegmonous erysipelas, and when there is great tension of the skin, relief may be given by scarifications; and the incision must be free and deep if sloughing have occurred, or matter formed. These must be followed by poultices and disinfectants.

PROPHYLAXIS.—Cleanliness, separation, and, if practicable, isolation. Apartments which have been occupied by the patient should be whitewashed and thoroughly cleansed. Two causes are active in propagating, if not in generating the disease in hospitals;—*the use of sponges in dressing wounds* and *wet scrubbing of the floors of the wards*. To avoid the first, fine tow should supply the place of sponges, a fresh bit being used for each patient. Sponges used in the operating theatre should be thoroughly washed after each operation, and subsequently immersed in hot water saturated with carbolic acid. To avoid the second cause, dry rubbing should be substituted for washing. Floors should never be wetted when patients are lying above them.

2. TRAUMATIC ERYSIPELAS.

In certain seasons, when idiopathic erysipelas is very prevalent, slight wounds and injuries are apt to be followed by erysipelatous inflammation; and those of a more severe character in persons of unsound constitution, or in the healthy inmates of hospitals or public institutions where the disease already prevails, are almost uniformly subject to this complication. The disease often appears in lines extending from an injured toe or finger along the leg or arm; and the lymphatic glands, especially those of the armpit, become affected with diffuse inflammation and suppuration. The symptoms do not differ from those of idiopathic erysipelas, and the treatment will be the same. But in the prognosis, the original injury and the consequent erysipelas need to be jointly considered; and as pyæmia is more common in this variety of the disease, our attention must be constantly directed to the lungs and pleura.

CHAPTER III.

FEBRES.—FEVERS.

CLASS I.

Non-infectious Fevers.

I. **FEBRICULA**	Simple Fever (see p. 262).
II. **FEBRIS INTERMITTENS** .	Ague.
III. **FEBRIS REMITTENS** . .	Remittent Fever.
IV. **FEBRIS ICTERODES** . .	Yellow Fever.

CLASS II.

Infectious Fevers.

I. **TYPHUS**	Epidemic Continued Fever
II. **ENTERIC OR TYPHOID** . .	Endemic Continued Fever.
III. **RELAPSING FEVER** . .	Famine Fever.
IV. **THE EXANTHEMATA.** . .	(See Chapter IV.)

NON-INFECTIOUS FEVERS.

GENERAL OBSERVATIONS.

Febricula has been already described. It is caused by some functional derangement. Ague, remittent and yellow fevers, are endemic, and originate in one common external cause, marsh miasma. Apart from their common origin, they have so many other resemblances that we may safely assume them to be varieties of one and the same disease, the differences being due to the variable intensity of the primary or exciting cause. Thus, if the marsh poison be small in amount, or highly diluted, a febrile attack may come on every second or third day, or after longer intervals. But if the dose be larger, the intervals between the paroxysms are shorter and are no longer intermissions—intervals of freedom from fever,—but mere remissions of a more intense febrile condition. If, again, the system receive a still more powerful dose of the paludal poison, the fever is continuous, and the internal organs are severely congested and deranged. Between intermittent and remittent fevers, and between remittent and yellow fevers, there are, in truth, no lines of demarcation: they run into each other.

Given a certain source of marsh miasma, the intensity of the fever generated by it will be, *cæteris paribus*, in proportion to the external temperature. In the Arctic regions these fevers are unknown, and the mildest variety of them rarely passes beyond the fifty-sixth degree of latitude. In the latitude of London, and five degrees south of it, the disease assumes the intermittent type; south of this line it becomes remittent; still nearer the equator, remittent is not to be distinguished from yellow fever.

These fevers are of great interest to a nation which has soldiers and sailors scattered over the whole of the habitable globe, and serving under circumstances of great exposure, fatigue, and privation. Remittent fever, though by no means unknown in England, assumes in some of our dependencies a character of great malignity, rivalling, and even surpassing the Oriental plague itself in violence, and the mortality it occasions. The records of our army serving abroad show that even if we include stations in which the disease is unknown, or very rare, remittent fever attacks one soldier in every eight, of which number at least one eighth die. If, however, we exclude the stations in which remittent fever is wholly or nearly unknown, the attacks exceed 1 in 7, and the deaths are between a seventh and an eighth of those attacked. The mortality, however, varies very much in different places. In the Tennaserim provinces, it is as low as 1 in 27, at Bombay 1 in 25, at Malta 1 in 24; while it destroys 2 in 11 in Ceylon, 4 in 11 in the Bermudas, and 1 in 2 in Western Africa, on which fatal coast the attacks are nearly equal.

The disease derives its name either from the places in which it prevails, or from some prominent symptom. Thus we have the Walcheren, Levant, and Mediterranean fever; the jungle and hill fever of the East Indies; the lake fever of America; the Bulam, Sierra Leone, African, and Bengal fever; the gall fever of the Netherlands; the bilious remittent of the West Indies; and the yellow fever of Jamaica, Gibraltar, and the Bermudas.

Yellow fever, and the more severe remittents, require for their development a combination of marsh effluvia and a temperature exceeding 75° Fahr. Low-lying spots near the coast are its favourite haunts, and it is believed to disappear at an elevation of about 2500 feet above the sea level.

FEBRIS INTERMITTENS.—AGUE.

Synonyms.—Intermittent fever. Fever and ague.

Definition.—A fever caused by marsh miasma, and consisting of paroxysms,* occurring at regular intervals with perfect intermissions.

Varieties.—1. The *Quotidian;* a paroxysm once in twenty-four hours. 2. The *Tertian;* a paroxysm once in forty-eight hours. 3. The *Quartan;* a paroxsym once in seventy-two hours.†

---

* The period between the end of one paroxysm and the beginning of the next is called the *intermission;* the period occupied by one paroxysm and one intermission is called the *interval.*

† Also, 1. The *double quotidian*, having two paroxysms every day. 2. The *double tertian*, having a paroxysm every day, those of the alternate days being

Symptoms.—Ague sometimes attacks suddenly; but in most cases it is ushered in by such symptoms as mark the onset of continued fever; and it is not till after several days, or even one or two weeks, that it assumes its perfect form. It is then recognized by the occurrence, at regular intervals, of a paroxysm consisting of three stages—a cold, a hot, and a sweating stage—following each other with great regularity. *The Cold Stage.*—Languor and listlessness; sighing, yawning, and stretching; pallor; blueness of the ears, lips, and nails; shrinking of the features; and constriction of the skin of the whole body (*goose-skin* or *cutis anserina*); a sense of oppression at the pit of the stomach; violent shivering, chattering of the teeth, and trembling of the limbs; pain in the head, back, and loins; the secretions diminished; the urine scanty, pale, and limpid; the pulse, small, frequent, and sometimes irregular; and the respiration short and nervous. These symptoms terminate at length in universal convulsive shaking. *The Hot Stage.*—The heat of the body gradually returns; at first irregularly by transient flushes, succeeded by a steady, dry, burning heat, often as high as 106° Fahr. The skin is now swollen, red, and pungent, the face flushed, and the eyes injected. The sensibility becomes preternaturally acute, and the aching of the head is exchanged for acute pain. The pulse becomes quick, full, and hard; there is great thirst; the urine is scanty and high-coloured. *The Sweating Stage.*—At length a moisture breaks out on the face and neck, which soon becomes a universal and equal perspiration. The heat now descends to its usual standard; the pulse resumes its wonted frequency and character; the respiration becomes free and tranquil; the urine deposits a sediment; and the patient is for the time restored to health.

Occasional Symptoms.—In the cold stage, coma or apoplexy; in the hot stage, delirium. Convulsions, syncope, rigid spasms, neuralgia, jaundice, dysentery, and petechiæ on the skin, have also been recorded. In ague districts, and in persons who have previously had ague, many diseases assume the intermittent character. Of these, hemicrania, or intermittent face-ache, or brow-ague, is the most common.

Duration of the Paroxysm, &c.—The quotidian is most common in spring, and generally occurs in the morning: usual duration upwards of twelve hours. The tertian is a common type;

---

of equal duration and intensity. 3. The *triple tertian*, in which two paroxysms occur on one day, and one on the other. 4. The *duplicated tertian*, which returns twice on each alternate day. 5. The *double quartan*, in which a paroxysm occurs on the day succeeding that of the regular quartan, so that there is a perfect intermission only on the third day. 6. The *duplicated quartan*, in which two paroxysms occur on the day of attack, with two days of intermission. 7. The *triple quartan*, in which a slight paroxysm occurs on each of the usual days of intermission. These forms of ague, as well as those which have longer intervals (such as five, six, seven, eight, nine, or ten days, a month, or a year), and are called *erratics*, require the same treatment as the three primary types.

occurs in spring and autumn, commences at noon, and lasts about eight hours. The quartan is rare; it is more severe, occurs in autumn, generally begins in the afternoon, and lasts about six hours. The quartan has the longest cold stage, the tertian the longest hot stage.

The type is subject to change: tertians and quartans become quotidians, and quotidians remittents; or they pass into continued fever.

The paroxysms of ague are sometimes *obscure* (*dumb ague*), or *incomplete*, or *inverted;* sometimes they are irregular or *erratic;* sometimes *partial*, affecting only a portion of the body.

PERIOD OF INCUBATION.—From a few hours to several days, weeks, or months. Average duration, from ten days to a fortnight.

PATHOLOGY.—During the cold stage, the blood leaves the capillaries of the surface, and collects in the deep seated parts, causing congestion of the head, chest, and abdomen. Such vascular, spongy organs as the spleen and liver, are specially liable to suffer, and if the disease last for any length of time, become large and hard (ague-cake).

TERMINATIONS.—In chronic enlargement, with induration, softening or suppuration of the liver and spleen, followed by ascites and anasarca; in fatal dysentery; in apoplexy; in fever of the remittent or continued type. In leucocythæmia. (See p. 260.)

CAUSES.—1. *Predisposing.* Weakness; intemperance; cold and moisture; middle age; male sex; a previous attack. 2. *Exciting.* —Marsh miasma, the effluvia from decomposing vegetable matter, and from certain soils, impregnated with moisture, but *apparently* free from vegetable decomposition. The danger is greatly increased by exposure to these effluvia at night.

DIAGNOSIS.—Ague can only be confounded with hectic fever, or with rigors arising from some local cause, such as the passage of a gallstone, the introduction of a catheter, or the formation of pus in some internal organ. In doubtful cases, therefore, we must search for a local cause.

PROGNOSIS.—*Favourable.* Cold and temperate climates. The paroxysms short, and of regular recurrence; the intermissions quite free from fever; the postponement of the paroxysms: short previous duration; the quotidian and tertian types; an eruption on the lips.—*Unfavourable.* The disease of long standing; the paroxysms anticipating the usual time; being strongly marked; long; and attended with anxiety and delirium; a feverish state in the intermission; complication with other diseases; enlargement of the liver and spleen; the quartan type.

TREATMENT.—*In the Paroxysm.* During the *cold* stage the patient should be put into a warm bed, a hot brick or bottle be applied to the feet, and warm tea, or weak wine and water, be given. In more severe cases bags of hot bran or salt on the pit of the stomach, or a warm, hot-air, or vapour bath, aided by friction of the back and limbs.

During the *hot* stage, cool air, cooling drinks, and tepid sponging.

During the *sweating* stage, the patient should be enveloped in a blanket, and when the fit is over he should have a warm bath, be thoroughly dried, and allowed to sleep. Afterwards he should take some nourishing food, and if much exhausted, a little brandy or wine with warm water.

In the intermission, quinine or arsenic should be given in full doses.

Quinine is the more fitting remedy: it may be given in pill, or in mixture with excess of acid, in doses of five, ten, twenty, or even thirty grains daily.

Arsenic (liquor arsenicalis ♏v, gradually increased to ♏x or ♏xx), may be given either alone, or in combination with laudanum, every four hours during the intermission. Its effect must be carefully watched.

Previous to the administration of the specific remedy, the bowels should be freely opened by a brisk aperient (Form. 250).

An occasional cholagogue purge will be needed. Emetics given, just before the fit, are often serviceable in arresting it, or in accelerating the sweating stage.

The treatment of hemicrania, of brow-ague, and of those intermittent maladies known as masked ague—*e.g.*, intermittent vomiting, diarrhœa, &c., is that of ague itself.

Prophylaxis.—Avoidance of the early morning and evening air, and of sleeping near the ground. The choice of hilly ground, or of a spot where the malaria is intercepted by a wood or broad surface of water. Quickly growing plants (such as Eucalyptus globus) decompose noxious accumulations in the soil in the process of growth, and vegetation of every kind should be encouraged with this view. Warm and nourishing food before labour in malarious districts. Sailors should not sleep on land in such districts; and ships should be stationed at a distance of two or three miles from unhealthy coasts. Small doses of quinine two or three times a day. Thorough drainage, the use of pure drinking-water, and extreme cleanliness.

Sequelæ of Ague.—These are anæmia, enlargement of the spleen and liver, and chronic dysentery.

FEBRIS REMITTENS.—REMITTENT FEVER.

Synonyms.—Bilious remittent, remittent marsh, or paludal fever.

Definition.—A non-infectious fever with distinct exacerbations of variable duration and severity, but with no complete intermission.

Symptoms.—The premonitory symptoms are those of ague, but with less sensation of cold, and perhaps no distinct rigor. The *head symptoms* are more severe; the countenance is flushed; and there is intense throbbing headache and occasionally violent delirium. Tenderness of the epigastric and right hypochondriac regions, nausea, and bilious vomiting, with torpid bowels and scanty urine, are among the early symptoms. The stools are dark, often greenish, and very offensive; and there is considerable pyrexia and a dirty brownish tongue. The pulse is variable in force and volume.

The fever subsides as the skin grows moist; and thus a remission or moderation of the symptoms occurs. The patient remains in a mild fever, accompanied by giddiness and lassitude for about two hours, when the febrile symptoms recur, and slowly increase till they attain their former intensity, or exceed it. Paroxysms and remissions follow each other in regular succession for 7, 14, 21, or 28 days; at the end of either of which periods a profuse perspiration may terminate the attack.

In severe cases the paroxysms are more intense, the remissions shorter and less marked, the skin becomes yellow and pungent, the tongue is covered with a slimy yellow mucus, the stools are fœtid: the strength sinks, the pulse becomes thready, sordes form on the teeth, tendinous spasms and stupor supervene, passing into fatal coma. This more severe form is not distinguishable from yellow fever.

Duration.—From five or six days, to four or five weeks. Usual duration about a fortnight.

Causes.—Those of intermittent fever. The disease is most common and severe in hot climates; in England it is rare, but this cannot be said of temperate latitudes generally.

Diagnosis.—From continued fever by the recurrence of intervals of comparative freedom from febrile excitement.

Prognosis.—*Favourable*, in proportion as the remissions are more distinct. *Unfavourable*. when the fever assumes the continued type, and in proportion to the suppression of the hepatic and renal secretions.

Treatment.—The worst forms must be treated in the manner recommended for yellow fever. As soon as the intermissions become well marked, the treatment for intermittent fever must be adopted. Quinine or arsenic may then be given, as in ague, during the remission.

Sequelæ.—Those of intermittent fever.

DENGUE, OR DANDY FEVER.

Under this and other names a febrile affection "*sui generis*," has been described by several Indian physicians.

Definition.—A remittent fever, characterized by severe arthritic pains and a rash or scarlet efforescence, resembling measles, and appearing first on the palms of the hands, thence rapidly spreading over the rest of the body.

Symptoms.—Those of a common cold—viz., lassitude, heaviness of the eyes, slight vertigo, and a sensation of cold creeping down the back. Some patients wake out of sleep with great pain in the head, loins, and all the joints, small and large; others are suddenly seized with arthritic pains and stiffness while walking in the street.

The hands become stiff and swollen, the eyes watery, the conjunctivæ suffused, and the whole countenance bloated, swollen, and flushed. There is intense aching of the eyeballs, which feel too large for their sockets.—The pulse is full, strong, and about 100; the tongue moist and coated, and the margins red or scarlet; the skin dry and hot. There is nausea with loss of appetite, and the bowels are usually confined. The excruciating pains shift rapidly from one joint to another, and there is great debility and restlessness.

Towards the end of twenty-four hours the headache and flushing of the face begin to decrease, and the pain assumes a dull, aching character. Perspiration now appears, and there is great prostration of strength continuing during the whole remission. About the end of the third day the febrile symptoms return, and sometimes even with increased severity. The skin is hot and turgid, and red blotches like measles or scarlatina, often elevated and rough, appear upon the swollen hands and feet, and produce distressing tingling and itching. During the next twenty-four hours this efflorescence gradually spreads over the rest of the cutaneous surface, but dies away the following day, and is followed by desquamation.

The pains generally, but not always, now begin to subside; but the disease does not usually pass away till the patient has suffered a second or even a third relapse of fever.

Duration and Sequelæ.—Relapses are frequent, and the disease may continue for several weeks, and be attended with much debility, and pain of the joints. Cachexia, jaundice, with subacute hepatitis, hæmorrhoids, and neuralgia, are frequent consequences of this disease.

Distribution.—This disease has prevailed epidemically in the West Indian Islands, and the southern parts of India.

Causes.—*Predisposing.* Heat, moisture, stagnation of the air. *Exciting.* Derangement of the digestive organs.

Pathology.—Gastric and biliary derangement seem to be the conditions out of which the disease arises, and in its leading features it bears a strong resemblance to the derangement which results in urticaria. The alvine dejections are of a dark green colour, or black, scanty and offensive.

Prognosis.—Usually favourable. But the debility is sometimes so great during the remission as to result in sudden death.

Treatment.—At the onset, emetics and free purgation by means of calomel and colocynth, followed by saline aperients. During the *remission*, quinine and the mineral acids.

FEBRIS ICTERODES.—YELLOW FEVER.

Synonyms.—Typhus or synochus icterodes; febris remittens gravior cum ictero; Bilious remittent of warm climates; Bulam fever; Mal de Siam; Vomito negro; Vomito prieto; Coup de Barre, &c.

Definition.—A remittent fever accompanied by yellowness of the skin, and vomiting of a black or dark-brown fluid. (The disease assumes, in different epidemics, and often in the same epidemic, the several types of continued, remittent, and intermittent fever, and appears in every degree of severity, from simple ephemeral fever to the worst forms, attended with yellow skin and black vomit.)

Symptoms.—The disease usually sets in with lassitude, listlessness, faintness, and giddiness, with frequent chills, acute pains in the back and limbs, pains in the head and eyeballs, a flushed face, an anxious expression, an injected, brilliant, and watery eye, and a hot, dry, and harsh skin. The mouth is clammy; the tongue generally white and moist, or watery, furred at the centre, and red at the tip and edges; and the patient is usually very thirsty. The pulse is frequent, full, and hard; the respiration hurried, and interrupted by frequent sighs; there is great tenderness of the epigastrium, with extreme irritability of the stomach, and vomiting of the ingesta mixed with a glairy fluid. The bowels are confined, and the motions often clay-coloured. The urine is sometimes tinged with bile.

After these symptoms have continued, with increasing severity, from a few hours to three days or more, a marked remission takes place, and the symptoms, as well as the sensations of the patient, continue for several hours so much improved as to excite sanguine hopes of recovery. Sometimes recovery dates from this remission, but more frequently the improvement is delusive. The febrile symptoms return, accompanied by increased debility; a small and frequent pulse; a cold and clammy skin; shrinking of the features; a dry tongue, covered with a brown or black fur; increased tenderness of the epigastrium, with an acrid burning sensation extending to the gullet, with extreme irritability of the stomach, and vomiting of all ingesta.

After a further interval of twenty-four or forty-eight hours, and sometimes earlier, the more characteristic symptoms appear—viz., jaundice; incessant hiccup, vomiting of inky black fluid; a feeble, irregular pulse; accumulation of sordes upon the tongue and teeth; petechiæ; dark and gelatinous stools; hæmorrhage from the mouth, ears, nostrils, or bowels. In fatal cases, death may occur as early as the third or fourth day; it usually happens about the eleventh day, but occasionally still later.

Such is the usual course of this disease. But the symptoms and mode of termination vary greatly in different countries, in different epidemics, and even in the same epidemic. The following are some of the varieties:—*a*. Sudden coma and death in convulsions. *b*. Sudden seizure with black vomit, and death in a few hours. *c.* Intense pain and tenderness in the epigastrium, incessant vomiting, and death from exhaustion. *d.* Great anxiety and restlessness, with a clean tongue, and nearly natural pulse, followed after a time by black vomit and fatal exhaustion. Death may be sudden, the sequel of a quiet sleep, and it is sometimes preceded by acute pain and strong convulsions.

SEQUELÆ.—Diseases of the lungs, liver, spleen, or other internal viscera. Chronic dysentery. Slow and tedious convalescence.

CAUSES.—*Predisposing.* A continued temperature of not less than 75° to 80° Fahr. The latter end of summer and beginning of autumn. The climate of the West Indies, of the south of Spain, of the seaports of intertropical America, of Mexico, and of parts of Africa. It occurs more or less frequently, and with greater or less severity, in the West Indian Islands, at the Havana, at Vera Cruz, at New Orleans, Mobile, Charleston, Baltimore, Philadelphia, and New York, at Gibraltar, and Barcelona. Male sex; intemperance; depressing passions; all the predisposing causes of common continued fever; especially imprudent exposure to night air. Recent arrival at the place where the disease exists. Want of protection by a previous attack. *Exciting.*—Marsh miasma, and decomposition of vegetable matter. The disease is most common in swamps at the mouths of rivers, in the low-lying parts of crowded cities, and in ships laden with vegetable produce, or kept in a damp and filthy state.

PERIOD OF INCUBATION.—Less than ten days.

MORBID ANATOMY.—General yellowness of the skin, sometimes interspersed with blue or livid spots; the brain and its membranes generally healthy, and rarely presenting effusion of serum or blood; red, livid, or dark-black spots and patches on the mucous membrane of the stomach, and in its cavity an inky black fluid (black vomit). The intestinal canal contains the same black fluid. The intestinal mucous membrane often shows patches of a brown or blackish colour, but no ulcers as in typhoid fever. The gullet is sometimes found inflamed and abraded; the liver is either greatly congested, or small and anæmic; the bladder is contracted and sometimes inflamed. In some epidemics blood has been effused into the structure of the muscles.

DIAGNOSIS.—In mild cases not easily distinguished from remittent and enteric fevers; but in severe cases, and in the more advanced stages, it is readily identified by the yellow skin and eye, and the black vomit.

PROGNOSIS.—*Favourable.* A regular and steady pulse; a soft and warm skin; a natural expression of countenance; a moist tongue; a free discharge of urine; a distinct remission; natural sleep of some hours' duration, undisturbed by vomiting; sudamina. *Unfavourable.*—Previous intemperance. Recent arrival on the spot where the disease is rife. The early occurrence of any of the characteristic symptoms, such as yellowness of the skin, especially if in patches, or the black vomit; pain in the back; tenderness in the epigastrium; acrid burning sensation in the stomach and œsophagus; incessant vomiting; deep sighing; singultus; great coldness of surface, with a sensation of internal heat; and an irregular or intermittent pulse. Recovery may take place after the most unfavourable symptoms, and, on the other hand, "it is known that in persons sitting up in bed amusing themselves, and apparently in a favourable state, the black vomit has suddenly appeared, quickly followed by death, to the utter astonishment of the medical attendants."—*Gillkrest.*

MORTALITY.—Very different in different epidemics. The deaths have amounted to 130 or 131 in 134; 19 in 20; 34 in 35; and 1,265 in 1,739; but they have been as few as 6,684 in 16,517; and even as 1 in 8. English regiments in Gibraltar have suffered a mortality of 1 in 11, and 3 in 11 of the numbers attacked; and in Bermuda of 1 in 3, and 4 in 11. The mortality is generally greatest when the epidemic is recent, and diminishes considerably in the course of time.

TREATMENT.—The stomach should be unloaded at the onset by an emetic (Form. 201). The thorough evacuation of the whole of the intestinal canal during the first two hours of the fever cannot be too much insisted on, and purgatives should be freely exhibited until the bowels have acted five or six times.

At first we may give one, two, or three drops of croton oil, or an ounce of castor oil, or from ten to twenty grains of calomel, followed in two hours by a saline aperient. Many practitioners depend mainly upon mercury, given not only to unload the liver and intestines, but also to affect the constitution. After the first aperient dose a quarter of a grain, combined with opium, may be given every two hours, and mercurial ointment may be simultaneously rubbed into the groins and armpits.

Whenever there is a marked remission of symptoms, xx grs. of quinine should be administered at once, or two grains every hour.

When the *skin* is universally hot and dry, tepid sponging and the affusion of cold water to the head are of the greatest advantage. When there is vigour of constitution, sweating may be induced by packing the patient in a wet sheet. When, on the contrary, the surface is cold, the warm bath, at 100° to 120° Fahr., and warm frictions, should be employed. The *sickness* may be allayed by demulcent fluids, effervescing draughts, ice or ice-water, the *pain in the eyeballs* and *forehead* by cold to the head, the hair having been previously thinned, or the head shaved. Moderate hæmorrhage from the stomach or bowels is beneficial, but when excessive, should be checked by sulphuric acid (Form 146), gallic acid (Form 155), or lead (Form 157.) *Collapse* must be treated by diffusible stimulants. Extreme *restlessness* in the advanced stages of the disease, and when great debility is present, may be met by opium in doses of one or two grains. The diet should be restricted to milk, gruel, and beef-tea. Wine may be given as soon as the patient appears to require support.

During convalescence, quinine or cusparia will be needed.

PROPHYLAXIS.—Temperance, cleanliness, regular exercise and a residence, if possible, on a hill or rising ground. The *avoidance* of unhealthy localities, of exposure to the sun, of impure water and stale food. Robust and plethoric persons newly arrived at a place where yellow fever prevails, should carefully observe all the rules of health; keeping the bowels open by the regular use of gentle aperients. The sick should be separated from the healthy; and hospitals should be spacious, cleanly, and well ventilated. Europeans embarking for tropical climates should arrange to arrive at the healthy season of the year.

INFECTIOUS FEVERS.

GENERAL OBSERVATIONS.

Modern observers have separated infectious fevers other than the exanthemata into three genera—viz. Typhus, Enteric, and Relapsing. These are collectively called "The continued fevers." The generic distinctness of relapsing fever was first established in the epidemic of 1843, and subsequent to this date a similar distinction was recognized between typhus and enteric fevers.

Relapsing fever is a rare epidemic. It appears in times of famine, and is not marked by any cutaneous eruption, by which, and by the abrupt cessation of the fever, and restoration to comparative health for a time, it is distinguished from typhus.

Typhus is essentially a "low" fever, setting in with complete prostration, which increases as the disease advances, until the vital powers become reduced to the very lowest ebb. A characteristic rash and head symptoms sufficiently distinguish this fever.

Gastric and intestinal symptoms, on the other hand, mark the access and progress of *enteric fever*.

Typhus, like relapsing fever, is the companion of squalor and want. It is supposed to occur only in epidemics, but we have reason to believe that it exists *continuously* to some extent and degree. Of these fevers, typhus is the most infectious; enteric the least so. The mortality in typhus and enteric is pretty equal; that of relapsing fever comparatively small.

TYPHUS.—EPIDEMIC CONTINUED FEVER.

SYNONYMS.—From its prevailing character —CONTAGIOUS, INFECTIOUS, PUTRID, PESTILENT, MALIGNANT, EPIDEMIC, ATAXIC, ASTHENIC, or ADYNAMIC FEVER. After a leading symptom—BRAIN FEVER: From the appearance of the skin—ERUPTIVE, PETECHIAL, MACULATED, or SPOTTED FEVER: After the places in which it most commonly prevails—PRISON, GAOL, CAMP, SHIP, and HOSPITAL FEVERS, and PARISH INFECTION.

Definition.—A continued fever of fourteen or twenty-one days' duration, accompanied by extreme prostration, great disturbance of all the bodily and mental functions, and a strong tendency to cerebral complications; and characterized, in most instances, at an early period, by a peculiar rash.

Symptoms.—The invasion is either sudden and well marked, or gradual and obscure.

In the first case, the disease is generally announced by a succession of severe shivering fits, followed by acute pain in the head, aching in the back and limbs, lassitude and weariness, an unsteady gait, and prostration. The surface is cold and pale, the skin contracted, and the pulse either small and weak, or full, quick, and very compressible. The breathing is quickened, and often interrupted by deep sighs. The expression is dull, anxious, and confused, and sometimes closely resembles that of intoxication. The appetite fails; in some cases there is nausea; the bowels are generally confined, and the tongue is coated with a dirty white fur; the pulse is feeble and fast, but rarely exceeds 120.

In the second case, the symptoms are often so obscure that it is not easy to determine whether the patient is suffering from continued fever, slight indigestion, or a common cold. He has no well-marked rigors, no severe pains in the head, back, or limbs: but he is pale, languid, weary, and drowsy, and complains of dull headache; is disinclined to exertion, and incapable of application. His appetite fails; the tongue is covered with a thin white fur, the bowels are constipated, the pulse somewhat increased in frequency; he passes restless nights, and wakes unrefreshed. This period of uncertainty may last three or four days; and the transition to a state of undoubted fever be so gradual that no precise time can be fixed at which the disease may be said to have been first present. The history of the cases, revealing the fact of an exposure to contagion, is often the best aid to a correct diagnosis.

This premonitory stage, whether the onset be sudden or gradual, passes more or less rapidly into fully-developed continued fever, marked by pungent heat of skin, frequent pulse, thirst, headache, throbbing of the temples, flushing of the face, suffusion of the eyes, and great restlessness and irritability. The countenance is dusky, and expresses indifference or confusion of mind. Questions are answered slowly, and as if with difficulty, but rationally. The patient grows weaker, and about the *fourth day* is in bed, lying on his back, and unable to rise without assistance. If he gets any sleep it is disturbed by dreams; he mutters and often starts, and wakes unrefreshed; but in some cases there is great drowsiness; in others a total absence of sleep. The tongue, which is at first coated with a moist dirty-white fur, or marked with a dry brown streak along, or on each side of, the middle line, becomes uniformly covered with a dry brown coat. The urine is scanty and high-coloured, and is apt to accumulate in the bladder.

About the fifth day, but varying from the fourth to the seventh, a

surface ,
fade away into the duskiness of the surrounding sk
have a florid venous tint, and disappear on pressur
are a day or two old they cease to be prominent,
of a dirty-brown colour, and no longer disappear o
the number is limited the spots are isolated and sca
the rash is copious they are loosely gathered into
About the *seventh day* delirium begins to attend
and the patient mutters constantly and incoherent
and wildly; and at this period there may be som
straining him, though usually he is not strong en
bed. The head is intensely hot, and the face and
a vivid coppery blush. Still the patient may b
open his mouth and fruitlessly attempt to prot
brown tongue, which, as well as the teeth, ar
sordes. The breath and cutaneous exhalation ha
cadaverous odour; the former contains free amr
ranges from 90 to 120, varies in volume; and is soft
Stupor now begins to alternate with delirium and
into a state of apathy. He is deaf; his expressi
eyes filmy; the mouth open; deglutition begins
are tremulous and convulsed, constantly graspin
air, or picking the bed clothes. This critical c
tinue for twenty-four hours or more, and then the
to rally. The crisis occurs about the *fourteenth*
able, the patient falls into a sound sleep, the skin
the pulse falls and increases in force, the skin ar
moisten, the patient regains consciousness, a gent
in, the alvine and urinary secretions become m
tongue rapidly cleans, and with this improvemen
there is a craving for food. The pulse may fall to

during the first week. It is attended by vertigo, and expressed by moans or cries. Towards the end of the week delirium takes its place. This is sometimes slight, being an incoherent muttering (typhomania); in other cases it is so violent as to be mistaken for acute mania; and the patient, if not narrowly watched and restrained, will sometimes effect his escape from his attendants, and throw himself out of window, or place himself in circumstances of great danger. Between these two extremes there is every degree of intensity, proportioned to the vital power of the patient, acute delirium being more common in the young and robust than in the aged and feeble. *Wakefulness* is present in most cases, and may continue for fifty hours or longer. *Somnolency*, *stupor*, *apathy*, and *coma* come on in succession as the disease increases in severity; at the same time the *special senses* become much blunted, at is well seen in the deafness which invariable accompanies the disease. *General convulsions* are rare, appearing occasionally towards the close of the disease; and often indicating suppression of urine. A fatal termination may be expected when such grave symptoms arise.

MUSCULAR SYSTEM.—*Prostration* and a painful sense of weariness are among the earliest symptoms; and *general muscular pains* simulating acute rheumatism and of considerable intensity, are sometimes present in the early stage, and may mislead us in our diagnosis. Later in the disease *paralysis* affects the sphincters of the bladder and rectum, the excretions are passed in bed, and the urine dribbles from an over-distended bladder. The muscles of mastication, deglutition, and vocalisation are similarly affected; the tremulous tongue cannot be protruded, fluids are swallowed slowly and with difficulty, the voice becomes feeble and the speech inarticulate. *Muscular tremor* is always present, and sometimes *tonic spasms* affect some group of muscles.

RESPIRATORY SYSTEM..—Pulmonary complications are very common. *Bronchitis* occurs to some extent in almost every case; *pneumonic* and *hypostatic congestions* in many; the former occurring in the earlier stages, the latter towards the crisis. They are indicated by difficult breathing, and lividity of the lips and face. Pain is rarely complained of, and the cough and expectoration are not in proportion to the pulmonary disease. Quick breathing, a little wheezing with slight cough, and occasional expectoration of colourless, frothy, or russet and viscid sputum, are sufficient indications of pulmonary mischief, and, on examining the chest, we detect extensive rhonchus and mucous crepitation. Congestion is indicated by dullness on percussion, and bronchophony. *Pleurisy* occasionally supervenes, and mostly with fluid effusion.

GLANDULAR SYSTEM.—1. The *Liver*.—Jaundice is very rare. 2. *Inflammation of the parotid, axillary, and cervical glands*, with rapid suppuration, is a severe complication. These affections often appear about the time of convalescence, and either prevent or greatly retard it, for the adjacent integument becomes indurated, and the sloughy cellular tissue surrounding the glands separates very slowly.

THE SKIN AND INTEGUMENT.—1. *Boils* sometim
convalescence. 2. *Erysipelas* is apt to occur whe
Gangrene and *sloughing* of the integuments, pre
of the skin, are common in the advanced stage o
parts subject to pressure, and large bed-sores are c
the sacrum and trochanters.

STAGES.—1. *Period of Incubation* about ten day
of Invasion, extending from the commencement
the appearance of the rash, from four to seven day
of nervous irritation, restlessness, wakefulness
extends from the end of the last stage till somnole
period of three or four days. 4. *The typhous sta*
last stage of many other diseases, as well as of ty
monly called the "typhoid" stage. We abandon
it is often used to designate enteric fever. In th
the patient lies on the back; has a rapid threa
ing delirium, stupor, or imperfect coma; a dull fi
open mouth, exhaling an offensive odour, and di
dry, and brown tongue, with sordid lips and teeth.
are passed involuntarily, and the hands are co
convalescent stage. A month is usually sufficie
patient to health; shedding of the hair is commo
permanent derangement of the functions.

DURATION.—Convalescence mostly commences
day, but in mild cases about the end of the first
sionally postponed to the twenty-first day.

PROGNOSIS.—*Favourable*, if the patient be you
and of a non-excitable temperament, if the pulse r

PATHOLOGY.—The *blood* is very dark and fluid; and if we meet with coagula, they are soft and friable. If pneumonia have existed, firm yellowish clots are found in the right side of the heart. Taken during life the blood is found to be deficient in fibrin; urea may often be detected in the serum, and ammonia is present in appreciable quantity. The *bile* is dark and thick, like treacle. I have observed its specific gravity as high as 1050. With water, it forms a golden yellow feebly alkaline solution, which possesses the reactions of healthy bile. On evaporation it yields a large glistening and brittle black residue, smelling strongly of fatty matter. The *muscles*, including the *heart*, are dark and easily torn. The *brain* and *nerve tissue* are firm and healthy, but the cerebral membranes are commonly gorged with blood. Passive effusion of serum tainted with urea between the membranes and into the ventricles is one of the usual results of typhus; inflammatory exsudations, such as jelly-like serum beneath the arachnoid, a few small patches of coagulated fibrin on the upper surface of the pia mater, and shreds of coagulated lymph in the lateral ventricles, are rare. The *kidneys* are often found greatly congested. The *alimentary canal* is everywhere healthy, or only congested in its most vascular portions. The *liver* and *spleen* are more or less congested and softened. *Effusions* into the serous cavities are common. The *respiratory organs* show various lesions. The mucous membrane of the respiratory tract is injected and soft; the lungs may be œdematous, engorged, or partly consolidated. The air-tubes are commonly filled with frothy fluid.

GEOGRAPHICAL DISTRIBUTION.—Typhus prevails in every country of Europe, and is therefore so far independent of climate. Italy, Spain, and Great Britain appear to have suffered most from its ravages; and in Ireland it would appear to be endemic. It is prevalent in Canada and the United States. We have no evidence of its existing in Australia and New Zealand; nor in South America, in Asia, or Africa, where fevers of all kinds have been confounded together. Many suppose the plague to be the typhus of tropical countries.

CAUSES.—1. *Predisposing: Depression of vital power* from mental or bodily exhaustion; hence the disease is most common in adults. *Season and temperature:* Typhus appears to prevail, *cæteris paribus*, irrespective of these conditions. *Overcrowding with imperfect ventilation* and *insufficient food* are very powerful predisposing causes. Even in London, typhus is rare among the middle and upper classes. The severest epidemics have appeared in times of scarcity.

2. *Exciting: The infection of a specific poison* generated within the bodies of persons suffering from prolonged privation, and exposed to animal exhalations. No other fever is so infectious as typhus. It spreads quickly through a family: nurses and medical attendants, if they do not use sufficient precaution, invariably take it. The poison is contained in the cutaneous and pulmonary exhalations of the patient, and is no doubt introduced into the system through the lungs.

Diagnosis.—Extreme muscular prostration, with general dull aching pains, a weak pulse, dusky complexion, dulness of the senses and intellect, heavy persistent headache, a peculiar dusky rash and a bad odour of the body, are the marks of typhus. But excepting the rash, which does not appear until the fourth or fifth day, these symptoms are not conclusive; and the true nature of the disease may be very doubtful during its early stages, when it may be mistaken for enteric, or relapsing fever, meales, phrenitis, suppression of urine, and for such diseases as pneumonia and pyæmia, when they assume the typhous character.

Enteric and *relapsing fevers* are distinguished at pp. 297 and 302. Coryza, catarrh, and a patchy, brighter-coloured rash distinguish measles. *Phrenitis* is ushered in by great irritability of temper; the senses are painfully acute, so that light and sound are intolerable, and the eyes are bright and wild. Strabismus and sympathetic vomiting are common symptoms; there is no rash. If *meningitis* be present, acute mania, with intolerable pain in the head, is superadded.

Low forms of inflammation of the brain are not difficult to distinguish. The history of the case, and the absence of much fever and rash, will guide us. *Uræmia* is characterized by the sudden accession of stupor, rapidly passing into coma; and convulsions, which are rare in typhus, are generally present in this disease. *Pneumonia.*—General pneumonic engorgement of asthenic form is still more difficult to distinguish from typhus; indeed, the typhus poison, in common with other animal poisons, often produces rapid engorgement of the lungs and depression of the vital power, and death occurs in such cases before the specific symptoms of the fever have had time to declare themselves.

Prophylaxis and Disinfection.—Avoid the exhalations from the patient; dilute and carry them away by direct and free ventilation; distribute about the room lumps of wood charcoal, and hang about the door-ways cloths wetted with carbolic acid water; subject all infected articles of clothing to the action of boiling water, or to steam, and subsequently rinse them in water holding carbolic acid in solution. Mattresses should be well baked in an oven, and feather-beds should be disinfected.

Treatment.—The patient should be placed in a cool, well-ventilated room, in which a brisk fire is constantly burning, with a nurse in constant attendance. If the skin be pungently hot, the patient should be immersed for five minutes in a warm bath; if there is less heat of skin, tepid sponging will suffice.

The heat of the head may be allayed by iced water, poured in a small continuous stream from a height for the space of ten or fifteen minutes. The head should be shaved whenever the brain symptoms are severe, and if the headache be not relieved by the cold douche, blisters should be freely applied to the forehead, or to the whole of the scalp. The bowels should be kept in free action by cholagogue purgatives. Sleeplessness, nervous excitement, and delirium must be combated by hypnotics. Of these opium is the best, given in moderate doses at first (♏. xv. of tincture, gr. v. of compound soap pill, or gr. x. of Dover's powder); if necessary the dose must be increased.

But the chief indication is to support the failing strength. Constant good nursing is indispensable. In the early stages food is generally taken well. It should consist of eggs, milk, beef-tea; three or four eggs may be given daily, with tea or coffee in the form of emulsion. Alcoholic stimulants are invaluable in typhus, and may be administered throughout the disease. The quantity must be determined by the state of the pulse. If it be of fair volume and under 120, little or no alcohol will be needed. If it be failing and the patient cannot take much food, we may give from ℥vj. to ℥xvj. of brandy or an equivalent quantity of wine in the twenty-four hours. Brandy is the best stimulant; it should be mixed with water, eggs, or milk, and given every one or two hours. Delirium does not contra-indicate it.

Of medicinal stimulants ammonia is the best. (See Forms. 1 to 15.)

After the crisis quinine and acid is a very useful combination.

Strict attention must be paid to the state of the bladder, especially in the later stages of the disease, when the patient becomes apathetic and the muscular tissues weak. When there is retention the urine must be drawn off twice a day.

We should carefully examine, from day to day, the integuments over the sacrum and trochanters: and ascertain the temperature of the feet. Bed-sores and mortification of the toes are grave complications, which may be generally prevented by proper vigilance.

The breathing must be carefully noticed. If the inspirations exceed twenty-five per minute, we must examine the chest. If pleuritis or pneumonia be present, hot poultices or blisters will be necessary. If there be cough and wheezing, with hurried breathing and mucous crepitation, mustard poultices or turpentine stupes should be applied to the chest, and expectorant stimulants (Form. 216) administered.

If inflammatory swelling of the parotid arise, we must endeavour to prevent suppuration. For this purpose a few leeches may be applied, and as this is a complication that supervenes about the time of convalescence, we may generally exhibit iron and quinine freely. The quantity of alcoholic stimulant should also be increased, and the diet should be as nutritious as possible. As soon as fluctuation is detected free incision should be made.

CEREBRO-SPINAL FEVER.

Under the terms, Epidemic Cerebro-spinal Meningitis, Purpuric Fever, &c., a variety of typhus in which spinal symptoms are prominent has been described. The early symptoms are those of typhus, with more severe myalgia than usual. Pain in the muscles of the neck is especially complained of; and the body generally, but more especially the spine and abdomen, is affected with acute neuralgia. The delirium and stupor are always great; the head is stiffly retracted and the muscles are in a state of tetanoid rigidity or spasm. As the patient lies a little over to one side, the body is often stiffly arched backwards; sometimes an arm is constantly retracted; sometimes the legs are rigidly flexed upon the thighs; occasionally the muscles of the face and eyeballs are implicated, as indicated by trismus, fixed risus, or strabismus. In most cases, a cutaneous petechial rash appears very early, and the petechiæ often form large blackish blotches, which may become raised, vesicular, and sometimes gangrenous. In some outbreaks herpetic eruptions are common.

At first there is hyperæsthesia, but the patient soon lapses into coma, and usually dies between the first and the eighth day. Sometimes the usual premonitory symptoms are absent, and the patient falls into a state of collapse, rapidly passing into coma, purpuric blotches appearing simultaneously.

After death, great vascularity of the pia mater of the brain and spinal cord, with more or less clear or milky serum effused into its meshes, will be found.

Examples of this variety of fever occur every now and then during epidemics of typhus, as has been particularly noticed in the United States, on the banks of the lower Vistula, and in Ireland. The treatment is that of ordinary typhus, with especial regard to the cerebro-spinal symptoms. The shaved scalp should be blistered, and a long narrow strip of blistering plaster placed over the upper half of the spine.

ENTERIC FEVER.

Synonyms.—Typhoid, pythogenic, gastric, intestinal, bilious continued, and cesspool fever; muco-enteritis; abdominal typhus.

Definition.—An endemic contagious (?) fever, generated by the contents of sewers or cesspools, and by water, milk, or other liquids polluted by excreta.

Symptoms.—The onset is generally insidious. There are no marked premonitory symptoms; chilliness, loss of appetite, and slight pyrexia—sometimes accompanied by nausea and a little diarrhœa, and sometimes not—mark the outset of the disease in most cases. In others, vomiting and diarrhœa, with some abdominal tenderness, are the earliest indications. On careful examination some evidence of gastro-intestinal irritation will always be found, and the abdomen is tender on pressure. The tongue is furred, and red at the tip and edges; the pulse is small, frequent, and sharp; the face is pale and somewhat pinched; but the cheeks have a circumscribed blush. The patient becomes weak, the skin is hot and dry, the lips cracked. There is complete anorexia and much thirst. This is usually the state of the patient when he first comes under the notice of the medical practitioner, and states that he has been feeling unwell for about a week. On the *seventh day*, or a little later, a few round, well-defined rose-coloured spots may appear on the abdomen, chest, or back. These spots somewhat resemble the papulæ of variola in their earliest stage, but they are not so large or so hard. They are elevated, and disappear on pressure. In at least half of the cases, and in the worst form of the disease, they are altogether absent. When present, they are easily overlooked, for in most cases they do not exceed half a dozen over the whole of the chest and abdomen, and very often not more than three. Their number bears no proportion to the severity of the disease. Forty-eight hours after their appearance the spots begin to fade and new ones arise, which in like manner disappear, and are succeeded by another crop. The abdomen is now usually found more or less tympanitic and tender, the tenderest part being the right iliac fossa, where pressure commonly produces gurgling. Now, if not earlier, diarrhœa usually sets in with greater or less severity, with watery stools of a light yellow colour. The tongue is covered with dirty white fur, and is cracked and apthous; but if the purging continue, it becomes, dry, brown, and contracted, or red and glazed: it is usually more or less fissured, and occasionally presents large patches of superficial ulceration. The teeth are crusted with sordes. The pulse ranges between 90 and 120; the skin is dry and hot, the thermometer usually showing a daily fluctuation from 102° to 103° Fahr. in the early morning, to 103° to 105° in the evening; the cheeks wear a hectic blush, and there may be much delirium. During the second week of the disease, and afterwards, hæmorrhage from the bowels may occur, and if severe, is indicated by sudden blanching. The patient dies without the discharge of blood per anum, and in this case the intestines will be found distended with blood. In other cases the hæmorrhage recurs and the patient becomes pallid and much prostrated. Hæmorrhage, however, is not the only danger. The patient is often cut off by perforation of the intestine. This dreaded result may be expected if the purging be frequent and persistent, if the tenderness and tympanites increase, and if vomiting and hiccough supervene. Perforation is usually preceded by symptoms of general peritonitis, excessive tympanites and persistent hiccough and vomiting. A paroxysm of more intense abdominal pain may indicate that perforation has taken place.

The patient may be conscious and acutely sensible of his condition throughout the disease to within an hour or two of his death; but when the diarrhœa is very exhausting and protracted he usually falls into a state of apathy, with a little delirium at night. He lies motionless in bed, and is now liable to bed sores. Emaciation occurs very rapidly, and if no amendment take place the typhous condition becomes established; the tongue and teeth are blackened with sordes; stupor with convulsive twitchings, delirium, and coma, succeed each other; the motions are passed involuntarily, and the patient gradually sinks.

and often non-apparent causes may be exp
Convalescence is in some cases int
generally traceable to some error of di
appear, and diarrhœa again sets in, to be
urgent symptoms.

The average duration of the disease is
rarely terminated in three. After a sever
much protracted, and the patient may not

COMPLICATIONS AND SEQUELÆ.—*Br*
pneumonia are frequent complications.
exsudations, and ulceration, is not uncom
tion is sometimes relieved by the ejectio
membrane. In such a case aphonia may
several weeks. *Abortion* and *phlegmasia*
during an attack of enteric fever. *Peri*
hæmorrhage occur as natural results of th
If the ulcers of the intestine erode a sm
hæmorrhage occurs. If the progress of the
it may soon reach the peritoneal covering
which may be local from adhesion of the
in the absence of such adhesions, genera
occurs about six inches from the ileo-cæcal
is generally supposed. The deepest part o
lies on the attenuated peritoneum, which h
slough, pretty firmly adherent, and retaine
effusion on the intensely inflamed serous
foration occurs, the peritoneal coat become
gives way in one or more places. The
small and rounded. *Inflammation and sup*
etimes occurs but more rarely than

and œsophagus occasionally present the same lesions if the disease be protracted beyond the third week. The stomach and duodenum, however, are unaffected, and the disease chiefly, in many cases exclusively, attacks the lower part of the small, and the large intestines. But it is upon the solitary and agminated glands (Peyer's patches) of the *lower third of the ileum* that the disease expends its virulence; and there we invariably find disease after death. In the early stage (on the fifth or sixth day) these normally obscure glands are red, swollen, and distinctly elevated above the surrounding mucous membrane; the blood vessels of the surrounding mucous membrane are seen converging towards their centres; and the corresponding part of the peritoneum presents a patch of dilated vessels. At length the swollen gland becomes soft and abraded; and this first stage of degeneration is quickly succeeded by sloughing or ulceration. Sometimes a whole Peyer's patch is covered with a discoloured, ashy-looking slough. When the slough has separated, or the ulcer advanced, the surface exhibits a ragged appearance, being formed of angry-looking granulations, of various sizes, enclosed in an irregular network of sloughy areolar tissue. The edges of the ulcer are hard and elevated: externally they are rounded and smooth, internally they are ragged with excavations. In proportion as the base of the ulcer nears the peritoneum, this membrane becomes inflamed, and when the ulcers are numerous the inflamed patches become confluent, the outer surface of the bowel presents the appearance of intense inflammation, and may be covered with plastic lymph. As soon as ulceration extends to this covering, perforation impends. The event, however, is often prevented by the adhesion of the part to a contiguous coil of intestine, or retarded by the deposition of solid lymph upon its outer surface. The aperture formed in the peritoneum rarely exceeds three lines.

The ulcers are in proportion to the number and size of the glands affected; if a solitary gland, or cluster of only two or three, the ulcer is a small spot; if a Peyer's patch, there will be a rounded or oval ulcer, from a quarter of an inch to an inch and a half in width. The ulcers are sometimes confluent. On recovery the ulcers heal, cicatrise, contract, and ultimately form a smooth, depressed surface, thinner and less vascular than the surrounding healthy coat, and devoid of villi.

When the *large intestine* is implicated, the disease is usually confined to the cæcum and the ascending colon. The cæcum is often severely affected, the ulcers being small, round, and uniform in size, unless they become confluent.

The *mesenteric glands* show their sympathy, if not their identity in anatomical structure and function, with the solitary and agminated glands, in becoming inflamed and swollen to several times their natural size. The inflammation may go on to suppuration.

The *spleen* is enlarged, softened and congested.

The *liver* speedily becomes fatty and enlarged. The mucous membrane of the *gall-bladder* is frequently found inflamed, but rarely ulcerated. The *bile* is thin and almost colourless, commonly acid, and of low specific gravity, and yields a very small proportion of solid matter.

GEOGRAPHICAL DISTRIBUTION.—Enteric fever prevails over all the world.

CAUSES.—1. *Predisposing. Youth.*—The mean age of 1772 cases admitted into the London Fever Hospital during ten years was 21. Of these half were between 15 and 25, one-fifth were under 15, less than one-seventh were above 30, and less than one-sixtieth exceeded 50.

Season.—Enteric fever is an autumnal disease, but it exists throughout the year, usually attaining its minimum in spring. It is more prevalent in dry and hot than in cold and wet seasons.

2. *Exciting.—Exhalations from putrid decay of animal matter.* —The two following instances are cited in Dr. Murchison's work on the Continued Fevers of Great Britain. I. Twenty out of twenty-two boys, at a certain school, were seized with fever, accompanied by symptoms of severe gastro-intestinal irritation. Two of the fatal cases were examined, and the usual lesions of Peyer's patches, and the solitary and mesenteric glands, were discovered. The cause was attributed to the opening, two days before the first case of illness, of a drain at the back of the house, which had been choked up for many years, and the distribution of its offensive contents over a garden adjoining the boys' playground.

II. In the year 1838 an epidemic of enteric fever desolated a commune in the department of Arriège. Nearly half the inhabitants were attacked, of whom nearly a third died. The disease was traced to a stagnant pool, the receptacle of dead animals and of all the sewage of the district. Three times the pestilence returned, and each time when the wind was blowing over the infected water.

In these cases it is assumed that the poison was conveyed by the air. In the following case observed by Dr. W. Budd, it appears to have been introduced into the system by water:—

III. The inhabitants of thirteen out of twenty-four houses of a certain crescent derived their drinking water from a well at one end of it; the remainder were supplied with water from another source. At the end of September it was evident that the water from the pump was tainted with sewage. Early in October intestinal fever broke out almost simultaneously in all the thirteen houses using the water.

Some observers, however, attribute the disease to a *specific poison*, contained in the alvine excretions of persons suffering from the disease, and deny that it may be spontaneously generated by putrid animal matter. Observed facts and the few experiments which have been made tend, however, to disprove these views.

Contagion and infection.—Much doubt prevails whether enteric fever be infectious or not. The question turns on the existence of a distinct specific poison. Positive proof that it may be conveyed from one person to another is wanting, and certainly the majority of patients derive it, on the clearest evidence, directly from one and the same source. Those in attendance on persons suffering from enteric fever do sometimes fall ill of it, but the source of the disease may be present in any house.

Diagnosis.—In the early stage, enteric fever may be mistaken for *typhus*, *variola*, *scarlatina*, &c. 1. Great muscular prostration and early cerebral disturbance, with dullness of the senses and mental faculties, mark the onset of typhus; while symptoms, more or less obscure, of gastro-intestinal disturbance indicate the presence of enteric fever; but sickness and diarrhœa may be absent and head symptoms may be prominent from the first in enteric fever. 2. *Abdominal tenderness* about the umbilicus and right iliac fossa, and, 3. *A moist thickly-furred aphthous tongue*, may teach us that the disease is enteric, and not typhus fever. 4. Light ochre-coloured fluid stools, sometimes compared to thin pea-soup, are diagnostic of enteric fever. If the motions are kept, as they should be, for the inspection of the physician, they will sometimes afford important indications of the severity and progress of the disease. They will be found to contain membranous flakes, blood, or pus; and the quantity of these will serve to direct our treatment. 5. When the eruption appears the diagnosis is certain. In typhus the rash appears about the fourth day; in enteric not before the seventh. In typhus it consists of a diffused dusky mottling composed of irregular, uncircumscribed spots, not raised, or only slightly elevated, tending to fade into dirty discoloration, or to become distinct petechiæ. In enteric fever the rash appears much later, never gives a mottled appearance to the skin, and is never confluent. The spots are rose-coloured, circumscribed, isolated, and elevated, so as to be distinctly felt by the finger; they always disappear on pressure and never become petechial. The only difficulty in diagnosis by the skin is that the freckled or mottled skin often seen in dark complexions, and the faint syphilitic maculæ present in others, may so mislead us that we may fail to observe the three or four minute pink papulæ which indicate the presence of enteric fever. 6. The *progress and duration of the disease.*—The dusky blush suffusing the head and neck in typhus, contrasts with the circumscribed hectic flush and pinched features of enteric fever. The one disease tends to death by coma, the other to death by asthenia; typhus kills or shows signs of departure in the second week, enteric fever continues for three or four weeks, and often much longer.

Variola.—If the acute lumbar pain and vomiting be absent and the eruption make its first appearance as a few isolated papules upon the chest and abdomen, the case may be doubtful for a day. For example, a patient has been feeling poorly for a week before he is seen, and then, he is in a state of high fever, complaining of headache and great and persistent nausea, but there is neither vomiting nor lumbar pain; he presents a large but faint vaccine scar; the tongue is coated with a dirty-white fur, the abdomen painful on pressure, and there is a distinct gurgling in the right iliac fossa, resulting from free action of the bowels induced by a purgative previously administered. Next day the tongue is dry and brown. and seven elevated rose-coloured papulæ, completely resembling those of enteric fever, are scattered over the abdomen and chest, There is no trace of eruption, or of that roughness of the skin, which precedes it, on the face or any other part of the body. In this stage it will be impossible to decide whether the case is one of small-pox or enteric fever, and we must defer our diagnosis for a while. A few hours, however, will suffice to decide the matter. In the case referred to, after a copious sweat the papules became harder and more prominent, and others began to appear on the face and limbs, and the case proved to be one of discrete variola.

Scarlatina.—I have shown* that the morbid anatomy of scarlet fever is identical with that of the first stage of enteric fever; that the two diseases occasionally coexist or are intercurrent; and that enteric fever is often a direct pathological sequent to scarlatina. Where such close relationship exists we must be guided by the previous history, and the symptoms actually present. (See the diagnosis of Scarlatina, p. 320.)

Chronic Tubercular Peritonitis presents many of the symptoms of enteric fever. The hectic flush, pinched features, abdominal pain, tenderness and gurgling, anorexia and diarrhœa, are all present in this disease, but the tongue is usually moist and clean; there is no eruption, and frequently the abdomen is moderately distended with effusion; moreover there may be evidence of tubercular deposit in the lungs.

PROPHYLAXIS and DISINFECTION.—Whenever a case of enteric fever occurs, we must examine into the condition of the drains and cisterns, and the nature of the drinking water; and ascertain whether there be any offensive accumulation of decomposing animal matter in or near the house. If it can be done speedily and without increasing the nuisance, drains should be cleared and flushed, and offensive accumulations removed. In the absence of all other water, that which is contaminated must be filtered through charcoal and boiled befere it is used; but whenever it is practicable the patient should be removed to a healthy locality. The dejections of patients suffering from the disease should be mixed with solution of chloride of zinc, of lime, carbolated lime or carbolic acid, and be speedily removed. Bad odours should be traced at once to their source and the cause removed, or their diffusion prevented by the substitution of stench-traps for open grating. A sufficient fall for the sewage should be provided, and in seasons of drought the drains should be occasionally flushed. Pipes connecting the waterclosets with the drain or sewer should be constructed of iron, and always placed on the *outside* of the wall of the house. If made of lead (which is readily eroded by rats) and carried down the *inside* of the house, the apartments are liable to be filled with foul air derived directly from the sewer. It is a common arrangement for the waste pipe of the cistern from which the drinking-water is obtained to pass directly into the soil pipe. In warm weather the cold sewer air rises and occupies the space between the surface of the water and the lid of the cistern: the foul gases are readily absorbed by the water which becomes thus directly contaminated. This evil is quickly remedied by cutting the waste pipe before it joins the drain, and cleaning out the cistern. Cisterns should be closed, or they may be poisoned by the body of a drowned rat.

---

* Medico-chir. Trans. Vol. LV.

When it is necessary to open a drain, or to empty cesspools, disinfectants should be freely used, and the air thoroughly impregnated with free chlorine. Fresh mould, lime, dry sifted ashes, and solution of chloride of zinc should be mixed occasionally with the offensive matter. The chlorine may be evolved from a mixture composed of ℥iv each of finely powdered black oxide of manganese and common salt, and ℥viii of sulphuric acid diluted with a little water, placed in a deep dish. Sulphate of iron, in powder, or solution, is also a commendable deodorant and disinfectant.

TREATMENT.—In the present state of our knowledge enteric fever must be treated as a local disease. We presume ulceration of the intestines, and fear its worst results. When the patient comes under our notice, inflammatory material has in most cases already been deposited in the intestinal glands, and it is generally too late to adopt an eliminative plan of treatment so as to remove that already formed. If, however, we see the case early, and have grounds enough to form a diagnosis, we may hope to arrest its further progress by judicious treatment. We shall often find that the alvine secretions are retained. In many cases the secretions are defective. The bowels should be relieved by moderate doses of castor oil and by enemata, and then, so long as the motions remain loose and pale, we may administer small and repeated doses of grey powder (gr. ii combined with gr. iii to gr. x Dover's powder) night and morning, and control the diarrhœa if it exceeds three or four motions in the 24 hours by an occasional enema of opium (♏xv træ opii, et decocti amyli ℥ij). This treatment may be continued until convalescence is established.

The diet must be carefully regulated and all solid food rigidly withheld; eggs, milk, and arrowroot, in various combinations should form the staple articles of food. The eggs should be lightly boiled, or given in emulsion with coffee or tea. Beef-tea may be frequently given; a few ounces of red wine may be allowed from the first, and increased to a pint or more during the progress of the disease if the strength fail.

If at any time in the course of the disease the bowels be constipated, ʒij to ʒiv of castor oil in combination with 10 drops of laudanum may be given. Sickness is best combated by small fragments of ice, or by iced soda-water to which a few drops of dilute hydrocyanic acid have been added. If there be abdominal tenderness or tumidity, linseed poultices should be retained by the slight pressure of a flannel binder, on the abdomen. The diarrhœa must be kept within the limits of one or two loose stools a day, and for this purpose we give an occasional dose of chalk mixture. If the abdominal symptoms be severe, with a temperature of 105°, or if it should appear that hæmorrhage impends, it will be well to apply a few leeches round the anus. If hæmorrhage occur, we must give lead (Form. 157), copper (Form. 160), or gallic acid (Form. 155). Cold fluids should be given, and a bladder of ice placed over the right iliac fossa. Turpentine in x or xx minim doses is a valuable remedy in hæmorrhage, and it is also useful in relieving the tympanites that often accompanies it. Assafœtida enemata are also useful in tympanites, which is sometimes not only very distressing, but may place the life of the patient in great jeopardy. In such a case a capillary trocar and canula should be passed through the abdominal walls into the distended bowel and the imprisoned air allowed to escape, for laceration of the diseased and attenuated coat of the intestine is very apt to occur in this distended condition.

If peritonitis, with or without perforation, supervene, we must exhibit opium very freely; 1 or 2 grains of the powder may be given every two or three hours: hot fomentations may also be kept applied to the abdomen. Hiccough is often a most painful complication. It may be relieved by the inhalation of chloroform.

Head symptoms and pulmonary complications require the treatment recommended in typhus fever.

During convalescence we must patiently pursue the same plan of treatment as regards diet, and give tonics (Form. 177). As the appetite improves and the stools become less frequent, darker and more solid, we may increase the quantity of food, and substitute another egg and a little fish in place of beef-tea, but solid meat, and vegetables should not be taken for a fortnight after the stools have become solid. An egg boiled moderately hard will sometimes be sufficient to produce a recurrence of diarrhœa and bring on a relapse. Cod liver oil, when the stomach bears it, is useful in removing emaciation.

RELAPSING OR FAMINE FEVER.

Synonyms.—Five or seven days' fever. Epidemic remittent fever. Bilious relapsing fever. Famine fever.

Definition.—A contagious fever of from three to seven days' duration, abruptly terminating, and recurring after complete apyretic intervals of about a week.

Symptoms.—Sudden and severe rigors, coming on without premonitory symptoms, and when the person is engaged in ordinary occupations. Severe headache and muscular pains soon follow. After an hour or two, intense febrile symptoms appear, with a full, bounding pulse; a dry, burning skin; and the tongue coated with white fur. There is severe pain in the epigastrium and vomiting of bilious fluid or of black, coffee-ground matters. The bowels are constipated and the urine scanty and high-coloured. On the third, fourth, or fifth day slight jaundice occurs in one-fifth of the cases. The stools are dark or even black, and sometimes contain blood, The headache becomes throbbing; the intellect remains quite clear, but there is constant watchfulness and great restlessness.

At the end of five or six days, sometimes earlier, sometimes later, the patient breaks out into a profuse perspiration, often accompanied by diarrhœa, and sometimes by intestinal or uterine hæmorrhage: the febrile symptoms are thus brought to an abrupt termination, and the patient feels well, eats, drinks, and may now go about as usual. After a week, or more rarely a fortnight, he suddenly relapses into his former febrile state. The second attack may be less severe than the first or more severe, and attended with jaundice and delirium. A second intermission occurs, usually after three days, and the patient is again restored to comparative health, complaining only of slight languor. A second or third relapse may occur at intervals of a week, but the patient may recover without a single relapse. In few cases, sudden collapse takes place; the patient becomes cold, livid, and comatose, and dies a few hours after the accession of the disease.

Complications and Consequences.—A *critical diarrhœa*, in some cases slight, in others attended with considerable griping and tenesmus. Occasionally severe persistent and fatal *dysentery*, occasionally also *chronic inflammation of the mucous membrane of the pharynx and trachea*. *Menorrhagia* and *abortion* are of frequent occurrence in women.

Mortality.—Relapsing fever is not very fatal. Of 441 cases admitted during the first epidemic into the London Fever Hospital, only 11 = 2½ per cent. were fatal; and of the 1741 admitted during the years 1869-71 only 30 or 1·7 per cent. died. The mortality, however, is greater in some epidemics than in others. In the Scotch epidemic of 1843, it was as high as 4 per cent.

Prognosis.—*Favourable*, if the patient be young and vigorous, and in the absence of complications. *Less favourable*, after middle age, if much jaundice be present, and persistent diarrhœa supervene. *Unfavourable*, if there be supression of urine.

Pathology.—No specific lesions of structure are found, but the tissues are usually more or less jaundiced. If gastro-intestinal symptoms have been present, patches of ecchymosed mucous membrane may be found in any part of the alimentary canal, and the lower part of the *ileum* is usually greatly congested; but neither Peyer's patches nor the mesenteric glands are in any way diseased.

The *liver* is congested, the gall-bladder and ducts are healthy; but the bile is dark and very thick. The *spleen* is greatly congested and soft. The *blood* is said to contain an unusual number of white corpuscles. The *kidneys* are commonly congested.

GEOGRAPHICAL DISTRIBUTION.—Relapsing fever, like typhus, appears to be more prevalent in Britain and Ireland than elsewhere. Ireland is its favourite habitat, and it has oftener prevailed in Scotland than in England. It has been observed in Silesia, and in 1855 attacked our troops in the Crimea. It has appeared in several parts of North America. It is unknown in the tropics.

CAUSES.—1. *Predisposing.*—Overcrowding and destitution favour the propagation of relapsing fever. The patients admitted into the London Fever Hospital come from the poorest and most populous districts, and the severest epidemics have occurred in times of famine. 2. *Exciting.—A specific poison* generated in the bodies of persons in a state of starvation. Medical men who have had experience of the disease are almost unanimous in the opinion that it is infectious. It successively attacks the members of a family, and spreads through contiguous houses. It appears that the disease has been several times imported into England and Scotland from Ireland. The Scotch epidemic of 1847 was ascribed to the immigration of a large number of destitute Irish; and epidemics in New York and other North American towns have been referred to the same cause. Medical men and nurses take the disease from patients.

DIAGNOSIS.—Relapsing fever may be mistaken for the other infectious fevers, and for remittent fever. From *typhus* and *enteric fevers* it is distinguished—1. By its sudden invasion, without warning. 2. By the absence of rash. 3. By the complete intermission and relapse. 4. By the absence of severe cerebral symptoms, except in those rare cases of relapsing fever in which collapse and coma come on. The early symptoms of enteric fever are obscure and the febrile symptoms slight. Vomiting, jaundice, and enlargement of the liver and spleen are often present in relapsing fever.

Remittent fever occurs in malarious districts and is non-infectious. *Variola.*—Lumbar pain, vomiting, and high fever attend the onset of this disease as well as of relapsing fever; but all uncertainty ceases with the appearance of the rash.

TREATMENT.—This should be directed to the relief of the congestion of the internal organs. Vomiting may be encouraged for a time; or, if absent, it may be induced (Form. 201). Cholagogue purgatives (Form. 250) should then be given. If there be much tenderness or pain in the hypochondria, leeches may be applied. The headache may be relieved by a bladder of ice or a stream of *iced water*. Perspiration may be promoted by saline diaphoretics.

We must carefully note the quantity of the urine, and if scanty, *we must* resort to the treatment required in such a case (see Sup-

pression of Urine). During the intermission care must be taken to secure the due action of the bowels; and the secretion of the liver should be encouraged. An occasional dose of calomel will be of much service, if dysenteric symptoms be absent. Tenesmus requires relief by an opiate suppository or enema.

Quinine with acid, in full doses, should be given till the strength is restored.

CHAPTER IV.

EXANTHEMATA.—ERUPTIVE FEVERS.

Definition.—Contagious diseases, attacking a person, for the most part, only once, beginning with fever, and followed, after a short and nearly definite interval, by a specific cutaneous eruption.

Variola	Small-pox.
Vaccina	Cow-pox.
Varicella	Chicken-pox.
Rubeola	Measles.
Scarlatina	Scarlet Fever.
Diphtheria	Diphtheria.
Pestis	Plague.

VARIOLA.—SMALL-POX.

Definition.—A contagious and infectious disease, setting in with severe febrile symptoms, followed by an eruption which passes through the successive forms of papule, vesicle, and pustule in about eight days.

Varieties.—1. Variola discreta, distinct small-pox. 2. Variola confluens, confluent small-pox. 3. Variola hæmorrhagica (probably the "Flox" of the early London Bills). 4. Varioloid, modified small-pox. Sydenham and Frank have also described a "Variola sine eruptione."

1. Variola Discreta—Distinct Small-pox.

Symptoms.—Rigors, lassitude, headache, severe lumbar pain, with extreme weakness in the back, and a white furred tongue, nausea, vomiting, and tenderness of the epigastrium. Drowsiness, and even coma, and in infants convulsions, are present in some cases. These symptoms are followed by inflammatory fever, with full, frequent pulse, hot and dry skin, diminished secretions, restlessness, and in some cases, delirium ; symptoms that continue till the eruption, preceded, perhaps by sweating, appears. In most cases the fever now subsides.

At the end of *forty-eight hours* from the first occurrence of rigors, but sometimes earlier, and sometimes as late as the fourth day, the rash appears on the face and forehead as distinct minute papules, about the size of a pin's head, sensibly elevated above the surface of the skin, and feeling like small shot beneath the finger.

During the *third* day, or the *third* and *fourth* days, the eruption extends over the rest of the face, and successively involves the neck, shoulders, hands and arms, trunk, legs and feet, being usually most abundant on exposed parts, and rose-coloured on covered parts.

About the *fifth* day, a minute circular vesicle, depressed in the centre, filled with a colourless fluid, and having an inflamed areola or margin, forms on the top of each pimple. The eruptive fever now rapidly subsides.

About the *sixth* day, there is some swelling of the throat, with difficulty of swallowing, hoarseness, and a flow of viscid saliva: the inflammation, or the rash itself, has extended to the mouth and fauces, where it can be seen as small round, white spots. The eyelids, and inner surfaces of the genital organs, are similarly affected.

By the *eighth* day the central depression has disappeared, the areola attained its full size, and the vesicles become purulent. The face swells; the eyelids are often so enlarged as to close the eyes; and the mouth, nose, and fauces are covered with pustules.

By the *eighth* or *ninth* day the pustules have attained their full size, and have a brown central spot. The inflammatory areola subsides, the swelling of the face disappears.

After this time the pustules break, and their contents ooze out, and dry into crusts, which soon fall off, and leave the skin beneath of a purplish-red colour, which often lasts for weeks. The swelling of the hands and feet gradually subsides, and about the seventeenth day the patient is convalescent. In severe cases permanent white scars are left on the face and other exposed parts.

The time occupied by the change from pimple to pustule is called the period of *maturation*. At some part of this stage, according to the amount of eruption, but generally about the eighth day, *secondary fever* sets in, characterized by extreme restlessness, sleepless nights, a frequent and quick pulse, dry brown tongue, scanty and high-coloured urine, and by delirium, especially at night. The bowels are usually constipated, sometimes obstinately so throughout.

2. VARIOLA CONFLUENS—CONFLUENT SMALL-POX.

SYMPTOMS.—This differs from the distinct form only in degree. The eruptive fever is more intense, and increases up to the period of maturation. The *secondary fever* is also more severe, and often assumes the typhous character. Coma and delirium are more frequent concomitants; and severe diarrhœa sometimes sets in.

The rash is also irregular in its appearance and progress. It is usually preceded by a red efflorescence on the swollen skin, from which the pustules emerge on the second day as small red points. Maturation takes place earlier; but the pustules, instead of being globular, are flat and irregular, and may contain, instead of pus, a brownish ichor. The inflammation extends to the subjacent cellular membrane, and sometimes ends in extensive sloughing. The swelling of the face and salivation commence early, and rise to a great height. The fever, though it generally abates somewhat, does not cease on the appearance of the rash; and about the ninth day there is a remarkable exacerbation, attended in some instances with all the worst symptoms of the typhous condition. The eruption turns livid or black; petechiæ, and passive hæmorrhages, bloody urine or dysentery, and sordes on the lips and teeth, make their appearance; and the patient often succumbs on the night of the eleventh day in convulsions or coma. In persons who recover, the scars are much deeper and more extensive than in the milder form.

3. VARIOLA HÆMORRHAGICA—BLACK SMALL-POX.

This variety is distinguished by an outburst of blood upon the free surfaces of the body, on the third or fourth day of the disease, simultaneously, in fact, with the eruption of the papules, the development of which, being thus directly interfered with, is wholly arrested. At first the skin is partially or generally spotted with bright red petechiæ, varying in size from a pin's head to three-fourths of an inch in circumference. There is profuse hæmorrhage from the vagina, the intestines, the mouth, or the nose; hæmaturia, too, is usually present, and the conjunctivæ are completely ecchymosed. The mind is clear and calm. The petechiæ increase in size, and become dark purple, and the hæmorrhage continuing, the patient rapidly sinks and dies an easy, and, to him, an unexpected death, on the fourth, fifth, or sixth day of the disease.

MORBID ANATOMY.—The left heart is usually found empty, and the right congested with dark, softly clotted blood. The lungs, spleen, and mesenteric glands are congested. Blood clots will be found in the pelvis of the kidney, and in the intestines, where they are derived from patches of severe ecchymosis. The large intestine is usually very severely congested, and maculated with petechiæ like the skin. The uterus and vagina are occupied with blood clots; and patches of ecchymosis may be observed upon the serous membranes.

DIAGNOSIS.—A few cases of this variety occur during every severe epidemic of small-pox. When once seen it is readily known; but as death occurs before the rash is developed, the true nature of these cases has been frequently overlooked.

The diseases with which it is liable to be confounded are, Purpura and Scarlatina. The eruption of blood within the skin, and the profuse bleeding from the mucous membranes assimilate it to the former of these maladies; while the severe premonitory febrile symptoms, and the bright, copious, and often very fine petechial eruption, have a great resemblance to the petechial variety of Scarlatina.

On carefully examining the skin and mouth, with the eye and the finger, we shall rarely fail to discover the true nature of the disease. A few white pustules may be found on the soft palate, and if there be no distinct papules observable on the skin, the finger will usually detect them as hard points beneath the cuticle. Here and there a few papules may have reached the depressed stage.

TREATMENT.—The free use of stimulants, and solution of perchloride of iron, ♏ xl of which may be given every two or three hours.

4. VARIOLOID—MODIFIED SMALL-POX.

Small-pox may be rendered less severe, and be otherwise changed in character by three causes:—A previous attack, inoculation and vaccination.

Small-pox modified by a previous attack, by inoculation, or by vaccination, has the following leading characteristics:—The eruptive fever, though often intense, lasts generally one day, or even less. The patient complains perhaps of indisposition in the afternoon, passes a restless night, and in the morning finds the rash out, and the fever gone. The first places in which the rash appears are generally the wrist and alæ of the nose, and a pimple in the latter situation, will often give the clue to the nature of the disease. The eruption itself runs a shorter course, is rarely confluent, and has not the uniformity of the regular disease. A few of the pustules, though small, are well formed, and have the central depression. Several of the pimples do not become vesicles, and the vesicles themselves shrivel (*Horn-pock*), or are unusually persistent, and transparent (*Pearl-pock*). All the stages of the eruption may be seen on the body at the same time, and all imperfect. As soon as the rash appears, the patient is well, unless it happen to be so extensive as to give rise to secondary fever.

CAUSE.—A specific poison, emanating from persons labouring under the disease, or from clothes worn, or things used by them. The variolous matter may be introduced into the system by inoculation, by the scab, or by cotton wool soaked in the matter and inserted in the nostril.

PROGNOSIS.—*Favourable.* The pustules distinct; the march of the disease regular; the form modified; the subject healthy. The period of childhood and youth.—*Unfavourable.* The confluent form; the fever assuming the typhous condition, and the pustules becoming flattened, livid, or interspersed with petechiæ. The sudden disappearance of the rash, with subsidence of the swelling of the face or extremities; depression of the pustules, followed by great prostration of strength, universal pallor, great anxiety, oppression at the chest, syncope, convulsions, coma, or delirium. A sudden rise in the pulse; great dyspnœa. Excessive vomiting setting in before the rash, and continuing after its appearance. Blood in the urine and other secretions. Complications with visceral disease, such as inflammation of the brain, throat, larynx, lungs, or alimentary canal, and suppurations in these viscera, or in the joints. Infancy, and advanced age.

The patient's fate is usually determined in the interval between the eleventh and seventeenth day, rarely during the primary fever. The secondary fever is sometimes terminated by a critical diarrhœa.

SEQUELÆ.—Abscesses, ulcers, boils, suppuration of the glands of the neck, sloughing of the skin, erysipelas, suppuration of the joints, ending in permanent lameness; ophthalmia, followed by blindness from opacity of the cornea; deafness, following suppuration of the internal ear; suffocation from swelling of the glottis; inflammation of the serous membranes of the chest and abdomen; pleurisy, terminating in empyema; inflammation of the lungs; hæmoptysis; hæmaturia, inflammation and suppuration of the kidneys; in females, menorrhagia; in pregnant women, abortion; melancholia followed by mania. During convalescence, patients may be attacked by other prevalent diseases, such as typhus, erysipelas, and hospital gangrene.

MORBID ANATOMY.—On the skin, the rash as described. On the conjunctiva of the eye, on the lining membrane of the air-passages, on the mouth, tongue, nostrils, palate, and fauces, on the prepuce and labia, small patches of false membrane, or of detached epithelium, or denuded spots of mucous membrane, or actual pustules. In rare cases, these appearances extend into the bronchial tubes and through the whole length of the intestines. Inflammation in various internal organs; the texture of the viscera softened; rapid putrefaction after death.

DIAGNOSIS.—The sudden attack, the intense pain in the head, back, and loins, the sickness, the absence of the local affections of the other febrile exanthemata, the prevalence of the disease at the time, and the exposure to contagion, are strong probabilities in favour of small-pox; and the regular successive changes in the eruption are conclusive. Before the appearance of the rash, and until it has assumed a characteristic form, the diagnosis may prove difficult. A typical case may be mistaken for *relapsing fever* (page 300); a modified form for *enteric fever* (page 297). During the primary fever there may be profuse sour-smelling perspiration, and general muscular pains, and this combination may be mistaken for *rheumatic fever*. The following are cases in point: 1. A profuse sour-smelling sweat had lasted forty-eight hours before the rash appeared; and the muscular pains continued two days longer. 2. The eruption was preceded by a copious, fiery crimson, finely-spotted, petechial rash, covering the trunk and upper parts of the limbs, and confluent at the flexures of the arms and thighs into vivid crimson patches, surrounded by distinct crowded petechiæ. The rest of the skin was dusky crimson, and the surface intensely hot. Two rose-coloured papules were noticed on the chest. The lumbar pain was intolerable. Twelve hours afterwards the eruption began to appear; and, though quite disproportioned to the petechial rash, the disease was confluent. At the outset such a case might be mistaken for *typhus*.

It is not always easy to distinguish the papular stage of small-pox from an acute attack of *syphilitic lichen;* but the papulæ on the alæ of the nose, upper lip, and wrist are highly characteristic of variola.

MORTALITY.—This is influenced by the patient's age, the severity of the disease, its previous occurrence; and the performance, or otherwise of vaccination. Childhood and old age both predispose to a fatal issue; and the danger, as in all analogous diseases, increases with the age. According to Mr. Marson, patients of all ages die at the rate of 50 per cent. in the confluent form; 8 per cent. in the semi-confluent; and 4 per cent. in the discrete variety. Inoculation, when performed with skill and care, was followed by a very low mortality.

Vaccination appears to afford a better protection against a fatal issue than a previous attack of small-pox itself.

Annual fluctuation considerable: *e.g.*, in 15 years (from 1840 to 1854) the deaths in London, in a million inhabitants, were as high as 890 in 1844, and as low as 225 in the year preceding, and only 87 in 1853. This fluctuation is in part due to recent legislation; but has always been a marked feature of the disease.

LAWS OF INFECTION.—Communicated by contact or through the air; by the living and dead body; by the contents of the vesicles and pustules; by the dried scabs; or by substances imbued with the variolous matter. Infecting distance considerable—from 30 to 50 feet, or more. The period at which a patient begins to communicate the affection, and at which he ceases to be dangerous to others, has not been ascertained. It rarely occurs twice in the same person; about one per cent. it is believed, are liable to a second attack. It may attack the fœtus in utero.—*Period of incubation.* Usual duration, twelve days; limits, ten to sixteen days.

TREATMENT.—*Before the appearance of the eruptive fever*, the treatment will be the same, whatever may be the nature of the impending disease. An emetic (Form. 200), followed by a brisk saline aperient (Form. 239), to remove any offending matter from the alimentary canal; the antiphlogistic regimen, if inflammatory symptoms run high; stimulants in extreme nervous depression; opium in great nervous irritability; local bleeding and stimulants in congestion, to promote reaction, and to relieve the circulation. *During the eruptive fever* the fever may be moderated by exposing the body of the patient to a cool atmosphere, by cold drinks, as lemonade, toast-water, soda-water, &c.; at the same time giving saline aperients, to keep the bowels loose. Cold affusion may also be used with advantage when there is much heat of skin; but cold or tepid sponging is to be preferred.

After the appearance of the eruption, the indications are:

I. To moderate the fever when violent. II. To support the strength when deficient. III. To subdue local inflammation and relieve occasional symptoms.

(I.) As the fever at once subsides on the appearance of copious perspiration, stimulant diaphoretics (Form. 1 or Form. 210) should be given every four hours; and a full dose of opium may be given at bedtime, if the patient be restless. The apartment must be kept cool and well ventilated.

(II.) If the strength fail, it must be supported by tonics or stimulants. Quinine, or the tonic infusions, in the lesser degrees of weakness, wine and ammonia in the greater.

(III.) Ophthalmia, if severe, will require leeches to the temples: if milder, solution of nitrate of silver (gr. v—℥i). Olive oil, cold cream, vaseline, or simply tepid water, are grateful applications to the swollen and irritable skin.

If the throat be attacked, and there be difficulty in swallowing, leeches may be applied to the neck, and an astringent gargle used.

Internal inflammation must be treated on general principles, but blisters and counter-irritants are contra-indicated, except in the discrete form of rash.

Obstinate vomiting, which sometimes proves both troublesome and dangerous, is best treated by effervescent salines, with a few drops of laudanum. If there be tenderness at the epigastrium, a warm poultice may be applied, preceded, in severe cases, by a few leeches.

If there be a tendency to the typhous condition, the treatment recommended in that stage of continued fever should be resorted to.

If, after the eruptive fever has passed away, the patient suffer from profuse sweats, a cool regimen, and the dilute mineral acids in combination with tonics (Form. 122), should be prescribed.

Diarrhœa, when excessive, should be checked by the usual remedies (Form. 148).

When the eruption suddenly recedes, or the pocks sink and shrink, and alarming symptoms, such as rigors, convulsions, or delirium, supervene, blisters should be applied to the nape of the neck, and sinapisms to the feet and legs. The cold douche to the head, whilst the body is in a warm or vapour bath, may be used with great benefit.

The *secondary fever* requires the treatment of continued fever of the same type and degree of severity. When much irritation is present, full doses of opium are indicated.

In favourable cases little treatment is required beyond an occasional saline aperient, and the avoidance of an excess in diet.

In all cases the warm bath should be used repeatedly during the convalescence.

Prevention of pitting.—All the means recommended for this purpose consist either (1) in protecting the parts from the air; (2) in letting out the contents of the vesicles before the change from lymph to pus; or (3) in exciting common, in place of specific, inflammation.

1. To protect the skin from the air, and to give it support, equal parts of collodion and castor-oil may be painted over the face in males, and the face, neck, and arms in females.

2. Puncturing the full vesicles with a fine needle, and absorbing their contents with soft cotton, is an effectual method, but it is very tedious.

3. Nitrate of silver in substance, or in strong solution. Tincture of iodine may be applied to the pustules with advantage.

VACCINA.—COW-POX, VACCINATION.

Synonyms.—Vacciola, vaccinia, kine-pox, vaccine disease.

Vaccination.—*Mode of performing the operation.*—Having charged the point of the lancet with recent lymph, that contained in tubes, or with the moistened lymph preserved on glass or points, pick up the skin over the insertion of the deltoid with the point of the instrument, and inclining it towards you, make a slight to and fro movement of the instrument, so as to insinuate the point underneath the skin obliquely, or almost flush with the surface, so as to avoid too free a puncture and any bleeding. After withdrawal of the lancet, only a scarcely perceptible red point should be apparent. To ensure success a little more lymph may be rubbed in with the flat edge of the lancet, or a slightly moistened point may be inserted into the puncture. Three such punctures should be made on either arm.

DESCRIPTION OF THE AREOLA.

When the operation is properly performed, the course of the eruption is somewhat as follows:—

Second day.—Small red points appear, which feel hard, but when viewed with a magnifier, are seen to be vesicular. *Third* or *fourth day.*—The spots larger and more perceptible. *Fifth day.*—Small pearly circular or oval vesicles corresponding to the punctures, and containing a minute quantity of transparent fluid. *Eighth day.*—The vesicle has its perfect form and full size, with depressed surface and raised margin. On the evening of this day the vesicle begins to be surrounded by a circular rosy areola, the skin for some distance round it is tense and painful, and there is slight febrile disturbance. *Ninth* and *tenth days.*—The areola enlarges, and is often accompanied by extensive erythema of the arm, and sometimes by a lichenous eruption over the whole body. *Eleventh day.*—By this time, the vesicle, if it have not been opened, has burst, the areola has begun to fade, the centre of the vesicle is covered with a brown scab, which hardens and blackens, and about the *twentieth* day falls off, leaving a deep indentation of a circular form, with as many pits as there were cells, and proportioned in size to the previous inflammation. Unless all these appearances follow the operation, the vaccine disease has been imperfectly communicated, and re-vaccination is absolutely necessary.

Precautions.—The best time for taking the lymph is from the fifth to the eighth day; after this it cannot be depended on. The disease will not be properly communicated if there be any other severe malady present; or if the vesicle be disturbed by friction. Boils, pustules, and leprous and impetiginous eruptions may succeed the vaccine disease; but seldom if the child's health is good at the time. Such eruptions are readily cured by mercurial alteratives and gentle aperients.

In years of epidemic small-pox, vaccination, in some cases, and especially in adults, gives rise to severe local and constitutional effects, consisting perhaps of successive crops of painful boils.

Infants may be vaccinated at any time after the sixth week. The age of three months is to be preferred, if the child be healthy.

Re-vaccination may be assumed to be unnecessary in a person who can show three well marked excavated scars. But as it may be very generally practised without inconvenience, it is well to resort to it when small-pox is epidemic.

The best argument for re-vaccination is the result of that operation in the Prussian army. In the year 1841 nearly 45,000 soldiers were re-vaccinated, and though, before that time, varioloid disease was very prevalent in the barracks, only eight cases occurred afterwards.

As it is most important that the amount of protection afforded by vaccination should be understood, the following tables are given:—

EPIDEMIC IN SCOTLAND, 1818-1819.—(DR. JOHN THOMPSON.)

	Unprotected.	Small-pox Second time.	Small-pox after Vaccination.
Cases	205	71	310
Deaths	50	3	1
Proportion	1 in 4	1 in 24	1 in 310

The following table, reduced to a uniform scale of 15,000, is founded on the facts recorded by M. Favart during the small-pox epidemic at Marseilles in 1828. The estimated population under thirty years was 40,000, of whom 30,000 had been vaccinated, 2,000 had had casual small-pox, or small-pox by inoculation, and 8,000 were unprotected.

MARSEILLES.—EPIDEMIC OF 1828.—(M. FAVART.)

	Unprotected.	Previous Small-pox or Inoculated.	Vaccinated.
Estimated number	15,000	15,000	15,000
Attacked	7,500	150	2,000
Died	1,875	30	10
Proportion attacked	1 in 2	1 in 100	1 in 15
Deaths to attacks	1 in 4	1 in 5	1 in 100

In the Small-pox Hospital, during the 11 years 1841-1851, there were 4,091 admissions with small-pox, distributed as follows:—

	Patients.	Deaths.	Mortality per cent.
Not alleging any protection	1,722	629	37
Alleging prior small-pox	36	6	17
„ vaccination, but no scars	166	56	34
„ vaccination, and scars	2,167	147	7

The plain inference from the facts is, that vaccination, though a less complete protection against attacks of small pox than a previous attack, or inoculation, is the best known protection against a fatal attack.

VARICELLA.—THE CHICKEN-POX.

SYNONYMS.—Swine-pox, Bastard-pox, Gland-pox, Crystalli.

DEFINITION.—A contagious and infectious disease ushered in by slight febrile symptoms, followed by a vesicular eruption which generally runs its course in five days.

SYMPTOMS.—Within twenty-four hours after slight symptoms of fever, such as lassitude, loss of sleep, wandering pains, and loss of appetite, a rash appears, consisting of small reddish pimples, resembling the first appearance of small-pox, first on the back. By the *second* day, the red pimples have become small vesicles, containing a faint yellow fluid, transparent or colourless. On the *third*, the vesicles arrive at maturity. Soon after, the tender vesicles burst, or are ruptured, or they collapse and dry; in either case, a thin yellow or dark brown scab is formed. Pus is never formed, as in variola. Generally before the *fifth* day the eruption disappears, leaving behind it no cicatrix or mark.

CAUSE. — *Predisposing.* Infancy and childhood. — *Exciting.* Contagion.

DIAGNOSIS.—*From variola.*—By the slight fever; the short interval (twenty-four hours) between the first symptoms and the appearance of the rash; by the pimples first appearing on the back; by the form of the eruption, which is never pustular nor depressed; by the separation of the scaly scabs about the fifth day, when the eruption in variola is only just completed. From *modified small-pox* by the entire absence of pits.

PROGNOSIS.—Highly favourable.

LAWS OF INFECTION.—The infection less powerful than that of the other febrile exanthemata, the infecting distance probably small, and second attacks rare. The latent period considerable.

TREATMENT.—Medicine is rarely needed. Gentle saline aperients with small doses of tartar-emetic may be prescribed, if the fever exceed its usual moderate standard. The treatment to be terminated by a warm bath.

RUBEOLA.—THE MEASLES.

SYNONYM.—Morbilli.

DEFINITION.—A continued contagious and infectious fever, commencing with catarrhal symptoms, and followed, about the fourth day, by a peculiar eruption of the skin.

Varieties.—1. Rubeola vulgaris. 2. Rubeola maligna. 3. Rubeola sine catarrho.

1. Rubeola Vulgaris.

Synonyms.—Morbilli vulgaris; Morbilli mitiores.

Symptoms.—The first symptoms are those of catarrh. After rigors and flushes, lassitude, heaviness, pain in the head, and drowsiness, there are ringing cough, hoarseness, difficulty of breathing, frequent sneezing, itching of the face, smarting of the eyes, and swelling of the eyelids, with copious secretion of watery fluid from the eyes and nostrils; nausea or vomiting, thirst, furred tongue, frequent pulse, and the general symptoms of fever. On the *fourth*, but sometimes as early as the third, or as late as the fifth day, small red circular spots, resembling flea-bites, appear, first on the face, neck, and arms, then on the trunk, and afterwards on the legs. The three crops of the eruption are usually separated by an interval of twenty-four hours. The spots are generally in crescentic clusters, of a deep red colour, do not rise into visible pimples, but are found by the touch to project slightly above the surface. Sometimes, however, the spots are distinctly papular, and, at the height of the rash, vesicular. About the *eighth* day, but sometimes as early as the *fifth* or *sixth*, the colour of the rash begins to fade; first upon the face, neck, and arms, then upon the trunk, and lastly on the legs; and in another day or two the eruption entirely disappears, with a mealy or furfuraceous desquamation of the cuticle. At this period diarrhœa sometimes sets in. The fever and catarrhal symptoms subside at the same time, and the expectoration changes from a transparent mucus to an opaque yellowish-white sputum.

The catarrhal and febrile symptoms sometimes subside when the rash appears; but in most cases they increase, the cough becoming more troublesome, and the breathing short, frequent and wheezy. The stethoscope reveals bronchitis more or less extensive, and sometimes pneumonia.

The usual duration of the disease is from nine to twelve days. The convalescence is often tedious.

2. Rubeola Maligna.

Synonyms.—Morbilli nigri; Morbilli graviores.

In this form the first symptoms are more severe, and the disease soon assumes the typhous character. The eruption appears early, but irregularly, alternately receding and re-appearing. It assumes a dark or livid hue (*rubeola nigra*), and is often interspersed with petechiæ. The fauces are of a dusky red or claret colour. There is great tenderness in the abdomen, with dark offensive stools; croup and severe pneumonia supervene with delirium; and the patient dies asphyxiated, exhausted by diarrhœa, or comatose.

3. Rubeola sine Catarrho.

The primary fever and eruption in a few cases occur in a mild *form*, without catarrhal symptoms. On the other hand, a fever, resembling in character and duration that of measles, may take place with catarrhal symptoms, but without the rash.

CAUSE.—*Predisposing.* Infancy and childhood; but the disease may occur at any age. The winter and spring seasons.—*Exciting.* A specific contagion.

MORTALITY.—This varies from 1 in 3 to 1 in 40, the average being 1 in 15. Annual fluctuations considerable; *e.g.*, 1,122 deaths in London in a million inhabitants in 1845, and only 249 in 1852.

LAWS OF INFECTION.—Spreads by fomites and through the air; and may be communicated by blood from the arm, or by serum from vesicles. It very rarely occurs a second time. The period of incubation is probably from 6 to 16 days; and it is also probable that the disease may be communicated during the primary fever.

DIAGNOSIS.—From *Scarlatina*, by the darker hue of the rash, the crescentic arrangement of the patches, and its appearance, as a rule, on or about the fourth, instead of the second day. Also by the marked catarrhal symptoms, and absence of severe throat affection; by its shorter course, and less fatal character. From *Roseola*, by the catarrhal symptoms; and greater severity of the fever. From *Typhus*, see p. 290.

PROGNOSIS.—Favourable, excepting in the malignant form.—*Favourable.* The febrile and other symptoms slight; moderate diarrhœa; epistaxis; early and free expectoration; a moist skin when the eruption appears.—*Unfavourable.* A high degree of fever; hot and dry skin; hurried and difficult breathing; flushed countenance. The fever increasing after the appearance of the rash, and assuming the hectic, or typhous form; great pain in the head and eyes; shooting pains in the chest; symptoms of pneumonia or croup; convulsions; a rapid and small pulse; co-existence with whooping-cough; delirium, or coma; continued diarrhœa or vomiting; a livid hue of skin.

SEQUELÆ.—Pneumonia, œdema of the lungs, pleurisy, croup, bronchitis, phthisis; diarrhœa; enlargement of the mesenteric glands; ophthalmia; abscesses in the ear; swelling and suppuration of the parotid, sub-maxillary or cervical glands; aphthæ and gangrene of the mucous membrane of the mouth; whooping-cough.

MORBID ANATOMY.—Marks of inflammation in the internal organs, especially the air-passages and lungs.

TREATMENT.—*Indications.*—I. To diminish inflammatory action. II. To relieve urgent symptoms.

(I.) The temperature of the sick-room should be maintained at about 70° Fahr. and kept free from draughts of cold air; the diet should consist of thin gruel, milk and water, or beef-tea containing a little bread or vermicelli.

Perspiration should be encouraged, and bronchial or pneumonic irritation alleviated by the application of large hot light bread poultices, with or without a little mustard, to the throat and chest.

The bowels should be freely relieved by an active purgative, such as from gr. xv to gr. xl of compound jalap powder.

When the febrile symptoms run high, and especially when local inflammation threatens, tartar-emetic must be given in nauseating doses at short intervals.

(II.) In milder cases saline refrigerants and diaphoretics in combination with squill or ipecacuanha (Form. 222) will suffice.

Lemonade, linseed-tea, a decoction of figs in milk, or barley-water, should be liberally supplied, as they are grateful to the inflamed mucous membrane. Inhalations of steam may be used with advantage.

If need be, we must administer a combination of henbane and opium to counteract restlessness and encourage sleep (Form. 80).

To relieve heat, and dryness of the skin, a warm bath is indicated.

Pneumonia, diarrhœa, whooping cough, or other complication, must be treated according to the urgency of the symptoms.

The malignant form must be treated as low fever (see *Typhus*), with special reference to the bronchial affection.

When the eruption disappears before the proper time, and convulsions, great anxiety, or delirium take place, sinapisms or blisters must be applied to the chest and feet, ammonia, camphor, æther, and hot wine and water being given freely and at short intervals.

During convalescence, the diet should be nutritious, the bowels regulated, and the dress warm. Great care should be taken to avoid exposure to cold, and to drafts of cold air.

PROPHYLAXIS.—The same precautions are required as in the case of other contagious maladies. Inoculation with blood taken from the patches, with the serum of the vesicles, when the eruption is vesicular, or with the secretion of the conjunctiva, has been practised with some advantage. The cases which have followed inoculation have been of a mild type.

SCARLATINA.—SCARLET FEVER.

DEFINITION.—A continued contagious and infectious fever, with inflammation of the fauces, and a scarlet rash on the skin, setting in on or about the second day, and terminating in desquamation.

SPECIES.—1. Scarlatina simplex. 2. Scarlatina anginosa. 3. Scarlatina maligna. 4. Scarlatina sine eruptione.

1. SCARLATINA SIMPLEX.

SYMPTOMS.—This form is characterized by the slight affection of the throat. It sets in with the usual symptoms of fever—cold chills, shivering, nausea, and sometimes vomiting, with pain in the head, back, and limbs, thirst, hot skin, frequent pulse, restlessness, and sleeplessness. On the *second* day, in most cases a bright scarlet efflorescence shows itself on the face, neck, and arms, extending over the trunk and limbs. At first it consists of innumerable red points, which soon coalesce, and in a few hours the redness becomes universal, being peculiarly distinct at the bends of the joints, on the chest and abdomen, the hips and loins. The colour disappears on pressure, but immediately returns. After *one* or *two* days, the efflorescence again becomes partial, is arranged in large irregular patches, and does not disappear on pressure. The skin is rough to the touch, and in some cases studded with small miliary vesicles. The rash generally begins to decline on the *fifth*, is very indistinct on the *sixth*, and wholly disappears by the *eighth* day. Desquamation generally begins on the parts first affected about the end of the *fifth* day, and soon extends to the entire body. The cuticle separates as a scurf from the trunk and limbs, and in large scales from the hands and feet. This is often accompanied by great itching, irritation, and tenderness.

The rash is preceded or accompanied by a sore throat, and some difficulty of swallowing; and, on inspection, the tonsils are found slightly enlarged and inflamed, and coated with a white tenacious mucus. The eyelids, lips, edges of tongue, soft palate, pharynx and nostrils are also inflamed. The papillæ of the tongue are elongated, and project as bright-red points through the white mucous covering; or the whole tongue is bright-red with prominent papillæ. In the first case it resembles a white strawberry; in the second a red one.

The fever does not abate on the appearance of the rash, but subsides with it, leaving the patient, in most cases, very weak. The pulse is generally very frequent (120 or 130), and the skin very hot (105°, 106°, and even 112° Fahr.), and there is usually some increase of fever at night, with slight delirium, even in favourable cases. The bowels are frequently confined; nausea and vomiting are not uncommon; and the urine is often scanty and high-coloured, and, in the decline of the disease, generally contains albumin.

Although the eruption in scarlet fever usually occurs on the second day, there are many exceptions to the rule. On the one hand, the rash may appear much earlier than the second day, as in a lad of sixteen, who first felt ill at five o'clock in the evening, and had the eruption full out upon him before midnight. On the other hand, during the prevalence of scarlet fever, many mild cases occur in which there is slight sore throat, and a suspicious appearance of tongue, with little disturbance of health for three, four, or five days, at the end of which time the rash makes its appearance. These cases present some difficulty; but however slight the other symptoms may be, there is always during this latent period a very frequent, full, and peculiarly compressible pulse. Whenever this pulse exists, some febrile disease (and scarlatina, if rife at the time) may be confidently looked for. (G.)

2. Scarlatina Anginosa.

Symptoms.—Those of scarlatina simplex, in an aggravated form, with a more severe affection of the throat and parts adjacent.

The submaxillary glands are enlarged and painful to the touch; the soft palate, uvula, tonsils, and pharynx, as far as the eye can reach, are of a florid red colour, the tonsils and soft palate much swollen, and the uvula enlarged and lengthened. A thick mucus collects at the back of the throat, and proves very troublesome to the patient, and specks are often observed resembling the slough in cynanche maligna; yet ulceration is rare, and when it does occur, superficial. Smooth yellow patches of fibrinous exsudation frequently form over the inflamed, excoriated, or ulcerated tonsils or pillars of the fauces, in all respects resembling that of diphtheria. The mouth is opened with difficulty, there is great pain in swallowing, and liquids often return through the nostrils. The tongue is very red, and its papillæ very prominent. The inflammation may extend to the mucous membrane of the nose, and through the Eustachian tube to the ears, causing a thin purulent discharge from those parts; the skin is of a deeper colour, and the eruption spreads more rapidly.

Often, after a few days' amendment, an unaccountable languor and debility supervene; the pulse is quickened; the sleep disturbed; the appetite lost; the secretion of urine nearly suppressed; and dropsical effusions take place into the limbs, abdomen, or chest, or in several parts at the same time.

3. Scarlatina Maligna.

Symptoms.—The tonsils, though less swollen than in scarlatina anginosa, are redder, and soon become the seat of rapid, extensive, and deep ulcers, interspersed with grey sloughs, which are detached slowly, leaving ragged sores, which heal with difficulty. Ashy ulcers also form on the interior of the cheek. The inflammation, extending into the nostrils, causes a thin acrid discharge, which inflames and excoriates the lip and chin, and the salivary glands are much swollen and inflamed. The eruption appears late, in irregular patches of a paler colour, which sometimes disappear suddenly. The other symptoms resemble those of typhus.

4. Scarlatina sine Eruptione, or S. Latens.

Sometimes the disease assumes so mild a form as to escape detection till some sequela, such as general anasarca, shows that the slight indisposition, "a feverish cold," was an attack of scarlatina. We must be careful not to overlook such cases; as want of proper nursing and precautions may entail consequences as bad as those of a severe form of the disease.

It is not uncommon for those who have had scarlet fever in its usual form, when again exposed to the contagion, to have the characteristic sore throat succeeding the usual premonitory symptoms, but no eruption. Desquamation of the cuticle, however, occurs in some of these cases, when no distinct rash has appeared on the skin. Such persons may communicate the common form of the disease.

Duration of Scarlet Fever.—In ordinary cases the first stage (from the commencement to the appearance of the rash) occupies twenty-four, forty-eight, or seventy-two hours; the second stage (from the appearance of the rash to its subsidence) from six to eight days, and the third stage (from the disappearance of the rash till recovery) from a few days to two or three weeks. Entire duration, from eight days to thirty days, or more.

Sequelæ.—Acute desquamative nephritis, with anasarca, and occasionally with other dropsical affections, such as ascites, hydrothorax, hydrocephalus, and hydropericardium—these often follow the mildest attacks. Acute rheumatism, with endo- and pericarditis. The other sequelæ show themselves mostly after attacks of scarlatina anginosa or maligna. They are the following:—Pain and swelling of the larger joints, with formation of serum, or pus; discharge from the nostrils; discharge from the ears, and permanent deafness; suppuration of the glands of the neck; troublesome ulcers of the tongue, pharynx, or epiglottis; croup; iritis and conjunctivitis; inflammatory affections of the internal viscera or of their serous coverings; abscess of the testis; mortification of the face, lower extremities, and pudenda; also of portions of the integuments on which the patient has lain; troublesome diarrhœa. Abscess of the brain is a remote result of cases of scarlatina that have been followed by pain and suppuration of the ear. The membrana tympani and small bones of the ear are destroyed, suppuration is set up in the cells of the petrous bone, followed by necrosis; and the neighbouring veins may become implicated and lead to purulent deposits in the brain, indicated by intolerable pain in the corresponding part of the head, quickly followed by coma, preceded or not by convulsions.

Terminations.—In complete recovery. In recovery after one or more of the foregoing sequelæ. In imperfect recovery, the patient suffering from one of these sequelæ. In profound coma on the first appearance of the rash, followed by death in twenty-four hours, as if from the effects of a strong narcotic poison; in violent delirium during the first five days of the fever. In death, on the first, second, or third day, with incessant vomiting, or diarrhœa, or both. In death later in the disease from exhaustion, or as a consequence of any of the sequelæ.

Morbid Anatomy.—Death in the early stage usually occurs from failure of the heart's action, and the cause of this is found to be the formation of large fibrinous clots in the right side of the heart, and the large vessels connected with it, their ramification often extending to the brain and remote parts of the lungs. The other post-mortem appearances are those of the first stage of enteric fever—viz., inflammatory swelling of the agminate and solitary glands of the intestines, the mesenteric glands, and the spleen; and a deteriorated condition of the bile, the solid matter being reduced to $\frac{1}{3}$ or *even* $\frac{1}{10}$ *of the normal* amount, the biliary acids usually existing *as a mere trace; in* some cases there is a total absence of bile

("Med.-Chir. Trans." vol. lv. p. 121). Besides the above, we shall find ulceration and purulent collections in the tonsils, with inflammation extending from the fauces through the œsophagus, and sometimes through the whole alimentary canal. Congestion or inflammation of the kidneys. Inflammation and swelling of the joints. If the patient die from delirium and coma, great congestion of the vessels of the brain.

PATHOLOGY.—The disease is essentially an inflammatory affection of the lymphatic system; resulting no doubt in imperfect sanguification, and that deteriorated condition of the blood which leads to internal congestions and the separation of fibrinous clots.

CAUSES.—*Predisposing.* Bad food and water.—*Exciting.* A specific poison (?).

MORTALITY.—The deaths in London in a million of the population vary from 350 to 2130, and average 900. The fluctuations from year to year are considerable, and *the rate of mortality* in different years has varied in the following proportions: 1, 2, 3, 6, 10, 16, and 25 per cent.

LAWS OF INFECTION.—The disease is supposed to spread by contagion; it rarely attacks the same person more than once, but may occur a second and even a third time; and it may be communicated by inoculation of the contents of the vesicles which are sometimes blended with the rash; it is thought to be communicable before the appearance of the rash, and for as much as three weeks after its disappearance. It prevails constantly. In some cases, reported by Dr. Ballard, the disease was communicated by milk, tainted by the hands of the milkers.

PERIOD OF INCUBATION.—From a few hours, or two or three days, to ten days or a fortnight. It is sometimes stated to be five days.

DIAGNOSIS.—Scarlatina may co-exist with *Enteric fever* (see p. 298). *From measles* it is distinguished by the absence of cough, sneezing, and coryza; by the affection of the throat; by the peculiar appearance of the tongue; by the brighter hue, greater extent, and less-defined form of the rash, which occurs in most cases on the second instead of the fourth day. The greater frequency of the pulse and the high temperature of the skin are also highly characteristic of scarlet fever, as are secondary dropsy, affections of the joints, and mortifications. From most cutaneous disorders by the extent of the eruption, the sore throat, and the fever. A supposed hybrid of scarlet fever and measles has been described under the term *Rötheln.* It is scarlatina *plus* cough, hoarseness, and lachrymation (symptoms of measles) due to the presence of the eruption on the mucous membranes. The rash on the skin is usually excessive in this form of the disease, and forms patches, and desquamation is usually very free.

Some cases of scarlatina which lapse into profound coma may be mistaken for narcotic poisoning, but the skin in such cases is *usually as* red as, or redder than, a boiled lobster.

For the distinction between Scarlatina and Diphtheria, see Diphtheria.

Prognosis.—*Favourable symptoms.* The concomitant fever purely inflammatory, and the throat affection slight; abatement of the fever, and of the throat affection, on the appearance of the rash; epistaxis; diarrhœa; or other critical discharge. [In one case, I have known all the threatening symptoms to pass away, after a profuse discharge of mucus from the nostrils.] (G.) *Unfavourable symptoms.* Early nausea and vomiting; the fauces dark red or purple, without swelling; ash-coloured or brown specks, quickly passing into ulceration or gangrene (*cynanche maligna*); brown tongue; great prostration of strength; early occurrence of delirium; coma; high fever after the occurrence of desquamation; dyspnœa, and stridulous voice, indicating the extension of the disease to the larynx and trachea; acute pain in the ear, with deafness and purulent discharge; acrid discharge from the nose; obstinate dryness of the skin; a fresh efflorescence and increase of fever; sudden disappearance of the rash. The pregnant, and especially the puerperal state, and teething.

A favourable convalescence may be expected when the pulse falls much below its natural frequency; and especially when the pulse at night is less frequent than in the morning. A frequent pulse, continuing when the urgent symptoms have subsided, is good ground for anticipating a lingering convalescence or secondary symptoms. (G.)

Treatment.—A moderate and equable temperature, about 60° Fahr.; a clean and spacious apartment; a light vegetable diet; cooling acidulated liquors for drink, and the saline draught as medicine; gentle aperients, especially towards the decline of the eruption. It is well to begin the treatment with an emetic (Form. 201), followed by a saline aperient, or full dose of castor-oil.

When there is much heat of body and dry skin, the patient should be immersed for ten minutes in a warm bath, and treated with saline diaphoretics.

When there is severe inflammation of the throat with external tenderness, and great difficulty in swallowing, from six to twelve leeches may be applied to the angle of the jaw, followed by a large hot poultice. In milder cases a linseed poultice, containing ⅛ part of mustard will suffice. Solution of nitrate of silver (gr v to ʒi) should be applied to the inflamed fauces twice a day. Astringent gargles (Form. 184) are very useful, and if the breath be offensive a little carbolic acid may be added. The following is a very useful form: Dissolve ʒii of chlorate of potash in an ounce of water, add ʒss of hydrochloric acid, and then water to ℥vi. This gargle may be swallowed. As soon as the patient's strength begins to fail, 4 or 6 ozs. of wine should be given daily.

When the patient is convalescent, tonics, of which quinine is the best, and a nutritious diet with wine, in moderate quantity, should be prescribed. For a full fortnight after desquamation the patient should be kept warm in the house, unless the weather is exceptionally mild. A sudden chill arrests the action of the skin and leads to congestion of the kidneys. About the time when desquamation sets in, a little albumen is generally contained in the urine, and disappears after a day or two. If it persist and increase, we must resort to the hot bath, and keep the patient in bed, Scarlatina, which at any part of its course assumes the typhous character, is highly dangerous, and requires the employment of stimulants in full and repeated doses, as recommended in typhus fever. When the throat is covered with sloughs, the stimulating and disinfecting gargles, and strong solution of nitrate of silver, must be used at short intervals.

Prophylaxis.—The same precautions are required to prevent this disease from spreading as are recommended in typhus fever. (See p. 290; also "Nursing," p. 248.)

DIPHTHERITIS.—DIPHTHERIA.

Definition.—A contagious and infectious disease, attended by inflammation of the commencement of the alimentary and respiratory passages, with fibrinous exsudation.

Symptoms.—The disease is most insidious in its attack, and may be fully developed when the patient is still unconscious of any affection of the throat. But generally, there is a little stiffness of the neck, soreness of the throat, and slight difficulty of deglutition; and on inquiry, we learn that the patient has been feeling weak and a little out of sorts for two or three days. Sometimes there is considerable constitutional disorder, indicated by chills, nausea, and diarrhœa, with weakness, and loss of spirits. The state of the skin and pulse varies in different cases. On examining the back of the mouth, the isthmus of the fauces and tonsils is seen to be swollen and of a dark claret colour, and in from twelve to forty-eight hours from the commencement of the throat affection, a smooth, tough layer of lymph, resembling wet felt or wash-leather, is formed over part of the inflamed surface. Sometimes the exsudation appears first on the tonsil, whence it spreads to other parts; or the soft palate is the starting-point. But it may first show itself on the mucous membrane contiguous to these parts. Occasionally the exsudation appears simultaneously at several points. From the points where it first appears it may spread down the œsophagus into the stomach, or, worse still, down the larynx, and along the trachea into the bronchial tubes. In about three days the whole inflamed surface is covered with a thick layer of lymph. If there be open ulcers on the skin, they are liable to be coated in a similar manner. The exsudation is tough and fibrinous, rarely soft and pulpy; detached with some difficulty, and then exposing a smooth bleeding surface, on which the exsudation re-forms in a few hours. The attack on the larynx is revealed by the voice, which is husky, or reduced to a whisper. The breathing may suddenly become croupy or stridulous, the face livid, the eyes prominent, the conjunctiva injected, and the supra-sternal and the supra-clavicular depressions sucked inwards in inspiration; and within a few hours the patient may die suffocated.

In proportion to the extent of the pharyngeal disease there is pain and difficulty in swallowing. In a later stage there is no pain. The parts have lost their sensibility.

The discharge from the nostrils consists of a thin muco-purulent matter like that which occurs in bad forms of scarlatina, so offensive that the whole atmosphere of the room is tainted by it; and the breath has the same putrid odour.

In such grave cases prostration rapidly comes on, and the patient lies on his back apathetic, or insensible and muttering. The heart's action, which had been feeble, though excited, now fails. The face is pallid, the pulse scarcely perceptible, and the patient dies of asthenia.

In many cases the urine is loaded with albumen.

The *duration of the disease* varies from forty-eight hours to fourteen days. Laryngeal symptoms usually show themselves early; and, if sudden, the patient dies within a week. In the absence of laryngeal symptoms, death from asthenia usually occurs during the second week.

Convalescence commences in the second week; but may be deferred to the beginning of the third.

SEQUELÆ.—These are of a very marked and important character. The most serious consists in great feebleness of the heart's action. When the patient is convalescent, and all things seem to be going on well, the heart may be losing force. Stimulants may be freely given, and yet the pulse becomes slower day by day, until it is reduced to half its normal number, and, the patient growing weaker and weaker, quietly expires.

Sometimes the whole muscular system is affected. The muscles become too weak to support the body or move the limbs; the patient cannot use his fingers to button his clothes or write a letter. This is not paralysis properly so-called; but is excessive depression of nerve force.

More frequently the debility affects only the muscles of deglutition and vocalisation; the fauces appear to have lost their sensibility; solids can be swallowed, but fluids return through the nose. The voice is weak, hoarse, and nasal. In rarer cases the special senses are affected, and there is blindness or deafness on one or both sides. Disordered sensation, such as tingling in the hands or feet, occasionally occurs. Paralysis of sensation in restricted areas may occur.

These symptoms of disordered innervation may set in at any time, even up to six weeks after convalescence.

CAUSES.—*Predisposing.* Debility. Childhood and youth; very rare in old persons.—*Exciting.* A poison, probably specific, generated within the body or external to it; and spreading by contagion and infection. It is epidemic at long intervals of time.

MORBID ANATOMY.—*Fibrinous, or fibrino-cellular exudations covering the mucous membrane* of the larynx, the upper portion of the whole of the trachea, and in some cases the bronchial tubes of their second or third ramifications. 2. The œsophagus and parts of the stomach reddened and inflamed, or covered with exsudation. The inflamed mucous membrane and submucous tissue thick and hard; sometimes ulcerated; the soft palate and tonsils may be gangrenous. Abscesses in the cellular tissue surrounding the tonsils and pharynx. The cervical glands enlarged and hard, and the areolar tissue infiltrated with serum. 3. In death from asthenia, large fibrinous coagula in the heart or great vessels.

Diagnosis.—From *Quinsy* by not being limited to the tonsils, and by the fibrinous exsudation. In *common sore throat* there is no exsudation, but a tendency to ulceration. *Croup* is the laryngeal part of the disease. Malignant *scarlatina* and diphtheria have so many resemblances, and so few differences, that satisfactory evidence of their being distinct diseases is wanting. The strongest argument in favour of their being distinct, is the fact that the one affords no protection against the other.

Prognosis.—Must be cautious and guarded, especially in the early stage. If, at the end of a week, there are no laryngeal symptoms, our prognosis may be favourable. A robust patient will be less liable to secondary nervous affections than one of weakly habit.

Treatment.—*Constitutional.* A sustaining and stimulant plan will have to be adopted from the first. If the pulse be feeble, ammonia and bark should be given every four hours, and half a pint of wine or brandy and water beaten up with egg, may be given every day: milk or beef-tea being administered in the intervals.

If the skin be hot, we should give diaphoretics; if cool and clammy, ♏xx–xxx of tincture of perchloride of iron in a wine-glassful of water, or a moderate dose of quinine and acid, may be given thrice a day. Daily action of the bowels should be induced by saline aperients (Forms. 242 and 244).

Local.—Hot bread-and-mustard poultices to the throat. The application by a small sponge or camel-hair brush of a strong solution (gr. xl to ℥i) of nitrate of silver to the inflamed fauces night and morning; or solid nitrate of silver may be passed lightly over the parts. The acid chlorine gargle (Form. 63), or perchloride of iron (ʒvi of the tincture to ℥viii of water), may be used if the act of gargling does not distress the patient. Laryngeal symptoms are much relieved by inhalations of hot water, or of a mixture of vinegar and water. A leech may be placed at once over either side of the cricoid cartilage. If the exsudation seems loosely attached to the mucous membrane of the larynx, we may give an emetic of sulphate of zinc. If suffocation be imminent, we must resort to tracheotomy: it may prolong life in many cases, and save it in a few. If the exsudation affect the lower part of the trachea, the operation will act only as a palliative.

Depression of vital power must be combated on the broad principle that stimulants are tonics to the weak.

PESTIS.—PLAGUE.

Definition.—A contagious fever, intermittent, remittent, or continued, accompanied by buboes, carbuncles, and petechiæ.

Symptoms.—The patient is attacked suddenly, or after slight premonitory rigors, with lassitude, depression and restlessness, dull pain of head, and giddiness, with an indescribable feeling of anxiety, and pain in the region of the heart. The eye is dull and sleepy, the eyelids closed, the mouth half open; and the gait staggering and uncertain, like that of a drunken man. There is nausea, or bilious vomiting, often accompanied by diarrhœa; the urine is scanty, high-coloured, and sometimes bloody; the tongue is swollen, furred, and glistening, but moist and clean towards the tip and edges; pulse from 115 to 130, and very feeble; respiration hurried; speech indistinct and faltering. After twelve hours, there is usually some reaction, with insomnia and delirium; the eye is bright, and the pupil dilated. The pulse is hard and full, or weak, fluttering, and intermittent; the tongue dry, red in the centre and at the edges, brown and cracked; the lips, teeth, and nostrils are coated with dry sordes; there is intense thirst, and constant nausea, with occasional vomiting of a black fluid; the evacuations from the bowels are dark and offensive, mixed with grumous blood; and sometimes there is hæmorrhage, perhaps from the nose. On the second or third day, sometimes much later, and sometimes as early as the first day, the characteristic external marks of the disease begin to show themselves. Darting pains in the axillæ, groins, or neck, direct attention to the glandular swellings and carbuncles, which, in favourable cases, are bright red: in dangerous ones, livid or purple.

The crisis is by profuse perspiration and suppuration of the tumours, the patient beginning to improve from the sixth or eighth to the fourteenth or twentieth day. In unfavourable cases, the skin remains harsh and dry; the pulse small and fluttering; low muttering delirium and laborious breathing set in; the eye is sunk, the countenance ghastly; the skin covered with petechiæ and vibices; while the buboes remain stationary. At length the patient becomes comatose, and death takes place, commonly on the fourth or fifth day, without a struggle.

In the mildest cases the patient goes about his usual avocations, though suffering from the swollen glands. In the worst cases, the patient does not rally from the first shock to the nervous system, but sinks within twenty-four hours, or as late as the second or third day, with buboes.

The plague may be said to assume four degrees of severity: 1. Slight fever, without delirium, or buboes. 2. Fever, delirium, and buboes. 3. Fever, delirium or coma, buboes, carbuncles, and petechiæ. 4. Congestive fever, fatal on the first, second, or third day, without buboes. The fever may be intermittent, remittent, or continued; the last-named form being most common.

CAUSES.—*Predisposing*. Poverty, filth, overcrowding, debility, disease, intemperance, adult age.—*Exciting*. Probably the same as enteric fever.

LAWS OF INFECTION.—Period of incubation, from a few hours to about twenty days. The disease is endemic in Egypt, often spreads to surrounding countries, and formerly prevailed in almost every part of Europe. An analogous disease is believed to exist in some parts of India. In common with other epidemics, plague attacks few persons at first, gradually attains its maximum intensity, and subsides as gradually. The rate of mortality is also greatest at the commencement of the epidemic, and at its first outbreak in each district.

MORTALITY.—At first, nine-tenths of the cases, or more; in the decline, a small proportion only. Throughout an epidemic, from one-third to two-thirds, or even four-fifths, of those attacked. In large cities, a third, or nearly a half of the population is believed to have perished. In Smyrna, during five months of 1834, out of 5,727 persons attacked, 4,831, or 84 per cent. died. 1 in 23 of the whole population suffered, and the deaths were about 1 in 27.

PROGNOSIS.—Highly unfavourable, especially at the outbreak of the disease: guarded even in mild cases.—*Favourable symptoms*. The early formation of firm and movable buboes passing rapidly into suppuration; profuse perspiration; an absence of severe fever; life prolonged beyond eight days.—*Unfavourable*. Subsidence of the buboes; suppression of urine; hæmaturia; petechiæ; obstinate vomiting; and all the symptoms which would be deemed unfavourable in continued fever. The puerperal state.

TREATMENT.—That of typhus fever, with warm poultices to the buboes and carbuncles, to promote suppuration, followed by prompt incisions. Mercury has been recommended, and most of the cases in which salivation has taken place have recovered· but it is doubtful whether these have not been cases that would have got well under any treatment. The disease appears to be almost equally fatal under all modes of treatment.

PROPHYLAXIS.—Separation from the sick and an unusually strict observance of all the laws of health. The avoidance of impure food and water. In the case of ships from infected places, a quarantine of twenty-one days; and if there are cases of plague on board, twenty-one days from the recovery of the last case.*

---

* For a condensed account of the Plague as Hodges saw it in London in 1665, consult Dr. Guy's "Public Health," Lecture IV., and the Black Death, in Lecture II. Also Howard on "Lazarettos," and Sir James McGregor's "Medical Sketches of the Expedition to Egypt from India." For the state of the places in which the plague is bred and nursed, see Sir Robert Wilson's "Expedition to Egypt," especially note at p. 116.

CHAPTER V.

Febris Hectica	Hectic Fever.
Febris Infantum Remittens	Infantile Remittent Fever.
Pyæmia	Pyogonic Fever.
Febres Puerperales . . .	Puerperal Fevers.
Cellulitis Venenata . . .	Dissection-wounds.
Farcinoma	Glanders.
Pustula maligna	Malignant Pustule.

FEBRIS HECTICA.—HECTIC FEVER.

Definition.—A remittent fever, caused by local irritation in a weakened constitution.

Symptoms.—Chills, succeeded by flushes, terminating in a hot skin and frequent pulse, and these by perspiration constitute the paroxysm of hectic fever; of which there are commonly two in the twenty-four hours. The first generally occurs about noon, and lasts about four or five hours. After a short interval of freedom, a more severe paroxysm occurs, which increases in violence till about two o'clock in the morning, when a perspiration, at first partial and then general, breaks out and carries off the fever.

The pulse during the paroxysms is quick and frequent, ranging from 96 to 130, or more; the temperature 102° to 105° Fahr., or more; the urine is high-coloured, and deposits a pink sediment; the cheeks wear a circumscribed crimson blush—the hectic flush—and there is a burning heat in the palms of the hands and soles of the feet. During the remission, the pulse and temperature falls, but seldom to the level of health. There is little loss of appetite, and the tongue is clean, moist, and red. The patient rapidly loses flesh.

At length the paroxysms become more violent and the remissions shorter; the appetite fails; colliquative sweats alternate with diarrhæa; and under an increased severity of these symptoms, and of the disease which causes them, the patient sinks.

Diagnosis.—From idiopathic remittent fever by the pre-existence of local disease.

Prognosis.—Favourable or unfavourable according to the nature of the local disease, of which the fever is the effect and symptom.

Causes.—Generally the formation of pus, as in suppuration of the lungs, liver, hip-joint, &c. But any local irritation in a weakened constitution, without suppuration, may occasion it. The infantile fever, caused by intestinal irritation, is but a form of hectic. It is in advanced stages of consumption and in extensive suppuration of joints that hectic fever is developed in its most characteristic form.

Treatment.—That of the disease of which the fever is symptomatic. When the local cause is obscure, the treatment must be that of debility, and quinine will be the appropriate remedy.

FEBRIS INFANTUM REMITTENS.—INFANTILE REMITTENT FEVER.

Synonyms.—Infantile gastric remittent—infantile hectic. Worm, or mesenteric, stomach fever. Low fever of children. Marasmus.

Definition.—A fever due to gastro-intestinal irritation, from worms, retention of fæces, or other functional disorder of the digestive organs.

Symptoms.—Pallor, languor, drowsiness, and chilliness in the morning; flushed cheek, hot skin, restlessness and feverishness towards evening, followed at night by profuse sweating, and towards morning by a distinct remission. Skin dry; tongue moist, but coated; breath tainted, pulse frequent; appetite variable and capricious or absent; urine scanty; bowels costive or relaxed, or both alternately; the evacuations slimy and sour smelling, dark green, deep yellow, pitchy, or clay coloured, and very offensive; the abdomen tumid and often hot to the touch. The child constantly picks the nose and lips, and rubs the corners of the eyes, and the anus.

In milder cases, the remittent character of the fever is less strongly-marked; the chilliness and languor of the morning, and the febrile exacerbation of the evening being very indistinct; but the child looks pale and listless, and loses appetite. After a time symptoms of phthisis, tabes mesenterica, hydrocephalus, or enteric fever, show themselves with rapid loss of flesh, till at last the plump and rosy features of the child are changed to the meagre aspect of shrivelled old age. The more the child wastes, the more restless and irritable does it become till the last stage of debility arrives, when he dies from exhaustion, in a state of total unconsciousness, or with the mental faculties unimpaired to the last.

Morbid Appearances.—Inflammation and ulceration of the small intestines. Enlargement, induration, or suppuration of the mesenteric glands. Inflammation of the lungs. Congestion and inflammation of the brain with serous effusion.

Diagnosis.—Rose-coloured spots, a fissured tongue, loose ochre-coloured stools, or hæmorrhage, declare the presence of *enteric fever*. Coma, strabismus, and convulsions; distension of the veins of the scalp, prominence of the fontanelle, and heat of head, indicate *hydrocephalus* or *tubercular meningitis*. An enlarged and tense abdomen declares *tubercular peritonitis* or *tabes mesenterica*.

Cough, and hurried respiration and diarrhœa excite suspicion of *pulmonary and abdominal phthisis.*

Prognosis.—*Favourable* when due to worms, constipation, or other simple derangement of the alimentary canal.—*Unfavourable.* When complicated with the diseases specified above.

Causes.—*Predisposing.* Bad air, want of exercise, improper or deficient food, dentition.—*Exciting.* Irritation of the mucous membrane of the intestinal canal by worms, constipation, diarrhœa, or improper diet.

Treatment.—This consists in restoring the tone and natural action of the stomach and bowels by proper aperients and a restricted diet.

As long as vomiting or diarrhœa is present, milk, milk-grüel, arrowroot, or broth without any form of solid food, should be prescribed. In the absence of diarrhœa, rice-milk, bread and milk, puddings of rice, corn-flour, and bread. In infants a still stricter diet is often necessary. The stomach is often very irritable, and rejects even the simplest farinaceous food. In such cases a table-spoonful of new milk from the cow should be given every half-hour or hour, combined, if acidity be present, with a little lime-water or carbonate of soda. This treatment is very effectual. The stomach wants rest; and the patient wastes, because it is not allowed to rest; it rejects food in ordinary quantity, and will bear none in any quantity but that which is natural to it at that early age.

In this disease as in enteric fever, it is of the first importance to watch narrowly the state of the alvine secretions, both before and after the administration of medicines. *Scybala, mucous discharges,* and *worms* indicate the necessity of aperients, of which there is none better than castor-oil, aided, if necessary, by enemata of warm water.

If the motions are pale-coloured, a cholagogue aperient or mercurial alterative (Form. 257) should be given every, or every other, night; followed by an occasional dose of castor-oil in the morning. If worms are present, an anthelmintic (Form. 258) should be given.

Diarrhœa will generally yield in a short time to a diet of milk-gruel, without any kind of solid food, and then the aperient treatment should be resumed. As the health improves, the diet may become less strict. It is a grave error in this disease to prescribe the more solid forms of nourishing food.

PYÆMIA.

Synonyms.—Simple pyogenic fever (Jenner). Septicæmia (Vogel). Ichoræmia (Virchow). Purulent diathesis (Tessier). Suppurative phlebitis.

Definition.—Severe pyrexia, the result of an admixture of pus or sanies with the blood.

deep-seated pain,
derness in the muscles of the calf, in th
or in all these parts in succession. The
swelling and tenderness in the course of
and deep-seated fluctuations may be de
muscles of the leg and thigh. The feve
the patient very weak: or, as is more us
the typhous condition, ending in death b
infection spread from the head, severe m
pleuro-pneumonia generally appear at an
upper extremity, there are pain and swel
shoulder and of the fore or upper arm, of t
cular joints, accompanied by phlegmon
corresponding parts of the integument, an
fluctuation.

Sometimes the disease is general, and a
body become painful, tense and fluctuating
the lungs are partially consolidated by
But the disease may be limited to a hand
abscesses make their appearance.

Pathology.—If the exciting cause
abscesses form in the muscular cellular ti
themselves. The areolar tissue round the
leading from the seat of injury, becomes ha
coats of the veins themselves thickened (p
veins are obstructed with dark, firm coagula
following is an example:—A patient had
removed from the fifth metatarsal bone of th
afterwards symptoms of pyæmia appeared.
first day; meanwhile the

selves. 2. The absorption of pus or sanies from any suppurating surface. And as ulcers sometimes form on the inner surface of the heart and arteries, it follows that pus may be directly discharged from them into the blood.

As to the absorption of pus—this may take place directly, from the inflamed inner surface of the divided vein, the open extremity of which communicates with the suppurating surface, or, by the capillary action of its empty portion.

Diagnosis.—White blood cells and pus corpuscles resemble each other so closely that when white cells are found in unusual quantity in the blood, our only means of diagnosis are the conditions anterior to their formation. If the patient died of anæmia, with or without disease of the spleen or lymphatic glands, we attribute the white cells to leucæmia; if pyogenic fever have been present, to pyæmia.

Prognosis.—Very *unfavourable* when the disease comes on after amputation, child-birth, or infectious fever; *favourable* in proportion as the fever subsides, the internal organs escape, and the disease is limited to the limbs, or the muscles and integuments of the trunk.

Treatment.—*General.* That recommended for the last stage of typhus fever; we promote sleep and alleviate pain by full doses of opium. Quinine with acid may be given in large doses in the early stage.—*Local.* Leeches and cold affusions to the head if necessary; hot fomentations and poultices to inflamed places; free incisions wherever fluctuation can be detected.

FEBRES PUERPERALES.—PUERPERAL FEVERS.

Under this title several forms of disease have been described, differing in many respects, but all of them combining a well-marked febrile affection with a local disease varying in seat, character, and intensity. The following distinct forms are recognized:

1. Acute puerperal peritonitis.
2. Adynamic, or malignant puerperal fever.
3. Puerperal intestinal irritation.
4. False puerperal peritonitis.
5. Milk fever.

General Remarks on Puerperal Fever.

The diseases usually characterized as Puerperal Fever are the first two of this group—*acute puerperal peritonitis* and *adynamic* or *malignant puerperal fever*. Both these have been observed in different epidemics; and cases of both forms in the same epidemic. These two forms, and all their varieties, have their origin in the same cause, *uterine phlebitis*, the result probably of the passage of sanious or purulent fluid from the uterine cavity into the uterine *circulation. If the uterus* remain large and tender, and the discharges offensive, we may apprehend the accession of puerperal

distended with pus. Diffuse pelvic cell
purulent collections, is not uncommon,
suppuration of the ovaries are among the
deposits in the muscles, joints, and phle
secondary affections.

There is no doubt that some local lesion
will be found on careful examination in eve
fever, and to this it is reasonable to attribu
observers hold that there is a specific poi
fever, and that the local lesions are its s
peral fever is indeed highly contagious, and
proved that a practitioner may, after the st
the disease from patient to patient in u
The experience of lying-in hospitals is
highly contagious, if not infectious nature
conclude that there is a *specific* poison h
that the common post-mortem poison and
rise to puerperal fever. The true explana
that just as diastase will bring about an
starch into sugar, so will a certain condit
induce a suppurative change in the tissue
only account for the production of puerpera
indicate the precautions medical practitione
parturient women. They must avoid cont
mortem fluids, and all putrid discharges;
into contact with them, the hands shoul
running stream, and several times soaked
acid.

1. Acute Puerperal Per

abdomen increase, the pulse becomes more and more rapid, the skin cold and clammy, the head first feels confused, and then muttering delirium follows; the tongue becomes dry and brown, the teeth covered with sordes; distressing eructation and vomiting, hiccough, subsultus tendinum, pinched features and cold extremities, usher in the fatal result.

Morbid Appearances.—Redness of the peritoneum, especially of that covering the uterus, and its appendages, with effusion of solid lymph and serum into its cavity. The uterus, ovaries, and Fallopian tubes covered with creamy matter. Purulent deposits sometimes found in the muscular structure of the uterus, and the ovaries often the seat of abscess.

Causes.—*Contagion.*—The common causes of inflammation. It is often epidemic, and coexists with or precedes the malignant variety.

Prognosis.—*Favourable*, but guarded, if the treatment be commenced early, and if the reigning epidemic be of a mild character.

Treatment.—*General.* Leeches to the abdomen in number according to the severity of the symptoms and strength of the patient; hot fomentations; calomel in doses of half a grain, combined with half a grain of opium, or five grains of Dover's powder, every two, three, or four hours, continued till salivation shows itself. Cooling drinks and cool air. Nourishing food and stimulants, as wine, brandy, and ammonia, or turpentine, taken by the mouth, and injected into the bowel.

Local.—The uterus should be thoroughly and frequently washed out with warm water containing $\frac{1}{20}$ part of an aqueous solution of carbolic acid. A purgative of castor-oil, or salts and senna, to be administered at the outset, and if swelling, tension, and tenderness continue, hot fomentations or turpentine stupes should be constantly applied to the abdomen.

2. Adynamic, or Malignant Puerperal Fever.

Synonym.—Puerperal hysteritis or metritis.

Symptoms.—More obscure than the foregoing: the rigor less strongly marked, the pain in the abdomen less severe, little increased by pressure, deep seated, more circumscribed, and often limited to the hypogastric or iliac regions. The pulse, from the first, extremely small, rapid, and weak, ranging from 130 to 160; countenance anxious; skin sallow; extreme restlessness; intellect, though sometimes clear to the last, generally wandering; low, muttering delirium; tongue at first white, then dirty yellow, then dry and brown; if blood be taken, it is dark coloured and the coagulum very loose; eructation, vomiting, hiccup, diarrhœa; the evacuations highly offensive; lochial discharges fœtid or suppressed; breasts flaccid; abdomen *tumid and* tympanitic; uterus large, uncontracted, *tender. Death after the usual* typhous symptoms, or slow recovery.

Morbid Appearances.—Peritoneum of a dusky hue; effused fluid dirty brown, often bloody and mixed with lymph. Fœtid gas in the intestines. Uterus softened, or gangrenous; ovaries reduced to a pulp. Pus in the veins of the uterus, and in the joints; inflammation, and abscess of the cellular membrane of the leg, &c. In a word, pyæmia.

Causes.—Uterine phlebitis. Contagion.

Prognosis.—*Unfavourable* in all cases.

Treatment.—The general and local treatment as in the peritoneal form.

As the source of the mischief lies in the uterus, its condition should be narrowly watched for the first few days after delivery, and if it remain large and tender, and the discharges become offensive, no time should be lost in washing out the disorganized clots and fœtid discharges with warm disinfecting fluids, and this operation should be repeated from time to time. Clysters of warm water may also be used.

3. Puerperal Intestinal Irritation.

Symptoms.—General uneasiness, coming on at any period after delivery, if the bowels have been neglected; loss of appetite; tongue furred; chills alternating with flushes; headache; frequent pulse; abdomen large and rather tense; slight, deep-seated pain, relieved by steady pressure; nausea and vomiting of a dark offensive fluid; diarrhœa; evacuations dark, fœtid, watery, or slimy; flatulence; fœtor of breath. In unfavourable cases extreme debility and despondency; the red tongue of acute gastric irritation; often aphthæ of the tongue and mouth. The diarrhœa continuing and the strength diminishing, the fever increases and assumes the typhous form.

Morbid Appearances.—Generally none. Sometimes inflammation, with or without ulceration, of the mucuous membrane of the intestines.

Prognosis.—More favourable than either of the preceding varieties.

Treatment. At first a full dose of calomel and opium followed by castor-oil, to relieve the intestines of retained or offensive matters. If need be the calomel and opium may be repeated, or a dose of castor-oil in place of it. The local and dietary treatment should be that of enteric fever. Diarrhœa to be treated by the chalk and opium powder.

4. Puerperal Peritoneal Irritation.

Symptoms.—After a slight rigor, pain and tenderness of the abdomen, a slightly-coated tongue, a rapid and very compressible pulse; with some heat of skin. It occurs chiefly in delicate and nervous females, after unusually severe after-pains, or from the violent operation of a purgative. Profuse perspiration and diarrhœa are present in some cases.

Prognosis.—Favourable.

Diagnosis.—From true puerperal peritonitis by the milder character of the symptoms.

Treatment.—Fomentations, poultices, diaphoretics, and opiates, with an occasional mild laxative. Ten grains of Dover's powder, or from 15 drops of laudanum, may be given at once, and repeated if necessary.

5. Milk Fever.

Symptoms.—About the third day after delivery a well-marked rigor, followed by a hot and then a sweating stage; great pain and throbbing in the head; intolerance of light and sound; flushed countenance; blood-shot eye: contracted pupils; pulse frequent, full, and hard; skin hot and dry; thirst excessive; tongue dry and coated; breasts hot, tense, and painful. If speedy relief be not obtained, the head symptoms become more severe, attended perhaps by slight delirium; the breasts are hard and painful, and suckling cannot be borne; and, after a time, local inflammation with an increase of fever sets in, followed by abscess of the breasts.

Causes.—Accumulation and retention of the lacteal secretion.

Diagnosis.—From other puerperal fevers by the local affection.

Treatment.—The free use of saline aperients. The breasts to be kept cool by an evaporating lotion, or gently rubbed with sweet oil or belladonna liniment. The infant or a breast-pump should be applied to the nipples as soon as it can be borne. If the congestion of the breasts continue, we apply a few leeches followed by warm poultices or fomentations.

CELLULITIS VENENATA.—DISSECTION WOUNDS.

Definition.—Inflammation of the cellular tissue, with severe febrile symptoms, caused by a poison contained in certain dead bodies, and absorbed from wounds.

The wound may be received in dissecting, or may exist previously, but in some cases there has been no wound or injury of any kind.

Symptoms.—In most cases the disease sets in, within a few hours of the accident, with inflammation at the seat of the puncture; but in rare instances the local affection is preceded by febrile symptoms, ushered in by severe rigors. The inflammation commencing in the puncture first affects the hand, then gradually extends up the arm till it reaches the axilla, whence it sometimes extends to the trunk, and even to the lower extremity. It is accompanied by swelling, tension, and throbbing pain in the parts affected; the course of the absorbent vessels is often indicated by dusky red lines, or by an erythematous blush, with irregularly defined outline, and the lymphatic glands above the elbow and in the axilla are swollen and painful. The inflamed parts are at first exquisitely tender, but become less sensitive as the disease advances. In favourable cases the inflammation terminates in serous effusion, which is gradually absorbed. In more severe cases suppuration of the cellular tissue, both superficial and deep-seated, occurs, and abscesses form under the theca of the punctured finger, or diffused abscess attacks the cellular membrane on the hand and arm, or even on the trunk. When the inflammation runs very high, it sometimes terminates in extensive sloughs. In some of the least favourable cases the local affection is very slight. The punctured part becomes the seat of a small vesicle or pustule, and the inflammation at once attacks the axillary glands; the neck and upper part of the chest are swollen, stiff, and painful, and the inflammation sometimes extends over the trunk and lower extremities. Occasionally deep-seated diffuse abscesses form without any superficial inflammation. The febrile symptoms often assume the typhous character, with profuse fœtid sweats, great debility, extreme depression, and high nervous excitement. The mind is generally unaffected; but the patient sleeps little, and is sometimes delirious at night. Recovery is often slow and imperfect, the hand remaining stiff from the slow absorption of effused fluids, the thickening of the textures, or the injury attending on suppuration or gangrene. Health returns but slowly.

Cause.—A contagious matter absorbed from a sore or wound on the hand, rarely through the unbroken skin, from animal matter in the first stage of decomposition.

Diagnosis.—Difficult in those cases in which no wound or sore can be discovered. The acute sensibility of the inflamed parts is very characteristic.

Prognosis.—The mortality in severe cases is about 50 per cent. *Favourable symptoms.* Inflammation limited to the cellular tissue, and, at the worst, axillary abscess.—*Unfavourable.* Extension of the inflammation beyond the axilla, and general pyæmia.

Treatment.—When local inflammation runs high, leeches may be applied to the inflamed part, followed by warm fomentations. When suppuration is taking place, warm poultices or fomentations should be kept constantly applied. Pus when formed to be discharged by free and deep incisions.

The patient's strength will have to be supported by stimulants, such as ammonia and æther, with wine and a nourishing diet.

When there is acute pain and great excitement, full doses of opium or of its preparations, are to be given; with ammonia or æther when the symptoms assume the typhous character.

Prophylaxis.—Wounds received in dissection, especially of bodies recently dead, should be immediately washed, and the wounded finger or part strongly sucked for some time. On the appearance of the least inflammation the part should be poulticed. Caustic to do good must be applied at once to the bottom of the puncture.

FARCINOMA.—GLANDERS.—FARCY.

Synonym.—Equinia.

Definition.—A contagious malady, characterised by inflammation of the nasal mucous membrane, and by inflammatory tumours and pustules in different parts of the body, caused by contact with the horse or other quadruped, or with persons suffering from the disease.

Varieties.—1. Acute glanders. 2. Chronic glanders.

1. Acute Glanders.

Symptoms.—The disease generally sets in with pain in the head, back, and limbs, rigors, nausea, thirst, great prostration of strength, with stiffness and pain in the joints, increased by motion. These symptoms are followed, after a short but variable interval, by tumours, red, painful, and tender, in different parts of the body, terminating in abscesses discharging a fœtid sanies, and passing quickly into gangrene. From the fourth to the sixteenth day a profuse discharge of a yellow or sanious fluid from the nostrils sets in, accompanied by redness, heat, swelling, and excoriation of the nose, lips, and cheeks; the eyes are inflamed, and the eyelids swollen. Pustules and black bullæ appear on the face, trunk, limbs, and parts of generation. These local symptoms are accompanied by a hot skin, urgent thirst, frequent, weak, and irregular pulse, and feeble respiration. The tongue is covered with a dark fur; the skin is bathed in a profuse and offensive perspiration; the evacuations are slimy and fœtid. These symptoms increase in severity, and are followed, after a few days, by diffused abscesses in different parts of the body, especially about the joints; typhous symptoms rapidly supervene; the nose and lips become gangrenous; the discharges extremely offensive; low muttering delirium sets in, and death takes place by collapse. The greater number of patients die within a fortnight; few survive till the third or fourth week. One death is reported at the end of more than two months.

Anatomical Characters.—Besides the superficial pustules and tumours, congestion of the mucous membrane of the nose, fauces, air-passages and alimentary canal; congestion of the lungs; phlebitis; purulent deposits in the lungs and joints; diffused abscess in the cellular membrane; and bloody fluid in the serous cavities.

Causes.—Contagion and infection. The disease originates in quadrupeds from overwork, privation, or overcrowding, and is most commonly communicated from the horse to the human subject.

Diagnosis.—The peculiar discharge from the nostrils, the seat and character of the pustules, the history of the case, and the occupation of the patient are quite characteristic. Farcy is distinguished from glanders by the absence of the peculiar discharge from the nostrils. But the two terms, Glanders and Farcy, are not used with much discrimination, at least in respect of the human more so. Prognosis is

TREATMENT.—No specific has yet
ment that of typhus fever: local tre

**PROPHYLAXIS.—Grooms in charg
wear gloves, avoid contact with th
lous cleanliness. Wounds or sores
by suction. Stables in which glan
should be thoroughly cleaned and f
washed, and harness and horsecloths
a high temperature, and thoroughly
freely used.**

2. CHRONIC GLANDERS.—In this
cede the fever, and they resemble the
After a few hours from the inoculatio
lymphatics, and extends along the ar
the parotid and submaxillary glands.
the cellular tissue of the limb, and, in
accompanied by dark bullæ, appears o
marked hectic fever. The duration of
siderable, both in favourable and in fat

The term chronic glanders is used
farcy; chronic farcy being a still milder

PUSTULA MALIGNA.—MALI

SYNONYMS.—Charbon. Sang-de-rate.

MPTOMS.—A deep red spot like a

CAUSE.—Contact with the bodies or carcasses of beasts affected with "*Charbon*" or "*sang-de-rate.*" According to some observers, the development of Bacilli in the blood, constitutes the essence of the disease. Dr. Bell, of Bradford, has called attention to the prevalence of the disease amongst persons engaged in working an inferior kind of mohair. Flies and gnats are said to convey the disease. It is not uncommon amongst the herds and flocks of the mountainous pastures of Europe and North America.

TREATMENT.—That of blood-poisoning (p. 331).

CHAPTER VI.

SCROFULA	King's Evil.
RACHITIS	Rickets.
MOLLITIES OSSIUM	Softening of the bones.
PURPURA	Scurvy.
RHEUMATISMUS	Rheumatism.
PODAGRA	Gout.

SCROFULA OR STRUMA.—KING'S EVIL.

DEFINITION.—The deposit of *tubercle* in several organs of the body, with a tendency to indolent inflammatory swellings and chronic ulcers.

The most common forms of scrofulous disease are, chronic inflammation and suppuration of the glands of the neck, strumous ophthalmia, and chronic ulcers of the cornea, indolent abscesses of the skin, enlarged tonsils, mollities ossium, diseases of the bones and joints, psoas abscess, tabes mesenterica, and pulmonary consumption. The scrofulous, too, are more subject than others to hysteria and to mental disorders.

The form of scrofula to be here described is that which attacks the absorbent glands of the neck. Other scrofulous affections will be considered under Rachitis, Tabes Mesenterica, Phthisis Pulmonalis, and Strumous Ophthalmia.

SYMPTOMS.—The scrofulous constitution is indicated by a lax habit of body, a thin fair skin, delicate rosy complexion, fair and fine hair, full upper lip, and tumid septum and alæ nasi. We recognize the same constitution in spare, pale children, with projecting foreheads, misshapen heads, narrow and deformed chests, swollen fingers, enlarged joints, irregular and unsound teeth, tumid abdomens, cold extremities, and great liability to chilblains. A weak digestion, variable appetite, and torpid, or disordered bowels are also of frequent occurrence in such children; who nevertheless often display great aptitude and acuteness, lively imaginations, and ardent affections, and frequently a great precocity of intellect.

The scrofulous affection of the glands of the neck first appears as a slight swelling of one or more of the glands of one or both sides, especially of those situate beneath the lower jaw. The tumour is even to the touch, movable, and neither tender nor inflamed. Sometimes the swollen gland or glands will remain in this state without perceptible change for weeks, months or even years; sometimes they gradually enlarge; sometimes coalesce, so as to form irregular knotty swellings; sometimes gradually disappear. In most cases they proceed to suppuration; fluctuation is perceived, the tumour points, the skin gives way, and pus, followed by a sero-purulent, mixed with a curdy or cheesy matter, is discharged by one or more openings. The abscess thus formed heals slowly, has an unhealthy appearance, a dull-red colour, with hard, swollen, irregular edges, and an uneven base, clogged with curdy matter. After the ulcer has healed, an irregular and unsightly scar occupies its site. Though the superficial glands of the neck are those most frequently attacked, the deep seated ones are often implicated; and the disease sometimes spreads along the course of the absorbents from one gland to another.

The constitutional disturbance which accompanies these local changes is usually slight. The patient retains his colour, does not lose flesh, and has every appearance of good health. When, however, the local disease is extensive, and the glands suppurate, hectic fever sets in, with great weakness and loss of flesh. In advanced stages of the disease, especially in young adults, pulmonary consumption may supervene; the two diseases then run on together until they destroy the patient.

CAUSES.—*Predisposing.* Hereditary taint; syphilis or gout, or a shattered constitution in one or other of the parents; disparity of age in the parents, or too near relationship; childhood, youth, and the early adult age. The disease is most common between the third and seventh year; comparatively rare after puberty, but may occur as late as thirty years of age.—*Exciting.* All causes of debility acting on the predisposed—such as sedentary habits of life; scanty and unwholesome food; the impure air of crowded and ill-ventilated nurseries, schools, workshops, and factories, and the confined rooms inhabited by the poorer classes; overwork; damp and low situations; exhausting maladies, especially fever, and the febrile exanthemata. The immediate exciting cause is often an attack of catarrh. The disease is common among prisoners.

DIAGNOSIS.—From simple glandular inflammation, by the indolent character of the swellings.

PROGNOSIS.—The disease, when limited to the absorbent glands, is rarely fatal, but tabes mesenterica, white swelling of the joints, disease of the spine, and pulmonary consumption are dangerous and fatal maladies. Scrofula is always tedious in its course, and uncertain in its duration.

MORBID ANATOMY.—The glands contain a soft curdy matter, and the other viscera, especially the mesenteric glands and the lungs, tubercular deposits. The joints and bones are softened by similar deposits.

TREATMENT.—A nutritious diet, adapted to the patient's age, with a due allowance of animal food, and wine and malt liquors in moderate quantity. In scrofulous infants, brought up by hand, the substitution of the mother's milk, or of pure milk from the ass or cow. *Daily exercise,* short of fatigue. Warm clothing (flannel *next the skin). Heavy* clothing should be avoided.

Change of air, especially from a low, damp situation to a high, dry, and bracing one. Sea-air and sea-bathing in the summer and autumn.

A cold or tepid bath daily, followed by friction with a rough towel, or a shower-bath once or twice a week; and gentle aperients at short intervals. A few grains of rhubarb, with small doses of hyd. c. cretâ may be given occasionally, followed by a tea- or dessert-spoonful of castor oil the following morning.

Chalybeate tonics, especially the tinctura ferri perchloridi, the ammonio-citrate, and the dried sulphate, or quinine and iron in combination.

Iodide of iron in doses of from one to five grains, three or four times a day, and cod-liver oil (a tea-spoonful three times a day gradually increased to a table-spoonful) are valuable remedies in scrofula.

II. Simple enlargement of the glands of the neck may be treated by the constant application of the emplastrum ammoniaci c. hydrargyro, or the frequent application of iodine paint. If the patient be at the seaside, poultices of sea-weed (the *Fucus vesiculosus*) may be kept constantly applied. Suppuration must be encouraged by poultices, and the matter let out by a small vertical or oblique incision. Caustic should never be used for this purpose, as it causes unsightly scars.

As open scrofulous ulcers have an indolent character, they must be treated by local stimulants, and in extreme cases by caustic. In treating other local affections in scrofulous habits, this indolent character must be borne in mind.

Remedies.—*Mercurial preparations given as alteratives*, such as Plummer's pill, or the perchloride of mercury (Form. 288). *Alkalies* and *alkaline earths*, of which the best is the liquor potassæ, in doses of from five to twenty drops, three times a-day in some tonic infusion; or from one to two drachms of lime water. The *mineral acids*, especially nitro-muriatic acid. The *chlorides of barium and of calcium*. (Liquor barii chloridi, ♏iii to ♏v, cautiously increased; or liquor calcii chloridi, ♏xxx to ♏xl, gradually increased.) *Conium.*

In consequence of the slow and uncertain progress of scrofulous affections, many remedies seem serviceable which are really inert; and it is so with pulmonary consumption, for which the most opposite remedies are confidently recommended and deemed efficacious.

RACHITIS.—RICKETS.

Definition.—A distortion of the bones, occurring in infancy and childhood, from deficiency of earthy matters.

Symptoms.—The disease sometimes begins soon after birth; more frequently when the child is five or six months old; more frequently still before the close of the second year, after which age it is very rare. The rickety child is observed to be less healthy and strong than other children of the same age. The face is pale and the body thin. Teething begins late, and goes on slowly, and the teeth soon become loose and carious. The fontanelles and sutures are usually open; the head, though smaller than usual, is generally large in proportion to the face, and the forehead prominent; the chest is flattened at the sides, and the sternum projecting; the epiphyses of the long bones become spongy, and the joints swell. This is commonly first perceived in the wrists and ankles. As the disease advances, the long bones yield to the weight of the body, and are twisted by the action of the muscles; the spine is curved and bent; and the pelvis distorted and narrowed. If the patient has begun to walk, the gait is unsteady and waddling. The mental faculties, except in cases of cretinism accompanied by distortion, are unimpaired, and even unusually acute.

Causes.—*Predisposing.* Hereditary tendency. A peculiar diathesis, allied to the scrofulous, but not identical with it; for enlargements of the cervical glands, and tuberculous deposits in the lungs, are not common in rickety subjects.—*Exciting.* Bad nursing, bad food, bad air, want of cleanliness.

Pathology.—Defective nourishment, or mal-assimilation of the food, leading to a deficiency of earthy matter in the bones. Dr. J. Davy found 100 parts of the dry tibia of a rickety child to be composed of 74 parts of animal matter and only 26 of earthy salts. The microscopic appearance of rachitic bone is very characteristic. Ossification has taken place so partially and imperfectly that the bone is made up of isolated and apparently independent masses of unaltered cartilage, blended with completely and incompletely formed bone. Owing to the imperfect ossification of the matrix, the conversion of the enlarged cartilage cells into lacunæ is readily seen (*f* and *g*, Fig. 53).

Fig. 53.



Prognosis and Results.—*Favourable.* The disease is very rarely fatal. In mild cases complete recovery often takes place, the swollen joints gradually returning to their natural size: in severe cases the distortion of the body is permanent, but the bones ultimately resume their normal composition, and even become more dense and compact than in persons originally healthy. Distortion of the pelvis endangers life by causing obstruction to parturition.

tonics, especially
steel-wine, the sulphate or potassio-t
the treatment. Cod-liver oil may al
tage. Children living in large town
country. The state of the bowels sho
In order to supply the defective bony
grains of phosphate of lime should b
suspended in chalk mixture. Prepara
at the same time. If the child be ve
monia may be given in lieu of phosphat
to ten grains, three or four times a da
equal parts is a suitable drink.

2. The distorted limbs must be sup
contrivances as do not interfere with
muscles; and care should be taken not
body to rest on those parts that show a

MOLLITIES OSSIUM.—SOFTENI

Synonyms.—*Osteo-malacia.* Malacost

Definition.—*Perverted* nutrition of t
absorption of the earthy matter and cons

Symptoms.—These are very obscure, a
recognized till it has made considerable pr
continued pains in the pelvis and lower
mistaken for the rheumatic pains presen
disease is generally recognized for the first
ring in some bone of the extremities on
force; by the bending, twisting, or disto
the limbs; or, in females, by the

general health, by nourishing diet, tonics, and such other medicines as are indicated by the existing state of the system.

PURPURA.—SCURVY.

Synonyms.—Hæmorrhœa petechialis. Petechiæ sine febre.

Varieties.—1. *Purpura simplex;* 2. *Purpura urticans;* 3. *Purpura hœmorrhagica* (land-scurvy); 4. *Purpura nautica* (sea-scurvy.)

1. Purpura Simplex.

Symptoms.—After slight uneasiness, or giddiness, an eruption of small rounded patches, of a dark claret colour, on the thighs and legs and sometimes over the whole body. After a few days, the first patches fade, and new ones appear. The skin is readily bruised, and bleeding even from slight wounds is often difficult to control. There is little disturbance of the general health. The disease may last from a few weeks to as many years.

Pathology.—Capillary hæmorrhage in the cutis occurring in isolated spots. Blood deficient in fibrin.

Causes.—*Predisposing.* Peculiarity of constitution, debility.—*Exciting.* Febrile states of system. It is often attributed to cold.

Diagnosis.—By the shape and colour of the spots, and the sound state of the cuticle.

Prognosis.—Favourable.

Treatment.—A nourishing mixed diet, and proper exercise, astringent chalybeate tonics, the mineral acids, and occasional mild aperients.

2. Purpura Urticans.

A form of urticaria, in which the patches are discoloured by blood poured out in small quantity into the cellular tissue. (See *Urticaria.*)

3. Purpura Hæmorrhagica.—Land Scurvy.

Symptoms.—Weakness, lassitude, and pains in the limbs, with a feeble pulse of variable frequency; petechiæ of larger extent than in the first variety; occasionally bullæ filled with liquid blood; gums swollen, livid, and spongy; hæmorrhage from the gums, nostrils, uterus, and mucous membranes generally; rigidity of the legs from effusion of blood into the muscles; extensive bruises. In severe cases, all the symptoms of sea-scurvy.

Pathology.—A diseased condition of the blood; with defect or excess of fibrin; but in either case a want of power of coagulation. Hence a loose, rotten clot. The albumin is said to be so changed as to require for its coagulation a temperature 8° higher than usual.

Causes.—Those of sea-scurvy.

Sequelæ.—*Ulceration* of Peyer's patches. Falling off of the *hair. Necrosis.*

for the potato, which does ; and the restor
to banish the disease. As the cheapest ar
table of its class, the potato should always
diet of prisons, workhouses, and hospitals.

4. PURPURA NAUTICA. SCORBUTI

SYMPTOMS.—Heaviness, weariness, dej
from exercise, dull pains in the limbs, esp
and oppression at the præcordia ; palp
breath on the slightest exertion ; a pale,
tenance ; the skin in some cases hot, in ot
the pulse in some cases infrequent, in ot
the tongue clean, moist, and pale ; the g
livid, bleeding upon the slightest touch,
from the teeth, which become loose ; the l
on various parts of the body ; the slightest
a foul ulcer ; the slightest pressure pro
cicatrices open afresh, and discharge a th
neous ulceration likewise takes place upon
face ; the joints become swelled and stiff ;
and of the calf especially, rigid, contracted,
the bowels are either obstinately constipat
the urine is tinged with blood, or transpa
acid. Great emaciation ensues ; passive
from the gums, nose, and ears, from the
occasionally from the lungs and bladder ;
intolerably fœtid ; but the appetite frequ
patient retains his intellectual faculties, a
t to faint on the slightest motion.

turbance and of contagion, and the presence of hæmorrhagic spots and discharges, distinguish this state from fever and all other diseases. Scurvy, as it formerly occurred on land, in besieged cities, camps, and monasteries, and occasionally among entire populations, and as it now sometimes shows itself in prisons and workhouses, is essentially the same disease as that which occurs at sea.

Prognosis.—Generally *favourable*, if the previous health and strength were good, and if a proper vegetable diet, or other proper substitute, can be obtained.—*Unfavourable.* Where there is great prostration of strength; extreme oppression at the præcordia; red eyes and flushed countenance; a rapid weak pulse; profuse hæmorrhages; dark-livid petechiæ of great extent; fœtid and involuntary evacuations.

Treatment.—*Indications.* I. To supply what is wanting in the diet. II. To palliate urgent symptoms.

I. The first indication is fulfilled by fresh vegetables, or fruits, as the orange, lemon, and lime; fermented and fermenting spirituous liquors, as ale, cider, and spruce beer, and the light French and German wines; Sauerkraut, and pickles; and for the very weak, punch, and the stronger spirits. At sea, ℥j of lemon or lime-juice should be served out daily to each individual.

Occasional aperients of infusion of tamarinds, cream of tartar, or the sulphates of soda and magnesia, may be given and the strictest attention must be paid to cleanliness and ventilation.

II. *Ulceration of the gums* requires astringent gargles of alum, muriatic acid, chloride of soda or of lime, or decoction of bark; or the steam of vinegar. *Acute pains* are relieved by opium; *oppression at the chest* and *difficulty of breathing*, by diffusible stimulants, such as nitric, sulphuric, or chloric æther with camphor; *contraction of the muscles of the legs*, by hot fomentations of vinegar and water, or emollient cataplasms, and by friction; *scorbutic ulcers* upon the surface of the body by slightly-stimulant applications.

The *hæmorrhagic tendency* and debility will be best combated by the free use of the mineral acids and chalybeate astringents.

Prophylaxis.—A due admixture with the food of fresh or preserved vegetables, or where these cannot be procured, lime-juice, lemon-juice, or citric acid. Also the acetate and bitartrate of potash. Among fresh vegetables, the potato and yam are the best. As a moist atmosphere is undoubtedly injurious, dry rubbing should be substituted for frequent washing in our ships.—Cleanliness and ventilation should also be rigidly enforced; and mental inaction and despondency should be met by suitable employments and amusements.

RHEUMATISMUS.—RHEUMATISM.

VARIETIES.—1. Acute. 2. Chronic. 3. Muscular.

1. RHEUMATISMUS ACUTUS.—RHEUMATIC FEVER.

DEFINITION.—Acute inflammation of the larger joints, usually shifting from joint to joint, attended by well-marked febrile symptoms; and in many cases, attacking the fibrous textures of the heart.

SYMPTOMS.—The disease generally sets in soon after exposure to cold and wet, with all the symptoms of a severe attack of catarrh; the pain in the back and limbs being unusually severe, and accompanied by a sensation of coldness and stiffness. In the course of one, two, or three days, inflammation shows itself in one or more of the larger joints, characterized by redness and heat of surface, acute pain, extreme tenderness, swelling, and tension. There is great constitutional disturbance, with extreme restlessness, intense thirst, and loss of appetite. The pulse ranges from 90 to 120, and is full, hard, and jerking; the blood, drawn from a vein, is cupped and buffed; the tongue is coated with a soft white fur; the bowels are usually obstinately costive; the urine is scanty and high-coloured, has a strong acid reaction, but at this period of the disease is generally free from sediment. The skin is hot (102° to 108° Fahr.), and usually bathed in a profuse strong sour-smelling sweat, which, however, affords no relief. The fever and pain generally suffer an exacerbation at night.

The disease is rarely confined to the joints first affected; but after some hours or days, attacks fresh ones, sometimes continuing unabated in those first seized, at others leaving them quite free from pain and swelling. In rarer instances, it returns to the joints first attacked, and ultimately extends to all the rest. Some amendment usually takes place in about a fortnight; the pain lessens, especially at night; there is less fever and perspiration; the urine is more abundant, and lets fall a copious deposit of the mixed urates; the appetite returns; the thirst diminishes; the pulse falls; and the patient's movements become more free. Convalescence, however, is rarely interrupted, and the affection of the joints often assumes a chronic form.

In a large proportion of cases, the disease extends to the fibrous tissues of the heart, and the younger the patient the greater the liability to this affection. The symptoms which denote this formidable complication are dyspnœa, palpitation, and a sense of oppression, increased by pressure in the intercostal spaces, by inspiration, and by lying on the left side. In some cases pain in the region of the heart is present: the pulse is quickened, and has a peculiar thrill. As this heart-affection is often obscure, it should be sought after, and its earliest indications attended to. For the stethoscopic signs, see Pericarditis and Endocarditis.

Sometimes, too, the disease is complicated, and recovery retarded, by bronchitis, pneumonia, or pleurisy; by inflammation of the brain and its membranes; and by inflammation of the sclerotic coat of the eye; diseases due to the rheumatic poison.

Morbid Anatomy.—Inflammation of the *fibrous* and synovial membranes of the parts affected, with effusion of clear or milky serum; rarely of solid lymph. In the heart, the results of Carditis and Pericarditis.

Pathology.—This is essentially a blood disease, and consists of accumulation of uric, and, perhaps, lactic acids. The blood also contains fibrin in large excess. The urine is very high-coloured, and contains much uric acid.

Causes.—*Predisposing.* Previous attacks. Youth. Debility.—*Exciting.* Exposure to wet and cold.

Diagnosis.—The pathognomonic symptoms of the acute form are inflammatory fever, with pains and inflammation of the larger joints, over which the integuments become distended, smooth, and of a peculiar pale-red colour. Rheumatism may coexist with *variola* (see page 308).

From *Podagra* (see Podagra). From *Neuralgia*, by the history of the case; by the presence of inflammation and fever; and by the fact that in neuralgia the pain is generally confined to a single joint. From *Syphilitic periostitis*, by the extreme tenderness on pressure of the inflamed bone in that disease, the cranium, sternum, and shin, are the bones usually attacked; the previous history will also furnish aid.

Prognosis.—*Favourable symptoms.* A general, but not too profuse, perspiration; repeated or continuous; sediment in the acid urine.—*Unfavourable.* Extension of the inflammation to the heart, chest, or brain. The disease is rarely fatal; but often leaves behind it organic disease of the heart, by which life is shortened; or chronic inflammation of the joints, with a great liability to future attacks. In favourable cases, and in persons otherwise of good constitution, the duration of the disease is from three weeks to a month, or six weeks, including the period of convalescence. Relapses are very common.

Treatment.—1. *General.* As the system is saturated with acid, the most rational treatment is the alkaline, and it is the most successful. From half a drachm to two scruples of the bicarbonate of potash may be given, dissolved in half a pint of water, every three or four hours, or an ounce of lemon-juice with thirty grains of bicarbonate of potash dissolved in three ounces of water. The nitrate, bitartrate, and acetate may also be given with advantage.

Salicylate of soda proves to be most valuable in relieving the pain and reducing the temperature. It may be given in doses of 15 to 20 grs. with citrate of soda every two hours, and then, as the symptoms decline, every four hours.

The bowels *must be kept* free by saline purgatives, such as a *Seidlitz powder, or from* 40 to 60 grains of compound jalap powder.

in cotton wool. When the skin
is very hot, cloths dipped in an alkali
aquæ Oi) and covered with oilskin, m
pain be very acute and the patient
belladonna or chloroform liniment may
applied to the joints as they are succ
relief.

When the heart is affected, cupping
region of the heart is indicated; or, if
blister alone.

2. Chronic Articular

Symptoms.—This form may be a co
may be independent of it. In the firs
weak, stiff, and perhaps œdematous;
before shifting, is now confined to par
however, it still shifts from joint to joi
acute inflammation or fever. Exposu
brings on an attack, which continues for
goes off leaving the affected joints weak
Chronic articular rheumatism, when
disease, generally attacks the smaller jo
and is then known as rheumatic gout.

Treatment.—When the disease is con
leeches on every marked return or increase
near the affected joint, or even to the
When there is much effusion about the jo
is more extensive, we must employ the
mended for the acute disease.

3. Muscular and Tendinous Rheumatism.

Varieties.—Some forms of this disease have distinct names; as *pleurodyne*, when it attacks the muscles of the side; *lumbago*, when its seat is in the loins; *crick in the neck*, when it affects the neck. Rheumatism of the muscles of the back of the thigh is sometimes, though incorrectly, called *sciatica*. The pain is sometimes limited to a particular tendon, such as that of the deltoid, or tendo Achillis.

Symptoms.—Pain, varying in character and severity, from a dull aching to the most acute darting pain, affecting the entire body, the trunk, a single limb, or a single muscle or group of muscles; coming on sometimes suddenly, at others after shivering and slight feverishness; often forming the most distressing features of a common cold and remaining after the other symptoms have vanished.

Prognosis.—*Favourable*. The disease is free from danger, and does not affect the general health. Its duration may vary from a few hours or days to as many months or years.

Diagnosis.—The pain is increased by motion of the affected parts, by percussion with the points of the fingers, and by the sudden removal of pressure; but is relieved by firm pressure gradually applied. It is sometimes augmented, sometimes relieved, by the warmth of bed. From the severe pains in the chest and abdomen, which accompany spinal irritation; it is distinguished by the state of the spine. (See Spinal Irritation.)

Treatment.—By preparations of colchicum when recent and acute, and by those of guaiacum when chronic. The colchicum may be given in union with a mild saline aperient, and the guaiacum with alkalies. Opiate liniments, or blisters, may be resorted to in obstinate cases.

Prophylaxis. — Persons subject to rheumatism should wear flannel next the skin; protect the parts most liable to the disease; and avoid exposure to wet and cold.

Pleurodynia.

Pain in the left side is present in almost all the functional diseases of young and middle-aged persons; in dyspepsia, amenorrhœa, menorrhagia, leucorrhœa, hyperlactatio, and chlorosis, and in debility, however induced. In males it is equally common on both sides. It often accompanies chronic rheumatic pains of the joints or tendons. Acute pain in the side generally precedes by some days or weeks the appearance of shingles, and sometimes remains after the eruption has disappeared. (See Herpes zoster.)

Causes.—*Predisposing*. Debility. *Exciting*. Over-exertion, as in coughing; flatulent distension of the stomach; the rheumatic *poison*.

suddenly round, or by a sudden inspir effect of slight percussion with the po the immediate increase of the pain on th neuralgic pain preceding the eruption severe.

Complications.—With chest disease sequence of a cough); with acute dyspe mentioned above.

Treatment.—If chronic, the emplast calefaciens should be applied to the sea mustard poultice. Symptomatic pleuro removing its cause. When the affection or gout, the treatment for those diseases

Allied to pleurodyne is an acute pa abdomen or diaphragm, or of both togeth is apt to be confounded with peritonitis, a The diagnosis is easy. Graduated pre when a sudden expiration throws the mu sudden removal of pressure, percussion wit and quick motion of the part affected, absence of severe constitutional symptoms as will also the kind of respiration, which, i in rheumatism of the muscles of the ab the diaphragm is affected, the respirations and acutely painful.

Muscular rheumatism also attacks i muscular texture of the heart, causing muscular coat of the œsophagus, giving lowing; and the muscular substance of the back may *point* at the lower part of the back itself, at any part of the abdominal parietes, or below Poupart's ligament.]

TREATMENT.—The general treatment as in other forms of muscular rheumatism (see *supra*). The local treatment consists in the application of heat, an opiate or belladonna liniment, the Emplastrum belladonnæ, e: opii, or, e: picis, may be applied to the back.

PODAGRA.—GOUT.

VARIETIES.—1. Regular gout; 2. Misplaced gout; 3. Atonic gout; 4. Retrocedent gout.

SYMPTOMS.—The first paroxysm of gout generally comes on about two o'clock in the morning, with pain in the ball of the great toe of one foot (more rarely in the heel, ankle, or instep), accompanied by rigor, followed by feverish heat, and great restlessness. The pain increases till it becomes perfectly excruciating. The joint itself is exquisitely tender, so that the patient cannot bear the weight of the bed-clothes, or the slightest jar or movement in the room. The pain having attained its acme towards evening, ceases suddenly, or subsides gradually, about midnight; a general moisture breaks out on the skin, the patient falls into a sound sleep, and perhaps wakes free from pain. But in the majority of cases, on awaking next morning, the parts, which were before so painful and swollen, are found of a deep red colour, tense and shining, the surrounding part œdematous, and the vessels turgid. For several days and nights the same round of symptoms recur, in a mitigated form, till at length the redness and the swelling subside, the skin desquamates, and the joint is either restored to its healthy state, or becomes the seat of the chronic form of the disease.

It rarely happens that one attack of gout is not followed, at a longer or shorter interval (sometimes of months, sometimes of years), by a second. Most patients, indeed, have several successive attacks, which at first occur at the same season of the year, but at length take place at all seasons, extending first to both feet simultaneously or in succession, then to the hands, and at length to almost all the joints. These subsequent attacks set in at all hours of the day and night, and commence in the hand or foot, in the great toe or thumb, in the knuckles, wrist, or ankle. They are attended with less pain, but with more constitutional disturbance. At length, after repeated attacks, the joints become deformed, stiff, and ultimately are the seat of accummulated chalky deposits.

The fits of gout sometimes appear without warning, but they are generally preceded by dyspepsia, with dejection of spirits, and irritability of temper; or by unusual coldness and numbness of the extremities, alternating with a sense of pricking or formication, frequent cramps, and unusual turgescence of the veins of the leg.

When the gouty diathesis does not show itself in inflammatory affections of the joints, it may appear as an affection of some *internal part*. *If it attack* the *stomach*, there is great depression and anxiety, followed by intense gastralgia, nausea, vomiting and eructations, attended perhaps by pains and cramps of the trunk and arms. Sometimes there is obstinate constipation, sometimes diarrhœa. If the *heart* be attacked, palpitation, syncope, and angina are the symptoms present; if the *lungs*, dyspnœa, asthma, and sometimes a persistent spasmodic cough; if the *head*, headache and giddiness, followed sometimes by apoplectic and paralytic seizures; if the *spinal cord*, severe neuralgic affections, terminating in paralysis. These affections of internal parts, without inflammation of the joints, have been termed *misplaced* gout, or *atonic* gout, on the supposition that the system lacks strength to throw the disease out.

Sometimes the inflammation of the joints suddenly ceases, while the disease is transferred to some internal part. This is called *retrocedent* gout.

PATHOLOGY.—A blood disease, caused by excess of uric acid. The local symptoms are due to the deposit of crystalline urate of soda in the inflamed part, both on the surface of the synovial membrane, and within the substance of the cartilages and fibrous tissues.

Uric acid is easy to detect in the blood of persons predisposed to, or suffering from, gout. Add six drops of ordinary acetic acid to ʒj of the serum and suspend a thread of cotton in the mixture. After twenty-four or forty-eight hours, a string of minute rhombs of uric acid will be formed along the thread. (Garrod.)

Chronic gout sometimes results in one of the most inveterate forms of albuminuria, and the kidneys are found reduced to half their size and weight, shrivelled and granular, the cortex atrophied, and the pyramids streaked with white lines of deposited urate of soda (Fig. 22, p. 127), constituting the "gouty kidney," of Dr. Todd.

CAUSES.—*Predisposing.* Hereditary taint. The male sex; the adult age (it seldom occurs before puberty, and in a large proportion of cases makes its first attack between 30 and 40); hereditary predisposition; plethora; a full diet of animal food; fermented and especially malt liquors; acid and acescent wines; a sedentary and studious life; dyspepsia. Gout is not peculiar to the rich, but attacks poor persons of temperate habits after long privation.

Exciting.—Cold to the feet; fatigue; anxiety; excessive evacuations; sprains and blows; intemperance; a change from active to inactive life; suppression of customary evacuations, as of piles, which are common in gouty persons.

DIAGNOSIS.—From *acute rheumatism*, by the solid nature of the effusion, by the affection of the smaller joints, especially the great toe, and by the more intense colour of the inflamed part. By the absence of the profuse acid perspiration of acute rheumatism. Sometimes by the age; acute rheumatism being common in childhood, while gout is very rare before puberty. By the more rapid and complete convalescence. Gout occurs in free-livers of full habit, rheumatism mostly in the debilitated. The extension from joint to joint, and the heart affections so common in acute rheumatism, are less frequent in gout.

PROGNOSIS.—*Favourable.* No hereditary taint. Youth, and an unimpaired constitution; a first attack. The more severe the paroxysm, the shorter its duration.—*Unfavourable.* Hereditary predisposition, impaired constitution; advanced age, the deposit of chalky matter in the joints, endocardial thickening and irritation.

TREATMENT.—1. *General.* An attack of gout may be effectually shortened by a full dose of the *Vinum colchici* (ʒj to ʒij), combined with opium taken at bed-time, and followed by a saline aperient in the morning; or, in a smaller dose (♏xx) three or four times a day, combined with a saline aperient, according to the state of the bowels. After a time the saline diaphoretics may be substituted.

The exciting causes must be avoided by regular living, abstinence from fermented liquors, and the moderate use of animal food. After the acute symptoms have subsided, we may direct friction; regular and brisk exercise; Bath or Buxton waters, the use of mild aperients, the occasional use of alkalies to correct any tendency to dyspepsia. Salts of lithia promise to be useful in the elimination of the gouty material. (See Form. 266.)

2. The *Local* treatment consists in wrapping the inflamed part in flannel, wool, or fleecy hosiery; and in rest. Opium and atropia lotions may be used to alleviate pain.

Treatment of retrocedent Gout.—If the stomach be attacked, the application of a blister to the epigastrium: æther, ammonia, camphor and musk, and sinapisms to the feet, with a view to restore the external inflammation. For other forms of retrocedent gout the treatment appropriate to idiopathic affections of the same organs.

GOUTY CONCRETIONS. Gouty concretions, or chalk-stone deposits, consist chiefly of urate of soda, and are deposited around the joints, in the bursæ mucosæ, in the cartilages, ligaments, aponeuroses, and connective tissue. The pain they occasion may be relieved by warm poultices, by rings of blistering plaster, above or below the swollen joints, or by iodine paint. An anodyne cataplasm or fomentation often affords great relief. Benzoic acid, combined with a salt of potash, in doses of a scruple about an hour after each meal; or benzoate of ammonia may be given and persevered in for a considerable period where extensive deposits have taken place. The waters of Aix-la-Chapelle, Vichy, Töplitz, Marienbad—all of which contain lithia—should be taken in lieu of spirits, wine, or malt liquors. Sometimes suppuration occurs around the chalky joint, and a foul chalky (*urate of soda*) ulcer results, which heals slowly and with difficulty. It should be dressed with rags moistened by a weak potash or lithia lotion, and covered with oil-silk.

SPECIAL DISEASES.

CHAPTER I.

DISEASES OF THE NERVOUS SYSTEM.

1. Of the Brain.
2. Of the Spinal Marrow.
3. Of the Nerves of Sensation.
4. Of the Nerves of Motion.
5. General Disorders of the Nervous System.
6. Mental Disorders.

DISEASES OF THE BRAIN.

CEPHALALGIA	Headache.
ENCEPHALITIS	Inflammation of the Brain.
MENINGITIS	Inflammation of the Membranes.
HYDROCEPHALUS	Water in the Head.
APOPLEXIA	Apoplexy.
CHRONIC DISEASES of the Brain.	

CEPHALALGIA.—HEADACHE.

Headache is a symptom of almost all acute and chronic diseases of the brain, as well as a distinct functional derangement of very frequent occurrence. It may be (*a*) External, or (*b*) Internal.

(*a*.) External.—1. Cephalalgia muscularis; 2. Cephalalgia periosteosa; 3. Cephalalgia neuralgica.

(*b*.) Internal.—1. Cephalalgia congestiva; 2. Cephalalgia dyspeptica, vel sympathetica. Cephalalgia organica.

EXTERNAL.—1. *Cephalalgia muscularis*, or pain of the muscular covering of the head, affects the occipito-frontalis and temporal muscles. *Diagnosis.*—The pain is diffused, is increased by motion of the eyebrows and jaws, by pressure, and by percussion with the fingers; and is generally accompanied by muscular pain in the neck, shoulders, or other parts of the body. *Cause.*—Exposure to cold. *Treatment.*—That of catarrh when recent, and of muscular rheumatism when chronic.

2. *Cephalalgia periosteosa.*—Seat, the pericranium. *Diagnosis.* —The pain is usually limited to one spot, and is increased by firm and deep pressure, but little, if at all, by action of the muscles. It sometimes affects the periosteum of the face at the same time, so that the nose is tender to the touch; and it frequently extends to other parts of the body, especially to the shin and sternum. When limited to one spot, it is commonly attended with swelling (*nodes*). *Causes.*—By far the most common cause is the syphilitic taint, which shows itself also in characteristic diseases of the skin, &c., as well as by the peculiar appearance and expression of countenance known as *Cachexia syphilitica*. *Treatment.*—That of secondary syphilis. Iodide of potassium in five-grain doses in a tonic infusion is the proper treatment. If the bone be affected, and matter formed, free incisions will be required, followed by the treatment prescribed in surgical works for disease of bone.

3. *Cephalalgia neuralgica vel periodica.*—Seat, the nerves of the inner angle of the orbit and side of the nose (*megrim*), fixed in one spot, causing a sensation as if a nail were driven into the head (*Clavus hystericus*), or of one side, commonly the left, of the head and face (*hemicrania*), tenderness of the sensory branches of the 5th nerve, tenderness and aching of the eyeballs. It occurs with regularity at the same intervals as ague, and in some instances at the long intervals of ten days, a month, or a year. In some cases the intermittent passes to a continued pain, and in many the disease is never distinctly intermittent, but is characterized by irregular intervals of perfect ease, and by being bounded by the median line of the head and face. The paroxysm may last for any period from an hour to two days. The disease is more common in women than in men, and in young than in old persons. But it may occur at any age. In the worst cases the pain is most acute, and is brought on by eating or speaking, or by draughts of air.

Cause.—Exposure to cold and wet—marsh miasma. *Treatment.* —The same as for ague—viz., quinine in large doses. But the liquor arsenicalis (Form. 291) cautiously administered, is to be preferred.

INTERNAL.—1. *Cephalalgia congestiva*, or *congestive headache*. This presents itself in three different states of constitution—the plethoric, the delicate and irritable, and the weak and leucophlegmatic. *Diagnosis.*—Obtuse pain, affecting the whole of the head, especially the forehead and occiput, combined in the *plethoric* with a bloated countenance, a full red eye, distension of the veins, a full pulse, and a dull, heavy expression of the face; in the *delicate* and *irritable*, with flashes of light, floating specks before the eyes, noises in the ears, cold extremities, and a small, frequent, quick pulse; in *anæmic* subjects, with pale skin, lips, tongue, and gums, cold extremities, beating at the heart, violent throbbing of the carotid arteries, and a small, frequent, quick pulse. In the two latter classes of persons, it is brought on in severe paroxysms, by sudden *noises, mental emotions*, or violent muscular exertion. Treatment.

—In the *plethoric*, that of plethora (p. 255). In the *delicate* and *irritable*, repose of mind, careful attention to the state of the stomach and bowels, and sedative medicines taken at bed-time occasionally (Forms. 73, 76). In *anæmic* subjects the treatment of anæmia (p. 256).

A congestive headache allied to the first form (the plethoric) may be caused by narcotics. It often accompanies chronic bronchitis, the early stage of phthisis, and febrile disorders, and precedes apoplexy.

2.—*Cephalalgia dyspeptica, vel sympathetica.—Sick headache.—Diagnosis.*—From other headaches by the marked disorder of the stomach, or of the whole alimentary canal —*Symptoms*. Pain usually fixed, in the left temple, over the right eye, or on the forehead, commonly commencing when the patient first rises in the morning, and in slight cases continuing till after breakfast. In more severe ones, it begins as a diffused dull pain, and gradually becomes fixed in one spot, attended by nausea, flatulence, sour eructations, and vomiting. There is also confusion of thought, dimness and indistinctness of vision, and singing in the ears. Sometimes the fit is removed by free discharge of food, of frothy mucus, or of bile from the stomach; perhaps accompanied, or followed by, diarrhœa. Its duration varies from some hours to three or four days. In confirmed cases it returns at short intervals, and is attended with great suffering. *Causes*. Derangement of the functions of the stomach and bowels. The abuse of aperient medicines, by which the tone of the alimentary canal is weakened. Sick headaches are common just before and after the menstrual period. *Treatment*.—Gentle aperients combined with alkalies, as rhubarb with soda, or magnesia. Regulated diet; exercise; emetics, where the cause is transient. In cases of obstinate sick headache, emetics of ipecacuanha may be administered every morning with the best effect. If large quantities of bile are ejected from the stomach (bilious headache), cholagogue purgatives (Form. 249) are indicated. When the bowels are irregular and very irritable, an occasional dose of Gregory's powder, or rhubarb and bismuth. When much flatulence is present, turpentine or kreasote may be given. Cold to the head sometimes acts as a palliative. A draught containing from five to ten grains of carbonate of ammonia given at the commencement of the attack will sometimes arrest it; and a full dose of brandy and water will generally act favourably in procuring sleep.

3. *Cephalalgia organica.—Diagnosis.* This is distinguished from the foregoing forms either by appearing to affect the entire brain, or by being fixed and deep-seated. It is also subject to marked increase and decrease of severity, but rarely suffers a complete intermission. In character the pain resembles that of the plethoric form of congestive headache. If associated with dyspepsia, it is not relieved by vomiting. The nature of the disease is at [illegible]gth made known by paralysis, spasms, or convulsions.—*Treat-*[illegible].—That of the disease of which it is the symptom. The state

of the circulation through the brain must be carefully watched, and local and general blood-letting, purgatives, and counter-irritants, must be resorted to; at the same time that strict attention is paid to the state of the general health. In chronic inflammatory affections of the brain, a course of mercury, so as to produce incipient mercurialism, will sometimes effect a cure.

Great caution is needed in inquiring into the cause of headache, and in discriminating one form from another. The treatment will entirely depend on the accuracy of the diagnosis. Sometimes for instance, a patient complaining only of frontal headache will be found to be suffering from phthisis pulmonalis. (G.)

ENCEPHALITIS.—INFLAMMATION OF THE BRAIN AND ITS MEMBRANES.

SYNONYMS.—Phrenitis. Meningo-encephalitis. Meningitis. Arachnitis. Attempts have been made to describe inflammation of the membranes of the brain, apart from that of the brain substance itself, but inflammation of the dura mater (see below) excepted, it is impossible to conceive hyperæmia of the covering membranes of the brain without implication of the grey matter of the convolutions.

VARIETIES.—1. *General*, that is, involving the whole, or the greater part, of the substance and membranes of the brain.—2. *Partial*, or affecting only part of the substance, or of the substance and membranes.

1. GENERAL INFLAMMATION OF THE BRAIN AND ITS MEMBRANES.

SYMPTOMS.—In one class of cases the disease sets in with acute pain in the head and violent delirium: in a second with nausea, bilious vomiting, and obstinate constipation; in a third with a general convulsive paroxysm; in a fourth, and very rare class, with loss of speech.

The disease, when fully formed, is characterized by excruciating pain in the head; throbbing of the temporal and carotid arteries; flushed face; injected and brilliant eye; contracted pupil; and a peculiarly wild expression. There is great intolerance of light and sound, extraordinary acuteness of the senses, constant watchfulness, want of sleep, fierce delirium, and convulsions. The skin is hot and dry, the pulse hard and frequent, sometimes full, sometimes contracted; the tongue red and dry, or covered with a white fur; there is intense thirst, with nausea and bilious vomiting; and the bowels are obstinately confined. These symptoms belong to the stage of *excitement*, and may last from one to three days, when, gradually subsiding, they are succeeded by moaning or low muttering delirium, deafness, indistinctness of vision, insensible pupil, strabismus, twitchings of the muscles, often a clenched hand, tremors, cold sweats, relaxed sphincters, and retention of urine, *with more or less profound* coma.

In *Isolation* or *sunstroke* the disease runs a rapid course, and death may occur in from one to forty-eight hours. The pupils are contracted and fixed, and the breathing hurried. The symptoms of encephalitis soon pass into coma. Occasionally there are convulsions from the commencement of the attack; but in the majority of cases the patient dies without making the slightest movement.

Inflammation of the dura mater is rarely idiopathic, but follows injuries to the scalp, or cranium, or inflammation of the ear. So long as the inflammation is confined to this membrane, headache is the chief, and usually the only, symptom, but even this may be absent (see p. 364).

TERMINATIONS.—When fatal, in coma; or in great prostration, with or without typhous symptoms. Recovery may be complete, or the disease may end in mania, dementia, or paralysis. Its duration varies from one or two days to two or three weeks, or even more.

CAUSES.—Excessive heat, or great vicissitudes of temperature; the direct rays of the sun (*coup de soleil*); violent exercise; excited passions; intense study; external violence; the abuse of spirituous liquids; gout, rheumatism, erysipelas, exanthematous fevers, dentition. Inflammation of the brain may also supervene on pneumonia, renal affections, and all febrile diseases, especially pyæmia. In childhood the most common cause is deposit of tubercle on the surfaces of the membranes. (*Tubercular meningitis.*)

DIAGNOSIS.—From *mania*, by the marked febrile symptoms and rapid course. From *febrile delirium*, by delirium being a primary and not a secondary affection. From the *effects of loss of blood*, by the history of the case, the inflammatory symptoms, and the flushed face. From *delirium tremens*, also by the history of the case, by the hot dry skin, and high fever, and the absence of tremor. In most cases of delirium tremens the face is pale and the skin moist; the limbs tremble; and the patient can understand and answer questions.

MORBID ANATOMY.—Thickening of the arachnoid, effusion of serum, lymph, or pus, under the arachnoid and in the meshes of the pia mater, or into the ventricles, with softening of their walls; the incised surfaces of the brain present numerous bloody points, the medullary surface is of a light pink hue, and the cortical of an ashy red, not removed by washing; suppuration, softening, or hardening of the brain substance. In death from sunstroke, great fulness of the lungs and right cavities of the heart. In tubercular meningitis, the effusion of tubercular masses external to the coats of the minute blood-vessels, appearing to the naked eye as minute semi-opaque greyish-white tubercles the size of millet seeds (Fig. 72).

PROGNOSIS.—*Favourable.* The return of sleep and consciousness; a warm and equable perspiration; diarrhœa; hæmorrhage from the nose; diminished frequency, and greater fulness and softness of the pulse. If preparations of mercury have been given, the occurrence of salivation.—*Unfavourable.* Stupor, difficult deglutition, profound insensibility, tremors, convulsions; involuntary evacuations; suppression of urine; pallor of the face. In sunstroke the mortality is often more than 50 per cent.

TREATMENT.—I. *During the period of excitement.—Indication.* To lessen the force of the cerebral circulation.

(*a.*) By applying to the shaved head cold lotions constantly renewed, ice, or a stream of cold water. The latter is greatly to be preferred, especially when there is violent delirium.

(*b.*) By cupping the nape, leeching of the temples.

(*c.*) By active purging at the outset with castor or croton oil, or a full dose of calomel and colocynth, and salivation, if possible, induced by half-grain doses of calomel every two, three or four hours.

(*d.*) By depressents, in doses short of inducing vomiting. Of these tartar-emetic is the best, in doses of a sixth to a fourth of a grain, given every hour until an effect has been produced upon the pulse.

(*e.*) By counter-irritants, such as the mustard poultice to the nape and lower extremities.

(*f.*) By hypnotics, opium, and chloral hydrate alone or combined, when the delirium is active, and the respiration free.

(*g.*) By complete rest and perfect quiet. The sick-room should be kept dark and silent. The head and shoulders should be raised and the patient most carefully watched.

II. *During the period of torpor.*—Brisk purgatives may be given with advantage, and the scalp freely blistered.

In extreme collapse, ammonia, wine, and brandy must be given, with beef-tea and nourishing food, and opium or laudanum may be cautiously administered. If deglutition be imperfect, food and medicine must be given by the rectum. The state of the bladder must be frequently ascertained, and, if necessary, the water must be drawn off two or three times a day.

III. *During convalescence.*—The patient must be narrowly watched, the diet carefully regulated, the bowels kept free by gentle aperients; and ordinary occupations interdicted till health is quite re-established. In case of relapse, cold applications to the head, counter-irritants, and more active purgatives should be resumed. If the mind does not recover its tone, the memory is impaired, and the patient remains weak and irritable, the cold douche or shower-bath should be used every morning, and an occasional blister to the scalp, or a seton in the neck or arm, may be resorted to.

In the treatment of sunstroke the cold douche is very serviceable.

2. PARTIAL INFLAMMATION OF THE BRAIN WITH OR WITHOUT IMPLICATION OF ITS MEMBRANES.

SYMPTOMS.—These are often very obscure; and vary with the extent, degree, and progress of the inflammation, as well as with the part of the brain attacked. In most cases, the first symptom is *pain in the head,* more or less severe, rarely altogether absent, but subject to increase from causes affecting the circulation, and accompanied from the first, or followed after a time, by giddiness, singing in the ears, indistinct or disordered vision, numbness or increased sensibility of the fingers, of the hands and arms, or of other parts of the surface of the body; and slight convulsive movements of the limbs, with occasional attacks of nausea and faintness. The patient is restless and irritable, or suffers from low spirits; the sleep is disturbed, and the intellect more or less impaired. The circulation is very variable, the pulse being at one time slow and regular, and the countenance pale; at another, the pulse frequent and the face flushed. These opposite states often alternate with each other at short intervals. The patient suffers from nausea and anorexia, and is liable to frequent attacks of vomiting. As the disease advances these symptoms become more strongly marked, and rigid contraction of particular muscles or groups of muscles is superadded, occasioning squinting, distortion of the features, difficult and indistinct pronunciation of particular letters or words, and sometimes great difficulty in swallowing. When the muscles of the extremities are thus affected the limbs assume a flexed position, and any attempt to move them occasions great pain. The pupils are generally dilated, or unequal, and the sight of one or both eyes is impaired. Ptosis is often present. In a still more advanced stage the partial contractions of the limbs are exchanged for very extensive and constantly increasing loss of power and sensation; all the senses fail, the sphincters are relaxed, and the patient sinks utterly helpless and exhausted. In some cases general convulsions, usually stronger on one side of the body, supervene.

The duration of this disease is extremely variable. It may assume from the first an acute character, and terminate fatally in a few days; or it may run a chronic course of several weeks, months, or years; or the chronic form may, at any time, be exchanged for an acute attack with extensive inflammation of the membranes of the brain.

MORBID ANATOMY.—Congestion of the affected portion of the cerebral substance; hardening of its texture; white or red softening, small extravasations of blood; infiltration of pus, contiguous to inflamed or necrosed bone; encysted abscess; fatty degeneration, ossification, or aneurism of the vessels; gangrene; a cystic entozoon surrounded by inflamed brain tissue; scrofulous tumours. The membranes of the part affected are usually more or less diseased, and effusion of serum is a common consequence of several of these conditions. In certain cases the local disease may be traced to obstruction of a cerebral vessel by a clot of fibrin derived from an aneurism or diseased cardiac valve.

CAUSES.—The eruptive fevers and pyæmia.—Scrofulous or syphilitic disease of the cranial bones or of the membranes of the brain. Disease of the petrous bone following scarlatina, often after the lapse of many years, is a very fertile cause.—Blows.—Entozoa.

DIAGNOSIS.—From general encephalitis, by the partial character of the rigidity, spasm or paralysis. Only one side of the body, or one limb or organ, may be thus affected. Inequality of the pupils, squinting of one eye and double vision, ptosis of one eyelid, deviation of the tongue or uvula from the median line, or numbness and twitching of a single limb may be the only indication.

The following facts will aid us in our diagnosis:—

1. Disease of one side of the brain causes paralysis, or some disorder of the opposite side of the body. But to this the face is often an exception. According to Burdach, "in 28 cases of cerebral lesion of one side, the muscles of the opposite side of the face were paralysed; in 10 cases those of the same side. Paralysis of the muscles of the eyeball occurred in 8 cases on the same side, in 4 on the opposite." The tongue is almost always paralysed on the side opposite to that of the face, its point being pulled towards the paralysed side.

2. So long as the disease is confined to the white substance of the *cerebral or cerebellar lobes*, without causing pressure on surrounding parts, its presence is not manifested by disordered nervous function.

3. Disease affecting the *corpus striatum* produces paralysis of motion (hemiplegia) on the opposite side of the body.

4. Disease of the *optic thalamus* results in loss of sensation on the opposite side of the body, with more or less disorder of vision.

5. Disease of the *crus cerebri*, or *pons Varolii*, produces paralysis of motion and sensation on the opposite side of the body.

6. A clot or tumour in the *centre of the pons Varolii* results in more or less complete loss of motion and sensation on both sides with disordered action of the muscles of the eyes and eyelids.

7. Disease affecting the grey matter of *the cerebellum* causes disordered motion on the opposite side of the body, with sensations of rolling, or of downward or upward movement.

8. Pressure within the fourth ventricle from blood clot, or any other cause, results in derangement of the functions of deglutition and respiration, hearing, and sensation.

Paralysis due to disease of the spinal cord is distinguished at a subsequent page.

The following statements will aid us in determining the particular nature of the cerebral disease:—

I. If the symptoms set in after a chronic discharge of offensive matter from the ear, we may infer that *caries of the petrous portion of the temporal bone* has induced suppurative inflammation of the contiguous part of the brain or its membranes.

II. When a delicate scrofulous child becomes sleepy, heavy, and listless, and gradually lapses into unconsciousness, with partial convulsive twitching and clenching of the hand, grinding of the *teeth, squinting* and uprolling of the eyes, we may generally conclude that there is a *scrofulous tumour* in the substance of the brain, or attached to its membranes.

III. Vertigo, and sudden circumscribed pain in the head, followed by severe and repeated epileptiform convulsions, have been caused by the cystic entozoa.

IV. *Chronic abscess of the brain* is a most insidious disease—*e. g.*, A lad received a lacerated wound over the left frontal eminence, was stunned for a few minutes, but soon recovered. Eight days afterwards he resumed work, and continued working till three days before his death. The wound cicatrised by the thirty-second day. There were no head symptoms, not even a trace of pain; the health and spirits were good, but he showed a little irritability of temper. On the thirty-ninth day he appeared pale and listless, and complained of pain in the epigastrium and sickness; he had passed urine during sleep the preceding night, and he faltered once in walking to the infirmary, as if he had lost for a moment the use of his limbs. He again wetted the bed at night, and the next day lost the use of his right side. The following morning he was unable to swallow, and by 4 P.M. was comatose with stertorous breathing, and a slow, laboured, irregular pulse. He continued in this state until 3.30 P.M. next day, and then died. A thick-walled abscess, containing six ounces of thick greenish matter, occupied the anterior lobe of the left cerebral hemisphere, distending the membranes.

As abscess of the brain caused by external violence may thus insidiously progress under the eye of the medical man. Hence we can scarcely hope to receive timely intimation of the presence of the disease when it arises from some internal cause, unless, indeed, it involve one of the centres of sensation or motion, or the root of a particular nerve.

Apoplexy and partial softening of the brain may arise in persons beyond middle age from disease of the blood vessels.

PROGNOSIS.—Unfavourable in every stage of the disease, but especially when rigid contractions or paralysis have set in.

TREATMENT.—Will depend on the cause. It is that of general encephalitis but less active. If there be great heat of the head, cupping or leeches. In milder cases, blisters behind the ears or to the nape will suffice. In chronic cases a seton may be inserted in the nape. Gentle saline aperients, a spare diet, and rest of mind and body should be prescribed. If the disease have a syphilitic origin, iodide of mercury will be required. When there is positive evidence of the formation of pus within the cranial cavity, the question of trephining will probably arise.

HYDROCEPHALUS.—WATER IN THE BRAIN.

VARIETIES.—1. Acute; 2. Chronic.

1. ACUTE HYDROCEPHALUS.

SYMPTOMS.—This disease, like those last described, varies in its *onset.* Sometimes it is preceded, for a long time, by languor, inactivity, loss of appetite, nausea, vomiting, parched tongue, hot dry skin, flushing of the face, and other symptoms of pyrexia, or by those of infantile fever. (See p. 328.) In a second class of cases, it begins suddenly with the symptoms of inflammation of the brain and its membranes. (See p. 359.) In a third class, it comes on obscurely, in the course of febrile disorders or of the exanthemata.

The disease in its first stage is characterized by acute darting pains in the head, with heat of scalp; great sensibility to light, suffused redness of the eyes, flushed countenance, a hot dry skin, contracted pupils and knit brows. The patient is very restless, moans incessantly, tosses about, and rolls the head from side to side. The sleep is short and disturbed by a start or scream. The gait is tottering, and the hand is often raised to support the head. The pulse is accelerated, hard, and quick: the respiration hurried and sighing. The tongue coated; there is nausea or vomiting; the bowels are either obstinately confined, or unusually loose, with fœtid evacuations; and the urine is scanty. Delirium and convulsions are sometimes present in this, the stage of *excitement.* In infants there is strong pulsation of the fontanelles; which afterwards become tense and bulge outwards.

After a longer or shorter period, the symptoms become less violent; the pain is less acute, and is expressed by a low moaning; an uneasy sleepiness succeeds to watchfulness; the pupils are dilated, and strabismus is often present; the muscles of the fore-arm are rigid and occasionally convulsed, and the fingers are clenched upon the thumb; the pulse is now preternaturally slow and often intermitting, but subject to great and sudden acceleration on change of posture; and the respiration is interrupted by deep sighs. The strabismus increases; the pupils become more dilated and cease to contract when exposed to light; and double vision, or complete loss of sight, with lethargic torpor, succeed.

In fatal cases the slow pulse changes to an extremely small and rapid one; the respiration grows stertorous; the limbs are convulsed or paralysed; the skin is bathed in a cold sweat; the evacuations become involuntary; and the patient expires in convulsions, comatose, or exhausted.

Acute hydrocephalus in the adult.—This is a rare occurrence, hydrocephalus being peculiarily a disease of infancy and childhood. But Heberden relates the following case:—"An adult was seized with intolerable pain of the head, sometimes had a voracious appetite, and sometimes none; became delirious, convulsed, stupid, and died: the ventricles of the brain were found so distended with water, that as soon as a puncture was made the water flew out to a considerable distance." (This was probably a case of hydatid tumour.)

Terminations.—In slow recovery; in death; in the chronic form.

Morbid Anatomy.—Sometimes enlargement of the head, separation of the sutures, and protrusion of the membranes. Serum, limpid or turbid, in the ventricles, or beneath the membranes; softening of the surrounding cerebral substance; flattening of the convolutions;

masses of tubercular matter in the substance of the brain. The pia mater unusually vascular; the arachnoid opaque; minute semi-transparent or opaque bodies, single or in patches, in the pia mater; or tuberculous matter from the size of a millet-seed to that of a pea on the surface of any of the membranes (*tubercular meningitis*, see Fig. 72).

CAUSES.—*Predisposing.* Infancy and childhood; debility; scrofulous diathesis.—*Exciting.* Intestinal irritation; dentition; inflammation spreading from the ear; fevers and the febrile exanthemata; premature application to study.—*Proximate.* In most instances tubercular deposits in the pia mater. Infantile fever is a common antecedent.

DIAGNOSIS.—Heat of head and distension of the fontanelles; spasm and twitching or actual convulsions, followed by strabismus dilated pupil, and profound stupor, are the distinguishing marks. The tubercular nature of the disease may be inferred from hereditary tendencies, actual presence of tubercles in the lungs, enlarged cervical glands, or other manifestations of the scrofulous diathesis. This disease may be distinguished from one of an opposite character, called *spurious hydrocephalus*, by the following characters: a *pale cheek*, a *cool* or *cold skin*, *great languor and an absence of febrile symptoms*, or, at the most, an occasional and transient flushing of the face; to which may be added, in the case of infants, a sunken instead of swollen fontanelle. On inquiry the child, will be found to have suffered from loss of blood, long-continued diarrhœa, or some other exhausting discharge.

PROGNOSIS.—Very unfavourable; especially if there be squinting, a weak intermittent pulse, great enlargement of the head, apoplectic stertor, difficult respiration, and involuntary evacuations.

TREATMENT.—The *general treatment* will be that apropriate to inflammation of the brain (see p. 359), due regard being paid to the strength and constitution of the patient, and to the existence of any special source of irritation. If the disease be acutely inflammatory, small doses of grey powder may be given every three hours. If the gums be hot and swollen they should be freely lanced, and a leech may be applied to the mouth or behind the ear. In the threatening convulsions and insomnia of dentition, conium (ʒss to ℥ij of the succus twice a day) is a valuable remedy. When the disease is protracted and the scrofulous diathesis well marked, the continued use of mercurials would be injurious, and we must trust to local treatment, to aperients and sedatives.

The *local* treatment consists in the application of cloths wetted with cold water, vinegar and water, iced water, or spirit lotion to the head. Cold water may be dropped on the slightly raised head, while the body and extremities are immersed in warm water. Counter-irritants, such as mustard poultices or blisters to the temples, back of the ears, or neck, may be used at the same time.

2. Chronic Hydrocephalus.

Symptoms.—Children are sometimes born with this disease; it is very rare in adults, but Dean Swift died of it. It may occur at any age from birth to the eighth year, seldom after. It either comes on insidiously, or follows the acute form. It is indicated by drowsiness, languor, strabismus, vomiting, costiveness, coma and convulsions; the bones of the head separate, the fontanelles enlarge, and the head may acquire an enormous size, and yet the patient survive for months or even years.

Causes.—*Predisposing.* The scrofulous diathesis.—*Exciting.* Injury to the brain during labour; tumours within the cranium; dentition; intestinal irritation. The acute form.

Diagnosis.—The history of the case, large size of the head, and prominence of the fontanelles.

Parents are often anxious about the large size of their children's heads, supposing it to be due to water in the head. The medical man will not attribute a large head to this cause, in the absence of other decided symptoms.

Prognosis.—The disease generally ends fatally, with convulsions. If the bones yield and separate, life may be much prolonged.

Treatment.—*Indications.* I. To promote the absorption of the effused fluid. II. To improve the health.

I. Blisters to the head, kept open by cantharides or savine ointment; frictions with tartar-emetic ointment; or an issue over the fontanelles. In several cases the anterior fontanelle has been punctured at the side of the longitudinal sinus, and much serum withdrawn, but the results have not justified the operation. Pressure by strips of adhesive plaster, and the constant application of cold, may check the further effusion of fluid, till the sutures are well knit.

II. Mercury; applied externally, and given internally, until the gums are tender. In constitutions tainted by syphilis and scrofula, iodide of mercury or of iron is appropriate.

The diet should be light and nutritious, and a little wine may be given at short intervals throughout the day. A change of air, especially if the patient live in a low and damp situation, to the sea-side, or a dry and bracing inland spot, is beneficial.

Among tonics the best is the Vinum ferri.

APOPLEXIA.—APOPLEXY.

Definition.—Sudden loss of motion, with more or less derangement of perception and sensation, caused by pressure on the brain with or without lesion of its substance.

Varieties.—1. Congestion—*i. e.*, fulness of the cerebral vessels without rupture; 2. Serous, or congestion with serous effusion; and, 3. *Hæmorrhagic, or* congestion with rupture.

Symptoms.—This disease makes its attack in one of three ways:— 1. Suddenly, the patient falling down without warning, as if from a blow. 2. After a short premonitory stage, consisting of acute headache, sickness, and faintness. 3. With sudden hemiplegia.

In the first variety, or congestive, the patient does not lose consciousness, though there may be a little confusion of intellect. Usually there is a feeling of pressure in the head, the speech becomes thick, slow, and hesitating; the gait a little faltering, with giddiness, and a sensation of numbness in the face, or in the hand. With the relief of the congestion, these symptoms pass off after twenty-four hours.

In the other varieties the symptoms are due either to pressure, or to local lesion and pressure combined. In the serous variety, headache is the first symptom, becoming very intense; at last it is relieved by a sleep, which commonly passes into coma, and the patient dies apparently in sleep. In the hæmorrhagic form, the symptoms come on suddenly: the patient reels and falls, with or without loss of consciousness, or impairment of speech, and on attempting to move he finds that the limbs on one side of the body are powerless. If the hæmorrhage be small, and confined to one lateral ventricle—its usual seat—the intellect is unaffected, but the patient feels faint, and usually vomits. If the hæmorrhage continue, the following symptoms will declare it: increasing, and in the course of a few hours, complete stupor; a slow and noisy, or stertorous and puffing breathing; difficult deglutition; flushed and livid countenance; prominent and motionless eye, and generally unequal pupils. The limbs are either motionless, rigid, or convulsed; and usually more so on one side. The bowels are either obstinately confined, or act unconsciously; the urine also is either passed involuntarily, or, being retained till the bladder is full, dribbles away. The pulse is full, strong, and quick; and often slow. The hemiplegia usually involves the tongue and the face; the latter is not always affected on the same side as the limbs, but the tongue most frequently points to the palsied side.

When the paralysis gradually involves the side which was at first unaffected, we may conclude that the blood has become diffused through both lateral ventricles. In slighter cases the patient does not become unconscious, and the speech is slightly and transiently affected. In other cases the chief indication of the paralytic seizure is loss or derangement of speech.

Apoplexy is sometimes preceded for a considerable time by premonitory symptoms, such as giddiness, pain and a sense of pressure in the head, confusion of ideas, incoherence, loss of memory faltering speech, flushing of the face, bleeding from the nose, noises in the ear, flashes of light, illusions, double vision, transient blindness or deafness, drowsiness, numbness of the limbs, pallor, nausea, vomiting, and faintness.

Terminations. In death, after a variable interval. In almost complete recovery; but usually in partial recovery, with some impairment of the intellect, and partial paralysis of one side; or of one arm only.

Morbid Anatomy.—In *simple* or *congestive* apoplexy, distension of the vessels of the brain, with or without effusion into the ventricles, or at the base. In *serous* apoplexy, serous effusion into the ventricles, or between the membranes. In *hæmorrhagic apoplexy*, blood in the substance of the brain, in the ventricles, at the base, or on the surface.

The most vascular parts of the brain are those in which hæmorrhage is most liable to occur. In 444 cases tabulated by Dr. Aitken, the hæmorrhage happened 268 times in the corpora striata; 39 in the thalami optici; 81 in the lobes of the cerebrum; 22 in the pons varolii; and 34 in the other parts of the encephalon, being at the respective rates of 60, 8, 20, 5, and 7 in the hundred. We often meet with evidence of a seizure previous to the fatal attack, in the form of a recent clot with circumscribed inflammatory softening of the surrounding nerve substance; an old contracted colourless clot containing blood crystals; or a small cicatrised cavity enclosing a little serum.

Diagnosis.—From the effect of spirituous liquors, by the odour of the breath. From the ordinary effect of narcotic poisons, by the history of the case. From both by some difference in the motor power of the two sides of the body; *e.g.*, one pupil may be contracted, and respond to the stimulus of light, while the other is dilated and immovable; the muscles of the limbs on one side may be perfectly flaccid, so that the arm or leg falls from the hand like a mass of inanimate matter, while the muscles of the limbs on the other side are more or less rigid. If the limbs be convulsed, the movements on the two sides will be found on careful examination to be unequal. Sooner or later some such evidence of local injury to the brain will be manifest. To make a correct diagnosis of the exact seat of injury, and form a just prognosis, attention must be paid to the facts enumerated in the diagnosis of partial encephalitis. (See p. 363.)

Prognosis. — *Favourable.* Youth; slight impairment of the intellect and senses; hæmorrhage from the nose or hæmorrhodial vessels; diarrhœa; profuse perspirations; a pulse of natural frequency and character; natural breathing.—*Unfavourable* in proportion to loss of consciousness. A full, hard, jerking pulse; loud stertorous breathing, with a puffing out of the cheeks; repeated shiverings, followed by high fever; repeated vomitings; spasm, rigidity, or convulsions; involuntary evacuations; retention of urine; strong retraction of the paralyzed leg.

Causes.—*Predisposing.* Age, from the fiftieth to the eightieth year: the liability increasing as the age advances. Few cases occur under twenty, and very few indeed in infancy and childhood. A certain make of body, combining a short thick neck, large chest, florid complexion, and stout person; but the disease may occur in persons of the opposite conformation. Hereditary tendency; a sedentary life with overfeeding; suppression of usual *evacuations; plethora;* valvular disease of the heart preventing the free return of blood from the head. The chief *proximate* cause is disease of the cerebral vessels, the several stages of which appear to be fatty degeneration, atheroma, and ossification, giving rise to loss of elasticity and contractility. The vessels become dilated and their coats attenuated, so that the least excitement of the circulation may cause rupture. (See p. 372.)

Exciting.—Violent exercise; strong expiratory efforts, as in singing and playing on wind instruments; straining at stool; fits of coughing; sudden and violent emotions; exposure to intense cold or heat; long stooping, or suddenly rising from the stooping posture; pressure on the neck; venereal excitement; intemperance; narcotic poisons, such as opium; suffocation by drowning, hanging or strangulation, or by the narcotic gases, especially carbonic acid and carbonic oxide.

TREATMENT.—During or immediately after the fit, loosen the neckerchief and shirt-collar, raise the patient's head, or place him, if convenient, in a chair, and open the window of the apartment. When the face is turgid and the eye injected, or, the face being pale, the pulse is full, hard and jerking, we may open a vein in the neck or arm, or partially divide the temporal artery, and allow the blood to flow till the approach of syncope, taking care that the patient does not faint. But when the face is pale and the pulse feeble and intermittent, the patient must be treated as if he were in a fainting fit, and the bleeding must not be practised till re-action has occurred, and the symptoms just stated have appeared.

In the after-treatment, the *indication* is to reduce the action of the heart, and diminish the force of the circulation through the brain.

1. Leeches and cupping glasses to the head and neck.
2. Drastic purgatives, of which croton oil, in doses of one or two drops, is the most easily used and most efficacious. Purgative enemata.
3. Cold to the head, if there be increased heat.
4. Blisters to the nape, and after a time to the scalp.
5. A diet, consisting at first of farinaceous food, passing to a more generous diet cautiously and gradually.
6. If the fit follow a full meal, an attempt must be made to evacuate the stomach by tickling the fauces with a feather, or by an emetic.

If the menstrual or hæmorrhoidal flux have been suppressed, leeches should be applied to the vulva, or anus. When there is profound coma or collapse, we may apply the liquor epispasticus to the nape and strong ammonia to the nostrils, and use a turpentine enema. The hot air-bath, or stimulants, in such cases, have produced reaction; and when this happens, depletion may be necessary.

When apoplexy supervenes after a retrocession of gout or of acute rheumatism, brisk aperients should be given without delay.

If the patient swallow with difficulty, great care is required in giving food and medicine. Medicines should be unirritating and not bulky, and nourishment be given by tea-spoonfuls. The bowels should also be relieved by purgative clysters, and the urine be drawn off twice a day.

On the repetition of the fit, we must again resort to the treatment required in the first attack, but in a less active form. When the patient is convalescent, we may insert a seton in the neck. For sleeplessness and great irritability, opium is the appropriate remedy; but it is contra-indicated in the early stages of apoplexy.

In treating apoplexy, in all its stages, we must take care not to carry depleting measures to an extreme. Undue activity in this respect may lead to fatal consequences, especially in aged and feeble persons in whom it will suffice to keep the bowels somewhat more open than usual, and to regulate the diet, giving wine and other stimulants, according to the state of the pulse.

Prophylaxis.—The patient should take regular exercise in the open air, be abstemious in his habits, keep the bowels free, and avoid tight clothing about the neck or chest. In persons of weak constitution, a light nutritious diet, with a moderate allowance of weak stimulants, combined with astringent chalybeates or acid tonics, should be prescribed; business and study must be laid aside, and all excitement avoided. For the treatment of paralysis following apoplexy, see Paralysis.

CHRONIC DISEASES OF THE BRAIN.

The chief chronic diseases of the brain are softening, atrophy, induration, hypertrophy. The symptoms and diagnosis of these diseases are extremely obscure and uncertain; for the same symptoms may be present in very different states of the organ; and in many cases there are no symptoms to lead us to suspect their existence. Thus, Louis states, that of twenty cases of fungus of the dura mater, three only had cerebral symptoms of any kind; and the same is true of abscesses, hydatids, cysts, and exostoses attaining great size.

1. Chronic Softening of the Brain.

Symptoms.—Those of failing intellectual and physical powers, gradually lapsing into imbecility. The gait becomes shuffling and unsteady, the grasp weak, the speech thick and slow, and the articulation imperfect (*aphemia*, *aphasia*); or the patient may constantly substitute a wrong for a right word (*paraphasia*). There may be similar disturbances in the writing power (*agraphia*). The memory is defective, and the animal functions torpid. A sensation of numbness and pricking affects the hands and feet. The radial and temporal arteries are seen and felt to be tortuous and hard. An "arcus senilis" frequently surrounds the cornea. The patient is liable to attacks of apoplexy. His spirits are usually depressed, he is listless and apathetic, and is easily moved to tears. Such persons are often the subjects of delusions, which usually assume an emotional and sanguine character. They conjure up visions of immense wealth, and great power and dignity, and, if not under restraint, are lavish in their expenditure.

TERMINATION. — Sooner or later in serous or sanguineous apoplexy.

MORBID ANATOMY.—Brain matter paler than usual, and so soft that a gentle stream of water easily washes it away. In extreme cases it is semi-fluid, and has little more consistence than cream. This softening is due to oily matter in large globules, or in a state of minute subdivision. In all cases the blood vessels are diseased, and the condition of the radial and other arteries may be taken as an indication of that of the carotid within the brain. The primary branches are sometimes dilated, thin, and stiffened here and there by patches of atheromatous deposit; sometimes converted into bony tubes. If the softened brain pulp be washed away, a network of atheromatous or bony tubes will be left.

CAUSE.—Defective nutrition of the brain, due to disease of the coats of the blood vessels; to the plugging of large arteries or one of their branches by a clot detached from an inflamed cardiac valve, or aneurismal sac.

PROGNOSIS.—Unfavourable.

TREATMENT.—Gentle exercise in dry mild air, light nutritious diet, with a liberal allowance of wine. Dilute nitric and phosphoric acids in bitter infusions, perchloride of iron and salts of zinc given for a week or two alternately. The patient should sleep with the head and shoulders slightly raised, and avoid all excitement, mental and physical.

2. ATROPHY OF THE BRAIN.

Shrinking of the brain, with effusion of serum around it or within its ventricles, or with thickening of the bones, is a common condition in the insane.

3. INDURATION OF THE BRAIN.

This is probably the result of chronic inflammation. The nerve-tissue is harder and less vascular than usual, pearly white, of the consistence of boiled white of egg. The induration may be partial or general. Convulsive movements are common symptoms of this disease.

4. HYPERTROPHY OF THE BRAIN.

Is a disease of childhood, allied to hydrocephalus, and occurs in children of scrofulous habit. The brain is softer than usual, the convolutions flattened, and the ventricles contracted. Pallor, anorexia, listlessness, occasional headache and giddiness are its symptoms, and death may be preceded by repeated convulsions.

DISEASES OF THE SPINAL CORD AND ITS MEMBRANES.

MYELITIS	Inflammation of the Spinal Cord.
SPINAL MENINGITIS . . .	Inflammation of its Membranes.

OTHER DISEASES OF THE SPINAL CORD.

GENERAL REMARKS.—Diseases of the cord neither affect the intelligence nor the special senses.

As aids to diagnosis of the seat of disease, the following facts must be borne in mind:—

1. Complete transverse section of the posterior columns of the cord entails loss of power to regulate the movements of the parts below the section, and partial injury incomplete control over the muscular movements. Hyperæsthesia occurs in both cases in the parts below the section.

2. Transverse section of the antero-lateral column produces paralysis of motion in the parts below the section on the same side of the body.

3. Transverse section of the whole of the grey central nervous matter causes loss of sensation in all parts below the section. Transverse section of one half of the grey matter results in loss of sensation of the opposite limb below the section.

4. Hence transverse section of an entire half of the cord causes in the parts below the section paralysis of motion with hyperæsthesia on the same side, and loss of sensation only, on the opposite side.

5. Inflammatory irritation in the seat of the disease, causes rigid contraction of the paralyzed limbs. In non-inflammatory disease, or when inflammation has passed away, the muscles are flaccid.

MYELITIS.—INFLAMMATION OF THE SUBSTANCE OF THE CORD.

SYMPTOMS—Dull aching pain in the part affected, with some tenderness; loss of sensation and voluntary motion; or numbness and impaired sensibility, with weakness of the upper or lower extremities, or of both, or of a single limb; or loss of sensation in one extremity, and of voluntary motion in another. The palsied limbs waste; but the reflex function is intact. The muscles of the affected limb may be relaxed, contracted, or convulsed. Sooner or later, retention or incontinence of urine comes on, the motions pass involuntarily, and bed-sores form on the back and hips. At last the patient sinks exhausted, or dies comatose from the extension of the disease to the brain.

The symptoms vary with the seat of the disease. When the *cervical* portion of the cord is affected, the arms are paralyzed, and there is difficulty in swallowing and in breathing, with a sense of tightness *around the* chest, and in the epigastrium. The pulse is *sometimes very slow.* Priapism is often a troublesome symptom.

When the *dorsal* portion is affected, the body is sometimes agitated by continued convulsive motions, and there are palpitations, difficult respiration, and sense of constriction in the abdomen.

When the *lumbar* portion is attacked, the arms and breathing escape, but the legs are paralyzed; and there is retention, followed by incontinence of urine, and constipation, followed by involuntary evacuations from the bowels. Impotence is a common consequence of disease of this part of the spinal marrow.

In some cases the disease comes on insidiously, without pain, and makes slow progress, but is finally succeeded by paralysis of the bladder, rectum, and legs.

Morbid Anatomy.—Inflammation ending in hardening, creamy softening, or abscess of the cord partial or complete. Tubercle.

Causes.—*Predisposing.* The adult age, and male sex.—*Exciting.* Blows and falls; violent exertions; exposure to wet and cold. Caries of the vertebræ; scrofulous disease. Venereal excesses.

Diagnosis.—From other diseases of the cord, by the more complete loss of sensation. The grey matter, the conductor of sensitive impressions, being most vascular, is most liable to inflammation.

Prognosis.—Usually the retained urine produces cystitis with ammoniacal ropy urine, large and deep sloughs form over the sacrum and buttocks, and the patient dies exhausted within three months. Complete recovery is rare.

Treatment.—In the early stage, leeches or cupping to the part affected, followed by blisters, issues, or setons. If there be retention or dribbling of urine, the catheter should be used twice a day, and the bladder washed out with the following: Glycerini acidi carbolici ♏x, aquæ tepidæ ℥x. The patient should lie on a water bed, and the most scrupulous attention be paid to cleanliness. Tonics (Forms. 117, 124) may be given in the chronic stage.

SPINAL MENINGITIS.—INFLAMMATION OF THE MEMBRANES OF THE CORD.

Synonym.—Spinal arachnitis.

Varieties.—1. Acute spinal meningitis. 2. Sub-acute spinal meningitis or spinal irritation. 3. Rheumatic spinal meningitis.

1. Acute Spinal Meningitis.

Symptoms.—Pain in the part affected, increased by motion, percussion, pressure, or heat. The pain, which often closely resembles that of rheumatism, and is brought on, or increased, by motion, extends along the back, and to the limbs, which are sometimes painful to the touch; or it shoots round the abdomen or chest. There are contractions of the back and neck, and of the limbs, varying with the seat of the disease, and assuming the form of trismus, torticollis, partial or complete opisthotonos, or general tetanic spasms. Sometimes there are convulsions, or choreic movements. There is a sense of constriction in the neck, abdomen, or chest, with urgent feelings of suffocation. In some cases the urine is retained and the bowels are confined.

The disease generally proves fatal from the tenth to the fourteenth day, with delirium, coma, or typhous symptoms.

Morbid Anatomy.—Inflammation of the arachnoid and pia mater, with effusion of serum beneath the arachnoid, or in the wide subarachnoid space between this membrane and the pia mater. In some cases inflammation and its consequences in the cord itself.

Causes.—Those of inflammation of the substance of the cord.

Diagnosis.—By the rigid spasm or convulsions, and in many cases by the affection of the bladder.

Prognosis.—Less unfavourable than when the substance of the spinal marrow is inflamed; but attended with considerable danger.

Treatment.—Leeches, and cupping to the part affected, followed by active aperients, a strict antiphlogistic diet, the recumbent posture, and perfect rest. After the bleeding, bags of ice may be applied, and counter-irritants in the neighbourhood of the part. The state of the bladder should be ascertained, and the urine, if necessary, frequently drawn off. Slight mercurialism may be induced. In collapse, the strengtn must be supported by diffusible stimulants and injections.

The chronic form of disease, attended by paralysis with shaking or stiffness of the limbs, requires counter-irritation by issues and setons.

2. Subacute Spinal Meningitis.—Spinal Irritation.

Symptoms.—Pain in the affected part of the spine, increased by firm pressure, percussion, or heat. Pain in the left side, or under the false ribs in all the muscles of the chest, over the whole abdomen, or even in all parts below the seat of disease, with dyspnœa and palpitation, hysteria, low spirits, irritability, constipated or disordered bowels, and flatulence. These symptoms may be aggravated after marriage, or during lactation and pregnancy.

Diagnosis.—By firm pressure with the fingers from the neck to the loins, we discover one or more tender points; and by striking the parts, the pains in the side, chest, or abdomen are either produced or increased. Sometimes these superficial pains are accompanied by convulsive movements of the trunk.

Causes.—*Predisposing*. The female sex. It is common in young females, in whom it is sometimes associated with spinal *disease*.—*Exciting*. Sedentary pursuits, tight lacing, want of active *exercise, constipation*, painful menstruation, leucorrhœa; the original cause and the effect continuing to react upon and increase each other. A tender state of spine is not uncommon in spasmodic asthma and chorea.

RATIONALE.—The tender spine is the middle link between some remote irritation of the uterus or intestinal canal, and the pains in the muscles of the chest or abdomen. The irritation travels through the nerves of the part affected, to the spine, where it shows itself as tenderness, and is thence reflected to the seat of pain. The connection of the muscular pain with the tender spine is shown by the effect of percussion in producing or increasing it; also in exciting convulsions when these are associated with the pain. In those severe cases of spinal irritation which border on acute spinal meningitis, pressure on the spine causes both acute pain and violent convulsive or tetanic movements, and the slightest pressure on the site of the reflected pain will also cause convulsions. Pressure or percussion on other parts of the skin, or on the spine above or below the affected part of the cord, are not attended either by pain or convulsions. (G.)

PROGNOSIS.—*Favourable.* The disease generally yields to treatment; but, if neglected, may assume the acute form, and prove fatal.

TREATMENT.—I. *Local.* Leeches or cupping-glasses to the tender part of the back. Counter-irritation by blisters, stimulant liniments, or tartar-emetic ointment. For muscular pains, emplastrum belladonnæ or opii.—II. *General.* The bowels must be regulated, and tonics, and sedatives of which henbane is the best, be given in combination. Disorder of the menstrual function must be met by appropriate treatment.

3. RHEUMATIC SPINAL MENINGITIS.

SYMPTOMS.—Diffuse pain, often acute, with tenderness near the spine; and severe pain along one arm or leg, according as the disease attacks the lower cervical and upper dorsal, or the lumbar region. After a time the pain and tenderness are limited to a spot on one side, near the spine; which is red and tender, and may become the seat of a herpetic rash. The pain in the limbs continues, with numbness and tingling of the fingers, loss of power, or complete paralysis.

PATHOLOGY.—Rheumatic affection of the fibrous tissues of the spinal sheath, and of the tendons of the neighbouring muscles; with limited cutaneous inflammation.

CAUSES.—*Predisposing.* Those of rheumatism and gout.—*Exciting.* Exposure to cold and wet. Fatigue.

DIAGNOSIS.—From muscular rheumatism by the local tenderness, and loss of power. PROGNOSIS.—Favourable, but guarded.

TREATMENT.—Leeches to the tender spot, followed by warm fomentations; and the remedies for rheumatism. (See p. 349.)

OTHER DISEASES OF THE SPINAL CORD.

Serous effusions occur within the spinal canal, as in the skull; outside the dura mater, within it, or beneath the arachnoid.

Extravasation of blood in the same situations, may be caused by falls, blows, slips, or violent pulling or lifting efforts. But effusion of blood (*spinal apoplexy*) may occur without accident. The symptoms are lumbar pain, spasm of the muscles, palsy of the bladder, rectum, and lower limbs, convulsions or coma, and death.

The membrane of the cord may be thickened and indurated like those of the brain, from the same causes; and fungous growths may form on the dura mater, causing pressure and paralysis. The cord is also subject to atrophy, sclerosis, general or disseminated, hypertrophy, tubercules, carcinora, hydatids, aneurismal and other tumours. The *diagnosis* of some of these affections is difficult, the prognosis in all unfavourable, and the treatment chiefly palliative.

The cord is also liable to *concussion* from falls, and to *compression*. In severe concussion, reflex motions of the limbs cannot be excited. The treatment is that of the like diseases of the brain.

A congenital malformation, known as *Hydrorachis*, or *Spina bifida*, consists in one or more fluid tumours on the lumbar, dorsal, or cervical vertebræ, communicating with the spinal canal. They vary in size, are often transparent, and of a natural, reddish, or livid hue. Pressure causes symptoms of compression. As a rule, the limbs are imperfectly developed, and the rectum and bladder are often paralyzed. The skin may be absent, and the tumour covered only by the membranes of the cord; the pia mater being congested. The spines of the vertebræ are wanting, or more or less widely separated along the median line. The medulla may be cleft, or even absent. The arachnoid cavity contains a serous, sanguinolent or purulent fluid.

These tumours have been treated, but ineffectually, by pressure, or by pressure following repeated tappings with a fine needle. When the integuments are absent or thin, a strong shield must be worn.

DISORDERS OF THE NERVES OF SENSATION.

NEURALGIA	Nervous pain.
NEURALGIA FACIEI . . .	Tic Doloreux.
NEURALGIA HYSTERICA . .	Hysterical pain.
HEMICRANIA	(See Cephalalgia, p. 356.)
NEURALGIA OF PARTS SUPPLIED BY THE LARGER NERVES .	Sciatica. Brachialgia.
ANÆSTHESIA	Loss of sensation.

NEURALGIA.—NERVOUS PAIN.

Pain is a symptom of almost all acute, and many chronic diseases. When it is a distinct affection of the nerves themselves, it is termed neuralgia. It has its seat in the nerves of common sensation, but may affect those of organic life.

Neuralgia has many causes. It is a common sequence of debility following prolonged lactation, long-continued and excessive discharges, or loss of blood. When confined to one side of the head or face, and intermittent, it is generally to be traced to the same cause as ague. It is often due to remote irritation, and is then termed sympathetic. Thus, pain in the shoulder is sympathetic of disorder of the liver, and pains in the upper arm of diseased heart. In these cases a connection is known to exist between the nerves supplying the organ affected, and those going to the seat of pain; but in other instances no such connection can be traced. Thus, tic doloreux may have for its cause acidity of the stomach, an overloaded intestine, or a diseased kidney; but may be due to pressure or irritation at the root of a nerve by a spicule of bone, or foreign body—a common cause of the most severe and inveterate neuralgia. Pain in the glans penis from stone in the bladder, pain in the thigh and testicle from irritation of the kidney, pain in the back of the thigh and leg, and verge of the anus from constipation, and flatulent distension of the hollow viscera, as in colic, are examples of neuralgia from pressure, or direct irritation. Other interesting and important pains are termed *reflected*. Their most common seat is the walls of the chest or abdomen, and the left side. (See p. 254.) Pains of the internal viscera, without signs of inflammation, form another class. Intense neuralgia of an intercostal nerve generally precedes shingles. Gastrodynia, enterodynia, and hysteralgia, are examples of pain in the organic nerves of the stomach, intestines, and uterus. Wandering pains in the muscles are common in aged persons, and in younger men through hard work, or after severe illness. Inflammation of the neurilemma, another cause of neuralgia, combines heightened sensibility with pressure. In most cases of neuralgia, no change can be detected in the nerve structure.

NEURALGIA FACIEI.—TIC DOLOREUX.

Definition.—Pain, with intervals of perfect ease, in some or all of the branches of the sensitive portion of the fifth or trifacial nerve.

Symptoms.—The disease is most common in middle-age, both in men and women. The pain is most acute, comes on at variable intervals, and considerably abates, or entirely disappears, without assignable cause, for days, weeks, months, or even years. At first it is limited to the supra-orbital, infra-orbital, or mental branches, its most frequent seat being the right infra-orbital. It is an acute darting pain, compared to electric shocks, or a severe burning. The pain may be attended by some redness, heat, and swelling of the part. If the eye be affected, there is a large secretion of tears; if the mouth or jaw, a copious flow of saliva. After a time all the branches of the nerve may be affected. If it begin beneath the orbit, it spreads to the upper lip, and thence to the upper and lower jaw; and it may mount over the forehead, spread over the entire scalp, and even for some distance down the spine. The general health is very little affected; the patient, in spite of the most intense suffering, recovers his flesh and healthy aspect in a few days of intermission, and often attains an advanced age.

Causes.—*Predisposing.* The female sex; pregnancy; the nervous temperament; anæmia; debility; fear; grief; anxiety.—*Exciting.* Irritation of the root of the nerve, or of one of its branches; inflammation of the peridental membrane, or a carious tooth; pressure of the bony canal in which the branch lies. Rheumatism.

Diagnosis.—From *hemicrania* and *brow ague*, by the seat and character of the pain.

Treatment.—As the sensitive branches of the trifacial nerve pass through bony canals, to be distributed to the teeth, we must examine the gums for traces of inflammation, the mouth for stumps or carious teeth; and if the pain be due to rheumatism of the sheath of the nerve, or of the periosteum lining the bony canals in which its branches run, it will yield to the appropriate remedies. If the pain be reflected from the stomach, bowels, or kidneys, we must treat the indigestion, constipation, and renal affection. In anæmia, iron alone or combined with quinine is generally successful. The saccharated carbonate or peroxide of iron, and also hydrochlorate of ammonia in doses of 30 grains thrice a day are occasionally successful, especially when the pain is confined to the jaws.

The best local applications are the inhalation of chloroform; or equal parts of chloroform and laudanum, rubbed into the gums, or over the painful nerve, linimentum chloroformi, linimentum belladonnæ, and veratria or aconitia ointments externally.

In a case of many years' standing, which had spread from the right infra-orbital nerve to the upper and lower jaw, over the scalp and down the spine, attended by excruciating suffering, after tonics and narcotics, bleeding, blistering, and salivation had afforded no relief; a stream of cold water poured on the forehead, and allowed to trickle over the face and neck, procured refreshing sleep in about five minutes, had the same effect on a repetition, was followed by the first good night the patient had had for weeks, and by a long interval of comparative ease. In this case the paroxysms were always accompanied with redness of the parts, and increased heat of surface. Where these characters are absent, cold may be expected to prove less efficacious. The patient died ætatis 76, having been a great sufferer for at least 25 years. (G.)

NEURALGIA HYSTERICA.—HYSTERICAL PAIN.

Hysterical women are subject to severe neuralgia, without evidence of local or constitutional disease. It may affect any part, and have its seat in a particular joint or bone; it may be superficial and seem to be imaginary; and disappear when the patient's attention is diverted from it. Rough handling gives no more pain than a slight touch; but that the pain may be both real and severe there is no doubt:—*e.g.* a healthy, unmarried woman about forty, complained of intense and constant pain in one knee. There was no evidence whatever of disease. Every kind of counter-irritation and of constitutional treatment had been adopted, and after repeated treatment as an in-patient in the infirmary, the surgeon yielded to her importunities, and amputated the leg. The knee-joint was perfectly healthy, and no disease of its nerves could be detected. After two years she was admitted for a similar pain in the other knee; and she entreated the surgeons one after another to amputate the leg; but they did not yield a second time to her solicitations. In another case there was a most acute pain in a small spot in front of the tibia; and the surgeon, thinking there was an abscess in the bone, trephined, but no disease was met with. The pain soon returned in the part, and continued for more than a year, at the end of which time the surgeon yielded to her wish, and amputated the leg. No cause for the pain could be detected.

In these cases the shower-bath as a tonic, bromide of potassium, and the light application of the actual cautery in lines to the affected part, afford the best chance of relief.

NEURALGIA OF PARTS SUPPLIED BY THE LARGER NERVES.

1. Sciatica.—*Symptoms.* Acute aching or darting pain along the course of the sciatic nerves from the nates to the knee, or even to the ankle: generally increased by firm pressure in the track of the nerve.

2. Brachialgia.—*Symptoms.* Pain of the same character as that of sciatica in the brachial plexus itself, or in one of its branches, and usually some tenderness in and near the axilla. When the ulnar nerve is affected, the pain radiates down the inside of the forearm to the hands, and involves the little and ring fingers. It is severe and paroxysmal, and readily excited by cold. After a time, the sensation of the little finger and ring finger is diminished. Some part of the motor fibres are usually implicated; and lead to contraction and diminished power of the fingers, or actual atrophy of the little muscles on the inner or outer part of the hand.

Causes.—In sciatica the pressure of accumulated fæces; in both diseases, the pressure of tumours on the nerve, and syphilitic or rheumatic affection of the sheath.

Diagnosis.—From *muscular rheumatism* by the pain being limited to the course of the nerve, and being little, if at all, affected by the motion of the limb.

Treatment.—The warm or vapour bath. Friction. Aperients so administered as to keep the bowels free. The general and local remedies recommended in neuralgia faciei. The subcutaneous injection of morphia or atropia at intervals not shorter than three or seven days. For precautions see 16 of the list of narcotics, &c., in the Formulæ.

I have seen several cases of sciatica, unrelieved by the remedies usually given in neuralgia, speedily cured by a few doses of compound colocynth pill, each followed by a black draught. (G.)

ANÆSTHESIA.—LOSS OF SENSATION.

Varieties.—*Anæsthesia*, paralysis of the nerves of sensation; *amaurosis*, of the retina; *cophosis* of the auditory nerves; *anosmia*, of the olfactory nerves; *ageustia*, of the gustatory nerves.

Anæsthesia, or loss of common sensation, may occur separately or with palsy of the voluntary muscles; may be general or partial, and may affect one side or both. It is an effect of one form of leprosy, and an occasional result of rheumatic neuritis. Facial anæsthesia is a well-known form of this disease. Numbness, in the hands and forearms, is an occasional symptom in Mimosis inquieta. (See p. 261.)

Treatment.—If induced by pressure, the cause must, if possible, be removed; if by deficient supply of blood, stimulants should be resorted to; if by cold, the circulation must be restored. In other cases the treatment will be that of the diseased conditions with which it is associated. It is rare as a separate malady.

Anæsthesia Faciei.

Symptoms.—Numbness or total loss of sensation in the forehead, cheek, nose, and chin, on one side of the face; also in the lips, tongue, inside of the mouth and nose, and surface of the eyeball, generally accompanied by paralysis of the temporal and masseter muscles on the same side. This loss of sensibility is sometimes attended by intense pain of the parts affected.

Terminations.—In some cases ulceration of the cornea and destruction of the globe of the eye.

Pathology.—Disease, compression, or mechanical injury of the fifth pair of nerves.

Prognosis.—*Favourable*, in the absence of anæsthesia or palsy of other parts. *Unfavourable*, if complicated with disordered functions of other cerebral nerves, or with symptoms of disease of the brain.

Treatment.—Leeches to the temples, followed by fomentations. Slight mercurialism; the continuous current. If the disease, in spite of this treatment, become chronic, small blisters in front of the ear, kept open by savin ointment.

DISEASES CHIEFLY AFFECTING THE NERVES OF VOLUNTARY MOTION.

- PARALYSIS
  - 1. HEMIPLEGIA.
  - 2. PARAPLEGIA.
  - 3. PARTIAL PARALYSIS.
  - 4. FACIAL PALSY.
- GENERAL PARALYSIS.
- BULBAR PARALYSIS.
- SCLEROSIS.
- PARALYSIS AGITANS.
- INFANTILE PARALYSIS.
- LOCOMOTOR ATAXY.
- WASTING PALSY.
- LEAD PALSY.
- MERCURIAL TREMOR.
- CHOREA.
- TETANUS.
- HYDROPHOBIA.
- CATALEPSIA.
- HYSTERIA.
- EPILEPSY.

PARALYSIS.—PALSY.

Paralysis, although only a symptom of disease. may, like dropsy, be conveniently considered under a distinct head.

VARIETIES.—1. Hemiplegia; 2. Paraplegia; 3. Partial Paralysis; and other forms of palsy, as above.

1. HEMIPLEGIA.

DEFINITION.—Loss of motion, or of motion and sensation, of one lateral half of the body.

VARIETIES·—Cerebral, Spinal, Epileptic, Choreic, Hysterical, and Peripheral.

SYMPTOMS.—In cerebral hemiplegia, the limbs of the affected side, if raised, fall by their own weight; the face usually on the same side is relaxed and void of expression, and drawn to the sound side; the tongue may deviate towards the palsied side: the speech is either lost, or it is thick, muttering, and unintelligible. In rarer instances, the mouth is drawn to the affected side, and the tongue protruded towards the sound side. Digestion is more or less imperfect. The loss of power is generally accompanied by anæsthesia, but in a few instances by hyperæsthesia; the temperature of the affected side is generally lowered, but occasionally raised. The mental faculties are sometimes unimpaired; but they frequently suffer, as shown by impaired memory, confusion of thought, inattention, irritability of temper, and depression. The pulse is often infrequent, but sometimes accelerated; and the breathing slow. The bowels are generally inactive. If the patient do not speedily recover, the palsied limbs shrink and grow cold. When the disease is partial, the arm is more commonly affected than the leg. If the power of the limbs be impaired, but not lost, the arm will be raised with difficulty, and often not without the assistance of the other, the hand cannot grasp firmly, the leg will be dragged after the sound limb, and in walking the patient will be very liable to trip. In patients who recover, the leg regains its power first; so that they can walk about, while the arm still remains palsied; but to this rule there are many exceptions.

Hemiplegia is most common on the left side. It usually occurs suddenly, constituting the "paralytic stroke."

Spinal hemiplegia.—In this very rare form the face and intellect are unaffected.

Epileptic hemiplegia.—After an epileptic fit, the limbs of one side remain paralyzed for a few minutes, sometimes hours, or days, or even much longer. Recovery usually takes place before the next attack.

Choreic hemiplegia sometimes occurs on that side of the body which is most affected by the choreic movements.

In *Hysterical hemiplegia* the palsy is incomplete, and limited to an arm or leg. In walking the leg is dragged along the ground.

The *Peripheral hemiplegia* of Dr. Todd, or *Creeping palsy* of Dr. Cheyne, commences with the sensations of "needles and pins" in the fingers or toes, and gradually creeps upwards, and, more or less, completely involves the extremities. The affection is occasionally paraplegic.

Causes.—Sudden and *complete* hemiplegia, or the "paralytic stroke," is invariably caused whenever the corpus striatum, or any part of the motor tract intervening between it and the medulla oblongata, is ploughed up by sanguineous effusion, as in the graver forms of apoplexy (see p. 368): or when it is subjected to pressure from effusions or tumours in its neighbourhood. If the disease come on slowly, it has for its cause a growing tumour or a softening of the nerve tissue. In the latter case, a weakness and numbness of the one side of the body may suddenly lapse into complete hemiplegia, from sudden lesion of the softening fibres without hæmorrhage.

Incomplete hemiplegia is the result of pressure or lesion of one side of the spinal cord, immediately below the decussation of the antero-lateral columns. The paralysis of motion is on the same side as the lesion, the paralysis of sensation on the opposite side.

Diagnosis.—Even in mild cases, cerebral hemiplegia is always associated with more or less paralysis of the face and tongue. In more severe cases the intellect is disturbed, speech is imperfect or obsolete, deglutition is more or less difficult.

In spinal hemiphlegia, the head, face, and tongue are unaffected, and sensation is impaired on the opposite side to the paralysis of motion.

Epileptic hemiplegia is of cerebral origin, and may be known by the history of the case.

Choreic hemiplegia is usually associated with some slight jerking movements of the paralyzed limbs; the face is unaffected; and the tongue is usually protruded and withdrawn in a characteristic manner.

Hysterical hemiplegia is known from choreic, by the presence, or previous existence, of hysterical symptoms.

PROGNOSIS.—*Favourable.* Youth; a recent, partial, and incomplete attack, without cerebral symptoms; a return of sensation, tingling, and increased temperature.—*Unfavourable.* In proportion to the age, the duration of the disease, and the degree of paralysis.

With a view to more correct diagnosis and prognosis cases of cerebral hemiplegia may be arranged in three classes.—1. Those in which the muscles of the paralyzed limbs are completely relaxed, the limbs being loose and flaccid, and the muscles wasted.—2. Those in which the paralyzed muscles exhibit a certain amount of rigidity from the moment of the attack or soon after. The muscles retain their plumpness and the limbs resist extension.—3. Those in which the wasted and relaxed muscles acquire, after some time, more or less tension, becoming shortened and feeling like tight cords. The phenomena of the first class probably result from white softening of the brain. Those of the second class are caused by irritation of healthy brain tissue in the neighbourhood of the clot at the time of its formation, and subsequently during the processes of absorption and contraction. The muscular phenomena of the third class result from lesion of softened nerve-fibres, with or without the formation of a clot, the late rigidity resulting from the irritation caused by slow cicatrization of the wound, and the consequent dragging upon the healthy neighbouring brain substance.

2. PARAPLEGIA.

DEFINITION.—Loss of motion, with more or less impairment of sensation of the lower half of the body; or of the whole body except the head; or, the head not excepted, coupled with complete insensibility (coma.)

The term paraplegia is usually applied to palsy of the lower half of the body.

VARIETIES.—1. Organic, functional, or reflex. 2. From constitutional disorder.

SYMPTOMS.—Like other forms of paralysis, organic paraplegia may occur suddenly or come on gradually. It is not often complicated with head symptoms. The extent of the paralysis will depend on the seat of the lesion. (See p. 363 and 373.) When the disease affects the lower part of the cord, and the paralysis is complete, there is complete loss of sensibility and motion in the lower extremities, with palsy of the bladder and rectum. The patient being confined to the horizontal position, the back and sacrum are apt to slough. The retained urine is generally highly ammoniacal, and ultimately becomes bloody and it is prone to form calculous deposits.

In less complete forms of paraplegia there is weakness of the legs, with a sensation of stiffness and heaviness, numbness, tingling, or formication, and an awkward, straggling, tottering gait. These symptoms gradually increase till perfect paraplegia, with paralysis of the bladder and rectum, results. In many cases the disease does not prove fatal till it has involved the arms, chest, and muscles of respiration. If the disease extend still higher into the cervical region, the roots of the phrenic nerve become involved, and life then necessarily ceases.

In many cases of paraplegia, and especially in the more complete forms, the reflex function remains intact, and irritation of the sole of the foot occasions involuntary muscular contractions. Sometimes these reflex movements are very troublesome, the limbs being affected for hours together with clonic spasm. In paraplegia resulting from spinal concussion reflex movements are absent.

CAUSES.—Injuries to the spinal cord. Chronic disease of the cord or of its membranes; increasing pressure from growing curvature of the spine; caries of the vertebræ and relaxation of the spinal ligaments; plugging of the aorta.

Functional paraplegia has many causes, amongst which the most common are intense cold, excessive sexual intercourse, masturbation, syphilis—a very frequent cause of organic disease. Many cases of incomplete paraplegia have been referred to nervous action, and have been termed accordingly "*Reflex paraplegia*," or "*Reflex paralysis*." Gonorrhœa, stricture of the urethra, nephritis, cystitis, uterine diseases and displacements, dysentery, dentition, and even irritation of the cutaneous nerves have been mentioned as causes of reflex paraplegia.

In such cases, the paralysis is supposed to be due to the arrest of the circulation in the spinal cord, from contraction of its blood vessels, the contraction being produced by an irritation transmitted om the nerves of the diseased or irritated surface to the nerves f the blood vessels distributed to the cord. The arguments in vour of such a theory are as follows:—1. Brown Séquard noticed ntraction of the vessels of the pia mater of the cord on applying ligature to the hilus of the kidney, or to the blood-vessels and rves of the supra-renal capsules. 2. Violent rigors and even vulsions (affections generally recognized as due to reflex irrita-) occasionally attend catheterism or dilatation of the cervix uteri. he absence of anatomical lesions of the cord in such cases of tional paraplegia as have been examined.

OGNOSIS.—*Favourable*, in functional disorder; but *highly unrable* in cases of actual disease of the cord or brain. In the favourable cases recovery generally occupies weeks or months: favourable cases, the patient may linger for years.

ATMENT.—For the acute stage, see Apoplexy, Myelitis, Arachnitis, and other diseased conditions of the brain and marrow.

n the disease has become chronic, we may resort to the ent chalybeate tonics, such as the perchloride of iron; nineral acids; to *quinine* when the system will bear it; but lysis from cerebral apoplexy we must intermit its use, if it s heat and pain of head. *Strychnia*, in doses of $\frac{1}{30}$ of a *vo or three times* a day, cautiously increased to the $\frac{1}{16}$ may be given with advantage. Its action on the system is indicated by twitchings of the paralyzed muscles; but these, taken as indications of returning power are delusive, as they depend on an affection of the excito-motory nerves. *Tincture of cantharides* (Form. 10) is useful in some cases of paraplegia, especially in that form which depends on disease of the urinary organs. It stimulates the bladder to more healthy action, and in cases dependent on effusion into the sheath of the spinal marrow, may act favourably as a diuretic. *Oil of turpentine*, in drachm doses, suspended in mucilage, may also be given with advantage in the same cases in which cantharides is beneficial.

Paralysis from constitutional disease or reflex action must be treated according to the cause. (See Syphilis, Hysteria, &c.)

As local remedies:—Friction with the flesh-brush, or stimulating liniments; blisters; the actual cautery; electricity. To apply electricity we must include the part we wish to operate upon between the two conducting wires of the battery, one wire or electrode being placed on the affected part, and the other over the nerve-centre or nerve-trunk corresponding to the affected organ. The muscles are excited through the skin.

Electricity may be applied in the following modes:—1. By including the part between two electrodes ending in sponges soaked in salt and water, and inclosed in metallic cylinders. 2. By including the part between two solid metallic electrodes, cylindrical or conical, and moving them rapidly over the affected parts. 3. By the *electric brush;* the sponges being replaced by a brush of fine metallic wires. 4. By placing the hands or feet in two basins of water, each containing one of the electrodes of the battery. The magneto-electric battery is the best generator of currents for medical purposes.

In applying electricity, it should be understood that, when the current is intense, and its action prolonged in the same direction, the excitability of the nerves is much enfeebled; so that to give tone to the nerves, we must pass feeble currents alternately in opposite directions; but with quick intermittencies, to maintain the contraction of the muscle, and increase its force. We thus imitate the voluntary motions. Slow intermittencies only produce trembling.

In anæsthesia, the most intense currents fail, if they do not succeed each other very rapidly. In the treatment of this, as of muscular atrophy, we must use currents with rapid intermittencies, which, it should be understood, are in direct proportion to the rotations of the armature in front of the magnet.

The cases of paralysis in which electricity is beneficial, are those caused by apoplexy of the brain or cord; but it must not be used till all irritation has ceased, until the absence of pain and lax state of the paralyzed muscles show that the clot has been absorbed.

In addition to electricity, we may use salt-water baths, *shampooing*, the warm or hot-water *douche*, and, when the power of the extremities has in some degree returned, exercise. These remedies also are inapplicable in the early stage of the paralysis that depends on acute disease of the brain or spinal cord. They should not be resorted to till inflammation has ceased, and the disease has become chronic.

When the urine is retained, the catheter should be used at least once a day; and if it become ammoniacal or bloody, the bladder should be washed out with dilute carbolic acid water (1 part in 30). Bed-sores must be carefully prevented by the use of the water-bed or cushion, and by rigid attention to cleanliness.

3. Partial Paralysis.

Particular muscles or groups of muscles, and especially the muscles of expression, are subject to paralysis from injury or disease of the nerves distributed to them. Injury or disease of the motor portion of the fifth nerve, gives rise to a less common form of partial paralysis. *Strabismus* may be caused by palsy of one or more of the muscles of the eye. The paralysis of the superior branch of the third or *motor oculi* nerve occasions falling of the upper eyelid and closure of the eye (*ptosis*); and disease of the facial nerve entails, as one of its consequences, an open state of the eye due to paralysis of the orbicularis palpebrarum (*lagophthalmia*); paralysis of the laryngeal nerves occasions *aphonia;* and paralysis of the hypoglossal nerve, loss of speech.

4. Facial Paralysis.

The *motor* nerves of the face being the portio dura, and the lesser root and third division of the fifth, and the *sensitive* nerves the first and second divisions, with the ganglionic portion of the third division, of the same nerve, it is easy to trace facial paralysis to its source. In complete paralysis of the face, the portio dura and motor branch of the third division of the fifth suffer jointly: when the latter only is affected, the motions of the jaw on that side are paralyzed, and there is usually some loss of sensation: but as the disease is confined to the muscles employed in mastication, there is no distortion of feature, beyond a flattening of the affected side of the lower jaw, and of the temple.

Symptoms.—In palsy of the muscles supplied by the facial nerve, the expression is very characteristic. The features are drawn to the sound side, making it appear shorter and narrower than the paralysed side. The two sides wear so different an expression that the patient is said to laugh on one side and cry on the other. He is unable to frown on the affected side, and when desired to shut the eyes, the eye of the sound side is firmly closed, while that on the palsied side is either partially closed or remains wide open, the pupil, at the same time, being rotated upwards or inwards. In sniffing, the nostril of the affected side collapses; in blowing, the air escapes from the paralyzed side. The saliva may dribble from the palsied side, and the food either slips from the mouth, or collects between the teeth and cheek, which is often bitten. The patient *cannot whistle, and* when he laughs, cries, sneezes, or coughs, the deformity is increased, the paralyzed side remaining motionless, while the sound side is strongly contracted. The cheek on the affected side is flaccid, and swells during strong expiration. The labial consonants, *b*, *p*, and *f*, are imperfectly sounded; but the patient can speak distinctly when the lower lip on the affected side is supported by the finger. The sensation of the palsied side is generally unimpaired.

Fig. 54.



The woodcut (Fig. 54) shows the expression of the face in a patient of King's College Hospital suffering from this disease. The right side is the seat of the paralysis; and the two sides present the striking contrast just described, the right having a sad, and the left a merry, expression—a difference readily perceived by covering one side of the face and then the other.

The second woodcut (Fig. 55) taken from a sketch of another patient of King's College Hospital, shows the expression of the face during the effort to close the eyes. Here the left side is the palsied one: and the eye of that side cannot be closed, while the right eye is firmly shut. The whole face is drawn forcibly to the sound side, all the features of which are strongly contracted.

Fig. 55.



Fig. 56 exhibits paralysis of the left facial nerve in a child, with inability to close the left eye.

These illustrations of paralysis of the facial nerve may be advantageously compared with the woodcut (Fig. 57), which shows the state of the face in a well-marked case of hemiplegia affecting the left side. The eyelids of the paralytic side are closed, though less firmly than those of the sound side, while the features of the two sides present the same contrast, though in a less degree than in Figs. 54 and 55. (Figs. 56 and 57 are from Marshall Hall's "Principles of Medicine.")

Fig. 56.



Diagnosis.—In paralysis of the facial nerve alone there is an absence of cerebral symptoms; the face retains its sensibility; the function of hearing is intact: the pupil is unaltered, and the eyesight unaffected (except as the result of the open state of the eye); the muscles of mastication retain their power; the speech is only affected as above stated, and is distinct when the paralyzed lip is supported by the finger. Complication with deafness would show that the other division of the seventh nerve was affected; the addition of anæsthesia that the fifth nerve was also implicated; and cerebral symptoms would indicate that the seat of the disease was within the skull and not external to it. Hemiplegic paralysis is known by disorder of innervation in the limbs.

Fig. 57.



Ptosis, or closure of the eye from palsy of the superior branch of the third nerve, is a more serious disease than palsy of the facial nerve, being more probably due to intercranial disease.

Prognosis.—*Favourable.* When the paralysis does not extend beyond the parts supplied by the facial nerve. The disease is often cured in about three weeks or a month. — *Unfavourable.* Complication with paralysis of other nerves, or with disease of the brain.

Sequelæ.—Inflammation of the conjunctiva, and in rare cases, ulceration of the cornea, and destruction of the eye, of the affected side.

Causes.—*Tumours* within the cranium, or disease involving the *root of the nerve.* Wounds and mechanical injuries. Disease of the petrous portion of the temporal bone in the vicinity of the tympanum. The caries resulting from scarlet fever often erodes the wall of the Fallopian canal, and the nerve, being laid bare, its function is lost. Pressure due to tumours of the parotid; effusions into and around the sheath of the nerve. Cold winds.

Treatment.—Simple paralysis of the face is best treated by small doses of mercurial preparations carried to the point of producing slight salivation. If inter-cranial disease be the cause of the palsy, and febrile symptoms be present, cupping or leeches behind the ear, followed by a blister to the same part, and preparations of iodine and mercury.

Parotitis must be treated as recommended under that affection. Caries of the internal ear, by daily injections of warm water, followed by weak solution of sulphate of zinc, by tonics, and attention to the general health.

GENERAL PARALYSIS, OR PARALYSIS OF THE INSANE.

Definition.—A form of progressive paralysis attended by gradual loss of mental power.

Symptoms.—These first appear in the tongue, causing indistinctness of speech and faulty or stammering pronunciation; it affects the muscles of both sides of the face, impairing the power of expression, and thence extends to the whole of the muscular system. The commencing palsy of the legs is indicated by slight lameness and occasional tripping, and that of the arms by the frequent dropping of food and other objects from the hand. The progress of the disease is gradual, but it terminates at length in complete paralysis, with palsy of the bladder and sphincter ani, of the muscles of deglutition, and of respiration. The patient often dies asphyxiated. The sensibility is little impaired. The common duration of this malady is four or five years. The palsy of the muscles is accompanied by loss of mental power.

Pathology.—Degenerative change in the grey matter, resulting from constitutional disease, or concussion of the brain.

Morbid Anatomy.—Osseous cicatrices, adherent dura matter, thickening and opacity of the meninges, chronic effusion of fluid into, and granular deposit upon, the surfaces of the ventricles.

Diagnosis.—This disease usually affects the male sex, and individuals in the prime of life. An able, intelligent man becomes unmindful of his work, and soon unable to attend to it. He sits listlessly with his hands before him, and his mind vacant. Sometimes he is mischievous, rarely dangerous. Imperfect speech and tottering gait attend loss of memory, and then the patient passes more or less rapidly into a state of imbecility.

In many cases, the cerebral symptoms are much in advance of those of the spinal.

Prognosis.—Being dependent on progressive degeneration of the brain, it does not admit of cure.

Treatment.—That of Cerebral Softening (see p. 372).

PARALYSIS LABIO-GLOSSO-PHARYNGEA. PROGRESSIVE BULBAR PARALYSIS.

Definition.—Increasing defect of speech and of deglutition, from diseases of the motor centres in the medulla oblongata, and usually associated with general paralytic symptoms and imbecility.

Symptoms.—Defective articulation, a monotonous nasal voice (imperfect modulation), frequent tendency to choking (imperfect deglutition), and weakness of the muscles of mastication, and labiation, attended with salivation, are the earliest indications of the disease. Emotional disturbance, with a tendency to crying, or more rarely, laughter, and general muscular debility often supervene. Progressive muscular atrophy and mental weakness attend the increased difficulty of articulation, and deglutition. The atrophied tongue lies motionless or slightly quivering on the floor of the mouth, incapable of protrusion; a constant flow of ropy saliva requires the constant use of the handkerchief. Later on paralysis involves the respiratory function, and, if the mind remain clear, as it does in some cases, there is a great fear of death by suffocation. The progress of the malady is variable. Three years may, perhaps, be taken as the average duration.

Morbid Anatomy.—Atrophy of the nerve nuclei in the floor of the 4th ventricle, and of the nerve fibres connected with them. This is usually associated with diffuse sclerosis of the medulla and spinal cord. Atrophy of the muscles of the thenar and hypothenar aspects of the hand is not uncommon.

Prognosis.—Very unfavourable.

Causes.—A nervous temperament with advancing age. The disease is rare before 40. In all prolonged emotional excitement, or exhaustion from anxiety and loss of sleep are exciting causes.

Treatment.—Tonics, especially iron and strychnia, sedatives if required, quietude, with agreeable diversion of the mind.

An acute form of the disease.—*Acute bulbar myelitis*—has been described. The local paralytic symptoms appear suddenly, and deglutition soon becomes nearly impossible, the breathing irregular and oppressive, and the distress is increased by hiccough, frequent vomiting, and fits of suffocating coughing.

MULTIPLE SCLEROSIS.

Definition.—A decidedly chronic degeneracy of the brain and spinal cord, or of either separately, producing partial or general paralysis, with or without loss of intellectual powers corresponding to and co-extensive with the morbid changes.

SYMPTOMS.—Extremely variable, according as the cord or brain is most involved; and as the disease is localized or generally distributed. Motor paresis, increasing to paralysis, beginning in one leg and extending to the other and to the arms; tremor of the limbs, or of the whole body on making a voluntary effort (volitional tremor); marked increase of tendon reflexes, making the gait very stiff, the feet seeming to cling to the ground, and the toes catching every obstacle; an irritable contracted condition of the muscles; the legs feeling hard and rigid when the least attempt is made to use them, are amongst the earliest and most constant symptoms. Inability to co-ordinate movements, and disturbances of sensation—paræsthesia, sometimes passing into anæsthesia, appear sooner or later as the paraplegia advances. Diplopia, nystagmus, often very marked, and amblyopia may be looked for. The voice, too, may become weak and monotonous, and the speech slow and indistinct. Later on the intellect may be involved, indicated by loss of memory. Emotional disturbances, insomnia, headache, and melancholia, attacks of vertigo, and even of apoplexy, occasionally supervene.

MORBID ANATOMY.—The altered condition of the nervous tissue is obvious to the naked eye, as greyish yellow or salmon coloured spots or nodules, varying in size from a grain of rice to an olive, scattered through any or every part of the nervous system. They are usually well defined, and of a dense, often leathery consistence, distinguishable by both the finger and the knife. Very rarely they are of gelatinous consistence; they may be discrete or confluent. Under the microscope, increase of connective tissue, with many lacunar cells, and the atrophy and disappearance of nerve cells and fibres are witnessed. Corporea amylacea, fat and granule cells, with degeneration of the walls of the blood vessels indicate an advanced stage.

CAUSES.—The chronic inflammation in which the morbid changes begin, are those which have been mentioned under Myelitis.

DIAGNOSIS.—The tremor which is initiated by voluntary movement, subsiding during rest, serve to distinguish multiple sclerosis from locomotor ataxia and chorea; but it is difficult, if not impossible, to draw a distinction between this disease and paralysis agitans, and probably no real pathological difference exists between them.

TREATMENT.—In the early stages, that of myelitis, and in the latter that of paralysis agitans.

PARALYSIS AGITANS.—SHAKING PALSY.—THE TREMBLES.

SYMPTOMS.—Weakness and trembling, usually commencing in the hands and arms, but sometimes in the head, and gradually extending over the whole body. At length the trembling becomes incessant, and when the patient attempts to walk, "he is thrown on the toes and fore part of the feet, and impelled unwillingly to adopt a running pace, being in danger of falling on his face at every step." In a still more advanced stage, the shaking continues during sleep: the patient cannot carry food to the mouth; and mastication and deglutition are performed with difficulty. The agitation at length becomes so violent as to prevent sleep; the body is bent forward with the chin upon the sternum; articulation is impaired or entirely lost; the urine and fæces pass involuntarily, and coma and slight delirium close the scene. In some cases the muscles of respiration are affected, and the breathing becomes extremely frequent. (In one case occurring in a vigorous young man, 73 in the minute, with a pulse of 72.—G.)

Morbid Anatomy.—Multiple or diffuse sclerosis, chiefly or exclusively confined to the anterior grey columns of the cord.

Diagnosis.—Tremor, and a shuffling, hurried gait and speech. Sclerosis is described at p. 392. It is distinguished by a progressive muscular weakness, increasing to paralysis; whereas, in paralysis agitans the tremor always appears first, and the paralysis is usually long postponed.

Prognosis.—Unfavourable in old persons. Less unfavourable when, as in rare instances, it occurs in persons in the vigour of life

Causes.—*Predisposing.* The male sex, advanced age.—*Exciting.* Violent exertion, mental or muscular; cold, rheumatism.

Treatment.—In persons advanced in life a combination of stimulants and sedatives is indicated. Conium and henbane are useful in the early stages; preparations of iron and galvanism in the later.

INFANTILE PARALYSIS.

This has been described under the term *Polio-myelitis anterior.* It consists in more or less complete and chronic hemiplegia, with atrophy of the paralyzed limbs.

Symptoms.—After a convulsive attack, attended with coma, more or less prolonged, the little patient recovers consciousness, and it is then discovered that there is loss of one side of the body, or of an arm or leg. The subsequent progress of the case is precisely that of ordinary hemiplegia. Sometimes the recovery is complete, but usually a certain amount of paralysis remains, and in some cases the arm or the leg may remain ever after perfectly useless, in which case the whole member remains atrophied.

Pathology.—It is commonly assumed that this affection is due to an acute myelitis of the grey anterior columns of the spinal cord; but all my cases tend to prove that the affection is a cerebral one, and that, as in ordinary hemiplegia, the lesion occurs in the *corpus striatum of the opposite* side. During an attack of ordinary convulsions, from dentition for example, blood is extravasated, and a portion of the motor tract corresponding to the lesion is torn across.

Treatment.—That of cerebral irritation in the early stage, and of hemiplegia in the later.

LOCOMOTOR ATAXY.—TABES DORSALIS.

Definition.—An affection of the lower extremities not amounting to paralysis, but consisting of a want of co-ordinating power.

Symptoms.—The muscular contractions are still, to some extent, obedient to the will, nor is there want of strength; but the movements are clumsy, staggering and uncertain, and the patient cannot walk steadily unless he *looks* at his legs, in order to guide their movements. He has great difficulty in rising from his seat, and in turning round is apt to fall. The disease may affect the muscles of the upper extremities, in which case the movements of the arms and hands become awkward and fumbling. There is no direct muscular wasting.

Diminished sensation is a constant attendant on this condition, and is generally proportionate to the want of co-ordinating power.

Lancinating pains in one or both of the legs occurring at intervals, and with every change of weather, or after exertion, almost invariably attend the disease in the earliest stages, and may exist without any other indication for years. Slight defects of sight and hearing are not uncommon, and progressive blindness is an occasional complication. The mind, usually clear, is also subject to a gradual impairment.

Diagnosis.—The "ataxic gait." There is little if any loss of power in the legs, but their movements are clumsy and wide of the mark; the toes are thrown upwards, and the heel is brought down with a stamp, and the eyes are vigilant to sustain the tottering body.

Prognosis.—Most unfavourable.

Cause.—Over exertion and exposure to cold and damp are predisposing causes; direct injury or irritation of the cord and venereal excesses and syphilis the exciting. Men between the ages of thirty and forty are the most liable to the disease.

Pathology.—Chronic myelitis of the posterior columns involving the bundles of the posterior nerve-roots, and the posterior grey horns, also resulting in atrophy of the nerve fibres, and cells with shrinking and hardening of the affected part, which becomes greyish yellow and translucent, and frequently exhibits a number of corpora amylacea. The upper lumbar and dorsal regions of the cord are those usually affected.

Treatment.—Some good may be expected from the judicious use of galvanism and alterative tonics.

WASTING PALSY.—SPINAL SCLEROSIS.

This is a form of partial or general paralysis, slowly progressive, and invading particular groups of muscles, or the whole of the muscular system, the intelligence remaining intact.

Fig. 58.



Pathology.—The affected muscles slowly waste until they are reduced to pale cords streaked with fat, or to mere bands or membranes composed chiefly of fibrous tissue.

The muscles of the upper extremity are most liable to the disease, and those of the ball of the thumb are most commonly affected. The hand through the wasting of its muscles, comes to resemble the foot of a bird—the "main en griffe" of French writers. When the muscles of the *face* are affected, expression is lost, and, but for the *motion of the eyes*, the countenance is as fixed as that of a statue.

The accompanying figure, from the photograph of a patient who was for many years under my care at St. Thomas's Hospital, well illustrates the outward signs of spinal sclerosis. The hands and legs are quite bird-like, and from atrophy of the muscles of the leg and foot he was unable to stand, unless the feet were braced in stout boots.

The brain is unaffected, and the general health good.

Morbid Anatomy.—General or local atrophy of the anterior roots of the nerves, and of the antero-lateral columns of the cord, increase of the neuroglia and atrophy of groups of the nerve vesicles. The deposit of semi-translucent, tough, greyish nodules varying in size from a millet seed to a hazel nut, composed of connective tissue (interstitial chronic myelitis).

Diagnosis.—The muscular wasting and the retention of co-ordinating power distinguish this form of disease from locomotor ataxy.

Prognosis.—Unfavourable.

Causes.—Injury either of a particular nerve-trunk or of the spinal cord itself. Plumbism, Syphilis.

Pathology.—Sclerosis of the anterior nerve-roots and anterior cornu, the result of chronic myelitis.

Treatment.—Galvanism. Iodide of potassium in the toxic form.

LEAD PALSY.—DROPPED HAND.

Symptoms.—The hands are generally first affected, and in some cases the forearm also suffers. The disease begins by weakness in the fingers, extending to the wrists, but rarely beyond them, accompanied by shooting pains in the forearms, arms, and shoulders. The parts affected gradually waste partly from disuse, and the hands drop powerless at the wrists. The disease is generally preceded by one or more attacks of colic, but may occur independently *of it.* Fig. 59 represents the condition in a painter aged 54. The

Fig. 59.



extensors of the right forearm are the weaker, the margins of the gums are bluish-black. He has had several attacks of colic, and wrist-drop twice. The knuckles are enlarged by chronic rheumatic arthritis

Diagnosis.—The history of the case. The seat of the palsy, assisted in many cases, by the discovery of a blue line on the margin of the gums.

Prognosis.—Favourable in first attacks and in slight cases. In some cases recovery after prolonged treatment. Sometimes incurable.

Causes.—The employments of the plumber and glazier, oil-painter, and enamel-card maker. Fishmongers who use lead counters, men employed in lead works, and persons who drink cider made by presses repaired with lead. Water kept in new leaden cisterns, or conducted through new leaden pipes, the danger being, as a general rule, in proportion to the purity of the water.

Pathology.—The presence of lead in the blood and nerve tissue.

Treatment.—*Indications.* I. To eliminate the poison from the system. II. To rouse the paralyzed muscles to action. To attain the first object we may give iodide of potassium in five-grain doses. Sulphur baths (Form. 301), or the vapour of sulphur. The second object may be attained by electricity, shampooing, friction with the flesh brush, or with stimulating liniments; and by the internal administration of strychnia (Form. 18). Electricity is a very valuable remedy in this disease. The current should be feeble and the intermittencies very rapid, and it should be passed in succession through individual muscles.

Prophylaxis.—In lead works, the use of a respirator of moist flannel. Scrupulous washing of the hands.

TREMOR MERCURIALIS.—MERCURIAL TREMORS.

Symptoms.—This disease usually shows itself first by weakness in the arms, which gradually increases. It is accompanied by slight convulsive twitchings, followed by tremors, increasing in violence till the patient is obliged to abandon his occupation. The trembling gradually extends to the legs, and at length to the whole body. It is brought on by every attempt to move, but it ceases when the limbs are supported, and the body is at rest. The patient dances rather than walks; he is unable to grasp objects; his speech is hurried and abrupt, and in extreme cases he cannot even masticate. If the patient continue exposed to the poison, restlessness, sleeplessness, and delirium supervene. Salivation is only occasionally present. The general health is impaired, and there are nausea and anorexia, a dry skin and a furred tongue; but there is no disorder of the circulation, or respiration, and no colic. In very mild cases, especially when they occur in women, the symptoms are those of Mimosis Inquieta (see p. 261).

Among the minor effects of working with mercury is a peculiar brittle state of the teeth, causing them to chip and decay.

Diagnosis.—From *paralysis agitans*, by the history of the case, and the absence of trembling when the limbs are supported.

Prognosis.—Favourable when the cause is excluded.

Causes.—The process of water-gilding; employment in quicksilver mines; long exposure in any way to the fumes of mercury, or to the absorption of the oxide by the skin.

Treatment.—A temporary cessation of employment; a combination of tonics and sedatives; preparations of iron; a generous diet, with a moderate allowance of wine; the shower-bath.

Prophylaxis.—Cleanliness and free ventilation of workshops, with an arrangement by which the fumes can be carried off, such as a funnel terminating in a chimney; eggs swallowed two or three times a day; the free use of milk as an article of diet. Those who handle mercury should use gloves.

CHOREA SANCTI VITI.—ST. VITUS'S DANCE.

Definition.—Functional derangement of the motor nerves resulting in irregular jerking movements, interfering with voluntary action.

Symptoms.—The disease generally sets in with slight convulsive movements of the face or of one of the legs, which gradually extend and increase in severity until they involve one side of the body, or the whole frame. When the disease is fully formed, the patient is in almost constant motion; the head is jerked to one side; if standing, the foot shuffles and scrapes the floor. The walk is hurried and uncertain; sometimes the affected leg is not lifted but dragged along, as if the whole limb were paralytic; and when an attempt is made to lift it, the limb becomes irregularly and ludicrously agitated. Even when the extremity is at rest, the foot is often turned alternately outwards and inwards. The arm of the same side is similarly affected, so that in trying to raise anything to the mouth, the patient often jerks it over the head, and succeeds only after repeated attempts; and swallowing is performed hastily and with ludicrous grimaces. If the patient be told to hold the arm extended, he cannot keep the fingers steady, but the arm is soon withdrawn, the movement being generally accompanied or followed by a grimace. The muscles are usually quiet during sleep; but there are exceptions to this rule. The health is generally only slightly impaired; but constipation is an almost constant symptom, and there is sometimes loss of appetite, a foul tongue, and offensive breath. In females, the uterine functions are sometimes disordered. Incoherence is an occasional accompaniment. A bellows murmur is often heard over the heart.

The tongue is commonly more or less involved. In severe cases speech is occasionally lost; there is inability to maintain the erect, or even sitting posture, and the patient is incapable of attending to his common wants. In a small proportion of cases, the intellect is involved, and the patient becomes obstinate, wayward, and morose.

The disease affects weakly boys and girls, but rarely attacks adults, and when it does so, the choreic movements are limited, and commonly affect the sterno-mastoid and trapezius, and later on the deeper muscles of the neck, of one side, producing the condition known as *spasmodic torticollis*. The following is a good illustration:—A maiden lady, aged 60, had been affected for two years with convulsive movements of the muscles on the right side of the neck, twisting her face during her waking hours towards her right shoulder. While in this position, it was jerked fifty times a minute still farther backwards. Sometimes the head was jerked suddenly backwards. When walking she was impelled to go fast, and sometimes stumbled. There was no evidence of cerebral or spinal disease; the health was otherwise good, and she took regular exercise. When her attention was engaged the movements decreased. During sleep, and when the attention was fixed, as in reading, the convulsive movement ceased. The affection commenced by a screwing of the right side of the face into the pillow at night. It was removed by the internal administration of sulphate of copper and the use of the sponge bath.

Chronic choreic movements of sets of muscles (such as those of a shoulder) is not uncommon in adults, and the affection is intractable.

Causes.—*Predisposing*. General weakness and irritability of the nervous system; youth (from 7 to 15 years); female sex. It may occur in adults of both sexes to the age of seventy.—*Exciting*. Intestinal irritation from constipation or worms; uterine irritation; strong mental excitement, as from fright or anger; blows or falls; irritation of the spinal cord or its membranes, fatigue. In many cases rheumatism precedes the disease, or is associated with it, and is therefore held by some physicians to be a cause of chorea as well as of the cardiac disease which frequently accompanies it.

Prognosis.—Favourable in the great majority of cases.

Treatment.—*Indications*. I. To remove causes of irritation. II. To improve the general health.

I. By far the most common cause of irritation is in the bowels, and purgatives, judiciously and perseveringly administered, are the chief remedies. A dessert or table-spoonful of castor oil, or other simple aperient, may be given every, or every other morning. More active purgatives may be used if necessary. The bowels should be kept open once or twice daily, but hypercatharsis should be carefully avoided. (I have never given any other medicines in chorea but *aperients; and one of* the worst cases I ever saw, one which combined constant restlessness and grotesque actions of the muscles, with mental incoherence, was cured within ten days by aperient medicines alone.—G.)

Hemlock is a valuable remedy when the disease arises from centric irritation. From ʒiss to ʒvi or more, of the succus conii, may be given once, twice, or thrice daily.

If the source of irritation be in the uterus, remedies appropriate to the disorder of that organ must be given. If there be tenderness of the spine, the case should be treated as one of spinal irritation.

II. The general health may be improved by tonics, of which arsenic, sulphate and valerianate of zinc, ammonio-sulphate of copper, and sulphate of peroxide of iron, in full doses, are the best, aided by cold effusion or the shower-bath, with nourishing diet, fresh air and regular exercise. It is surprising how well large doses of arsenic are borne in many cases of this disease; they should, however, be gradually increased. Arsenic improves the secretions and keeps them free.

TETANUS OR TRISMUS.—LOCKED JAW.

Varieties.—1. Traumatic Tetanus. 2. Idiopathic Tetanus (including Tetanus neonatorum).

Symptoms.—In most cases the onset of the disease is obscure. Traumatic tetanus is generally preceded by pain at the seat of the injury. In both forms, the first symptom is usually a sense of stiffness in the nape of the neck, rendering the motion of the head difficult and painful. This is soon followed by a sense of tightness and stiffness in the lower jaw, with difficulty in swallowing. The patient also complains of pain, often violent, referred to the sternum, and thence shooting to the back. This is followed, after a variable interval, by increased rigidity of the lower jaw, and by spasms of the muscles of the neck, pulling the head strongly backwards. The teeth at length become closely and firmly set, when the affection is called *trismus* or *locked jaw*; and the features gradually stiffen into a ghastly fixed smile (*risus sardonicus*).

As the disease advances, the muscles of the trunk and spine become involved, so that the whole body is bent forcibly backwards (*opisthotonos*), or forwards (*emprosthotonos*), or to the side (*pleurosthotonos*).

At length the disease extends to every organ of voluntary motion; the limbs are rigidly extended; the abdominal muscles strongly contracted; the eyes fixed; the forehead furrowed; the jaws strongly closed, and the angles of the mouth powerfully retracted and wrinkled, producing the sardonic grin. These violent contractions occasion the most excruciating pain. The pulse is accelerated, the respiration suspended or laborious, and the skin covered with a profuse hot perspiration. A partial remission of the symptoms occasionally takes place every ten or fifteen minutes, but they are renewed, with aggravated torture, on the slightest disturbance, even the least motion of the body, or the touch of an attendant. If the patient fall asleep, the muscles relax.

In fatal cases, the symptoms rapidly increase in severity; there is urgent dyspnœa, with an agonising sense of suffocation; a cold clammy sweat; a small and imperceptible pulse; froth or bloody mucus in the mouth; the countenance becomes livid; delirium sometimes supervenes, and the patient dies exhausted, or suffocated by the rigid spasm of the muscles of respiration. The mind in most cases remains intact to the last.

The *duration* of the disease varies. One case of acute tetanus is on record which proved fatal in a quarter of an hour; the common duration of fatal cases is from four to eight days. In cases of recovery, the duration varies from a week to two or three months.

LATENT PERIOD.—From a few minutes to ten weeks. Most common period, from the fourth to the fourteenth day.

CAUSES.—*Predisposing.* The male sex; robust and vigorous constitution; warm climates; the period of infancy.—*Exciting.* Vicissitudes of temperature; exposure to cold and damp, or to excessive heat; great fatigue; wounds, especially punctured wounds of the extremities; injuries of nerves or tendons, by puncture or laceration; irritating, indigestible food in the alimentary canal (the common cause of the *tetanus neonatorum*); irritation of the extremities of the nerves; affections of the mind; strychnia and other vegetable poisons, and also the more active metallic ones.

MORBID ANATOMY.—Not constant. In some cases increased vascularity of the spinal cord and its membranes; but in many instances those parts are perfectly healthy, the disease being due to some remote irritation conveyed to the spinal marrow, and reflected on the muscles. Traces of injury to the nerves in cases of traumatic tetanus. The muscles often ruptured and gorged with blood.

DIAGNOSIS.—From the *effects of strychnia* by the obscurity of the first symptoms, their slow development, and local character (the stiffness of the jaws and difficulty of swallowing preceding, often by a long interval, the affection of the muscles of the trunk and extremities); also by the interval of several hours or days which elapses in tetanus before the patient dies or recovers; to this rule there are a few exceptions in cases of injury to the spine. Strychnia, on the other hand, is fatal in from a quarter of an hour or less to within three hours. From *tetanic* spasms following the action of other poisons by the coincidence in such cases of other characteristic effects of the poison.

PROGNOSIS.—Extremely unfavourable; more so when the disease arises from wounds or injury to the nerves than when proceeding from cold; when it comes on suddenly, and soon after the receipt of an injury, and rapidly increases in severity, than when slow in its progress; when the spasmodic contractions quickly succeed each other, and are excited by very slight causes, than when there is a considerable interval. Survival beyond the fourth day is a favourable circumstance.

TREATMENT.—To be directed to the relief of the excitement of the motor function of the cord by means of conium, tobacco (Enema tabaci), or the Calabar bean ($\frac{1}{16}$ to $\frac{1}{4}$ grain of the extract), remedies which act directly in repressing convulsive action. The object of these remedies is to produce muscular relaxation. Conium is the most appropriate. If the patient can swallow, ʒiii–ʒviii of the succus conii may be given at intervals of a few hours. If the medicine cannot be given by the mouth, it may be injected into the rectum.

There is reason to believe that electricity properly applied might prove advantageous. When a continuous current of electricity is passed along a nerve, its excitability is diminished; and M. Remack thought that he could prove in man that these currents possessed the property of causing involuntary contractions to cease by preserving to the muscles the faculty of obeying the will. Nobili and Matteucci have succeeded in relaxing muscles affected with tetanic spasm by passing a current through them, the direction of which was the reverse of that which naturally circulates in the nerves. We may, therefore, hope to control the excessive electrical excitement of the spinal cord by passing through it a continuous current, from a voltaic pile or trough, taking care that the conductor in connection with the zinc plates be placed at the top of the spine and the other lower down, or upon the surface of the limbs, in succession. In order to bring the cord within the more immediate influence of the current, a stout needle or two in connection with the conductor may be passed through the integument and muscles covering the spine.

If the paroxysms be very severe and painful we may anticipate them by bringing the patient under the influence of chloroform, until the muscular relaxation has been induced by conium. But it is worse than useless to persevere with this remedy.

If there be any heat or tenderness of the spine, a bladder of ice may be applied to the whole length of it.

The rest of the treatment will consist in giving wine and nourishment at short intervals, and keeping the patient as quiet as possible.

If the mouth continue firmly closed, food and medicines must be given by means of a flexible tube passed through the nostrils, or behind the last molar tooth, or by enemata.

TETANUS NEONATORUM.—INFANTILE TETANUS.

SYNONYM.—Trismus nascentium.

SYMPTOMS.—In the second or third week after birth, tetanic spasm, beginning in the muscles of the jaw, and thence, in some cases, extending to the whole body, and proving rapidly fatal.

CAUSES.—Improper diet, as in the Westmann Islands, off the coast of Greenland, where the food of children consists almost exclusively of fish; intestinal irritation in hot climates; the impure air of crowded foundling and lying-in hospitals. Intense cold.

Treatment.—An aperient, a drachm of castor oil, at once, followed by a warm bath. ♏xv to lx of the succus conii every 4 or 6 hours. The diet should be restricted either to the mother's milk, or to that of the cow.

HYDROPHOBIA.—CANINE MADNESS.

Definition.—Intense excitability of the nervous system, with irritation of the fauces acting on the spinal cord through the incident nerves, and giving rise to reflex spasm of the muscles of deglutition.

Symptoms.—At an uncertain interval after the bite of a rabid animal, pain, stiffness, or some unusual sensation, often accompanied by inflammation, is felt in the seat of the wound, followed, in many cases, by pains darting thence along the nerves. These local symptoms are not always present. After a few hours or days, wandering pains are felt in different parts of the body, with stiffness of the neck and throat, restlessness, irritability, and drowsiness; the spirits are depressed; there is frequent deep sighing, and the sleep is disturbed with frightful dreams.

The true nature of the case is first revealed by an unusual difficulty in swallowing liquids, which increases till it becomes intolerable. The moment any fluid is brought near the patient, or the motion of the fluid is heard, he starts with horror; and the attempt to swallow is hurried, accompanied with sobbing or deep-catching sighs, and followed by convulsions.

There is intense irritability; the countenance expresses great anxiety, alarm, and suspicion; the eyebrows are contracted, the eyes wild, staring, and glassy; there is intolerance of light and sound, urgent thirst, a parched tongue, a hot and dry skin, and retching. The sufferer often screams violently, talks in a loud, authoritative tone, and spits out the viscid saliva between his closed teeth, with loud and noisy strainings, not unlike the barking of a dog. In spite of these severe sufferings, the mind may remain unaffected to the last, but in some cases the patient lapses into wild delirium, talks incessantly and incoherently, and is in a state of the most distressing restlessness; the slightest motion, a sudden change of posture, a breath of air, a ray of light, a polished surface, the least noise, will excite a sensation of suffocation or convulsions; in some cases delirium takes place, the convulsions become more frequent, and the patient dies convulsed, exhausted, or asphyxiated.

Duration.—Generally from two to three days. In one case, thirty-six hours; in rare instances, eight or nine days.

Latent Period.—From three or four weeks to some months, or *even years; most* common period from twenty to forty days.

DIAGNOSIS.—The disease cannot be confounded with any other. The cause and symptoms are alike peculiar and characteristic.

PROGNOSIS.—Fatal. The disease has hitherto defied all remedies.

MORBID ANATOMY.—Not constant. Slight traces of inflammation in the spinal marrow and its membranes. Inflammation of the fauces and air passages, with increased secretion.

TREATMENT.—*Indications*. I. To prevent the absorption of the poison. II. To remove the irritation of the throat. III. To diminish the excitability of the nervous system.

I. Persevering suction of the wound should be used without a moment's delay; this should be promptly followed by excision of the part, and the subsequent application of a poultice. If this cannot be done at once, and the wound is on the arm or leg, a ligature should be applied above the wound. This treatment is to be preferred to the use of caustic.

II. The second indication is best fulfilled by constantly swallowing ice.

III. The third indication may be fulfilled by powerful doses of conium alone, or in combination with opium. Chloroform is a very useful palliative.

Ice was swallowed with great advantage in a remarkable case admitted to King's College Hospital, under the late Dr. Todd. The patient, a boy seven years of age, labouring under hydrophobia in its most marked form, and refusing, with characteristic horror and impatience, everything previously offered him, whether in a liquid or solid form, and who had taken ten drops of dilute hydrocyanic acid, repeated at short intervals, and at length twenty drops in one dose, without apparent effect—after the most severe convulsive paroxysms which had yet seized him, was offered a fragment of rough ice. This he swallowed with avidity. Fresh pieces were swallowed with the greatest ease. In less than half an hour, he had taken about a pound and a half of ice. At the same time that it was given internally, a bladder containing a mixture of broken ice and common salt was applied to the whole length of the spine and around the throat. Under the external and internal application of cold, all the symptoms of hydrophobia referable to the throat and chest, with the exception of occasional hawkings, had passed away; the viscid mucus no longer flowed from the mouth, the mucous râle disappeared from the chest, and nothing remained but extreme restlessness, violent excitement, and incoherence. The patient sat up in bed with a large fragment of rough ice in each hand, talking incessantly and incoherently in a loud voice, and showing an aimless eagerness. The intense excitement continuing, and all the peculiar symptoms of hydrophobia having subsided, the cold *douche* was applied, but the system did not rally from the shock. (See *Lancet*, January 22, 1842.)

I am inclined to attribute more benefit to the internal than to the external use of ice in this case, but the joint administration, while the rest of the body is kept warm, seems to be the most rational treatment yet recommended. It may not save life, but it will certainly mitigate suffering. (G.)

KAKKE,* OR ISERIBERI.

This remarkable disease, to which our attention has been lately directed, has been long recognized in China, Japan, India, Ceylon, and the southern parts of Brazil. I extract the following brief notice of it from an article by Dr. W. Anderson, published in vol. vii. of St. Thomas's Hospital Reports, and embodying his experience of the disease in Japan:—

DEFINITION.—A recurrent, non-febrile, non-contagious disease, endemic in low-lying, over-crowded, badly-drained districts, characterized by temporary anæsthesia and motor paralysis, most commonly affecting the extremities, and a tendency to serous effusion—especially hydro-pericardium with cardiac disturbances, syncope, and death.

SYMPTOMS.—The illness usually begins with numbness and weakness of the legs, the integuments over the tibia pits slightly on pressure, the numbness extends to the tips of the fingers and the lips. There is general debility and great muscular fatigue; palpitation, usually associated with anæmia; anæmic-cardiac bruits, and in the acute form of the disease a rapid and irregular action of the heart, with palpable thrill, loud diffused murmurs, and signs of pericardial effusion. Febrile disturbance is exceptional. A rise of 2° to 4° Fahr. is occasionally seen, but its subsidence does not coincide with or herald any marked change in the other symptoms, and when acute symptoms set in, the temperature usually falls 1° or 2°, or even more, below the normal level. Vomiting sometimes occurs early, sometimes immediately precedes the cardiac symptoms, and is apparently of central origin. The urinary secretion is normal. The average duration of the disease is about five weeks. In the chronic forms of the disease there is a progressive wasting of the muscles, nearly always associated with tenderness and cramps.

PATHOLOGY AND MORBID ANATOMY.—The early anæsthesia and paresis, increasing in some cases to actual palsy, and resulting muscular atrophy, point to congestion of the spinal cord passing into a chronic partial myelitis. Hitherto autopsies have been rare, and have only revealed dropsical effusions.

CAUSES.—As the disease is endemic only in the low-lying, ill-drained, and over-crowded parts of great cities, such as Kiyosto, Osaka, and Yedo, it may fairly be assumed to be due to a neglect of hygiène, and not to the development of any specific poison.

TREATMENT.—As the disease is associated with debility, iron and strychnia have proved beneficial. Aconite is serviceable in relieving the muscular tenderness. The cardiac symptoms require the general treatment described under anæmia and pericarditis. As the kidneys are healthy, the tendency to dropsical effusion may be obviated by stimulant diuretics.

---

* *The Japanese pronunciation of two Chinese characters signifying leg-disease.*

CATALEPSIA.—CATALEPSY.

Definition.—A sudden loss of consciousness with retention of the posture in which the patient happens to be at the moment of seizure.

Symptoms.—This is an extremely rare disease, allied to those of the present section. Its essential features are, a fixing of the body in the position in which it happens to be at the moment of the seizure, or in which it may be placed during the fit, accompanied by total insensibility. The fit itself is rarely, if ever, fatal; but the intellectual faculties seem to suffer by its frequent repetition.

A lad of about fourteen years of age, a playmate of my own, was subject from childhood to this disease. He was often seized in the midst of his sports, without previous warning, and fixed like a statue in the attitude in which he happened to be at the moment. The fit rarely lasted more than one or two minutes, and when it ceased, he resumed his play with a slight air of surprise and embarrassment. He was found dead in a bath, into which he had fallen. (G.)

The *causes* of this disease are obscure, and little is known of its appropriate treatment. The general principles on which it should be conducted are the same as those of epilepsy. Existing irritation must be removed, and any occasional determination of blood to the head relieved by appropriate remedies.

HYSTERIA.—HYSTERICS.

Definition.—A nervous disorder, usually attended with marked disturbance of the functions of digestion and respiration, and characterized by convulsive fits in which those functions are signally affected, and the controlling power of the will strangely impaired, without complete loss of consciousness.

Symptoms.—The hysteric paroxysm, or fit, is generally preceded by an uneasy sense of fulness and weight at the pit of the stomach, with nausea, acidity, heartburn, and flatulence; followed by sighing, yawning, and stretching, dejection of spirits, shedding of tears, alternate chills and flushings, difficulty of breathing, and palpitation. There is often a sharp pain in the left side, about the flexure of the colon, with the sensation of a ball or globe rolling about (*globus hystericus*), and a peculiar gurgling and rumbling sound (*borborygma*), the ball seeming gradually to rise into the stomach, and thence to the throat. The fit having arrived at its height, the patient appears threatened with suffocation; the face is flushed, the nostrils are distended, the abdomen is protruded and tympanitic, the head is thrown forcibly back, and the limbs are strongly convulsed. The patient bursts into violent fits of laughter, sobbing, or screaming, utters incoherent expressions, and is in a state of temporary delirium; from which, however, she is readily roused so as to answer questions rationally. The spasms at length abate, a quantity of flatus is noisily expelled by the mouth, there is an abundant flow of limpid urine; and the patient recovers, recollecting imperfectly what has taken place. The fit is often followed by a severe pain in the head, and a sensation of soreness over the whole body.

Sometimes the hysteric fit consists in a sudden apparent loss of speech, sense, and motion, with a distinct recollection of what has been said and done. Sometimes, again, it is characterized by a sudden access of laborious breathing, swollen neck, flushed cheeks, and a closed and trembling eyelid; and the patient recovers, crying and sobbing.

CAUSES.—*Predisposing.* Female sex; celibacy; the age from puberty to the fifty-fifth year; studious and sedentary life; grief; anxiety; delicate health; plethora; the scrofulous diathesis. It is rare in the male sex, but may occur, under mingled debility, and mental excitement.—*Exciting.* Constipation; dyspepsia; flatulence; excessive evacuations; suppression of the menses or lochia; the plethoric and anæmic states; violent emotions; imitation or sympathy; tight lacing, or other impediments to the breathing. Spinal irritation.

DIAGNOSIS.—From *epilepsy*, by the retention of consciousness, and of some control over the convulsive movements; by the marked affection of the respiratory muscles, as shown in sighing, sobbing, and yawning, cries, shrieks, and laughter; by the absence of any great distortion of the features; and by the peculiar trembling of the eyelid. (This latter sign is of great value, for whenever it is present, whether in men or women, whatever the name given to the disorder, whether hysteria, catalepsy, trance, or mesmeric slumber, it is a sign of safety, and strongly suggestive of cold affusion.—G.) From *mimosis inquieta*, by the marked character of the hysteric fit; but the true hysteric fit may be superadded to the group of symptoms which bears that name.

PROGNOSIS.—*Favourable.* In males affected with hysteria there is some ground to apprehend future mental unsoundness.

TREATMENT.—I. *During the fit.* In general nothing more is necessary than to dash cold water repeatedly into the face; and to address the patient in a loud and decided tone. The stays should be loosened, and ammonia applied to the nostrils. Assafœtida, æther, valerian, castor, &c., are of little use.

(The persevering use of cold water as a shock, not only serves to remove the existing attack, but often effects a cure, after antispasmodics have been used in vain. In a young man who had

had repeated attacks of hysteria in a marked form, and had taken the strongest and most nauseous remedies for several weeks without effect, this simple means speedily effected a cure. I have seen a prompt and a permanent cure follow the disuse of tight lacing. —G.)

II. *During the intermissions.*—The bowels must be kept free by gentle aperients; and the dyspeptic symptoms removed by appropriate remedies. If there be debility, stimulants or tonics, of which the metallic are the best, will be required; if plethora be present, a restricted diet. For anæmia, spinal tenderness, mimosis inquieta, and disorders of the uterine function, the remedies proper to those disorders. Change of scene, cheerful society, regular exercise, and the shower-bath may be prescribed with advantage.

Hysteria is common in perverse and irritable females, and in persons of both sexes possessed of little self-control. An education combining excessive mental, with defective physical exercise, predisposes to hysteria in young females.

Hysteria is rare in strong-minded women: and of four cases which have come under my notice in the other sex, three occurred in men remarkable for their want of self-control, two of whom became insane; and the third was a single attack occurring in a medical student on obtaining a prize for which he had long been anxiously striving. (G.)

In the foregoing description, the term hysteria has been restricted to a disorder accompanied by fits; but it is usual to give to this term a much more extended meaning, and to designate as hysterical all the more obscure diseases of females. This indiscriminate use of the term often leads to unsatisfactory views of the real condition with which we have to do. There are affections, however, which may, without impropriety, be designated as hysterical: such as aphonia, dysphagia, dry noisy cough, dyspnœa, hiccough, flatulence, paralysis, syncope, brow ague, irritable breast, besides a large class of anomalous nervous affections, which often closely simulate diseases of a more formidable character. The mind of hysterical females is often in a state bordering on insanity; an intense desire for sympathy being the mainspring which sets the strange machinery in motion. The mind, in fact, is in the same state as the body; and as the convulsive movements are partly due to an excited state of the reflex function, and partly to an absence of self-control, so the extraordinary mental condition is the effect of the extension to the brain of the same condition of the nerves accompanied by the same absence of self-control.

We shall often be greatly assisted in determining the true nature of these anomalous diseases by observing one or other of the following circumstances:—1. That the patient, seeming to labour under a disease which is usually accompanied by emaciation and a decided appearance of ill-health, loses neither flesh nor colour; so that if she has long been confined to bed with paralysis, her limbs remain plump and firm; if she has not been able to swallow for weeks, or is troubled with incessant vomiting, she seems to have taken at least three meals a day; if she has been a martyr to excruciating pain, her face is as free from wrinkles as if she had never had a care or a pang.—2. That though, in some anomalous cases, the patient seems to be altogether insensible, the pulse beats as usual, the face has its natural colour, and while all other parts are motionless, the eyelids vibrate rapidly, and especially when any effort is made to rouse her.—3. That a great portion of these affections are associated more or less with disorders of the respiratory function.—4. That the patient is, or has been, subject to flatulence, borborygma, globus, hystericus, or well-marked hysterical fits. In the treatment of these disorders, the medical man must combine great firmness with kindness, and not spare cold water. Cold affusion is the only remedy which can be relied on. It is worth a whole pharmacopœia of anti-spasmodics. (G.)

EPILEPSIA.—EPILEPSY.

Synonym.—Falling sickness.

Definition.—Fits recurring at regular intervals, with sudden loss of sense and power of motion, frequently preceded by a shriek, attended by general convulsions, and usually followed by coma.

Symptoms.—The patient is seized suddenly, or after a short warning, with loss of consciousness and of power, so that, if he be standing, he suddenly falls, or is thrown to the ground. The fit, which is frequently preceded by a loud piercing cry, consists in strong convulsive motions of the limbs and trunk, and various distortions of the countenance. The brows are knit; the eyes fixed and staring, or turned up beneath the lids; the pupils are dilated and do not contract when exposed to light. The hands are firmly clenched, and the arms are tossed about. The breathing is gasping and difficult, or altogether suspended; the heart beats violently; the vessels of the head become turgid, and the face is livid; foam, often bloody, issues from the mouth; the jaws are contracted with great force, so that the under lip, or the tongue, if protruded, is apt to be severely injured. The fæces, urine, and semen are sometimes expelled, and priapism is not uncommon. After the convulsions have continued for a few minutes, they cease, leaving the patient motionless, but in a state of insensibility, and apparently in a profound sleep. He gradually recovers, and, if left to himself, will generally sleep for some hours. Sometimes there is a succession of fits, with intervals of torpor, lasting for several hours. Occasionally the epileptic fit is followed by maniacal paroxysms of great violence: sometimes by incoherence.

There is a form of epilepsy, of frequent occurrence, called by the French *petit mal* in contra-distinction to the foregoing which is designated the *grand mal*. It consists in sudden and transient giddiness with *loss of* consciousness, confusion or incoherence of *mind, and unsteadiness* of gait, accompanied in some instances by erections of the penis, in others by slight convulsions. Such slight fits are often followed by great confusion of intellect, and sometimes by maniacal incoherence. (In one case of epilepsy belonging to this class every fit of epilepsy was followed by an unconscious exposure of the person.—G.)

Premonitory symptoms.—In some cases pain in the head; lassitude; bright circles of colours before the eyes, sudden flashes of light, in rare instances spectral illusions; or there is a loud noise in the ears; or an offensive smell; or a bitter taste; unquiet sleep; unusual dread; palpitation of the heart; coldness of the joints; fluttering at the epigastrium; vomiting; a sensation of cold, or a pain arising in some part of the extremities, and gradually creeping upwards till it reaches the head (the *aura epileptica*), when the patient is instantly deprived of sense, and falls as above described. (In a case that came under my notice, every fit was preceded by the utterance of the same incoherent sentence, to which the patient attached no meaning.—G.) But in the majority of cases, the fits are not preceded by any warning. They occur at variable intervals; sometimes in the day, sometimes at night, during sleep; and there are often several fits in the twenty-four hours; in other cases, there are intervals of months or years.

CAUSES.—*Predisposing.* Drunkenness, epilepsy or insanity in parents or ancestors; scrofula; malformation of the head: debility in nervous persons; dissipation, intemperance, self-abuse, and excess or suppression of discharges.—*Exciting.* Sudden fright; fits of passion, or vehement emotions of the mind; sexual intercourse; masturbation; plethora of the vessels of the head; anæmia of the brain and spinal cord, such as occurs in cases of excessive uterine hæmorrhage (epileptic convulsions terminate the lives of animals bled to death); reflex irritation from worms; dentition; acute pain; suppression of urine or bile; tumours compressing the brain, or any part of the nervous system; parasites in the brain (the cænurus cerebralis is the common cause of convulsions in sheep). Drink, and syphilis are two of the commonest causes of self-induced epilepsy. Epilepsy sometimes occurs as a symptom of poisoning, especially by arsenic and lead.

MORBID ANATOMY.—In most cases there is congestion of the vessels of the brain. In the remainder, such causes of irritation as thickening of the membranes, spiculæ of bone, internal nodes, tumours, or the cystic form of tænia.

DIAGNOSIS.—From *hysteria*, by the total suspension of consciousness, the solitary cry which precedes, and the deep sleep which succeeds, the fit. From *feigned* epilepsy, by the total insensibility, extending even to the retina. From *apoplexy*, by the transient nature of the fit, the absence of the stertorous breathing, and, in most cases, by the absence of paralysis, and the completeness and universality of the convulsions. From *tetanus*, by the insensibility, and the clonic character of the convulsion.

PROGNOSIS.—*Favourable.* When sympathetic, occurring before the age of puberty, and arising from exciting causes easy of removal; or originating in functional derangement of the uterine system.—*Unfavourable.* When the disease comes on after puberty; hereditary predisposition; scrofulous diathesis; long previous continuance of the malady and frequent occurrence of the fits; misshapen skull; the epileptic physiognomy; impairment of memory and judgment.

TREATMENT.—I. Immediately before the fit. II. During the fit. III. During the interval.

REMEDIES.—*Immediately before the fit.* Pressure on the carotids; a ligature between the parts from which the *aura* first proceeds and the brain, as round the thumb or little finger when it begins there; a strong mental effort; violent exercise; irritation of the nostrils, with snuff, or strong smelling-salts; dashing cold water over the face and head; an emetic, a full dose of opium or laudanum.

During the fit.—The patient should be placed, if possible, on a soft bed, the neckcloth and shirt-collar loosened, and the tongue protected by a piece of India rubber, soft wood, or a pad of linen placed between the teeth. When the fits occur during sleep, and the tongue is liable to be bitten, the patient should wear a smooth rounded guard, fitting closely to the teeth. After the fit, he should be allowed to sleep, and if much exhausted, may take some slight stimulant.

In the interval.—The recurrence of the fit is sometimes prevented—

1. By removing all causes of irritation, as constipation, intestinal worms, the irritation of teething, &c.
2. By avoiding the exciting causes, such as over-distension of the vessels of the head, however induced, fits of passion, or other violent emotions of the mind; intemperance, dissipation, or other bad habits.
3. If the patient be plethoric, by occasional bleeding, abstemious diet, and saline aperients. Issues or setons in the neck or arm, or antimonial ointment rubbed into the spine, sometimes give relief.
4. If the patient be weak and irritable, tonics: as quinine, sulphate, oxide, and valerianate of zinc, sulphate and peroxide of iron, sulphate or ammonio-sulphate of copper, nitrate of silver (an objectionable remedy, as causing permanent discoloration of the skin), arsenic. He should rise early, take regular exercise, nourishing but not stimulating diet, and use cold bathing, or the shower-bath.

In females, attention should be paid to the state of the uterine function, both in young persons and at the change of life, according to the rules given elsewhere for the treatment of disorders of this function.

5. Bromide of potassium in doses of from 5 to 10 grains, increased to 30 or 40 grains, is an excellent remedy.
6. If there be a syphilitic taint, mercury, or iodide of potassium.

In cases preceded by the aura, division of the nerve running from the part where it begins has been recommended, and even amputation; but these operations are of very doubtful efficacy.

DISORDERS OF THE MIND.

MANIA	Furious Madness.
MELANCHOLIA	Melancholy Madness.
HYPOCHONDRIASIS	Vapours.—Low Spirits.
DELIRIUM TREMENS	Drunkard's Delirium.

MANIA.—FURIOUS MADNESS.

SYMPTOMS.—This disease sometimes comes on suddenly, but more frequently slowly and almost imperceptibly. For some months, or even years, the thoughts, habits, tastes, temper, and affections become more and more the reverse of those that are natural to the patient. He suffers from a distressing confusion of ideas, a failure of memory, depression of spirits, a loss of interest in his ordinary pursuits, with extreme irritability of temper, restlessness, and wakefulness; and he has a miserable consciousness of loss of mental power and change of character. The general health suffers; there is pain in the head and giddiness; the appetite fails, the sleep is disturbed, the bowels are confined or irregular, or affected with diarrhœa; the tongue is furred; the pulse frequent and quick; the patient grows thin, and the features alter. But before the disease shows itself in its marked form, the bodily health often improves, and the painful consciousness of unsoundness disappears.

After these symptoms have lasted for a variable period, without attracting much attention, some accident, injury to the head, mental shock, or unusual excitement of the mind, or some more trivial circumstance, brings on decided mania.

The symptoms of mania, whether they set in suddenly or come on gradually, are the following:—anxiety, uneasiness, restlessness, sleeplessness, alternate excitement and depression, or continued agitation and violent muscular efforts, rapid and incoherent discourse, fits of loud laughter, or shoutings, grinding of the teeth, spectral illusions, mental delusions, and unfounded antipathy to certain persons, particularly to near relations or intimate friends. There is a peculiar wildness and fierceness of countenance, the pupil is dilated, the eyelids widely open, the eyes glistening and unsteady, the features strongly marked, and the countenance flushed. The patient will sometimes complain of severe pains in the head, giddiness, loud noises in the ears, and bright spots before the eyes. The sensations are generally more obtuse than usual, or they are disregarded, so that the patient will bear the most intense cold or heat, prolonged abstinence from food or drink, and long-continued want of sleep. The bowels are usually costive, and require strong aperients; the taste is often depraved, and the appetite variable; the tongue is dry and furred; the pulse full and quick; the habits are careless and often filthy. The disease is often the result of chronic disease of the brain, and is associated with epilepsy and paralysis.

Some maniacs have lucid intervals, which occur with regularity; others are subject to paroxysms of very irregular occurrence. The maniac can also, under certain circumstances, exercise considerable self-restraint, conceal his delusions or designs, and carry out his plans with the cunning and contrivance of a sane man.

Attacks of mania sometimes seem to suspend other diseases, such as gout and consumption; they may also be attended by a remarkable improvement in the general health; and they are consistent with the attainment of old age. Relapses are common. Mania often supervenes on less acute disorders of the mind, and it generally passes into dementia, often complicated with paralysis.

Morbid Anatomy.—Thickening and opacity of the arachnoid; effusion of serum beneath the membranes or in the ventricles; increased or diminished vascularity; atrophy or increased density of the substance of the brain; softening of the grey matter, especially in cases accompanied by paralysis. But there is no morbid appearance proper to insanity.

Causes.—*Predisposing*. Hereditary tendency; the adult age (Heberden never saw it earlier than the sixteenth year).—*Exciting*. Violent emotions; intense application to study or business; immoderate indulgence of the passions; violent exercise; frequent intoxication; parturition, lactation, and change of life; blows on the head; acute febrile disorders; disease of the brain; and antecedent attacks of epilepsy.

Diagnosis.—From *encephalitis*, by the absence of febrile symptoms. From *delirium tremens*, by the more violent excitement, the more complete incoherence, the absence of tremor, and the history of the case.

Prognosis.—*Favourable*. Following some other disease, or arising from some temporary cause, such as an occasional excitement of the mind or a single debauch; the attacks being slight and infrequent; youth; hæmorrhage; diarrhœa.—*Unfavourable*. Coming on after the middle period of life, or having been of long continuance; complication with epilepsy or paralysis.

Treatment.—In the early stage, the *medical* treatment must be determined entirely by the condition of the bodily functions. Symptoms of determination of blood to the head must be met by remedies suitable to that state. Constipation will require the use of aperients. When the secretions are disordered, the patient must be put under a course of alteratives; suppressed discharges must, if possible, be restored. If there be anæmia, or debility arising from other causes, tonic remedies are indicated, and if the habits of the patient be in any respect unfavourable to health, a change must be insisted on. The habitual use of the shower-bath, change of air, a nutritious and unstimulating diet, regular hours for meals and rest, and an abstinence from business, with change of scene, and cheerful society, should be particularly enforced. The *moral* treatment will consist in removing as much as possible all causes of excitement; all unnecessary opposition to the patient's plans and wishes; with great forbearance on the part of relations and attendants.

When the disease is fully developed.—If there be decided symptoms of determination of blood to the head, bleeding, cupping, leeching, cold to the head, brisk purgatives, and low diet must be prescribed. When the patient is extremely violent and sleepless, conium juice or opium should be given in large doses. We may give from ʒi to ʒii of the former every six hours, or five grains of the latter, and increase the dose to ten, fifteen, or even twenty grains. This treatment seems to be peculiarly applicable to cases brought on by exhaustion, whether from loss of blood, starvation, intemperance, or dissipation, and in puerperal mania. If the face be pale, or the attack of mania have been preceded by loss of blood, debilitating discharges, or exhausting diseases, tonics or stimulants, according to the degree of the debility, in combination with opiates, must be resorted to. In all cases allied to hysteria, the shock of the cold affusion, or the shower-bath, is highly advantageous.

The moral treatment.—In recent cases it is necessary to prevent the patient from offering violence to himself or others by the strait waistcoat, or the coercion of powerful attendants. The fury of madmen and the viciousness of brutes can be tamed by similar means. While treating him kindly, the attendant must make the patient feel that he is both wiser and stronger. In chronic cases, and in lunatic asylums, personal restraint can often be foregone, and constant watchfulness, gentle and conciliating treatment, and occasional seclusion may be substituted. Much depends upon gaining the confidence of the maniac, and keeping out of sight all irritating means of restraint.

The patient should be engaged, if possible, in some exercise or pursuit that will interest the mind, and thus divert it from one invariable train of thought; and he should be removed from familiar objects, and out of reach of things and persons associated with the origin of his disease. When there is a tendency to suicide, the most constant vigilance is required.

Mania is only one of many mental disorders, but it is the one which the practitioner is most likely to be called upon to treat. The other forms of mental unsoundness, not treated of in the present chapter (viz., idiocy, imbecility, and dementia), rarely require more than skilled attendance and moral treatment.

For a more minute account of many of the phenomena of unsound mind, see Part I. p. 105–118.

MELANCHOLIA.—MELANCHOLY MADNESS.

Symptoms.—This disease is characterized by dejection of spirits, seclusion, timidity, fickleness, and great watchfulness, and is generally accompanied by disorders of the digestive organs, with flatulence and costiveness. The mind pursues one object or train of thought, which usually bears a near relation to the patient himself, or to his affairs, which he views with great and unfounded apprehension, and extreme depression. This painful state of mind is often attended by a strong propensity to suicide. In one form of the disease the patient refers some bodily sensation to imaginary and impossible causes, as living animals, or even persons, in the stomach or bowels.

Causes.—*Predisposing.* Hereditary tendency to insanity.—*Exciting.* Chronic diseases of the liver and organs of digestion; suppressed evacuations; distress of mind; sudden mental shocks; anxiety; excessive evacuations; intemperance.

Diagnosis.—From mere depression of spirits by its exaggerated and persistent character, and the existence of delusions. The term melancholia is sometimes improperly used for monomania.

Prognosis.—*Favourable.* The absence of hereditary tendency; the previous short duration of the disease; the reappearance of habitual evacuations, sound sleep.—*Unfavourable.* Hereditary predisposition; the chronic character of the disease, or its association with epilepsy.

Treatment.—The *medical* treatment consists in regulating the functions of the stomach and bowels by aperients and alteratives, and in the use of remedies adapted to the state of the patient's constitution. The shower-bath may be prescribed with advantage.

The *moral* treatment consists in changing the scene, amusing the mind, and diverting attention from the existing train of thought. Travelling, rural sports, cheerful society, and music may be recommended, according to the tastes and previous habits of the patient, and the experience of friends or attendants. If he betray any tendency to suicide, he must be constantly watched. If he suppose the stomach or bowels to contain some living animal, a pretended operation for its extraction may effect a cure.

HYPOCHONDRIASIS.—VAPOURS.—LOW SPIRITS.

Symptoms.—Dyspepsia, with dull pain in the hypochondria; languor, listlessness, irresolution, seriousness, sadness, and timidity. The patient pays close attention to his health, exaggerates his symptoms, and takes desponding views of his case.

Causes.—*Predisposing.* The melancholic temperament.—*Exciting.* Dyspepsia; painful mental impressions; distressing events.

Diagnosis.—From *melancholia*, by the more constant dyspeptic symptoms, and the absence of well-marked delusions. From *dyspepsia*, by the exaggerated importance attached to existing symptoms.

Treatment.—That of dyspepsia. The patient should be kept, as much as possible, from thinking of his complaints. Change of air and scene. Active remedies should be avoided.

DELIRIUM TREMENS.—DRUNKARD'S DELIRIUM.

Synonym.—Mania a potu. Alcoholism.

Drunkenness is the most common, but not the only, cause.

Symptoms.—Sleeplessness; restlessness; strange illusions of sight and hearing; and delirium, during which the patient recognizes those about him, answers questions rationally, and does hurriedly what he is told to do. He talks incessantly, is very anxious to be doing something; will be found busily looking, in unlikely places, for some object on which his mind is intent; or he will transact his ordinary business in a dreamy way. He is timid and suspicious, thinks he is surrounded with enemies, or in a strange place, from which he is constantly trying to escape; or that some great evil is impending, or has actually befallen him. He is rarely violent, but may expose himself to danger in trying to escape. Trembling of the lips, tongue, hands and limbs, is generally present, and particularly in speaking, or making any effort. There is profuse perspiration, a moist and slightly furred tongue, and a small, quick, frequent, compressible pulse. The face, in most cases, is pale, and the manner composed and rational, even when describing symptoms and imaginary events likely to excite and interest persons in their right mind. But symptoms of phrenitis, indicated by hot head and flushed face, may accompany the delirium. In fatal cases, the patient falls into the typhous state, the tremor becomes subsultus tendinum, and the evacuations pass involuntarily; or the mucous râle ushers in death by apnœa. The disease is apt to recur.

The illusions are peculiar, and generally relate to living things. The patient will listen to the arm of a chair, believing it a serpent, or scratch it with his nail, alleging it to be the hiding-place of a scorpion; or he confounds inanimate with living objects. Thus a groom will lift the leg of a table as if it were that of a horse, and harness chairs with string, &c.

Morbid Anatomy.—In traumatic delirium no morbid appearances. In death after repeated attacks of mania a potu, hardening of the brain, and a little fluid in the ventricles and subarachnoid spaces. In some cases fulness of the vessels and serous effusion. Alcohol has been detected in the serum of the ventricles.

Causes.—*Predisposing.* The abuse of alcoholic liquors, opium, or other narcotic drugs. Exhaustion by intense study or by anxiety.

Hot weather.—*Exciting.* An occasional debauch; continued intemperance; sudden abstinence from an accustomed stimulant; loss of blood; exhausting maladies; shock, physical or mental; severe wounds (delirium traumaticum).

Diagnosis.—From *meningitis*, by the absence of headache, and usually of fever; trembling hands; peculiar illusions; the timid and suspicious manner; and generally by the absence of febrile and inflammatory symptoms. The distinction between meningitis and delirium tremens coming on after a single debauch, or short indulgence in habits of intoxication, must be drawn from the patient's history, and of that of the attack.

Prognosis.—*Favourable.* In proportion to the physical strength of the patient.—*Unfavourable.* If the pulse be small, weak, and intermittent, and opium fail to produce sleep.

Treatment.—*Indications.* I. To procure sleep. II. To sustain the strength. III. To reduce inflammation when present.

I. This indication is fulfilled by opium. Two or three grains of solid opium, or from half a drachm to a drachm of laudanum, may be given, followed after one, two, or three hours by a grain of opium, or twenty drops of laudanum, till sleep is procured. The opium may be combined with ammonia, wine, or the patient's usual stimulant. Subcutaneous injections of morphia may be substituted for opium.

II. If the pulse be very feeble, ammonia and bark, beef-tea, brandy and eggs, must be freely administered. Large doses of digitalis have been recommended, but the remedy is of doubtful efficacy, and must be used with caution.

III. Inflammatory symptoms are best treated by cold to the head. The bowels should be kept moderately open.

The patient must be watched, and the windows well secured by bars or shutters; and one or two strong persons should be in attendance. If the patient be violent, the strait waistcoat must be used.

CHAPTER II.

DISEASES OF THE CIRCULATING SYSTEM.

1. Of the Heart.
2. Of the Arteries.
3. Of the Veins.

DISEASES OF THE HEART.

1. Functional or Nervous Affections.
2. Structural or Organic Diseases.

1. Functional or Nervous Affections.

Palpitatio	Palpitation.
Angina pectoris	Spasm of the Heart.
Syncope	Fainting.

PALPITATIO.—PALPITATION.

By Palpitation we mean frequent, strong, and tumultuous movements of the heart, without appreciable organic lesion. It is, however, a common symptom of organic disease of the heart. When existing in an extreme degree, the heart's beats are both heard and felt by the patient, especially when lying on the left side; and they may even be seen by the bystander. They are sometimes accompanied by a slight and transient *bruit de soufflet*, which ceases when the heart becomes quiet. The palpitation is attended by a painful sensation of sinking, referred to the region of the heart or pit of the stomach, and spoken of as "a sinking of the heart." In some cases there is a tendency to syncope. Fits of palpitation often occur on first waking in the morning.

Causes.—*Predisposing*. The nervous temperament; the female sex.—*Exciting*. Strong emotions—joy, grief, anger, sadness, fear, anxiety. Violent exercise. Debility following chronic and acute diseases; excessive loss of blood; inordinate natural discharges; abuse of purgatives; dyspepsia, accompanied by flatulency, want of nourishment, intemperance, the excessive use of tobacco, want of sleep, anxiety and distress, intense study, dissipation and debauchery, excessive sexual intercourse, onanism (hence the frequency of palpitation among prisoners). In females, change of life.

Palpitation frequently accompanies valvular disease of the heart, and is a prominent symptom in anæmia, hysteria, spinal irritation, mimosis inquieta, and leucorrhœa, in females; and plethora, dyspepsia, bronchitis, emphysema, and pulmonary consumption in both sexes.

Long before any other symptom of pulmonary consumption has made its appearance, the patient will often complain of distressing palpitation; and this is so common, that palpitation, not otherwise accounted for, should lead to an examination of the lungs.

Chlorotic girls are often supposed to labour under organic disease of the heart, when there is only functional disturbance. They complain of palpitations, difficulty of breathing, and pain in the left side, and are sometimes leeched, cupped, and blistered when they require an opposite treatment. In females suffering from spinal irritation, the heart is often very irritable, and the pulse may exceed 160 in the minute.

Diagnosis.—The absence of the physical signs of organic disease; the peculiarly distinct character of the sounds of the heart; the absence of inequality and irregularity of the pulse (except in rare cases of dyspepsia); the intervals of entire freedom, the great frequency of the pulse when the finger is first placed upon it, and the gradual diminution, which follows as the patient's apprehension disappears.

Treatment.—Idiopathic palpitation in plethoric individuals may require the abstraction of blood from the arm, or by leeching or cupping to the region of the heart, followed by saline aperients, low diet, and rest. In most cases the medicinal and hygienic treatment will be that appropriate to *anæmia*, *chlorosis*, or *mimosis inquieta*. But in obstructive pulmonary diseases, and in valvular diseases of the heart itself, the palpitation, which was at first but a symptom of these diseases, may subsequently become a cause of their aggravation, and our first endeavour must be to subdue the excitement of the heart. When its action is very tumultuous and irregular, much benefit may be obtained from digitalis or hydrocyanic acid. An anodyne plaster of belladonna or opium may at the same time be applied to the præcordia.

In persons subject to nervous palpitations, it is of the first importance to procure tranquillity of mind; and as a fear of organic disease of the heart is often present, the assurance of the medical man that the heart is free from structural disease will go far to effect a cure.

Irregular and intermittent pulsations of the heart often arise from the causes which produce nervous palpitations, especially from dyspepsia attended with flatulence, and are relieved by the same remedies. But they may depend on organic disease of the heart.

The pulse at the wrist and heart may be irregular and intermittent during health, become regular during acute disease, and return to its former condition during convalescence or recovery.

Pulsation in the epigastrium is usually produced by flatulent distension of the stomach, and is removed by carminative aperients. *(Form. 243, 347.)*

ANGINA PECTORIS.—BREAST PANG.

SYNONYM.—Syncope anginosa.

DEFINITION.—Sudden and acute pain in the chest, referred to the sternum, accompanied by intense anxiety and fear of death.

SYMPTOMS.—This disease generally occurs in persons having every appearance of good health. It consists of fits, or paroxysms, which come on during exercise, especially when walking up an ascent against the wind, or after a full meal. The attack is announced by a sudden and violent pain across the chest, extending down the left arm, or down both arms as far as the insertion of the deltoid muscles, and in some cases, to the wrists, or fingers, accompanied with a sense of stricture so acute as to threaten immediate death. The patient is instantly obliged to stand still, and the moment he does so all the symptoms vanish. After repeated attacks, the fits, excited by slighter causes, are more violent and last longer. They often occur on the patient's waking from his first sleep, and he is, at times, incapable of lying down. At length, a fit more violent than usual puts an end to his existence, or death takes place suddenly without pain or other warning.

MORBID APPEARANCES.—Defective supply of blood to the muscular tissue of the heart, from absence of one coronary artery, or ossification of both; ossification of the valves; morbid accumulation of fat; fatty atrophy of the heart. In a few cases the disease has been caused by the pressure of tumours in the chest; in a few others there has been no morbid appearance, and death has been attributed to spasm of the heart.

CAUSES.—*Predisposing.* The male sex; age above 50: it is rare in women. (Of nearly a hundred cases, three only occurred in women, and one in a boy twelve years old. The rest were men, near or past 50 years of age.—Heberden).—*Exciting.* Violent exercise, strong mental emotion, and any kind of excess; flatulence; organic diseases.

DIAGNOSIS.—The suddenness of the attack, the acute pain, and the intense anxiety distinguish it from simple palpitation.

PROGNOSIS.—The probable termination is in sudden death. This usually occurs without pain, the person being found in bed as if quietly asleep. The fatal event is often postponed to an advanced age. In a small number of cases the disease is transient.

TREATMENT.—*Indications.* I. In the paroxysm, to revive the failing action of the heart. II. In the interval, to regulate and invigorate its movements.

The first indication is fulfilled by the immediate administration of stimulants and antispasmodics, such as æther, ammonia, brandy and water, and strong coffee. The patient should always have at hand some diffusible stimulus, or combination of this with an opiate. (Form. 105.)

To meet the second indication the patient should be directed to lead a quiet life, to put away all anxiety and excitement, and to avoid hurry, strong muscular exertions, and walking up hill. The diet should be light and nutritious; food should be taken often, and in small quantities. Whenever a feeling of weariness comes on, a little wine or brandy should be taken. Attention must be paid to the general health, and especially to the pulmonary circulation.

A sudden sharp pain in the region of the heart sometimes attacks nervous and dyspeptic persons. It has been attributed in some cases, and with apparent reason, to excessive indulgence in strong tea. The pain is not attended with the extreme anxiety of angina pectoris, and does not extend beyond the region of the heart. The treatment of this affection must depend on the state of the patient's health, and the ascertained cause of the individual paroxysms. Benefit is often derived from the application of a belladonna plaster.

Spasm of the heart is described by Laennec, though disallowed by Bouillaud. But there is no reason why the heart should not suffer from spasm as well as other muscular organs.

The muscular structure of the heart would also seem to be the occasional seat of rheumatism; the symptoms being constant dull pain, increased at intervals, and palpitation without any abnormal sound.

SYNCOPE.—FAINTING.

Symptoms.—A person about to faint experiences an indescribable distress. The sight fails, and objects appear to swim before the eye; there is a sense of singing or buzzing in the ears; the lips and countenance become pale; a cold perspiration bedews the whole body; the pulse and breathing are almost imperceptible, and the patient, if unsupported, falls senseless to the ground. In some cases, not the smallest sign of life can be perceived, the face has a death-like pallor, the extremities are cold, the eyes closed, and the limbs flaccid. Recovery is announced by deep, prolonged sighs, is frequently attended with vomiting or purging, or it may pass into epileptic convulsions.

In milder cases the loss of sense is incomplete, the pulse is diminished in force and volume, the patient merely becomes pale and sick, and drops of sweat appear upon the brow.

Diagnosis.—Syncope does not usually continue longer than a few seconds, but in some cases it persists for several minutes. In hysterical syncope the pulse beats as usual, the skin is warm, there is no pallor of countenance, and the eyelids vibrate.

Causes.—*Predisposing.* A nervous and delicate constitution; weakness; profuse evacuations, especially of blood; functional or organic diseases of the heart. *Exciting.*—Strong emotion; severe *pain; loss of blood.*

TREATMENT.—Nervous syncope is rarely dangerous. The recumbent posture, a draft of fresh air, cold water sprinkled on the face and neck, and ammonia to the nostrils, will soon restore animation. Such articles of dress as impede respiration should be immediately loosened. Hysterical syncope must be treated by cold affusion.

When fainting fits are the result of diseases of the heart, the same remedies must be employed, and ammonia and hot brandy and water administered internally.

Since chloroform causes death chiefly by paralyzing the heart's action, a few words on its administration, and the treatment of the state of profound syncope sometimes induced by it, will be appropriate in this place.

Precautions to be used in the administration of Chloroform.—1. The chest of the patient should be carefully examined, and if there be valvular defect of the heart, or intermittent action from debility or atrophy, or if there be any obstruction to the free action of the lungs, from tumours, interstitial deposits, and *especially from emphysema*, chloroform must not be administered.

2. The inhaler should be so constructed as to secure a rate of evaporation as nearly equal as possible; and to guard against the air in the reservoir becoming charged with more than six per cent. of chloroform vapour. The instrument contrived by Dr. Sansom, and made by Mr. Matthews, provides these essential safeguards.

3. The receptacle for the chloroform should be on a lower level than the patient's mouth, and should be carefully kept upright, otherwise the unmixed vapour of the chloroform, which is four times heavier than air, will flow undiluted into the lungs of the patient.

4. The finger should remain on the pulse, and the eyes be steadily directed to the chest and face during the whole of the process. If the pulse intermit, or fall below sixty; if the breathing become abnormally slow, or feeble and shallow, or the countenance livid, the inhalation must be promptly stopped.

The state of insensibility which it is desired to induce should have the following characters. Pulse and breathing tranquil, and the expression of the countenance that of ordinary sleep; but if there have been much noisy struggling in the first stage, it may appear a little congested. The eyelids closed and insensible, the eyeball fixed, and the pupil contracted, but respondent to the stimulus of light. The skin insensible and the limbs flaccid.

Chloroform kills by paralyzing the heart, and death usually takes place with great rapidity, the breathing and pulse rapidly becoming slower, and, in a few seconds, imperceptible; the pupils dilated and insensible to light; the face pale and sometimes livid.

The *post-mortem appearances*, due to the effect of chloroform, are congestion of the lungs, an empty and flaccid condition of the heart, and a fluid state of the blood.

The means of resuscitation should always be at hand, to be promptly employed if the symptoms just mentioned appear. They are strong ammonia, hot and cold water, artificial respiration, electricity. While ammonia is being applied to the nostrils and mouth, and a large sponge saturated with almost boiling water to the region of the heart, cold water should be dashed in the face, and artificial respiration employed, the tongue being pulled forcibly forwards. If these means fail, electricity (by means of the magneto-electric apparatus) may be applied to both sides of the body simultaneously—one electrode being placed on the neck, the other on the chest, so as to direct the current from above downwards.

STRUCTURAL DISEASES OF THE HEART AND PERICARDIUM.

Pericarditis . .	Inflammation of the Pericardium.
Endocarditis . .	Inflammation of the Endocardium.
Carditis	Inflammation of the Substance of the Heart.
Atrophy . . .	Fatty Degeneration of the Heart.
Diseases of the Valves of the Heart.	
Hypertrophy . .	Enlargement of the Heart.
Dilatation . .	Of the heart.
Cyanosis	Blue Disease.
Entozoic Disease of the Heart.	

PERICARDITIS.—INFLAMMATION OF THE PERICARDIUM.

Varieties.—1. Acute. 2. Chronic.

1. Acute Pericarditis.

Idiopathic pericarditis is very rare. The disease is commonly an accompaniment of acute rheumatism or of pleurisy.

Symptoms.—After rigors, which are sometimes extremely severe, pain, more or less acute, under the left nipple and towards the lower end of the sternum, occupying a part or the whole of the præcordial region, radiating towards the left axilla and arm, and sometimes extending down the left arm to the elbow or wrist. The pain may be lancinating, or dull and obscure; or there may be merely a feeling of oppression. When pain is present, it is increased, when absent, often produced, by deep pressure in the intercostal spaces over the region of the heart, by upward pressure against the diaphragm, or by an attempt to lie on either side. There is also violent and often irregular palpitation.

In addition to the cardiac symptoms, there is more or less fever; a frequent, full, hard, regular, and *jarring* pulse, or a small, unequal, irregular, and very rapid one; dyspnœa, or respiration interrupted by sighs, sobs, or hiccough; an insupportable sense of oppression, restlessness, jactitation, and an urgent want of fresh air; the skin may be bathed in sweat, or very dry and hot; the countenance is pale, contracted, and expressive of extreme anxiety. Sometimes there are attacks of partial convulsions, or a slight and momentary delirium, and if the patient sleep he awakes with fearful dreams; in other cases there is complete insomnolence. The anxiety and agony are sometimes so insupportable that the slightest motion occasions an apprehension of sudden death. When the disease proves fatal, the breathing becomes more and more laborious, the countenance livid, the eye glassy, the skin covered with a clammy sweat.

Terminations.—1. In complete recovery. 2. In chronic pericarditis. 3. In adhesion of the pericardium. 4. In death.

Morbid Anatomy.—Effusion of serum, with shreds of coagulable lymph, or with pus, sometimes tinged with blood; rough deposits of lymph on the membrane; slight soft adhesions between the two surfaces. In many cases, endocarditis, more or less extensive.

Diagnosis.—The disease is apt to be confounded with pleuritis, pneumonia, or even with simple fever. When the *physical signs* are well marked the diagnosis is easy.

Auscultation.—Within a few hours, or one or two days of the commencement of the disease, a superficial *to-and-fro* sound (*bruit de frottement*), caused by the rubbing of the inflamed surfaces of the pericardium, corresponding to the two sounds of the heart, and resembling the sound caused by rubbing the hands backwards and forwards against each other. When the lymph is more consistent, the sound resembles the creaking of new leather (*bruit de cuir*), or in still more marked cases, that of a file or a rasp (*bruit de scie, bruit de râpe*). As the secretion into the sac of the pericardium increases, or if the opposite surfaces become adherent, the to-and-fro sound disappears. The sound is first heard a little to the left of the mesial line, and about the centre of the sternum, whence it gradually extends over the whole præcordial space. It is often accompanied by a bellows sound synchronous with the systole of the heart, and this, which is *endocardial*, often remains when the to-and-fro sound has ceased. Sometimes it is very difficult to determine whether the sound be *endo-* or *exocardial*. The exocardial sound may be distinguished—1. By its nearness to the surface. 2. By its independence of the sounds of the heart. 3. By its limitation to the region of the heart—endocardial sounds are frequently prolonged over the great vessels. 4. By its occasional disappearance and change of character. *Percussion* detects præcordial dullness, co-extensive with the effusion. When there is much liquid effusion, the sounds of the heart are at first muffled, and in proportion as it increases, they become less and less distinct, till, in extreme cases, they are almost inaudible.

Prognosis.—Complete recovery only occurs in those cases in which the effusion is fluid. Solid effusions generally lead to some thickening of the pericardium, or adhesion of the opposed surfaces.

CAUSES.—*Predisposing.* Hereditary tendency to rheumatic and gouty affections; male sex; age from 10 to 30.—*Exciting.* Cold, and, in most cases, the extension of acute articular rheumatism; adjacent inflammations of the pleura or lungs; renal disease; pyæmia.

TREATMENT.—*Indications.* I. To subdue the existing inflammation. II. To promote the absorption of effused matters.

I. The first indication is fulfilled by general or local bleeding, according to the strength and state of the patient. If the disease come on suddenly in a vigorous plethoric person, blood may be taken from the arm, so as to make a decided impression on the pulse; and this may be followed by cupping, or leeches over the heart. But if the disease supervene, as it generally does, in the course of an attack of acute rheumatism, or in one whose strength is already reduced, topical bleeding by cupping or leeches will suffice. In no case should depleting measures be carried to excess. They may be assisted by purgatives, rest, and the antiphlogistic regimen; and when the depletion has been carried to the proper extent, a blister may be applied over the region of the heart, and kept open some time by savin ointment.

II. The second indication is fulfilled by mercury given every one, two, or three hours with opium (Form. 295), and accompanied by mercurial inunction till the gums are sore. When the fever is great and the skin dry, the mercury may be combined with tartar emetic in doses of $\frac{1}{8}$ to $\frac{1}{4}$ of a grain. Rheumatic pericarditis should be treated with blisters and the appropriate remedies. Mercury is useless.

2. CHRONIC PERICARDITIS.

SYMPTOMS.—Palpitation and dyspnœa, accompanied sometimes by dry cough; inability to lie on the left side; slight pain or uneasiness in the region of the heart; sense of oppression; great debility; and slow and imperfect convalescence, or a fatal termination in hydro-pericardium.

CAUSES.—Chronic pericarditis is generally a sequel of the acute form of the disease; and is especially apt to follow an attack of acute rheumatism. The symptoms are sometimes very obscure.

TREATMENT.—Blisters to the region of the heart. In the rheumatic, the appropriate eliminatives; in the debilitated, iron, in combination with iodine or quinine. During convalescence violent exercise should be avoided, and a nourishing, unstimulating diet allowed.

SEQUELÆ.—Important structural changes often remain when the symptoms of pericarditis, whether acute or chronic, have been removed. The pericardium may be thickened, and the subjacent capillary vessels enlarged. There may be serum, or lymph, or pus *in the pericardium,* adhesions, partial or general, and organized deposits of fibrin, in the form of granulations and vegetations. The false membranes may become fibro-cartilaginous, or even osseous. The effused fluid, or the thick false membranes, embarrass the action of the heart. The muscular tissue may, like the serous, fibrous, and cellular tissues of the heart, become thickened, and hypertrophied, indurated or softened, by the extension of the inflammation from the pericardium (see Carditis).

These changes may be detected by careful stethoscopic examination. The superficial to-and-fro sound of acute pericarditis is generally absent. The denser deposits on the surface of the pericardium are indicated by harsher and louder sounds, corresponding to the apex or base of the heart.

Partial adhesions of the two layers of the pericardium are sometimes productive of no unusual sounds; at others, of some modification of the friction sounds.

Extensive adhesions of the two layers of the pericardium generally lead to irregular action of the organ, and are accompanied by a well-marked retraction of the epigastrium, and hollowing of the intercostal spaces with each systole of the heart; and the heart's beat continues to be perceptible in the same spot, in all positions of the body, and in all states of the respiration.

An abundant effusion into the sac of the pericardium constitutes Hydro-pericardium.

Hydro-Pericardium.

VARIETIES.—1. Active, from inflammatory action. 2. Passive, from obstruction to the circulation.

The symptoms of the *passive* form are generally obscure. They are a sense of weight and oppression in the præcordia, great dyspnœa, a dusky, suffused countenance, a tendency to syncope, œdema, and a small, frequent, irregular pulse. The patient usually sits up in bed, afraid of the least exertion, or slightest change of position.

LOCAL SIGNS.—When the effusion is considerable, prominence of the præcordia, with bulging of the intercostal spaces, extensive dullness, reaching sometimes from nipple to nipple and nearly the whole length of the sternum; the pulsations of the heart imperceptible when the patient lies down, and shifting their place in the erect and sitting posture; the sounds indistinct in the region of the heart, but more audible at the upper part of the chest; the dullness varying in situation and extent with the posture.

PROGNOSIS.—Unfavourable.

TREATMENT.—That of dropsies in general, by drastic purgatives and diuretics, modified according to the state of the patient and existing complications, and assisted by large blisters to the region of the heart, kept open by savin ointment.

In a few cases, where the accumulation of serum has been very large, and the disease is free from other visceral complication, tapping has been practised with success. The spot selected for the operation is the fifth intercostal space, through which a trocar of small size is introduced—from below upwards.

ENDOCARDITIS.—INFLAMMATION OF THE ENDOCARDIUM.

Symptoms.—General feeling of uneasiness, anxiety, and oppression at the præcordia, with a tendency to syncope; but no pain, unless the disease be complicated with pericarditis or pleurisy. In the more severe cases there is well-marked fever, hot and dry skin, thirst, and restlessness; violent and irregular action of the heart, with a small, feeble, and often intermittent pulse; jactitation; cold sweats; pale and shrunken features, expressive of extreme alarm; dyspnœa, faintness, or actual syncope; lividity of the lips and cheeks; slight swelling of the hands and feet; and short convulsive seizures.

Morbid Anatomy.—1. Redness of the endocardium, sometimes general, but more often partial; usually confined to the valves, and accompanied by some thickening, infiltration, and softening of the membrane. 2. Effusion of white, elastic, glutinous masses of coagulable lymph, firmly attached to the free borders of the valves adherent to the parietes, twined round the valvular tendons and fleshy columns, and often prolonged into the large vessels. 3. Vegetation, varying in size from a millet-seed to a small pea, single or clustered, smooth or rough, and when very numerous resembling a cauliflower, on the free borders of the valves, and sometimes on the surface of the cavities. 4. These valvular vegetations are often accompanied by fibro-cartilaginous or calcareous indurations, which contract the orifices of the heart so as to impede the circulation, and cause cardiac dropsy. Sometimes the opposite borders of the valves adhere.

Causes.—Those of pericarditis, which it often accompanies.

Diagnosis.—The stethoscopic indications mentioned under diseases of the valves. The murmurs are generally of a low pitch, and are sometimes musical. We cannot be sure of the existence of *acute* endocarditis unless the murmur be developed under observation.

Prognosis and Terminations.—The disease is rarely fatal in its acute stage. Its duration is uncertain, and much influenced by the habits of the patient. It may continue for years, with slowly increasing embarrassment of the circulation; forming a *chronic valvular disease*, with *hypertrophy*, and ending either in sudden death or in dropsical effusions. If particles of fibrinous exsudation become detached from the inflamed valves and carried along in the arteries, they may eventually block up some of the smaller branches, and thus produce the condition known as embolism and its *consequence (See pages* 78, 439.)

Treatment.—That of pericarditis. In the acute form, and in vigorous subjects, active and prompt treatment is still more necessary.

When endocarditis becomes chronic without organic disease, the symptoms may be alleviated by small and repeated bleedings, cupping or leeching; gentle aperients; counter-irritants; the warm bath; repose; and a strictly regulated diet.

CARDITIS, OR MYO-CARDITIS.

Symptoms.—Carditis, or inflammation of the substance of the heart, rarely occurs as a distinct affection, and the post-mortem appearances which characterize it have generally been found combined with pericarditis, or endocarditis, or both. The muscular tissues of the heart may, however, be separately affected, as are the ordinary muscles in muscular rheumatism.

Palpitation, with strong and abrupt contractions of the organ, a very frequent, full, and bounding pulse, and a dull, heavy sensation in the region of the heart, with paroxysms of severe darting or shooting pain, extending to the shoulders and down to the arms, with some degree of dyspnœa, are the symptoms present in this disease. Muscular rheumatism in other parts of the body may be looked for.

I have known such symptoms supervene on a severe attack of muscular rheumatism, without any indication of inflammation in the pericardium or endocardium. The treatment should be that of muscular rheumatism, with counter-irritation to the region of the heart, and, in the most severe cases, general or local depletion. (G.)

The symptoms are often very obscure. After death we may find softening, suppuration, ulceration, and even perforation of the cardiac parietes.

ATROPHY.—FATTY DEGENERATION OF THE HEART.

Symptoms.—Occasional fainting, and transient attacks of giddiness, in some cases, and the symptoms of angina pectoris in others. The most common termination is in sudden death under change of posture or slight exertion, the patient having previously suffered from debility, with great pallor of countenance and anasarca; but in some instances he is stout and apparently healthy. The respiration is sometimes affected in the manner described at §§ 817. The pulsations of the heart are small and feeble, the impulse weak, and scarcely to be felt, and the sounds indistinct. The least exertion renders the heart's action fast and irregular, and then some of the pulses become so feeble as not to be appreciable at the wrist. The pulse is very compressible, intermittent, and small, and, in a state of quietude, usually below the natural frequency.

Causes.—*Predisposing.* The male sex; age above 50; habits of intemperance, combined with a sedentary life; exhausting diseases; such as hæmorrhage, typhus fever, pulmonary consumption, emphysema of long standing, and dropsy.—*Proximate.* Compression of the heart by deposits of fat, by effusion of fluid, by tumours; carditis; congenital absence of one, or defect of both coronary arteries.

Morbid Anatomy.—Fatty degeneration of the muscular tissue of the heart, which is soft, flabby, and of a dirty dark-brown, or pale drab colour. When cut, a greasy film is left on the scalpel. In extreme cases the walls of either ventricle may be broken down between the thumb and finger. The fibres lose their faint striation, and the sarcous matter is more or less completely changed into fat, observable in the form of distinct highly refractive spherules. Fig. 59 shows the early (A), and the latter stage (B) of fatty degeneration of the muscular fibres of the heart. In A the oily particles are arranged in rows, in B they are irregularly distributed. Fatty degeneration of the liver and kidneys, and of the aorta, emphysema of the lungs, and ulceration of the stomach, are frequent concomitants.

Fig. 60.



Treatment.—Nutritious diet, digitalis, tonics, (Form. 150), and stimulants (Form. 2), and occasional doses of brandy; carriage exercise. Great watchfulness on the parts of the attendants, if the condition be suspected. The disease does not admit of cure.

DISEASES OF THE VALVES OF THE HEART.

Symptoms.—When the valves of the heart are the seat of disease the blood is not only impeded in its flow out of the heart, but, from defective closure of the valves is subject to regurgitation. The obstruction to the circulation of blood through the heart thus set up leads to hypertrophy of the organ, and sooner or later to congestion of the lungs or other viscera, ultimately ending in grave diseases, of which dropsy is the prominent symptom. The symptoms attendant on valvular disease are by no means uniform; they vary with the valve which is the seat of the disease, and with the nature, extent, and duration of the morbid change itself. The general symptoms are tumultuous palpitation, a frequent pulse, a sense of weight, tightness, and oppression, sometimes accompanied by pain in the region of the heart and at the epigastrium; dyspnœa; an inability to lie on one or both of the sides; flatulency; frequent feelings of faintness and giddiness, or fits of syncope; an anxious expression of countenance, *with slight knitting* of the brows; the face sometimes pale, sometimes suffused. These symptoms are greatly increased by active exertion, walking up hill, or mounting stairs, and by violent mental emotion.

In order to ascertain the effects of valvular disease upon the several parts of the circulation, and their influence in the production of disease of the viscera, it will be necessary to consider each valve separately, premising these two facts: first, that disease may affect more than one valve simultaneously; secondly, that while the valves on the left side are very prone to disease, those on the right are rarely affected.

Disease of the right auriculo-ventricular (tricuspid) valve, allowing regurgitation from the ventricle into the auricle.—Proximate effects. Slight hypertrophy of the right cavities, and increased præcordial dullness to the right; epigastric and right sternal impulse. A soft *systolic* murmur at the ensiform cartilage. *Remote effects.* Cervical veins distended, varicose, and pulsatile; when a finger is pressed upon them they do not become empty below it; congestion of the venous circulation, producing corresponding obstruction to the arterial. The brain becomes oppressed, and the patient suffers from congestive headache, and is liable to apoplexy. The liver becomes gorged with blood and enlarged; the portal circulation is impeded, and the mucous membrane of the stomach and intestines congested. Piles, and voiding of blood from one or other, or from both extremities of the alimentary canal, are among the symptoms. The kidneys soon become congested, and the urine scanty, and sooner or later albuminous; ascites, œdema of the legs, and at last general anasarca follow.

Disease of the right auriculo-ventricular orifice obstructing the flow of blood from the auricle into the ventricle.—If the tricuspid orifice be merely constricted, the action of the valves remaining perfect, there would be but slight congestion of the venous circula-without pulsation in the veins, and a *diastolic* (*auricular systolic* or *præsystolic*) murmur would probably be heard at the ensiform cartilage. But such a condition is exceedingly rare.

Disease of the pulmonary valves with permanent patency.—Proximate effects. Signs of hypertrophy of right cavities of the heart; and "along the sternum a well-marked *double* murmur, similar, in every respect, to that observed in the ordinary case of permanently open aortic valves, loudest at the base of the heart, and becoming less distinct as the stethoscope is moved towards the apex, where it ceases to be audible." (Stokes.)—*Remote effects.* Dyspnœa, palpitation, some venous congestion.

Disease of the pulmonary valves obstructing the passage of blood into the lungs.—If the pulmonary orifice become contracted, the pressure of accumulated blood in the right ventricle will lead to regurgitation into the right auricle, followed by general venous congestion, as detailed under regurgitant disease of the tricuspid valve, and hypertrophy of the ventricle.

Disease and congenital defect of the pulmonary valves are very rare.

Disease of the left auriculo-ventricular (mitral) valve, permitting regurgitation from the ventricle into the auricle.—Proximate effects. Enlargement of the left ventricle; increased præcordial dullness towards left side; apex-beat lower and more to the left; impulse greatly increased, often giving rise to a perceptible systolic thrill. A *systolic* murmur partially or completely obscuring the first sound of the heart, most distinct at the apex, and disappearing beyond the base, but heard distinctly on the left side, as far as the inferior angle of the scapula.

Remote effects.—The arteries do not receive their full share of blood, and the pulse is consequently small and contracted; congestion of the lungs.

Disease of the left auriculo-ventricular orifice, causing obstruction to the flow of blood into the ventricle.—If the mitral disease result in *contraction of the left auriculo-ventricular orifice*, as is sooner or later the case, pulmonary symptoms in proportion to the contraction supervene. The lungs become congested, and there is constant liability to pulmonary hæmorrhage, evidenced by pulmonary apoplexy, or hæmoptysis, often to a large amount. Dyspnœa is often very urgent; and there is chronic bronchitis. Sooner or later the obstruction to the pulmonary circulation affects the right side of the heart, its cavities become enlarged, general venous congestion ensues, and its ultimate result, anasarca, appears. A soft *diastolic* (*auricular systolic* or *præsystolic*) murmur, best heard at the apex, and not masking the second sound, is diagnostic of contracted mitral orifice. Later on, when the heart becomes enfeebled and the orifice much contracted, the murmur is no longer heard.

Disease of the aortic valves obstructing the exit of blood from the left ventricle (constriction of the aortic orifice).—Proximate effects. Great hypertrophy of the left ventricle; systolic thrill; strong heaving impulse; a loud, harsh *systolic* murmur at mid-sternum, inaudible, or nearly so, at apex.—*Remote effects.* If the constriction be great, the pulse, though regular in force and rhythm, is small, hard, rigid; hardness and force imply hypertrophy. When the action of the heart is weak, or the constricted orifice very smooth, the murmur may be absent, and in this case, even if the opening be no larger than a pea, there may not be the slightest œdema, even of the ankles.

Disease of the aortic valves preventing the closure of the orifice, and therefore allowing of regurgitation.—Proximate effects. Extreme hypertrophy of the left ventricle, and corresponding heavy prolonged impulse with diastolic and systolic thrill. A systolic or diastolic murmur, or both, obliterating the first or second, or both sounds of the heart, heard best at mid-sternum, distinctly heard in an upward direction towards the right shoulder; but weaker at the apex. The diastolic murmur is best heard in a downward direction towards the apex, where it may be either faint or strongly pronounced.—*Remote effects.* A characteristic sudden jerking pulse.

The pulsation of the superficial vessels is visible, and accompanied by considerable movement; slight pressure upon them often produces a sensible thrill.

Of all the affections of the valves of the heart this produces the least injurious effect on the circulation. Of itself it never causes dropsy.

MORBID ANATOMY.—Dilatation of the orifices, and incomplete closure by the valves; partial adhesion of the valves; contraction of the orifices with rigidity and roughening of the valves from fibrinous, atheromatous, cartilaginous, or bony deposits within their substance. Rupture of the valves or chordæ tendineæ.

DIAGNOSIS.—*Disease of the several valves and orifices* may be correctly diagnosed if attention be paid to the following points:—

1. The left side of the heart is very much more frequently affected than the right.—2. Generally, when the right side is the seat of disease the left side is affected also.—3. Diseases of the right side chiefly affect the venous circulation, causing regurgitation into the jugular veins (the *venous pulse*).—4. Diseases of the left side affect chiefly the arterial pulse, giving rise to irregularity and inequality. —5. Disease of the right side generally leads to dropsical effusions; disease of the left side to affections of the lungs; and disease of the aorta to head symptoms.—6. Sounds, whether on the right or left side, which accompany or take the place of the first sound of the heart, and are synchronous with the pulse, are due to the passage of the blood out of a ventricle—that is to say, to regurgitation into the auricle, or onward movement into the artery of side affected.—7. Sounds, whether on the right or left side, which accompany or take the place of the second sound of the heart, and are not synchronous with the pulse, are due to the entrance of blood *into* the ventricles, in consequence of the contraction of the corresponding auricles, or to regurgitation from the corresponding arteries. —8. Sounds heard at the base of the heart, and in the course of the aorta towards the right clavicle, becoming less audible towards the apex, indicate disease of the valves or coats of the aorta. If the sound accompany the contraction of the ventricle, and be synchronous with a regular, equal, *thrilling* pulse, it is due to disease of the valves or coats of the aorta; but if the sound accompanying the diastole of the ventricle be not synchronous with the pulse, which is, at the same time, abrupt and *jerking*, and the abrupt second sound of the heart be absent or very obscure, the sound is due to reflux through the open aortic valves.—9. If, on the other hand, the sound be synchronous with the systole of the ventricle, and with the pulse, which, at the same time, is wanting in volume, the sound is due to reflux from the left ventricle, through a diseased mitral valve, into the left auricle; but if the sound be not synchronous with the contraction of the ventricle, it is due to the passage of the blood from the auricle to the ventricle, through a diseased mitral valve.—10. The same rules apply to the right side of the heart. If the disease were in the pulmonary artery, the sound would be heard in the track of that vessel, towards the left clavicle.

uses.—Rheumatic fever, chronic rheumatism, gout, Bright's se of the kidneys, violent exertion, obstruction to the pulmo- circulation, atheromatous degeneration of the valves or great vessels, aneurism of the aorta or pulmonary artery.

eatment.—Must be directed to regulate the action of the and to prevent the tendency to dropsy, by relieving the mic congestion. This is effected by hydragogue purgatives, ccasional and cautious abstraction of blood by a small orifice, , moderation in diet, and abstinence from all violent exertions trong emotions. In the more advanced stages of the disease the ment must be suited to the existing complications. The general iple of treatment will be to avoid all excitement of the lation, and all remedies which impair the power of the heart; at the same time, to relieve any unusual embarrassment by rate depletion. Undue action of the heart may be moderated ıe internal use of digitalis and henbane, and the external cation of belladonna or opium plasters.

HYPERTROPHY OF THE HEART.

is is the direct result of obstruction in some part of the circu- ı, of which it is, therefore, merely a symptom. The hyper- y is due to the increased exertion made by the heart to over- the obstruction to the flow of the blood. It may affect the whole , or be limited to one or other of its chambers.

ıe hypertrophy is usually accompanied by dilatation of the y or cavities.

mptoms.—Since the hypertrophy exactly compensates the ob- tion, its effects involve the heart alone. The symptoms, there- which are associated with hypertrophy must be referred to the ses that produce it, and not to the hypertrophy itself.

ysical Signs.—The impulse of the heart is greatly increased, prolonged, and extends over a large space. It is visible to the and forcibly raises the stethoscope. The first sound is obscure, ı there is little or no dilatation; louder, more abrupt, and heard a larger space when it is considerable; the second sound ıre in the former case, unusually distinct in the latter. There llness, varying with the degree of enlargement, and most ex- ve where dilatation is combined with hypertrophy. In some nces the left side of the chest is perceptibly wider and more ıinent. When the right side of the heart is affected, the dull- is most marked over the lower part of the sternum, and the ılse is felt in the infra-sternal fossa.

uses.—Violent exertion; prolonged efforts, as in gymnastic cises; plethora, valvular diseases and obstruction of the large els, or in the heart itself; pericarditis and endocarditis; chronic ses of the lungs, especially emphysema: diseases of the kidney.

Prognosis and **Treatment** have reference to the diseases which produce the hypertrophy. (See Valvular Diseases of the Heart.)

DILATATION OF THE HEART.

Definition.—Dilatation of the cavities of the heart without corresponding increase of muscular tissue.

Symptoms *of dilatation with thinness of the parietes.*—This is most common on the right side; and is characterized by fluttering of the heart, and a full, frequent, weak, and irregular pulse. In extreme cases swelling of the veins of the neck, and distinct venous pulse; great dyspnœa; a dusky skin; a bloated and anxious countenance; drowsiness; slight delirium; dropsical effusions.

Physical Signs.—Impulse feeble, short, and flapping, or tremulous, felt over a greater extent than usual; first sound short and peculiarly distinct, heard over a great extent of chest both before and behind.

Causes.—Debility; anæmia; chronic diseases of the lungs; emphysema; especially valvular diseases of the heart.

Treatment.—Tonics. Repose of body and mind, careful regulation of the diet, aperients. Gentle opiates and sedatives may occasionally be of service to allay irritability; dry cupping if there be urgent dyspnœa.

Partial dilatation, or *true aneurism* of the heart, consists in a protrusion of some part of its walls through disease of the muscular tissue. It is an equally rare, obscure, and fatal disease, differing little in the symptoms from those of more general dilatation of the cavities. The physical signs are obscure; the prognosis, when the disease is recognized, is in the highest degree unfavourable, and the treatment similar to that for more general dilatation—complete repose of body and mind, the cautious use of narcotic and sedative remedies, and, in cases of extreme urgency, cautious depletion. When the aneurism bursts, effusion into the pericardium takes place; the rupture is announced by a piercing cry of anguish, and usually by instantaneous death.

CYANOSIS.—BLUE DISEASE.

Symptoms.—A blue tint of the skin, lips, mouth, and tongue; universal coldness of the surface; palpitation; fits of extreme dyspnœa; faintness, or actual syncope, on slight exertion, or from mental excitement; feeble and irregular pulse; œdema or dropsical effusions.

Morbid Anatomy.—Congenital deficiency or malformation. A single auricle and ventricle. A communication between the two sides of the heart, or between the two sets of vessels arising from it with disproportionate size of the two ventricles, generally combined with narrowing of the pulmonary artery. Extreme contraction of the pulmonary artery, the mitral orifice, or the left ventricle. Transposition of the aorta and pulmonary artery. Dr. Peacock finds that males are more frequently the subject of defective development than females, the proportion being as 57·2 : 42·8.

Physical Signs.—A very loud and superficial murmur immediately over the seat of the communication indicates that the communication is affected by a contracted orifice.

Prognosis.—Death during a paroxysm at an early age; in rare instances the patient attains the adult age; and in one case recorded by Louis, the age of fifty-seven.

Treatment.—Rest of mind and body; pure air; warm clothing; strict diet; careful attention to the state of the stomach and bowels.

DEVELOPMENT OF ECHINOCOCCUS IN THE HEART.

This is a rare disease: but as it may simulate valvular disease of the heart, tubercular disease of the lungs, embolism, or disease of the arteries, it is worthy of consideration here. The symptoms vary with the situation of the cyst, and are urgent and characteristic according as it breaks into the right or left ventricle. The patient is usually well nourished. When the cyst bursts into the right ventricle, pulmonary symptoms—urgent dyspnœa, bloody expectoration, severe pain in the præcordia, and death by suffocation—result. If rupture take place into the left ventricle, the symptoms are more remote and obscure. Mortification of a part of a limb, or of an entire extremity, from obstruction of a large artery by one of the secondary or tertiary cysts, is a likely result.

DISEASES OF THE ARTERIES.

Obliteration.
Atheroma.
Aneurism of the Aorta.

OBLITERATION.

The arteries are liable to obliteration from any cause which for a time arrests the circulation through them. It appears that when their coats are inflamed the current of blood is retarded, and becomes at last quite stagnant; coagulation follows, the clot adheres to the walls of the contracted tube, and the result is a fibrous cord. The most common cause of obliteration is a process termed by Virchow, *embolism*—*i.e.*, the impaction of clots, fibrinous concretions, or atheromatous matter in the remote arteries.

Symptoms.—Inflammatory obliteration is attended by local symptoms, *such as tenderness* and hardness of the vessel. The process is usually so slow as to allow of the establishment of collateral circulations. If more than one of the main trunks were simultaneously affected, dry gangrene would result. Embolism occurring in the extremities, would also result in gangrene. If it occur in the internal carotids, softening of the brain, loss of vision, and hemiplegia may, one or all, result. If the pulmonary artery be blocked by a clot at its bifurcation, death, more or less sudden, from asphyxia, will be the consequence. If the smaller superficial arteries be the seat of the embolism, sloughing ulcers may ensue.

ATHEROMA.

Definition.—This term comprises both fatty and calcareous degenerations of the blood vessels, atheroma proper being an intermediate condition. After the age of fifty the walls of the vessels are very liable to degeneration. The aorta, in particular, becomes dilated, the elasticity of its wall impaired, and its inner surface roughened by large, irregular, elevated patches of morbid matter, lying immediately beneath a superficial layer of the inner coat, and composed of a mixture of earthy and fatty matter.

Symptoms.—When the disease affects the smaller arteries, such as the radial and temporal, they become rigid and tortuous, and feel like cords. A dilated atheromatous condition of the aorta is indicated by a loud systolic bellows murmur, commencing at mid-sternum, and extending thence towards the right shoulder, most distinct to the right of the sternum, and thus distinguished from murmurs due to disease of the aortic valves. Atheromatous disease of these valves is, however, very frequently associated with a similar degeneration of the contiguous part of the aorta. Owing to the diminished elasticity of the diseased artery, the pulse has the same sudden, jerking character as in regurgitant disease of the aortic valves. (See page 431.)

Morbid Anatomy.—At first an opaque whitish spot is observed on the inner surface of the artery. It consists of a fatty degeneration of the tissues, immediately bedeath the innermost layer. A vertical section presents the appearance shown in Fig. 61: *i* being the unaltered innermost layer; at *h* the corpuscles of connective tissue are enlarged; at *p* these cells are observed to be multiplying; at *a* the fatty degeneration in them is seen commencing; at *a′* this is in an advanced stage.

Fig. 61.



The next stage of the process consists in the deposit of molecules of earthy matter, and the separation of cholesterin. If we examine the disintegrated portion of the arterial wall at this stage, we observe large rhombic plates or prisms of cholesterin *c c c* (Fig 62); and cells of the internal coat transferred into fatty-granule globes *a a*, imbedded in free granular matter, composed in part of earthy matter, and in part of free drops of oil, large and small. (Virchow.) These accumulated deposits either form a pultaceous matter, which may be discharged into the blood through an aperture formed in the internal coat, leaving the so-called atheromatous ulcer; or they may, by the increase of the earthy particles, become petrified into irregular ossific plates. In the smaller arteries the ossification proceeds much more uniformly, and they become at last more or less completely converted into smooth bony tubes.

Fig. 62.



The capillaries are equally liable to degeneration. When their walls are invaded with fat, they present a granular appearance.

As a result of this condition their elasticity and contractility is impaired, they become permanently dilated, and the blood tends to become stagnant in them.

Effects. — *Proximate.* Rupture; atheromatous ulceration of the inner coat, with aneurismal dilatation of the outer: dilatation resulting first in congestion, and finally in rupture of the capillaries, especially those of the brain, causing sanguineous apoplexy.—*Remote.* Hypertrophy of the heart; embolism.

Causes.—The rheumatic and gouty diathesis.

Treatment.—The avoidance of hurry, exertion, and fatigue; animal diet; tonics in combination with alkalies.

ANEURISM OF THE AORTA.

1. Aneurism of the Thoracic Aorta.

Symptoms.—The general symptoms produced by an aneurismal tumour in the chest are the same as those due to any other tumour of equal size and similar situation—*dyspnœa*, and more or less consolidation of the lung, from pressure of the aneurismal tumour; a harsh, harassing cough, with little or no expectoration, paroxysmal *dyspnœa, from pressure* on the bronchial tubes; aphonia, and obstruction of the glottis, from unilateral atrophy of the laryngeal muscles due to pressure on the left recurrent nerve (Bristowe); *dysphagia*, from pressure on the œsophagus; *obstruction to the venous circulation*, accompanied in extreme cases by dropsical effusions into the cellular membrane of the face, neck, chest, and upper extremities, from compression of the large venous trunks; *neuralgia of the back* and *paraplegia*, from absorption of the vertebra and pressure on the spinal marrow; and defective nutrition, from pressure on the thoracic duct.

Diagnosis.—Difficult, when the tumour is of small size, or occupies the origin of the aorta. When it involves the *arch of the aorta*, or its first branches, and especially when it has so far increased as to rise out of the chest, the diagnosis becomes comparatively easy. When, again, the tumour, by its gradual increase in size, causes the protrusion of the sternum or ribs, or leads to their absorption, its strong heaving impulse will make the diagnosis certain.

A *whizzing* sound, or a bellows murmur, single, or double, is usually heard over the tumour; but these sounds are not always present, nor are they to be depended upon in the absence of other symptoms, since they may be produced by any tumour pressing upon the larger arteries. A palpable thrill, and a quick thrilling pulse, are occasionally present. When the tumour occupies the arch of the aorta, or its branches, we may expect to find some marked inequality in the pulsations of the radial and carotid arteries. Sometimes there is an absence of the pulse at the wrist, of one or of both arms, and occasionally of one or both carotid arteries; and there are signs of disturbed circulation through the brain, such as giddiness, faintness, and indistinct vision. Hæmorrhage from the lungs or stomach will have additional value as a sign of aneurism in the ascertained absence of symptoms of pulmonary consumption and obstruction to the portal circulation; if the tumour be large, dullness and bronchophony in proportion to the compression of the lung will be observed. A sensation of throbbing in the chest, difficulty of deglutition, and, in the later stages, vomiting and spasmodic dyspnœa, complete the evidences of thoracic aneurism.

Morbid Anatomy.—Laceration of the internal coats of the artery, and saccular dilatation of the external. Extravasation of blood between the layers of the artery, causing their dissection and dilatation. But the commonest cause of aneurism is fatty or atheromatous degeneration.

Prognosis.—Unfavourable; but the disease progresses slowly.

Treatment.—Perfect repose of mind and body, a cool moderate diet, a free state of bowels, occasional cautious depletion when urgent symptoms require it; a belladonna plaster to the region of the heart, and digitalis in small and repeated doses to moderate the heart's action. The dry harsh cough will require the use of sedatives, with expectorants, and anasarca must be treated by the remedies prescribed under that head.

2. Aneurism of the Abdominal Aorta.

Symptoms.—These vary with the size and situation of the tumour, and the viscera on which it presses. When the aneurism presses on the stomach, it gives rise to severe gastric disturbance; on the nerves of the solar plexus, to neuralgic pains; on the bowels, to obstinate constipation or violent colic; on the nerves issuing from the spine, to severe pain in the loins, abdominal parietes, or lower extremities, simulating rheumatism of those parts, sciatica, lumbar, and psoas abscess, or spinal disease. By pressure on the rectum, it has sometimes led to a suspicion of stricture of that part. When the tumour occupies the upper part of the abdominal aorta, it may thrust up the diaphragm, and give rise to dyspnœa, and other symptoms of pulmonary disease.

Occasionally the diseased part of the artery is suddenly blocked by a detached clot, and the patient, who was to all appearance in perfect health, drops down as if shot; he is taken up completely paralyzed as to motion and sensation in the lower limbs, and on examination no pulsation can be detected in the femoral arteries. Such a case occurred in my practice a few months ago. The patient died within a fortnight, the lower part of the body, including the bladder, being in a gangrenous state.

Diagnosis.—A tumour occupying the situation of the aorta, strongly pulsatile at the sides. The pulsation of a healthy aorta is communicated to a loaded intestine or other tumour seated over it, but that of an aneurism is stronger and more diffused.

Prognosis and Treatment are those of aneurism of the thoracic aorta.

DISEASES OF THE VEINS.

Phlebitis	Inflammation of the Veins.
Phlegmasia Dolens .	White Leg.

Preliminary Observations.—*Thrombosis*, *Embolia*, and *Pyæmia*. —Before describing diseases of the veins it is necessary to say a few words on the formation of clots in the circulatory organs, to which process the term *thrombosis* has been given. When foreign matters such as iron, or liquids such as mercury and pus, are introduced into the vessels, the blood coagulates upon their surfaces; and a clot of fibrin, or of blood formed within the blood vessels, tends to increase by superposition of layer upon layer of coagulum. Thrombosis, therefore, may be caused by phlebitis, arteritis, and endocarditis, in consequence of solid inflammatory exsudations on the inner surface of the veins, arteries, or heart. A film forms on the roughened inflamed surface; and, subsequently, layer after layer is deposited until a clot or thrombus of considerable size is formed, which is attached by one extremity to the inflamed surface, while the other may freely vibrate in the passing current of blood, or may reach to the other side of the vessel and obstruct the flow of blood from below.

The subsequent changes which these clots undergo give rise to some most interesting and important pathological processes. If they slowly deliquesce without undergoing further change, no bad effects result. If the entire thrombus, or a large fragment of it, be detached, it may be carried from a large vein into the pulmonary artery, and produce instantaneous suffocation; thrombi from the left side of the heart may become impacted in a carotid or brachial artery; clots from the surface of the aorta may block up any of its branches: in either case sloughing ulceration of a part, or mortification of the whole limb, will most probably ensue. If the clot undergo gradual disintegration into fine particles, these will be arrested in the capillary circulation, giving rise to *capillary embolia*, resulting in softening or ulcerative degeneration of the contiguous part. But even greater evils may result from the presence of clots in the circulation. The central parts are often changed into a puriform mass, composed of granules (A, fig. 63) derived from the disintegrated fibrin; corpuscles undistinguishable from pus corpuscles (B); and altered blood discs (C). Virchow says that the second form are "Colourless blood corpuscles set free by the softening." But evidence is wanting to prove that leucocytosis can take place to this extent in the blood itself; and the effects of the metamorphosis resemble those of pyæmia. It matters little whence the pus-cells are derived, the result is the same. They form, wherever they are carried, the nuclei of other clots, which, in process of time, become centres of suppurative inflammation; and thus abscesses may be deposited simultaneously in all parts of the body.

Fig. 63.



PHLEBITIS.—INFLAMMATION OF THE VEINS.

Varieties.—Adhesive, and suppurative (pyæmia).

Pathology.—Idiopathic adhesive phlebitis commences in inflammation of the coat of the vein, causing dilatation and impairment or loss of contractility, leading to stagnation and subsequent coagulation of the blood. The disease is strictly local at first, and if the coagulated blood be very gradually disintegrated or absorbed, it may remain so, and the vein may be ultimately restored to its original condition. If, however, portions of the coagula become detached, embolism may result. If they undergo purulent degeneration, the phenomena of suppurative phlebitis (pyæmia) appear.

Symptoms.—In the superficial veins, swelling and induration, sometimes accompanied by lines of redness; pain increased by pressure; œdema of the cellular tissue, and enlargement of the veins below the part. In the suppurative form, all the symptoms of the pyæmia (see p. 330). As the disease advances, the joints often become painful and tender, inflammation of the viscera, or of their serous investments, shows itself, and collections of pus, with little or no inflammation of surrounding textures, form in different parts of the body.

Causes.—*Predisposing*. Cachexia.—*Exciting*. In rare instances, cold; in most cases, inflammation spreading from surrounding tissues, or injury to the veins themselves, and operations generally, as in bleeding. Phlebitis is also apt to supervene on fractures, or on operations on bones; and it often originates in the internal viscera, as in the uterus after childbirth.

Morbid Anatomy.—Discoloration of the inner coat of the vein: inflammation and thickening of the other coats; inflammation and suppuration of the surrounding textures; formation of coagula and pus within the vein; deposits of pus in the joints and serous cavities or in the spleen or kidneys; but chiefly in the lungs and liver.

Diagnosis.—From *inflammation of the absorbents*, by the absence of superficial redness and the larger size of the inflamed vessel, which forms a tender, hard, knotted cord.

Prognosis.—Favourable in inflammation of the external veins, arising spontaneously or from cold. Less favourable in phlebitis following wounds, or injury to the vein. Secondary abscesses in external parts may be regarded as favourable.

Treatment.—Leeches in the course of the inflamed vein. A position favourable to the return of blood to the heart. Warm fomentations. If the fever be great, aperients, or calomel and opium; if of the typhous character, wine, brandy, and diffusible stimulants, with opium. In most cases quinine, with a liberal allowance of wine or brandy. Close attention should be paid to uneasiness or pain in parts of the body remote from the seat of the disease, as indicating collections of pus requiring prompt relief by the knife.

PHLEGMASIA DOLENS.—PHLEGMASIA ALBA.—WHITE LEG.

Definition.—Obstruction, usually of an inflammatory character, of the femoral vein, or of the femoral and iliac veins.

Symptoms.—From one to five weeks after delivery, a painful elastic swelling of one or both legs, beginning generally in the groin, labium, and thigh, and thence extending downwards; characterized by great heat and tenderness, a pale, shining surface, and stiffness. It is commonly ushered in by rigors, with pains in the loins or belly; and is accompanied by fever, thirst, a quick and *frequent pulse, headache*, nausea, and a furred tongue.

CAUSES.—*Predisposing*. The puerperal state.—*Exciting*. Inflammation of the iliac and femoral veins, generally commencing in the veins of the uterus and viscera of the pelvis.

PATHOLOGY AND MORBID ANATOMY.—Those of adhesive phlebitis.

DIAGNOSIS.—From *œdema*, by the absence of pitting on pressure. From *common inflammation* by the pale, shining aspect of the surface.

PROGNOSIS.—Generally favourable, but recovery often tardy.

TREATMENT.—Leeches, warm fomentations to the painful limb, which should be kept in the horizontal position. The bowels should be free. If there be much fever, saline diaphoretics and slight mercurialism. After the inflammation has subsided, iodide of potassium; friction with mercurial or iodine ointments.

CHAPTER III.

DISEASES OF THE ORGANS OF RESPIRATION.

1. Of the Larynx and Trachea.
2. Of the Bronchial-tubes and Air-cells.
3. Of the Substance of the Lungs.
4. Of the Pleura.

DISEASES OF THE LARYNX AND TRACHEA.

LARYNGITIS	Inflammation of the Larynx.
APHONIA	Loss of Voice.
TRACHEITIS	Croup.
LARYNGISMUS STRIDULUS .	Crowing Inspiration.

LARYNGITIS.—INFLAMMATION OF THE LARYNX.

SYNONYM.—Cynanche laryngea.

VARIETIES.—1. Acute. 2. Chronic.

1. ACUTE LARYNGITIS.

SYMPTOMS.—The disease sets in with rigors, followed by pyrexia, and usually by some inflammation of the tonsils, a hoarse voice, a husky and convulsive cough, constant hawking of glutinous mucus, with pain and constriction in the larynx, generally increased by pressure. The respiration is difficult and noisy. There is great pain in deglutition, and particles of food and liquid are apt to get into the imperfectly closed glottis, causing convulsive fits of coughing and dyspnœa. The fauces are generally found red and swollen; and, if the tongue be pressed downwards and forwards, the epiglottis may be seen thickened, inflamed, and erect. There is inflammatory fever, with flushed face, hot skin, and full, hard pulse. These symptoms are followed by others of a more formidable character. The countenance becomes pale and anxious; the lips livid; the eyes suffused; the nostrils expanded; the pulse frequent, feeble, and irregular; the voice reduced to a whisper or lost; the throat often œdematous. There is extreme restlessness, and urgent fear of suffocation. The patient is obliged to maintain the sitting posture, and if he fall asleep he soon awakes dreadfully agitated, gasping and struggling for breath. Delirium and coma ensue, and death takes place in from four to five days. But the patient may *die suffocated at a much* earlier period.

MORBID ANATOMY.—Injection and thickening of the lining membrane of the larynx, with œdema of the sub-mucous tissue, and surrounding cellular membrane. The glottis and epiglottis red, swollen, and infiltrated with serum, or pus. In some cases œdema of the glottis is the only post-mortem appearance.

DIAGNOSIS.—From *spasmodic affections of the larynx*, by the presence of fever and local pain, and by the gradual progress of the disease; from *tracheitis*, by the absence of the peculiar stridulous voice, and of the croupy inspiration; and, as a general rule, by the greater age of the patient.

PROGNOSIS.—Unfavourable if the dyspnœa be extreme, the face livid, the circulation languid, and the head affected. Decrease of dyspnœa, a free expectoration, an improved aspect of countenance, and greater ease in swallowing are favourable signs.

CAUSES.—*Predisposing.* Previous attacks of quinsy, undue exertion of the voice, syphilis.—*Exciting.* Exposure to wet and cold; extension of inflammation from the tonsils or salivary glands; swallowing scalding or corrosive liquids; inhaling acrid gases or hot air; extension of inflammation in erysipelas, scarlatina, small-pox, measles, and diphtheria.

TREATMENT.—I. The most prompt and active measures are needed to reduce the inflammation and prevent effusion. Two to six leeches must be immediately applied over the part, followed by tartarized antimony, and calomel. A grain of calomel, with from an eighth to a sixth of a grain of tartarized antimony, and a third or half a grain of opium, may be given every one, two, or three hours, according to the urgency of the symptoms. The object of this treatment is to reduce inflammation by the tartar-emetic, to supersede inflammatory action by the mercury, and to soothe existing irritation by the opium.

II. If effusion have already taken place, blisters should be applied on either side of the larynx, and the mercury be continued till slight salivation is produced. It may be facilitated by the inunction of mercurial ointment.

When the laryngitis supervenes on some other disease, the treatment must be modified according to the disease and existing state of the system.

III. When, in spite of the remedies, the dyspnœa increases rapidly, and there is urgent danger of suffocation, the operation of opening the trachea should be resorted to without loss of time.

Throughout the treatment the patient should be prevented from talking, and protected by a warm (75° Fahr.) and moist air.

2. CHRONIC LARYNGITIS.

SYMPTOMS.—Hoarseness, sometimes increasing till the voice is reduced to a whisper, or quite lost; dry, husky cough; pain or soreness in the larynx, increased by lateral or backward pressure. The cough is brought on by exertion, or cold air, and is accompanied, in the first stage, with scanty mucous expectoration; in more advanced cases, and when ulceration is present, the sputa are purulent, and streaked with blood, or sanious and fœtid. In confirmed cases dyspnœa is always present, coming on generally in paroxysms, and leaving the patient nearly free in the intervals; but in the last stage of the disease, it is increased to orthopnœa, obliging the patient, during the fits, to sit up in bed. In the intervals the breathing has a peculiar hissing sound. The patient generally dies cold, livid and asphyxiated.

Morbid Anatomy.—Inflammation and its consequences in the mucous and submucous textures of the larynx; enlargement of the mucous follicles; œdema; ulceration of the mucous membrane; ossification, or caries of the cartilages.

Causes.—Those of the acute form: the inhalation of air loaded with dust or irritating particles of matter; syphilis; the abuse of mercury; tubercle. Ulceration from the cause last named occurred in about a fourth of the cases of phthisis quoted by Louis.

Diagnosis.—By partial or complete aphonia, the husky cough, hissing breathing, and pain or tenderness in the larynx. Tubercular laryngitis may be distinguished from simple inflammation or œdema by the co-existence of phthisis; and syphilitic laryngitis by the presence of other secondary symptoms.

Prognosis.—*Favourable.* The absence of signs of disease of the chest; the catarrhal or syphilitic varieties of the disease.—*Unfavourable.* Increasing difficulty of deglutition from the spasmodic cough caused by the passage of food into the air-tubes; orthopnœa; lividity.

Treatment.—I. The chronic inflammation may be subdued by the repeated application of a few leeches to the upper part of the throat, and by the use of blisters, mustard-poultices, and iodine ointment. Talking should be interdicted.

II. In the syphilitic form, mercury should be given in small doses, so as to affect the mouth, or iodide of potassium, in five-grain doses.

III. The tone of the relaxed mucous membrane may be restored by the inhalation of steam or spray holding some stimulant in solution, as kreasote, camphor, turpentine, or one of the balsams; or by the still stronger stimulants, nitrate of silver, and sulphate of copper, applied directly to the part, in a liquid or solid form. The preference should be given to a strong solution of nitrate of silver, applied by a small probang to the epiglottis and upper part of the larynx. Solid substances must be used in the form of an impalpable powder, and drawn into the larynx through a tube. Nitrate of bismuth; calomel with twelve times its weight of sugar; red precipitate, sulphate of zinc, or sulphate of copper, mixed with thirty-six times their weight of sugar; alum with twice its weight; and acetate of lead with seven times its weight—are remedies suitable for this purpose.

IV. The paroxysms of dyspnœa, or convulsive cough, may be relieved by opium, æther, camphor, belladonna, or stramonium, inhaled or given in the form of lozenge. When the patient cannot swallow, it may be necessary to feed him by the œsophageal tube and stomach-pump; when the urgent symptoms cannot be otherwise relieved, tracheotomy must be performed.

V. The improvement of the general health may be effected by tonics, especially iron, and the mineral acids, nourishing and wholesome diet, bracing air, the cold or shower bath, with strict attention to the functions of the stomach and bowels, and to the state of the secretions.

APHONIA.—LOSS OF VOICE.

As every condition which impairs the functions of the vocal cords produces a corresponding loss of voice, the causes of aphonia are very numerous; and for their correct diagnosis the use of the *Laryngoscope* is indispensable. This instrument consists of two mirrors, one for the forehead (the frontal), the other for the mouth (the laryngeal). The following are the directions for using it:—In the absence of direct sunlight, which is always to be preferred to artificial light, seat the patient in a dark room, and place an argand gas burner, or moderator lamp, so far behind his right shoulder that the face is in the shade, the light being on a level with the eye of the operator seated in front. Cause the head of the patient to be thrown so far back that the light from the frontal mirror may shine brightly into the back of the mouth against the soft palate. The distance betwen the frontal mirror and the mouth, which gives the brightest illumination, is about a foot. If the patient cannot command the tongue so that it may lie relaxed on the floor of the mouth, the tip, being covered with a handkerchief, should be seized between the thumb and finger, and drawn forwards.

The laryngeal mirror is now warmed (by passing it twice or thrice above the flame of the lamp), and introduced to the isthmus of the fauces just within the pharynx, so as to tuck up the uvula and soft palate above and behind it; at the same time avoiding contact with the tongue and back of the pharynx, otherwise expulsive action is excited. On depressing the handle of the mirror, the back of the tongue, the epiglottis, and finally the vocal cords and parts bounding the aperture of the glottis, are brought into view (Fig. 64). In some persons, and under favourable circumstance, the rings of the trachea, and the apertures of the right and left bronchi, may be seen as the patient takes a deep inspiration (Fig. 65). The vocal cords appear as two ivory-like rounded ridges, and if the patient be directed to ejaculate "ah!" they are seen to approximate closely, and then, during inspiration, to become widely divergent. The movements are vibratile, and very rapid.

When the fauces are very irritable, a few drops of chloroform may be inhaled. In some nervous subjects two or three sittings may be required before a view of the glottis can be obtained.

Causes of Aphonia.—These may be functional or organic. 1. *Functional Aphonia* is caused by paralysis or excessive debility of the muscles of the larynx, as in cerebral-apoplexy, diphtheria, cholera. Hysteria is a common cause of aphonia, but in this disease the voice is not lost but suppressed, and the patient may talk in her sleep, or be induced to do so under the influence of electricity. Severe fright occasionally causes temporary loss of speech. In all cases of functional aphonia the vocal cords lie almost parallel, separated by a variable interval, and immovable.

Fig. 64.



Fig. 65.



z, base of the tongue. *e*, epiglottis. *e w*, cushion of the epiglottis. *s*, cartilages of Santorini overlying the arytenoid cartilages. *w*, cartilage of Wrisberg lying in the fold of membrane which extends from the summit of the arytenoid, on either side, to the epiglottis. *g a*, tubercle which sometimes exist between the cartilage of Santorini and Wrisberg. *u st*, inferior, or true vocal cords. *o st*, superior, or false vocal cords. *v M*, the depressions between them, leading to the ventricles of the larynx. *a e*, aryteno-epiglottic ligament, lying in the aryteno-epiglottic folds of mucous membrane. *t l*, rings of trachea. *bd*, *bs*, right and left bronchus. (Czermak.)

2. *Organic Aphonia.*—The causes of organic aphonia are the following:—Laryngitis; œdema; chronic thickening; ulceration; tubercular deposits; cancerous, warty, or cystic tumours of the vocal cords or arytenoid cartilages; abscesses or other tumours of the *contiguous parts* projecting between the vocal cords, or pressing

Fig. 66.



Œdema of the glottis, the superior vocal cords *a a*, and the aryteno-epiglottidean folds much swollen, the former almost meeting over the true vocal cords.

Fig. 67.

Partial loss of the epiglottis (syphilitic) and swelling of false vocal cords. Symptoms, hoarseness, passing into aphonia. (Czermak.)

on them. The margin of the glottis is a very common seat of warty excrescences.

Treatment.—Functional aphonia generally, and especially that caused by paralysis, is benefited by electricity. In debility the treatment recommended under diphtheria will be required. Strychnia in $\frac{1}{16}$ grain doses twice or thrice a day has proved serviceable in some cases. Astringent and stimulating gargles may be used simultaneously. Hysterical aphonia requires the treatment of hysteria. The treatment of organic aphonia will vary with its cause. If there be tubercular infiltration, we may apply a leech over the thyroid cartilage occasionally, or direct croton liniment to be rubbed in; the general treatment being that of phthisis. If there be follicular enlargement or ulceration, solution of nitrate of silver (gr. v in ʒj) may be applied within the lips of the glottis by means of a camel-hair brush fitted in a handle suitably curved. Granular enlargements and chronic ulcerations may be removed by the repeated application of solid nitrate of silver. Malignant disease may be kept

Fig. 68.



a a, the true vocal cords, below which are two sub-glottic swellings, meeting in the centre. *b*, epiglottis. *c c*, arytenoid cartilages. *d*, back of tongue. (Gibb.)

Fig. 69.



Polypus attached to the right vocal cord, the real cause of a supposed nervous aphonia. (Czermak.)

Fig. 70.



Large epithelial tumour arising from the inferior vocal cord, and occupying the aperture of the glottis. Symptoms, hoarseness, followed by aphonia. (Czermak.)

Fig. 71.



Syphilitic excrescences on true vocal cords. (Condylomata of the larynx.) Symptoms, severe hoarseness. (Czermak.)

in check by the same means. Small pedunculated tumours may be removed by Dr. Gibbs's laryngeal écraseur. Abscesses and œdema may be relieved by a suitably curved bistoury.

Acute œdema requires very prompt treatment. When practicable, the œdematous part may be freely pricked here and there with a curved and fine-pointed armed bistoury, so as to induce free bleeding. If this operation cannot safely be performed, a strong solution of nitrate of silver may be applied to the larynx and a few leeches to the throat; and ♏xxx tincture of perchloride of iron may be given. If no relief be afforded, and suffocation impend, tracheotomy must be performed.

TRACHEITIS, OR CYNANCHE TRACHEALIS.—THE CROUP.

Symptoms.—The disease generally begins with hoarseness wheezing, and a short dry cough. Sometimes there is a rattling in the throat during sleep, and the child is often observed to raise the hand to the throat. After a time the breathing becomes difficult, the voice husky or absent, and the breath is drawn in with a sound as if passing through a constricted orifice or narrow tube, and in speaking or coughing, it acquires a peculiar or shrill sound, similar to the crowing of a cock. The cough is dry; but at length a viscid matter is brought up, and flakes or tubes of false membrane, with efforts often so distressing as to threaten strangulation. The disease is accompanied by inflammatory fever, with hot skin and flushed face, and generally terminates fatally about the second or third day; the lips become blue, the pulse thready, and after much distress the patient becomes drowsy and comatose, and ultimately dies suffocated.

Anatomical Characters.—Inflammation of the lining membran, of the trachea, often extending to the larynx and bronchi, and the formation of a false membrane, which, in extreme cases, fills the trachea and bronchi. Large portions of this false membrane, casts of the tube, have been expelled during fits of coughing and vomiting.

Causes.—*Remote and Predisposing.* Age from three to fourteen; low and damp situations, inland, or on the sea-shore. *Exciting.* The common causes of inflammation. The disease is somewhat epidemic, and some suppose it to be contagious.

Diagnosis.—By the peculiar breathing, speaking, and coughing above described. From *laryngismus stridulus.*—See that disease.

Prognosis.—*Favourable.* Early and free expectoration, the breathing not much impeded, the voice little changed, the febrile symptoms moderate.—*Unfavourable.* Great anxiety and difficulty of breathing, with shrill whistling inspiration; livid face, and cold extremities.

Treatment.—*Indications.* I. To subdue inflammation. II. To *obviate urgent symptoms.*

I. The first indication is fulfilled by the free application of leeches to the larynx and trachea; followed by a warm bath and tartar-emetic in nauseating doses. The treatment may be commenced by an emetic of from half a grain to a grain of tartar-emetic, according to the age. The bowels should also be freely opened.

Calomel should be combined with the tartar-emetic, and mercurial ointment be rubbed into the thighs or armpits, so as rapidly to affect the system, and prevent the further effusion of lymph. Mercury may be used with the more freedom in children, as they are not easily affected by it.

II. If the symptoms be urgent, the false membranes may sometimes be brought up by the operation of an emetic, and removed by the hand. If suffocation threaten, tracheotomy must be performed. As the inflammation quickly extends to the lower part of the trachea, or even into the bronchial tubes, the operation should not be delayed.

LARYNGISMUS STRIDULUS.—FALSE OR SPASMODIC CROUP.

Synonyms.—Crowing inspiration; child-crowing; spasmodic asthma of children; thymic asthma.

Symptoms.—The principal feature of the disease is a remarkable crowing inspiration, unattended by cough, coming on suddenly, and often on first waking from sleep. For a short time the child makes ineffectual efforts to inspire air, and struggles violently, but at length the difficulty is overcome, and the breath is drawn in with a loud, crowing sound. If the impediment be less complete, the respiration is hurried and laborious, each inspiration being attended by the peculiar crowing sound; the face becomes livid, the eyes staring and suffused, convulsions supervene, the thumbs are clenched in the hands, the fingers and toes are flexed, and the joints of the wrist and ankle forcibly bent. In extreme cases, death takes place by asphyxia, or the little patient falls, pale and exhausted, into the nurse's lap.

Pathology.—Irritation reflected through the inferior or recurrent laryngeal nerve on the muscles of the larynx, in consequence of irritation of the gums, stomach, or bowels. A diseased condition of the bronchial and cervical glands, producing irritation of the pneumogastric nerve, or its recurrent laryngeal branches.

Causes.—*Predisposing.* Infancy; from birth to the age of three years: the scrofulous diathesis.—*Exciting.* Teething; intestinal irritation; worms; enlargement of the glands of the neck and chest.

Diagnosis.—From *croup*, by the sudden accession and departure of the fits; by the free breathing in the intervals; by the absence of febrile or catarrhal symptoms; and (except in rare cases during the fit) of cough.

Prognosis.—The disease generally terminates favourably. Fatal cases are rare.

Treatment.—*During the fit.* The patient should be placed in a warm bath, the face being exposed to a current of fresh air, and cold water should be dashed over the chest and face. If suffocation be imminent, tracheotomy must be performed.—*During the intervals.* The treatment must depend on the existing causes of irritation. If the disease continues when these are removed, change of air, a suitable diet, and attention to the state of the bowels will generally effect a cure.

Spasmodic diseases of the larynx, with croupy respiration, and convulsive cough or loss of voice, are of frequent occurrence in females, and belong to the long list of anomalous hysteric affections. They must be treated in the same way as other hysterical symptoms.

DISEASES OF THE BRONCHIAL TUBES AND AIR-CELLS.

Catarrhus	Catarrh.
Catarrhus Epidemicus	Influenza.
Bronchitis	Bronchitis.
Asthma	Asthma.
Emphysema	Emphysema.
Pertussis	Whooping-cough.

CATARRHUS.—CATARRH.

Acute catarrh, commonly called "a cold," is a febrile affection, complicated with inflammation of one or other of the mucous membranes. If confined to the mucous membrane of the eyes and nostrils, it is called *coryza*, or a *cold in the head;* if it extend to the bronchial tubes, it is termed *bronchitis;* if it attack the mucous membrane of the bladder, it becomes a *catarrhus vesicæ.* Sometimes the inflammation affects the mucous membrane of the alimentary canal, and is attended with sickness and diarrhœa, or both, assuming the form of gastritis, enteritis, or gastro-enteritis mucosa. Its essential characters, therefore, are increased secretion of mucus from the nose, fauces, bronchi, intestinal canal or bladder, with pyrexia.

Symptoms.—Slight rigors followed by pyrexia; weight and pain in the head; oppression of the chest, and impeded respiration; sense of fulness and obstruction in the nose; repeated sneezing; watery inflamed eyes; cold shiverings, succeeded by transient flushes of heat; soreness of the fauces and tonsils; herpetic eruptions on the lips; cough; pains about the chest; rheumatic pains in the back, neck, and head. After an interval increased mucous secretion from the affected parts. The chronic form is known as common bronchitis.

Diagnosis.—The absence of bronchial, pneumonic, and pleuritic symptoms.

CAUSES.—Cold, or wet and cold, applied to the body.

TREATMENT.—In most cases the best remedy for a cold is ten grains of Dover's powder given at night, followed by a hot bath, or hot water to the feet, a basin of warm gruel, and a warm bed. By these means a profuse perspiration is excited, which effectually removes the febrile action. The Dover's powder may be followed next morning by a saline aperient. A drachm of spiritus chloroformi may be substituted for Dover's powder. A large draught of cold water, taken at bed-time, will often effectually remove a common cold. If the fever run high, the best remedy is tartarized antimony in nauseating doses and at short intervals, with cooling drinks and saline purgatives.

If there be much smarting and running at the eyes, relief may be obtained by holding the head over the steam of hot water, or bathing the eyes repeatedly with warm water.

CATARRHUS EPIDEMICUS.—INFLUENZA.

SYMPTOMS.—Those of a common cold in an exaggerated form, with sudden and extreme prostration, loss of energy, and depression of spirits. The febrile symptoms, which generally assume a remittent type, do not run high, nor is the pulse much increased in frequency. Sometimes the catarrhal symptoms are very slight, the disease being characterized by extreme debility without local symptoms.

TERMINATIONS AND COMPLICATIONS.—Pneumonia, tonsillitis, bronchitis, and pleurisy, are often intercurrent. Muscular and articular rheumatism; diarrhœa and dysentery; erysipelas; continued fever, are occasional sequences.

CAUSES.—*Predisposing.* The male sex; adult and especially old age; a former attack; low, damp situations. *Exciting.* A peculiar condition of the atmosphere.

Laws of the Epidemic.—The influenza was epidemic in the years 1510 and 1557; in 1729, 1733, 1743, 1762, 1775, and 1782; in 1830, 1837, 1841, 1844, 1847, and 1851. It seems to have originated in the East, and after an uncertain period to have shown itself in the north of Europe, whence it spread westward till it reached England; and from England passed in a south-easterly direction to France, Spain, and Italy, and across the Atlantic to America. Its course is very similar to that of the Asiatic cholera, of which it has more than once proved the precursor. Australia has been visited in recent epidemics. The disease, in every epidemic, has attacked a very large proportion (estimated at three-fourths, four-fifths, and nine-tenths) of the population, as well as many of the domestic animals. The mortality occasioned by it is considerable. In a million inhabitants of the metropolis the registered deaths from influenza were 65 in 1844, 117 in 1841, 150 in 1851, 295 in 1848, and 572 in 1847. In a recent year the total deaths in the metropolis from this cause were 1253. Its latent period is believed to be from a few hours to two or three weeks. It commonly remains in the same district or country from a month to six weeks.

Diagnosis.—From *common catarrh*, by its greater prevalence, the suddenness of its attack, the extreme debility which attends and follows it, and by its occurring indifferently at all seasons of the year, and in all states of the atmosphere. From *ephemeral fever*, by the extreme prostration, and, in many cases, by the herpetic eruption on the lips.

In the epidemic of 1844–5, several cases of influenza assumed a well-marked remittent character, with exacerbations on alternate days, and the herpetic eruptions on the lips. (G.)

Prognosis.—Rarely fatal to the young and robust, unless complicated with pneumonia; dangerous to the aged, to the feeble, and the intemperate, and to persons subject to asthma and consumption.

Treatment.—In mild cases, that of catarrh; in severe ones, and in aged persons, stimulants, combined with opiates, a nourishing diet, and liberal use of wine, and appropriate local treatment. In the treatment of local complications, the adynamic character which they assume in influenza must be borne in mind. As soon as the severe symptoms have passed away change of air is one of the best remedies.

BRONCHITIS.

Varieties. 1. Acute. 2. Chronic. 3. Plastic (Bronchial Polypi).

1. Acute Bronchitis.

Symptoms.—Bronchitis often supervenes upon severe catarrh, the inflammatory affection of the mucous membranes spreading from the upper part of the respiratory tract into the lungs. The *general symptoms* are severe in proportion as the inflammation extends towards the air lobules. The skin is hot and dry, the pulse full and rapid; there is more or less urgent dyspnœa with wheezing inspiration, and a sense of great oppression referred to the epigastrium. The patient is exhausted by a dry wheezy cough, which often comes on in severe paroxysms; the head is hot and painful, the tongue coated, the urine scanty and high coloured, and deposits lithates.

After a few days the cough becomes moister, and a clear viscid frothy mucus is expectorated. This gradually loses its adhesiveness, and becomes thick and purulent; free expectoration now sets in, affording much relief, the fever and dyspnœa subside, and the cough alone remains. At first it is so frequent that little continuous sleep can be obtained; in a few days the expectoration begins to diminish, the cough subsides, and the patient convalesces. The mucous membrane, however, recovers but slowly, and it often remains in a congested state, and liable, on the least change of temperature, to renewed attacks of inflammation, which tend to become chronic.

When the inflammation spreads into the vesicular structure, and becomes diffused through both lungs, the symptoms are very urgent, the dyspnœa extreme, the face dusky and anxious.

The *local signs* of the disease are highly characteristic. The sitting posture is chosen to allow of the free expansion of the chest, the arms and head are firmly fixed to give effect to the action of the extraordinary muscles of inspiration; the chest is everywhere resonant; on applying the ear, the air is heard, during inspiration, to traverse the bronchial tubes with a sighing, wheezing, or whistling sound; and, during expiration, to pass back again with a prolonged sonorous rhonchus. These sounds are loudest about the roots of the lungs—*i.e.*, about the middle parts of the chest in front and behind. At the bases, apices, and sides the vesicular murmur may still be heard, but feebler than usual, and here and there obscured by the coarser morbid sounds, or its place is supplied by crepitation. The rhonchus and sibulus are often so loud and general that the vesicular murmur is nowhere heard.

While the inflammation prevails, the elasticity of the lungs is more or less impaired, and in some severe cases the air in imprisoned in the distended lobules by the inflamed and constricted smaller tubes. In this condition the dyspnœa is extreme; we hear dry, wheezing, and whistling sounds, but no vesicular murmur.

As soon as secretion begins, moist sounds are heard. If the inflammation have involved the finer air tubes and the vesicular structure, a fine mucous crepitation is heard over the whole of the back and sides of the chest; and in the larger tubes coarser crepitation or mucous râles, with more or less musical wheezing. During an attack of acute bronchitis, the ingress of air to an entire lobe of one of the lungs may be suddenly stopped. During a violent fit of coughing, the tenacious mucus brought together from the smaller tubes is drawn back into a large bronchus by the forcible inspiration which accompanies the convulsive cough, and becomes firmly impacted. The symptoms are sudden and extreme dyspnœa, or actual suffocation. No air is heard to enter that part of the lung to which the obstructed bronchial tube leads, but, since it is distended with imprisoned air, the corresponding part of the chest retains its natural resonance.

Acute bronchitis often occurs in children; its most severe and urgent form has received the name of suffocative catarrh, and is characterized by a sudden and copious secretion of mucus, extreme and urgent dyspnœa, and fine mucous crepitation in every part of the lungs.

2. Chronic Bronchitis.

Symptoms.—This disease is the sequel of the acute form. In middle-aged or old persons it returns every winter with increased severity, and reappears for several years in succession, in which case it is called winter cough. When the mucous membrane secretes freely, and the breathing is very difficult, the disease is called humoral asthma. The symptoms of this disease are habitual cough, shortness of breath, and copious mucous expectoration. After repeated attacks of the disease, the pulmonary tissue becomes weakened, and emphysema results, marked by increased dyspnœa, and a peculiar dusky hue of countenance. The sufferings of the patient are often increased by flatulence.

In advanced age there are drowsiness, extreme and increasing debility, and coldness of the surface, and the patient is at length suffocated by the accumulated mucus, which he has no longer strength to expectorate.

Dilatation of the bronchial tubes frequently accompanies chronic bronchitis. The symptoms are bronchorrhœa, dyspnœa, unusual resonance of the chest, with tracheal or even amphoric breathing. Gurgling and pectoriloquy may also be heard if the dilatation be considerable. The excessive expectoration leads to wasting of the body.

Morbid Anatomy.—Swelling and redness of the tracheal and bronchial mucous membrane, especially at the termination of the trachea, and in the first divisions of the bronchi. The air passages contain a large quantity of tenacious mucus, or muco-purulent fluid. Portions of the lungs are occasionally *collapsed.* Collapse may be diffuse or scattered. Diffuse collapse may affect the whole lobe of a lung. When it is complete, the part has the colour and consistence of fœtal lung, pale, and containing a little blood. The scattered form of collapse affects only single lobules or small aggregations of lobules, and usually those situated in the anterior edges of the lungs. The collapsed lobules form little depressions like cicatrices, usually of a dark colour. Collapsed lung may be readily inflated, and is thus distinguished from consolidated lung. The mechanism of collapse is very simple. A plug of mucus is drawn by a forcible inspiration into a bronchial tube; the contraction of that portion of the lung to which the obstructed tube leads may dislodge the plug sufficiently to allow the passage of air in expiration; but on inspiration it is again drawn back. The plug thus acts as a valve, allowing of the egress, but preventing the ingress, of the air, until at last the obstructed lung is completely deprived of air. The chest being an air-tight cavity, collapse of one part of the lung must be complemented by dilatation (emphysema) of another, and thus one morbid condition generates another. *Emphysema* alone is the commonest result of long-standing bronchitis. *Dilatation of the bronchi* is another morbid condition often found in chronic bronchitis; the tubes may be uniformly enlarged for a distance, or they may present spindle-shaped, globular, or saccular dilatations here and there, and the dilated part of the tube may be very thin; but usually its walls are greatly hypertrophied. The dilatation is due to atrophy, or abscess of the lung-tissue in the neighbourhood of the larger bronchi, the dilatation being complementary.

3. Plastic Bronchitis (Bronchial Polypi).

Symptoms.—Plastic bronchitis is known by the expectoration *of branched fibrinous* casts moulded in bronchial tubes of the third or fourth diameter. Sometimes the casts are hollow and shreddy, but more usually they are solid and compact. The disease is always associated with hæmoptysis. It recurs after variable intervals. The physical signs are dulness almost as complete as in pneumonia, and absence of breath as well as voice-sounds, in the affected portion of the lung, by which the disease is distinguished from pneumonia.

Pathology.—Croupy, fibrinous exsudations from the mucous membrane, the detachment of which occasionally leads to hæmorrhage and the formation of coagula, which may take the form of the tubes.

Prognosis.—The disease is rarely fatal, but it is very obstinate.

Diagnosis.—Bronchitis occupying the whole of both lungs, occurring in a young adult of either sex, and not speedily yielding to treatment, justifies a suspicion of miliary tubercles. Chronic bronchitis with bronchorrhœa and dilatation of the bronchi may, at first sight, be mistaken for phthisis. The bronchorrhœa accompanying dilated bronchi may cause emaciation, and give rise to trachael breathing and pectoriloquy. But the history of the case, the nature of the expectoration, and the other physical signs, will furnish decisive evidence of the nature of the disease.

Sequelæ.—Emphysema, hypertrophy of the heart, and dropsy.

Prognosis.—Generally favourable in the acute and chronic forms; guarded in bronchitis senilis.

Causes.—Exposure to cold, the rheumatic and gouty diatheses, heart and kidney diseases. In children, measles and whooping-cough.

Treatment.—Of *acute bronchitis.* In very acute attacks, occurring in persons previously in strong health, tartar-emetic in nauseating doses may be necessary; blisters, mustard poultices, or turpentine stupes, may be applied to the chest. In very severe cases leeching. The general treatment of bronchitis consists in the exhibition of expectorants, such as a combination of squill and senega. Free sweating and diuresis should be induced by appropriate medicines. When the expectoration is freely established, we may give squill or ipecacuanha in combination with the mineral acids. If the circulation be feeble, we may give a moderate amount of whisky or brandy. If hypnotics be required, we must use henbane or chloral hydrate in combination with opium. Opium must be given cautiously, especially in the early stages of the acute disease.

In the *chronic form of bronchitis* the treatment must be nearly the same as in the milder form of the acute disease. Compound squill pill is an excellent remedy, and it may be combined with comp. ipecac. powder, or the extract of conium. When there is a considerable collection of mucus in the air tubes, with urgent dyspnœa, an emetic may be given early in the morning, or twice in the week, with the greatest advantage. The body should be kept warm, and the chest may be protected by a full-sized emplastrum picis. The balsams, gum resins, and oleo-resins, such as myrrh, benzoin, tolu, ammoniacum, galbanum, copaiba, and turpentine, often do much good.

The *plastic form of bronchitis* is not very amenable to treatment. In otherwise healthy persons it gradually subsides. ♏xx tincturæ ferri perchloridi, and the inhalation of the vapour of turpentine, are the remedies most likely to do good. As a prophylactic, the patient should never remain in a heated atmosphere. In the bronchitis of children, emetics are very serviceable by promoting expectoration.

In *old age*, when the debility is extreme, the appropriate remedy is a combination of stimulants and narcotics. A nourishing diet and a liberal allowance of wine are also required. When dropsical effusions supervene, diuretics and expectorants must be given in combination with stimulants. The body and extremities should be kept warm, and exposure to cold avoided. The rooms should be kept as nearly as possible of a uniform warm temperature night and day. On leaving the room during the winter, the mouth and nose should be lightly covered with a silk handkerchief or the fold of a woollen or fur garment. In many cases, exposure to cold air gives temporary relief, but the symptoms return with renewed severity when the circulation is restored by the warmth of the room.

ASTHMA.

Definition.—Paroxysms of dyspnœa, with intervals of freedom.

Varieties.—1. Humoral. 2. Congestive. 3. Spasmodic. 4. Hay. 5. Hysteric.

1. **Humoral Asthma.**—Bronchorrhœa, or bronchial flux.—*Symptoms.* The attack is usually preceded by a sense of fulness at the pit of the stomach, lassitude, depression of spirits, drowsiness, and pain in the head; followed, on the approach of evening, by a sense of tightness across the breast, and dyspnœa, which continues to increase for some length of time. Both inspiration and expiration are performed slowly, and with a loud wheezing noise, and there is a dry cough. The face is either turgid and livid, or pale and contracted. At length the difficulty of breathing becomes so great that the patient, threatened with suffocation, leaves his bed, paces up and down the room, stands in a stooping posture, or sits with the body bent forward, the arms resting on the knees, the shoulders raised, the abdomen contracted, and all the muscles of respiration thrown into violent action; and, still finding no relief, seeks at the open window a supply of cold air. These symptoms usually continue till the approach of morning, when a copious expectoration of a thin frothy mucus comes on, the breathing becomes less laborious and more full, the patient speaks and coughs with greater ease, and, feeling every way relieved, falls asleep. The *dyspnœa* and tightness of the chest, with evening

exacerbations, remain for some days. The attack often comes on about midnight.

Physical Signs.—Percussion-sound generally good. Sonorous and sibilant rhonchi at the commencement of the attack, followed by mucous râle and crepitation. Some wheezing and sibilus usually remain after the attack.

Morbid Anatomy.—More or less bronchitis, often extensive pulmonary adhesions; dilatation of the right heart. Emphysema is common in this, as in the other forms of asthma.

Causes.—*Predisposing.* Hereditary peculiarity; lax habit of body; long-continued dyspepsia; gout.—*Exciting.* Sudden change of temperature; disorders of the alimentary canal, especially flatulence; impalpable particles of hay, ipecacuanha, or other substances.

Diagnosis.—From other diseases affecting the respiration, by the distinct paroxysms with intervals of perfect freedom. From congestive and spasmodic asthma by the copious secretion which ends the fit.

Prognosis.—Asthmatic patients often attain to an advanced age, and the prognosis is favourable when there is no tendency to phthisis or organic disease of the heart.

Treatment.—I. *Immediate.* An emetic at the onset of the attack, if the patient is strong enough to bear it. In vigorous persons full doses of tartar-emetic, of ipecacuanha, or of the lobelia inflata (♏xv to ʒj of the æthereal tincture) may be given with great advantage. In the weak, stimulants are required, such as strong coffee, ammonia, or æther. These may be combined with opium in moderate doses. Heat applied to the extremities, or to the entire surface, by means of the warm or vapour bath, is extremely serviceable at the onset of the attack. When the fit has already lasted some time, and the expectoration is abundant, it may be encouraged by inhalations of conium.

II.—*Subsequent.* The exciting causes must be carefully avoided, the general health improved, and the digestive organs carefully regulated. The bowels to be kept free, but hypercatharsis avoided; liquids should be taken in moderation; the diet should be plain, the meals light; and acescent fruits, and such vegetables as occasion flatulence, be avoided. The internal remedies will vary with the state of the system. Astringent tonics are serviceable in most cases. I have found alum, combined with ginger, very serviceable in removing the distressing flatulence which often precedes and accompanies the fit. Ten grains of the one, with five grains of the other, and three or four grains of rhubarb, may be given three or four times a day. I have also more than once met with spinal tenderness in the cervical and dorsal regions, and have used tartar-emetic ointment with much benefit. (G.)

2. Congestive Asthma.—Dry Catarrh. This, like the foregoing, comes on in paroxysms of severe dyspnœa, but differs from

in the scanty expectoration that attends the cough and terminates
ı fit. The sputa are scanty, highly adhesive, filled with air
bbles, and speckled with round black or grey spots, and, at the
ght of the fit, often tinged with blood. After a time they be-
ne more abundant and less tenacious, and the fit passes off with
reased expectoration.—*Physical Signs.* Those belonging to a
ollen state of the mucous membrane of the air tubes—viz., clear
ınd on percussion, indistinct respiratory murmur, with sibilant
nchi, or a peculiar click, and, in limited portions of the chest,
ı mucous crepitation.—*Morbid Anatomy.* A deep red or violet
our of the mucous membrane of the air tubes, with scanty
cous secretion.—*Causes.* Those of the humoral asthma. Valvular
eases of the heart.—*Prognosis.* Generally favourable, except
en of long standing, or complicated with other functional or
;anic diseases.—*Treatment.* Nauseating expectorants, as tartar-
etic, squills, ipecacuanha, lobelia inflata, are indicated in this
m of the disease, together with inhalations of steam, tar-vapour,
monia, and conium. Dry cupping and counter-irritation to the
›st may be beneficial. Smoking stramonium is sometimes found
rantageous, as in spasmodic asthma. Strict attention must be
d to the general health and the digestive organs; and the bowels
ıst be kept free by aloetic purgatives.

:. SPASMODIC ASTHMA.—This term is applied to dyspnœa occurring
fits, unaccompanied by signs of congestion or inflammation of the
nchial tubes, and presumed to depend on spasm of the muscular
res of the air tubes.—*Symptoms.* Those of humoral asthma;
; that the fit comes on more suddenly, and terminates without
ectoration.—*Physical Signs.* Sound on percussion less clear
ın usual, respiratory murmur very faint, and occasionally accom-
ıied with slight wheezing or whistling. If the patient be desired
hold his breath for a few seconds, or to count till the air in the
ıst is exhausted, and then to inspire slowly and steadily, the air
l be heard to enter as usual. The respiratory murmur soon
omes feeble again. *Causes.—Predisposing.* The same as in
ıer spasmodic diseases; hereditary peculiarity; hysteria.—
citing. Attacks of dyspepsia; extreme flatulence; irritation of
ı upper part of the spinal cord; pressure of tumours on the pul-
nary plexus or on the vagus.—*Prognosis.* Favourable in the
ence of complications; dangerous when combined with other
eases of the lungs, or with those of the heart. It often causes
monary congestion and hæmorrhage, and induces emphysema,
l dilatation and hypertrophy of the heart. *Treatment.*—I.
ıen the fit has actually commenced, some relief may be afforded
counter-irritants to the chest, epigastrium, and extremities; by
:i-spasmodics, as opium, æther, chloroform, belladonna, assafœtida,
l valerian. Opium and æther in combination (tr. opii. ♏xv to
ı, and æther ʒss to ʒi) is a useful remedy in the fit. When the
ient is aware of the approach of a fit, he may sometimes ward
ff by an emetic, by smoking stramonium or tobacco, or by the

cold douche. The ascertained causes of the fit must be carefully avoided.

II. The diet should be light, wholesome, and easy of digestion; and all substances which encourage flatulence should be avoided. The state of the bowels must be carefully attended to. For the improvement of the general health, the shower-bath, or cold sponging, followed by frictions of the chest every morning; and tonics. Where much flatulence is present, alum in combination with ginger may be given with advantage. If there be tenderness in any part of the spine leeches may be applied, or the tartar emetic ointment, or both.

When the spasm of the bronchial tubes is combined with congestion of the mucous membrane, or with increased secretion, depletion or counter-irritation must be employed with anti-spasmodic remedies.

4. Hay Asthma.—Hay Fever.—*Symptoms.*—Those of catarrh or humoral asthma. *Causes.*—*Predisposing.*—Peculiarity of constitution. *Exciting.* The odour of hay, or that of a stable. In some cases fine powder floating in the air, especially that of ipecacuhana. *Treatment.*—That of humoral asthma during the paroxysm. In the interval, the careful avoidance of the exciting cause. Chloroform inhaled with due precaution is an excellent remedy in many cases.

5. Hysteric Asthma.—*Symptoms.*—This disease has its seat in the external muscles, and is closely allied to chorea and hysteria. It is characterized by extraordinary frequency of the respiration, with perfectly healthy sound of the chest and breathing; and a rapid pulse. Sometimes also it is a marked symptom of paralysis agitans, the muscles of respiration partaking of the agitation.

A remarkable case of spasmodic asthma in a female aged twenty-two, came under my notice several years ago. The fits, which were of variable duration, were characterized by extreme frequency of breathing, with comparatively little general disturbance of health. There was amenorrhœa, some tenderness of the upper part of the spine, and constipation. The disease was cured by purgatives carefully and perseveringly administered. No other remedy was applied. Hypercatharsis was invariably followed by a paroxysm. In a case of the same kind in which there were 140 respirations to 144 pulses, much benefit was derived from cold affusion. (G.)

EMPHYSEMA.

Symptoms.—Permanent shortness of breath, increased to extreme dyspnœa by occasional exciting causes, such as exercise, flatulence, or a common cold; and in extreme cases by assuming the horizontal posture; with a dusky hue of countenance and cold extremities. Fits of orthopnœa, with violent palpitation and blueness of the face and lips, come on suddenly in the night, obliging the patient to sit up, and to open the doors and windows of the room for air. The dyspnœa is attended by cough, with scanty expectoration, which varies in character, consisting in most cases of a thin mucus, mixed with small tenacious clots, and filled with air-bubbles. The expectoration is often increased by a supervening attack of bronchitis; and it becomes abundant towards the end of the fit. In cases of long standing the general aspect of the body undergoes a change; the face becomes pale, and of a dusky hue, the body grows thin; and the legs and abdomen swell.

PHYSICAL SIGNS.—Abdominal respiration; a prominent, barrel-shaped tympanitic chest, in which the respiratory movements are greatly diminished, and the area of resonance everywhere increased, even to effacing the præcordial and hepatic dulness. Displacement of the heart downwards and to the right so that the apex beat approaches the ensiform cartilage; great hypertrophy of the right heart; indistinct respiratory murmur, and prolonged inspiratory and expiratory sounds; and, in some cases, a dry crepitation. In marked cases, the chest bulges in all directions; but when the emphysema is confined to one lung, or to a part of one lung, it is irregularly enlarged. It is usually associated with bronchitis.

MORBID ANATOMY.—Dilatation of the lungs; the anterior margins almost meet and conceal the pericardium; the heart and diaphragm are depressed; usually there are extensive old adhesions between the pleuræ, and the cartilaginous ribs are ossified. The lungs are pale, dry, and bloodless, and have a soft, woolly feel; their cells are enlarged; and the distended lobules are often ruptured and communicate with each other, forming little bladders which collapse on the slightest touch of the scalpel. These are usually found on the thin anterior margins of the lungs. Displacement and hypertrophy with dilatation of the right side of the heart. General venous congestion.

SEQUELÆ.—The permanently distended condition of the air-cells, opposing as it does the entrance of a proper quantity of blood into the lungs, ultimately produces hypertrophy of the right side of the heart; fatty degeneration of the liver and kidneys; anasarca and ascites.

DIAGNOSIS.—From asthma, by the permanent shortness of breath. But as emphysema is common in chronic bronchitis, and supervenes after repeated attacks of all the forms of asthma, only spasmodic asthma can be thus distinguished.

CAUSES.—Repeated attacks of bronchitis, impairing the contractility and elasticity of the air-cells. Pleuritic adhesions, preventing the contraction of the lungs. Old age, causing degeneracy of the lung-tissue.

PROGNOSIS.—The disease is rarely fatal in itself, but ultimately leads to dropsy.

TREATMENT.—I. *During the paroxysms.*—The fits may be greatly relieved by dry cupping and diffusible stimulants. Half a drachm to a drachm each of æther and compound spirit of ammonia may be administered at the onset. The shoulders should be well raised, *the doors and windows* thrown open, and the body, especially *the lower extremities,* kept warm. In extreme cases, cupping between the shoulders, or the cautious abstraction of blood from the arm by a small orifice, may be necessary. When the patient has reason to expect an attack, an emetic, by emptying the stomach, and removing flatulence, may prevent it; and similar relief is sometimes afforded by the free action of a calomel and colocynth pill, followed by a black draught.

II. *During the intervals.*—This disease does not admit of cure. The treatment consists in attending to the complications which may exist with it, and in a few simple precautions, such as the avoidance of colds by warm clothing and dry feet, the daily use of cold sponging or the shower-bath, regular and moderate meals, aloetic aperients, and the astringent chalybeates.

Emphysematous patients suffer most in close, moist weather, when the function of the skin is impeded; and least when the weather is open and the air dry and bracing.

PERTUSSIS.—WHOOPING-COUGH.

Synonyms.—Tussis convulsiva, chin-cough, kinkhost.

Definition.—An infectious malady, characterized by a peculiar cough occurring in fits terminated by vomiting.

Symptoms.—The disease generally begins as a common cold, and it is not till after two or three weeks, or, in rare cases, as many months, when the febrile symptoms have somewhat abated, that the characteristic symptoms show themselves. The cough now comes on in distinct fits, consisting in a series of violent and convulsive expirations with congestion of the face, and threatening of instant suffocation, and sometimes with involuntary discharge of the urine and fæces, followed by a sudden, long-drawn inspiration, accompanied by a peculiar whoop which gives the disease its name. The convulsive coughing is renewed, and continues as before, till a quantity of mucus, thrown up from the lungs, issues from the mouth and nostrils, perhaps mixed with blood; or till the contents of the stomach are discharged by vomiting. After the fit the patient has an interval of perfect freedom from cough, and often expresses a desire for food; but when the attack has been severe, it is succeeded by much fatigue, hurried respiration, and general languor and debility. Children evince great fear of the fits, and will run to their nurses or mothers for relief. Adults are seized very suddenly, and the paroxysms are usually very severe. The disease generally attains its greatest severity at the end of the fourth or fifth week, after which the paroxysms become less severe, and at length, after a further variable period of from two weeks to four months, entirely cease. In some instances, however, the disease is protracted for several months, and even for more than a year.

Sequelæ and Complications.—Bronchitis, with collapse of the lung; Pneumonia; Pleuritis; Gastritis; Phrenitis; Convulsions; Apoplexy; Epilepsy.

Morbid Anatomy.—Inflammation of the bronchial tubes, with large accumulation of mucus in the air-passages. Collapsed spots, diffused or scattered, with complementary emphysema. Pneumonia. Inflamed bronchial glands. Inflammation of the mucous membrane of the stomach and intestines, with enlargement of Peyer's and Brunner's glands. In other words, an inflamed condition of the parts supplied by the eighth pair of nerves, which latter have been observed to be red.

Causes.—*Predisposing*. Childhood. Adults, however, are not exempt; and the disease may attack persons of seventy and eighty years of age. The seasons of spring and autumn.—*Exciting*. A specific poison acting on the eighth pair of nerves.

Diagnosis.—In the early stage, by the abundant sputa, the occasional vomiting, the violence of the paroxysms, and the perfect freedom in the intervals. When fully established, the convulsive cough, peculiar whoop, and characteristic termination above described.

Prognosis.—*Favourable*. In proportion as the fits and bronchial inflammation are mild.—*Unfavourable*. A severe form of the disease in children under two years of age, and especially while suckling or teething; and in children born of phthisical or asthmatic parents. Complication with diffuse bronchitis.

Laws of Infection.—Rarely attacks the same person twice. May coexist with small-pox, measles, and other febrile disorders; but is sometimes cured on their appearance. Latent period, five or six days.

Mortality.—The deaths in London during 15 years, in a million persons of all ages, fluctuated between 582 and 1217; average, 857. Two diseases only (Typhus Fever and Scarlatina) are more fatal.

Treatment.—1. In the early stage tartarated antimony in doses sufficiently large to produce nausea. From a twelfth to a sixth of a grain, according to the age of the patient, may be given at short intervals. Occasional gentle aperients, and a bland farinaceous diet should be prescribed; and the patient must be guarded from cold, and kept in a pure, warm air. When there is extreme restlessness, and great distress in the fits, the tartar-emetic may be combined with opium. Half an ounce of antimonial wine, with a drachm of laudanum, and distilled water in sufficient quantity to make a mixture of ℥iss, is a very good combination. The dose, for a child of ten years old, may be a teaspoonful twice or thrice daily. When the mucus is brought up with difficulty, an emetic should be given once, twice, or thrice a week. A warm bath should be given occasionally.

2. If there be signs of inflammation in the lungs, a few leeches may be applied over the upper part of the sternum, followed by a poultice. Linseed and mustard poultices, stimulating embrocations,

or even blisters to the chest, may be used with advantage. If there be determination of blood to the head, leeches to the temple and cold applications. If the child be too weak to bear antimony, give ipecacuanha or squills in combination with spirit of chloroform and belladonna. Expectorants combined with mineral acids often do much good. When the severity of the disease has passed away, change of air is the best restorative; and it is sometimes of the greatest service in the height of the disorder. Debility must be treated by tonics, especially the preparations of steel. When the symptoms of bronchitis, or bronchopneumonia have been relieved, bromide of potassium (gr. iij to v), with conium (succi conii ʒss to ʒij), is very serviceable in relieving the nervous irritation and spasm. Belladonna and henbane are also successfully employed in combination with expectorants.

DISEASES OF THE SUBSTANCE OF THE LUNGS.

Pneumonia	Inflammation of the Lungs.
Gangræna Pulmonum . .	Gangrene of the Lungs.
Hæmoptysis	Spitting of Blood.
Phthisis Pulmonalis . .	Pulmonary Consumption.

PNEUMONIA.—INFLAMMATION OF THE SUBSTANCE OF THE LUNGS.

Synonyms.—Peripneumonia. Pulmonitis. Pneumonitis.

Symptoms.—*General.* The disease sometimes sets in with rigors, followed by pyrexia; at others the local symptoms are the first to show themselves. There is high fever, with increased heat of surface, especially on the chest; flushed face; injection of the eyes; headache; frequent, quick, and compressible pulse; thirst, furred tongue; anorexia; and great debility. The chest symptoms are a diffused, dull pain, deep-seated, rarely acute, unless the disease involve the pleura; a short, dry cough, at first with scanty mucous expectoration, but after the lapse of one or two days, with a rusty-coloured, very adhesive sputum; the respiration is frequent and short, rising from 18 to 30 and upwards. In some cases (pure pneumonia, as distinguished from broncho-pneumonia) there is a complete absence of expectoration.

In favourable cases the symptoms gradually subside, and the sputa become less viscid and more abundant and of a purulent or mucopurulent character, and convalescence is effected in ten days or a fortnight. In unfavourable cases the symptoms increase on the third or fourth day; the breathing becomes more frequent; the sputa of a deeper hue, more viscid, and often streaked with blood; the pulse increases in frequency and feebleness; the tongue dry and brown; the skin hot and pungent; the debility extreme; and delirium and coma come on, with all the symptoms of the typhous state. In the last stage, the expectoration ceases; the dyspnœa increases; the pulse is small and fluttering; the face pale; the lips livid; the skin covered with a clammy sweat; there is an increasing rattle in the throat; and at length the patient dies exhausted, asphyxiated, or comatose. Fœtid odour of the breath, and putrid sanious expectoration, announce the occurrence of gangrene.

Local Symptoms.—Dulness over the inflamed lung, unless it lie far from the surface; very fine crepitation; bronchial breathing and bronchophony, with increased respiration in the unaffected portions. Fine crepitation is the first indication of the congestive stage. It supersedes the vesicular murmur; continues to be heard for a day or so, and then gradually decreases till it is inaudible; and it is now that the bronchial breathing and bronchophony are most marked. If the inflammation subsides, a little mucous crepitation begins to be heard, and soon increases in intensity and extent, until at last it becomes general, the bronchial breathing and bronchophony meanwhile decreasing, and at last becoming extinct. The inflamed lung is again permeated by air, and the expectoration of viscid, rusty-coloured sputum is re-established. As the inflammation subsides, the moist sounds give place to the natural vesicular murmur, showing that the lung is being restored to its normal condition. Resonance on percussion is, of course, established, *pari passu*, with the recovery of the lung. If, however, resolution do not take place, the dulness, tracheal breathing, and bronchophony become very marked and persistent, and there is complete absence of vocal fremitus. But if the whole of one lung become consolidated, tracheal breathing and bronchophony are absent, because no air can be drawn into it. If portions of the hepatised lung suppurate, and the abscess be discharged, the physical signs of a cavity—viz., pectoriloquy, amphoric breathing, and gurgling (see Phthisis) will be present. The parts most commonly affected are the lower lobes of one or both lungs; and the local symptoms are most marked at the sides and back of the chest.

VARIETIES and COMPLICATIONS.—Pneumonia is a frequent concomitant of the latter stages of continued fevers, of erysipelas, and pyæmia; but is very liable to be overlooked. Great heat of the chest, unusual dyspnœa, and sudden aggravation of symptoms, should lead us to suspect this complication. The physical signs are the same as in idiopathic pneumonia. It often results in the deposition of miliary tubercle in the lung, constituting *tubercular pneumonia*. It attacks patients in the advanced stage of phthisis: and is a frequent concomitant of bronchitis. Its most common combination is with pleurisy (pleuro-pneumonia).

MORBID ANATOMY.—In the first stage, *sanguineous congestion*. The lungs are gorged with blood, but still float in water. In the second they are in a state of *red hepatisation*, and sink in water. Examined with a pocket lens, the broken surface of the solidified lung has a fine granular appearance. The third stage is that of *yellow hepatisation* or *diffused suppuration*. The lung tissue is soft and rotten, and a depression made with the finger soon fills with purulent fluid.

CAUSES.—*Remote* and *predisposing*. Sanguineous temperament, and plethoric habit, winter and spring seasons, a peculiar state of the atmosphere. Great debility and privation in the poor of large towns.—*Exciting*. The common causes of inflammation; vicissitudes of temperature, violent exercise; congestion occurring from common causes, or in the course of various febrile diseases; tubercular deposits; heart disease.

DIAGNOSIS.—The adhesive, rusty-coloured sputa, the minute crepitation, the short, quick, silent breathing, with the physical signs just described, characterize pneumonia. The history of the case distinguishes idiopathic pneumonia from typhus fever with chest complication.

PROGNOSIS.—*Favourable*. An early and copious mucous expectoration, the small crepitation changing to distinct mucous râle; later in the disease, an abundant muco-purulent expectoration, with return of resonance and respiratory murmur; warm, equable, and free diaphoresis; diarrhœa; diminished frequency of respiration (an extremely favourable symptom); the absence of complication; the disease of limited extent.—*Unfavourable*. Violent fever with delirium, or typhous symptoms; no expectoration, or the expectorated matter tinged with blood of a dark colour or black; sudden cessation of pain, followed by change of countenance, and a sinking or irregularity of the pulse; increasing frequency of respiration; a previously broken constitution; the disease extending to the whole lung or to both lungs; occurring in very young children, in the weak, or the aged.

TREATMENT.—Will vary with the stage of the disease. *During the first or congestive stage*, and in plethoric and vigorous subjects, and where the consolidation is extensive, leeches may be applied to the chest, followed by a linseed poultice, and a brisk aperient. Half a grain of tartar-emetic, with two of calomel, may be given every one or two hours, and mercurial ointment should meanwhile be rubbed into the arm-pits and groins until the gums are affected. In slighter cases, the application of a black blister over the dull portion of the chest wall, and the continued use of hot linseed poultices. A grain of opium, with one or two grains of calomel, every four or six hours, and half an ounce of acetate or citrate of ammonia every three hours, is a more appropriate treatment, and may be continued in the *second stage*, or that of hepatisation. If the pulse should indicate failure of strength, ammonia, and brandy, or whisky, will be needed. In the *third stage*, or that of suppuration or gangrene, plenty of nourishing food, wine, opium and astringent tonics are required.

In chronic pneumonia following the acute form, a course of mercury so as slightly to affect the system, counter-irritation, iodide of potassium with decoction of bark, with change of air, regular exercise, and temperate diet, may be resorted to. The patient must be closely watched, and the chest examined from time to time.

GANGRÆNA PULMONUM.—GANGRENE OF THE LUNGS.

Symptoms.—A muddy anæmic complexion; fœtid breath; extreme prostration; a frequent, feeble pulse; expectoration of dingy-green sputa, mixed with blood, and of a peculiarly offensive odour; mucous râles and gurgling; marked typhous symptoms; and death from exhaustion.

Cause.—Pneumonia.

Diagnosis.—The pre-existence of inflammation, and the peculiar colour and offensive odour of the sputa.

Prognosis.—Highly unfavourable, especially when the disease involves a large portion of the lungs. About an eighth of the cases terminate favourably.

Treatment.—A liberal allowance of wine or spirits, and a nutritious diet. The chlorine gargle and mixture as recommended in Scarlatina. Inhalations of tar-water. Quinine wine with the mineral acids.

HÆMOPTYSIS.—SPITTING OF BLOOD.

Symptoms.—*General.* Spitting of blood is often preceded by a sense of weight and oppression in the chest, or of uneasiness in some one spot, with slight febrile symptoms, a frequent, sharp, and compressible pulse, some difficulty of breathing, and a dry, tickling cough. In some cases the mouth constantly fills with blood, without cough or irritation of the throat; but in other cases the blood is brought up alone, or mixed with mucus, after long fits of coughing. The patient usually complains of a salt taste in the mouth.

Local.—In some cases the chest affords the natural sound on percussion, and there is slight mucous râle; in others there is dulness over a limited spot, surrounded by fine crepitation. In the first class, the hæmorrhage is from the bronchial tubes (bronchial hæmorrhage); in the second, blood is effused into the substance of the lungs (pulmonary apoplexy). In a third class of cases the spitting of blood occurs as a symptom of advanced phthisis.

Causes.—*Predisposing.* A certain age—from the period of puberty to the forty-fifth year; sanguineous temperament; plethora; narrow conformation of the chest; previous attacks of the same disease.—*Exciting.* Excessive heat; violent exercise; the lifting of heavy weights; excessive exertion of the lungs in speaking, singing, &c.; external violence.

The most common cause of hæmoptysis is the existence of tubercular deposit in the lungs, the hæmoptysis in some cases preceding, in others following, the deposit. The next in point of frequency is vicarious hæmoptysis, the consequence of amenorrhœa. Less frequent still is hæmoptysis dependent on disease of the heart, or rupture of an aneurism. Least frequent of all is hæmorrhage, caused by plastic bronchitis. Hæmoptysis may occur in congestion of the lungs, however produced, as in pneumonia; in the fit of congestive asthma; and with hæmorrhage from other organs, as in purpura.

DIAGNOSIS.—The blood is brought up by coughing, in small quantities, or mouthfuls at a time, of a florid red colour, preceded by, or mixed with, a little frothy mucus. An abundant discharge of *florid* blood leads to the inference that the hæmorrhage comes from the lungs, or from a ruptured artery communicating with the air passages.

From *hæmatemesis*.—The blood thrown up in hæmatemesis is usually in much larger quantity, of a dark colour, more grumous, mixed with food and usually without cough. From *hæmorrhage from the nose, fauces*, or *gums*.—By the negative result of a careful examination of those parts, and the history of the case.

PROGNOSIS.—The prognosis is generally favourable, when the hæmorrhage is not sudden and abundant; and when it takes the place of the menses in amenorrhœa. In most cases, in both sexes, its occurrence justifies a suspicion of the existence of tubercle: and, in their ascertained absence, of disease of the heart.

TREATMENT.—*Indications*. I. To remove congestion. II. To keep the circulation quiet. III. To contract the relaxed vessels.

I. The first indication is best fulfilled by the abstraction of blood. The circumstances which justify the adoption of this remedy are plethora, a full, frequent, and jerking pulse, great dyspnœa, a flushed countenance, and abundant hæmorrhage. When the countenance and skin are pale; the pulse small and weak, and the respiration little affected, bleeding is not required. It is also contra-indicated in phthisical hæmoptysis. Sufficient relief may generally be obtained by leeches or cupping.

II. Low diet, perfect repose, fresh cool air, cold liquids, or ice held in the mouth, with gentle aperients, fulfil the second indication. The head of the patient should be raised, and he should avoid talking. If there be still some febrile action, tartar-emetic, in doses of one-eighth to one-fourth of a grain, every three or four hours.

III. After congestion or febrile symptoms have been removed, or in cases where there has been from the first no congestion or fever, the third indication will be fulfilled by remedies belonging to the class of astringents. (Form. 157.) Digitalis, veratrum viride, and gallic acid are serviceable remedies. (Forms. 194, 193, 158.)

PHTHISIS PULMONALIS.—PULMONARY CONSUMPTION.

Definition.—Tubercular deposit in the lungs, giving rise, sooner or later, to suppuration and hectic fever.

Symptoms.—*General.* The disease usually begins with a short dry cough, on first rising in the morning, so slight as to become habitual before it excites attention. It is sometimes accompanied by slight dyspnœa, increased on exertion, and the patient generally loses flesh, is soon fatigued, and easily thrown into a perspiration; or he complains of unusual chilliness. Slight dyspepsia, diarrhœa, frontal headache, and a small, frequent, quick pulse, are also among the early symptoms; and, on inquiry, we often learn that the patient formerly spat blood.

These early symptoms are often disregarded, or misinterpreted; so that the disease appears to begin suddenly with profuse hæmorrhage from the lungs, with pneumonia, or bronchitis.

When the disease sets in in either of these ways, it sometimes destroys life in three or four weeks (*Acute Phthisis*). But in the great majority of cases it is chronic; and after the symptoms above described have continued for several weeks, months, or even years, in consequence of a cold, or some trivial exciting cause, the cough becomes more constant and troublesome, and is attended by expectoration, at first of a frothy mucus, afterwards of a more viscid and opaque sputum, often mixed with small round particles of tubercular matter, with pus, or with streaks of blood; or well-marked hæmoptysis occurs. The dyspnœa increases, there are shooting pains in the chest, or superficial tenderness, and in many cases a peculiar hoarseness of the voice.

As the disease advances, the cough and dyspnœa become more urgent, the expectoration more abundant, the emaciation and weakness more considerable, the pulse more frequent; there are chills at noon or in the afternoon; the face flushes towards evening; the palms of the hands and the soles of the feet are burning hot; in a word, hectic fever sets in, followed towards morning by profuse perspiration. The urine is high-coloured, and deposits a pink sediment. The tongue, from being white, is now preternaturally clean and red, and the appetite often improves. Profuse diarrhœa, sometimes tinged with blood, colliquative sweats, extreme emaciation, shedding of the hair, œdema of the legs, aphthæ in the mouth and throat, hectic fever in its most marked form, and a very feeble, rapid, and often irregular pulse, usher in the fatal termination. In some cases, the patient dies suffocated, having escaped many of the most distressing symptoms. In other instances delirium and other indications of tubercular meningitis, precede the fatal event by some weeks. The appetite and spirits often remain good to the last; and the patient flatters himself with the hopes of speedy recovery, and forms distant projects of interest or amusement.

Local Symptoms.—In the incipient stage, before suppuration sets in, dulness on percussion over the clavicles and in the supra and infra clavicular regions, but generally greater on the right than on the left side. Similar dulness between the scapulæ. The upper part of the chest, in some instances, is obviously contracted, the clavicles being very prominent, the supra-clavicular regions deeply hollowed, the anterior and upper part of the chest flattened, and the shoulders thrust forward. The respiratory movements are diminished. The stethoscopic indications are a roughness in the respiratory murmur; a prolonged expiratory sound; bronchial respiration and bronchophony, heard more distinctly on one side, and most to be depended on as a sign of incipient phthisis when heard towards the point of the shoulder; mucous crepitation; increased resonance of the voice; in some cases, extremely indistinct respiratory murmur; puerile respiration in the sound parts of the lungs. The heart sounds are abnormally distinct over the whole chest.

In *advanced* phthisis, one or more of the following physical signs are superadded to the foregoing:—coarse crepitation; more decided bubbling sound or click, which is most distinctly heard when the patient coughs or takes a full inspiration; cavernous rhonchus; cavernous respiration; pectoriloquy; amphoric resonance; metallic tinkling; distinct gurgling when the patient coughs; and, in rare cases, equally distinct sound of fluid in motion on succussion; the cracked-pot sound, on sharp percussion. The situation in which these sounds occur, and the limited space which the occupy, will generally serve to distinguish phthisis from other conditions of lung productive of the same or similar sounds.

The sputa are at first frothy, as in bronchitis; then mucous, then flocculent, resembling "irregular balls of flock or wool, of a yellow or greenish colour, sinking and breaking down in water;" and lastly purulent, often sinking in water, and sometimes containing particles of clotted matter, like softened cheese. The sputa are often streaked or spotted with blood; sometimes they are discharged in the masses, designated "nummular sputa," which the patient compares to "oysters." In rare instances, distinct portions of pulmonary tissue are spit up, having under the microscope the appearance depicted in Fig. 52, p. 198, and still less frequently cretaceous or earthy matter. The frothy and mucous expectoration attend the early stages of phthisis, the flocculent and purulent the more advanced. Hæmoptysis may occur both in the early and advanced stages.

MORBID ANATOMY.—Tubercular matter, as miliary tubercules or granulations scattered through the lungs; or as opaque yellowish white or cheesy masses infiltrated into their texture. Cavities of various size and shape, sometimes found in every part of the lung, but generally confined to the upper lobes, larger and more numerous in the right than on the left side. The liver enlarged, and changed in appearance and consistence (the fatty or nutmeg liver). Tubercular deposits in the various organs of the body. Tubercular ulcerations of the larynx, trachea, and intestines (see Partial Enteritis). Of Louis' cases ulceration of the larynx occurred in $\frac{1}{3}$, of the trachea in ⅚, of the intestines in ⅙. Tubercle is a molecular and cellular formation, the constituent cells being imperfectly developed; many are little more than mere nuclei, and the largest, are rather smaller than pus corpuscles. The vessels of the *pia mater* in tubercular meningitis (Fig. 72) present at intervals spindle-shaped (A) swellings which cause obstruction of their channels. These tubercles are formed partly by the separation of molecular fibrin from the blood, and partly by the growth of the corpuscles of the outer connecting coat of the vessel (B); the exsudation and morbid growth going on simultaneously as the result of inflammatory irritation. This process is readily studied in the easily isolated vessels of the brain. It is identical with that which occurs in the formation of tubercles in the lungs.

Fig. 72.



Tubercle, like pus, may be developd from the corpuscles of the connective tissue in any part of the body. As long as the cells remain unaltered, the tubercle retains its grey semi-transparent appearance, but sooner or later they become disintegrated into fatty granular débris, and are changed into a yellowish cheesy mass. Fig. 73 shows the whole succession of transitions from (*a*) the connective tissue corpuscles, up to the production, by the division and multiplication of their nuclei, of the tubercle corpuscles (*b*). Those in the centre of the tubercular mass are undergoing disintegration into cheesy matter (Virchow).

Fig. 73.



Complications.—Bronchitis, pneumonia, and pleurisy, followed by adhesion, or by pneumothorax. Ulceration of the larynx and *trachea*. *Enlargement* of the liver; peritonitis; œdema of the ankles, anasarca, ascites; ulceration of the intestines; fistula in ano.

DURATION.—Average about two years. In acute cases, from a few months to one or two years. In very acute cases, three weeks or a month. In chronic cases, death often takes place after the lapse of years, and after repeated attacks of hæmoptysis.

CAUSES.—*Predisposing.* Hereditary predisposition (in about one-fourth the cases); the scrofulous diathesis; adult age; the male sex. A particular formation of the body, marked by a long neck, prominent shoulders, narrow or deformed chest, long slender fingers, with filbert nails, regular, white teeth, and gums with a deep red margin; thin upper lip; a fine clear skin, delicate complexion, and fine hair. Dr. Buchanan's recent laborious researches have elicited the important and comprehensive fact that "*wetness of the soil is a cause of phthisis to the population living upon it.*" —*Exciting.* Foregone attacks of pneumonia, catarrh, asthma, scrofula, syphilis, variola, rubeola. The dust to which needle-pointers, stone-cutters, pearl-button makers, millers, &c., are exposed. Irritating fumes.

MORTALITY.—The disease is fatal (but often after several attacks) in the vast majority of cases. It destroys about a ninth part of the English population, and about a fifth of those who attain the adult age. In the metropolis it causes about a seventh of the deaths at all ages, and about a fourth of those of adults. The old bills of mortality show a like proportion of deaths among adults.

DIAGNOSIS.—The symptoms and physical signs taken together render the diagnosis of confirmed phthisis easy, but it is often difficult in the incipient stage, in cases of extensive miliary deposit without suppuration, and when complicated with other chest affections. The following observations may facilitate the diagnosis. The first onset of phthisis is marked by very slight and very variable symptoms, such as debility; debility and slight emaciation; perspiration on slight exertion; dyspepsia; diarrhœa; slight hæmoptysis; hacking cough, with scanty mucous expectoration in the morning; palpitation. A few well-directed inquiries will generally bring to light some additional symptom. In all obscure cases, the character of the pulse deserves special attention, as it affords indications quite as valuable as those obtained by examination of the chest. When the disease is advanced, it is most liable to be confounded with bronchorrhœa, with dilated bronchi (see Bronchitis), and with suppuration of the lung after pneumonia. From the latter it is distinguished by the previous history, and by the character of the sputum.

The *Pulse* in some cases excites suspicion, in others confirms it, by 1, increased frequency; 3, diminished volume; 3, increased quickness or sharpness; or 4, by all three combined.

1. In the great majority of instances it exceeds the usual average, while in five cases out of six the number of the pulse exceeds the highest number (92) observed in *apparently* healthy males of the

same mean age. Sometimes this increased frequency of the pulse accompanies the first feelings of indisposition, and continues throughout the disease. I have known it as high as 140, where debility was the only marked symptom. On the other hand, cases do occur, though very rarely, in which the pulse is even less frequent than the average in health. [Jan. 1853.—P. D., aged 34, a policeman. When 24 years old he had an attack of pneumonia (?), which confined him to bed for six weeks. During the attack he spat half a pint of blood mixed with yellow sputa, for several days in succession. When 26 years of age he had an attack of pleurisy, for which he was bled. During the two years that he has been in the police force he has always had a cough, and when aged 33 again spat a little blood. Spits large quantities of yellow sputa, but no blood at present. There is dulness on percussion above and below both clavicles, with cavernous respiration, increased expiratory murmur and pectoriloquy above the right clavicle; increased expiratory murmur and slight crepitus about the left clavicle. Pulse, standing, 64. He is still able to follow his employment. August, 1853.—External appearance and symptoms little changed, but the pulse now above 100, in the same posture. June, 1858.—Still in delicate health, but following his employment as a beadle.]—2. The diminished volume of the pulse is an almost constant character, and is present even in such exceptional cases as the above.—3. The quickness of the pulse—that is to say, the promptitude with which each separate pulse rises beneath the finger—is also even more constant than the increased frequency, and may exist with a pulse of 70. The pulse of health is exactly the reverse of this, rising slowly, and, as it were, deliberately, beneath the finger; so also is the infrequent pulse of mere debility. To quickness is superadded smallness of pulse in phthisis, whilst the pulse in health is of moderate fulness.—4. The combination of the three characters of pulse—the frequency, the smallness, and the quickness—should always lead to an examination of the chest; but the small quick pulse alone is sufficient ground of suspicion. These observations apply only to men, as the characters here pointed out form a striking contrast to those of the male pulse both in health and disease: while, on the contrary, the pulse of the female, even in health, possesses these three characters in a marked degree, and assumes them in most functional and in many organic diseases. A small, quick, and frequent pulse is, therefore, less indicative of consumption in women than in men. The slight effect produced by a change from the erect to the sitting posture will also assist the diagnosis in the male, by distinguishing the debility of phthisis from simple debility due to other causes. Whenever, then, a man presents himself for advice complaining of debility, or of other obscure symptoms of phthisis, or even of symptoms proper to functional diseases of other organs, and is at the same time obviously free from acute disease, the pulse should be examined, and if, after allowing the patient's agitation to subside, it is either very small and frequent, or very small and quick, or if it combine the characters of increased frequency, smallness, and quickness, the chest should be examined, and in by far the majority of cases the physical signs will justify the suspicion raised by the pulse. In examining persons offering themselves for assurance, the state of the pulse should be particularly attended to. It may be well to observe that, in consequence of its quickness (the promptitude with which each beat is performed) the pulse usually seems much less frequent than it is. It should, therefore, be always counted by the watch. (G.)

Headache.—A dull, persistent pain in the forehead and over the eyes has often led me to examine the chest, and in most instances with the result of confirming my suspicions. (G.)

Palpitation.—This too, may be the very first symptom to engage the patient's attention. (G.)

PROGNOSIS.—*Unfavourable*, as to the ultimate event, but guarded as to that of an existing attack, for the patient may survive three, four, or more severe attacks. An existing attack is likely to terminate fatally when there is a high degree of hectic; great frequency of pulse and respiration; much emaciation and debility; a morbidly-clean or fiery-red tongue; fixed pain in the chest; colliquative sweats or diarrhœa; profuse purulent expectoration; œdema of the legs; aphthæ; and stethoscopic indications of extensive and advanced disease, or of fresh pleurisy.

There is a better prospect when the disease is limited in extent, and not traceable to hereditary predisposition: when there is little loss of strength and flesh; when the pulse and respiration are but little increased; when there are no night sweats, no diarrhœa, and no complications. When the disease is very limited, ultimate recovery is probable; and every experienced physician has met with a few cases in which patients, who had every symptom of consumption in early life, have attained advanced age. In females, the first attack is more generally fatal than in males.

Pneumonia in the young or middle-aged adult, not yielding to treatment, and accompanied by rapid loss of flesh and strength, is probably due to tubercular deposit. Bronchitis, also, occurring at the same periods of life, and characterized by similar features, is probably due to miliary deposits occupying the whole, or the greater part, of both lungs.

TREATMENT.—I. Of incipient phthisis. II. Of confirmed phthisis.

I. In *incipient* phthisis, the indications are—(*a*) To promote the absorption of the tubercular matter; (*b*) To prevent or subdue local inflammation; (*c*) To improve the general health.

(*a*.) With a view to promote the absorption of tubercle, iodide of potassium or of iron may be prescribed. Iodine may also be inhaled with the steam of warm water.

(*b*.) Local inflammation may be prevented by guarding against cold and all causes that excite the circulation. Warm clothing; the avoidance of wet and cold; and due attention to the secretions, will fulfil the first part of this indication. Inflammation may be subdued by leeches applied occasionally over the painful spot; by counter-irritants, of which blisters and croton liniment are the best.

(*c.*) The general health may be improved by proper exercise, wholesome diet, regular habits, pure air, change of air, especially to the sea-side, sea voyages, cold sponging, followed by friction every morning. Chalybeate tonics. Iodide of iron. Cod-liver oil if there be emaciation.

II. In *confirmed* phthisis—that is to say, where suppuration has already taken place—the indications are (*a*)—To facilitate expectoration; (*b*) To subdue local inflammation; (*c*) to mitigate distressing symptoms; (*d*) to support the patient's strength.

(*a.*) When the patient's strength is little impaired, and the expectoration is abundant, emetics may sometimes be given with the best effect—a scruple of sulphate of zinc on first rising in the morning, once or twice a week, according to the strength, followed by a moderate quantity of warm water or chamomile tea.

I am inclined to restrict the use of emetics to those cases in which there is abundant expectoration. In incipient phthisis, attended with a dry cough, or scanty expectoration, emetics are as useless as they might *à priori* be expected to be. (G.)

(*b.*) Local inflammation must be combated as before indicated.

(*c.*) The most distressing symptoms are night-sweats, febrile flushes, palpitations, sickness, diarrhœa, and hæmoptysis. The *palpitation* may be relieved by digitalis, in doses of from x to xx drops of the tincture; the *cough*, by small doses of opium, in combination with compound squill pill, or by small and repeated doses of the more powerful sedatives. Of these the best is extract of stramonium, in the dose of the sixth of a grain made into the form of a lozenge with extract of liquorice, and sucked frequently in the course of the day and night when the cough is most urgent. A linctus containing chloroform and hydrocyanic acid may also be given with advantage. The *febrile flushes* are relieved by tepid sponging and cooling drinks. The *night-sweats* often subside under the use of the dilute sulphuric acid (Form. 146). This may be combined, when there is much restlessness, with a quarter of a grain of morphia. The distressing *sickness* which sometimes accompanies phthisis is relieved by the use of hydrocyanic acid and bismuth (Form. 75), with a bland farinaceous diet. *Diarrhœa* commonly subsides by strict regulation of the diet, and the prohibition of every form of solid food. If it be caused by ulceration, the treatment recommended under partial enteritis must be adopted. In *hœmoptysis*, the dilute mineral acids (Form. 46), or, if these fail, Forms. 56, 58, 73.

(*d.*) The patient's strength is best supported by nourishing and unstimulating diet. In the last stage of the disease, however, stimulants, such as wine and ammonia, may be given with advantage.

REMEDIES.—In incipient phthisis, a sea voyage, or a change of *air and scene,* or a change from a low damp spot to a dry bracing air, prove as useful as to other persons whose health is impaired from whatever cause. This is probably the extent to which change of climate is beneficial in the early stage of phthisis. As, however, it has been shown that, in the East Indies, there is among our troops, as well as among the natives, a comparative immunity from consumption, a residence in that climate may be reasonably recommended, both to persons labouring under the incipient disease, and to families deeply tainted with scrofula. The places now usually recommended have not this probability in their favour, and the evidence in support of the change is on a level with that in favour of tar-water, naphtha, frictions to the spine, or dry-cupping to the chest. The fact is, that everything that has ever been recommended, however trivial, has seemed to effect a cure of consumption, simply because patients suffering from it do continually recover from existing attacks, and in rare instances regain perfect health, though pent up in towns, breathing the foul air of crowded workshops, living in unhealthy habitations, and surrounded by every unwholesome influence; exposed, in a word, to the continued action of the predisposing and exciting causes of the disease; while, on the other hand, many cases, stated to be phthisis, are merely sympathetic functional disorders of the lungs, or real diseases of the lungs of a non-tubercular origin. To recommend a change of climate in advanced stages of consumption is both unwise and cruel. But in incipient cases, a change may be fairly recommended, if it do not entail great inconvenience; for it is always a choice of evils, which ought to be fairly stated. The benefit is not sufficient to counterbalance great inconvenience or a large pecuniary sacrifice. (G.)

PROPHYLAXIS.—Persons who have an hereditary predisposition to phthisis, and those who have habitually delicate health, require unusually careful management. During childhood, nourishing and wholesome food, proper exercise, warm clothing, pure air within doors, moderate mental work, and careful attention to the state of the bowels, are necessary. During youth and adolescence exercise in the open air, especially horse exercise, cold sponging, and friction, every morning; the moderate employment of the voice in singing or reading aloud; and careful avoidance of all excesses, bodily or mental, should be insisted on. All unwholesome employments and sedentary occupations should be avoided. Residence in a dry warm climate, such as Undercliff, Torquay, Hastings, Cork, Madeira, the East and West Indies, the south of France, or Italy, Algiers, Cape of Good Hope, or Australia. Astringent chalybeate tonics.

DISEASES OF THE PLEURA.

Pleuritis	Inflammation of the Pleura.
Hydrothorax	Water in the Chest.
Empyema	Pus in the Chest.
Pneumothorax	Air in the Chest.

PLEURITIS.—INFLAMMATION OF THE PLEURA.

Varieties.—1. Acute. 2. Chronic.

I. Acute Pleurisy.

Symptoms.—*General.* After rigors, and the symptoms of inflammatory fever, a sense of weight in the chest, which in a few hours become acute pain, referred to the side, about the level of the nipple, thence shooting to the sternum, clavicle, and arm-pit, and, in rare case, over the whole of the affected side. There is a short, dry cough, unless the disease be complicated with bronchitis, pneumonia, or phthisis; in which case the patient expectorates sputa characteristic of those diseases. The countenance is expressive of anxiety; the breathing is short and catching, and performed chiefly by the abdomen; the pain is increased by deep inspiration, by the act of coughing, or by lying on the affected side. The pulse is frequent, hard, and contracted, vibrating under the finger like the tense string of a musical instrument. The tongue is covered with a white fur; the urine is scanty and high-coloured; the skin hot, and the cheeks flushed.

Sometimes severe and extensive pleurisy occurs without these marked characters. The pain is more diffuse, less severe, or produced only by pressure between the ribs of the affected side; and in some instances it is altogether absent. In most cases the acute pain, as well as the fever, subside on the third or fourth day, and the cough and dyspnœa abate, though the pleura is still inflamed.

Acute effusion into the pleural cavity and great collapse of the lung may occur without any other symptom than debility and quick breathing.

Local.—When the disease is recent, the effusion scanty, and the surfaces of the pleuræ not adherent, there are feeble respiratory murmur from diminished motion of the chest, slight dulness, friction-sounds, cessation of vocal fremitus, and ægophony. If adhesion takes place, the friction-sounds cease; and if effusion occur to a considerable extent, the physical sounds are those stated under Empyema.

Terminations.—In resolution; in adhesion; in effusion followed by collapse of the lung; in the chronic form.

Morbid Anatomy.—Injection of the subserous cellular membrane with dryness of the surface of the pleura; effusion of coagulable lymph, or of pus mixed with flakes of lymph; and recent adhesions. Abundant effusion of clear serum and collapse of the lung.

Causes.—*Predisposing.* Rheumatic diathesis.—*Exciting.* Cold; external injuries, fractures of the ribs, &c.; febrile state; the inflammation of adjoining parts; tubercle; fever.

Diagnosis.—From *pleurodynia*, by the severe constitutional symptoms and characteristic local signs. From other diseases of the chest, by the physical signs.

Prognosis.—*Favourable.* A recent attack promptly treated; absence of complications; if the disease be not recent, the absence of hectic, and of great debility.—*Unfavourable.* Rapid and extensive effusion; implication of both sides of the chest; the co-existence of organic disease; hectic fever and great debility; dropsy.

Treatment.—In the robust a full bleeding from the arm, followed by full doses (¼ to ½ gr.) of tartarated antimony, every one, two, or three hours; brisk aperients, and a strict antiphlogistic diet. For slighter degrees of inflammation, diaphoretics with opium (Forms. 208 and 83), linseed and mustard poultices, cupping or leeches and blisters.

2. Chronic Pleurisy.

Symptoms.—Chronic pleurisy is usually a consequence of the acute form: the effusion remains, and usually increases, and if there be continued pyrexia, it sometimes becomes purulent. Emaciation, dyspnœa increased by exertion, and inability to lie on the healthy side, are the chief symptoms. These are apt to alternate with acute pain, and increased dyspnœa. Hectic indicates that the effusion has become purulent.

Treatment.—To promote the absorption of the effused matter, mercury (Form. 294) may be given until constitutional effects are produced; or, if there be much debility, the continued use of iodide of potassium, the infriction of iodine unguents, the repeated application of blisters.

The general strength must be supported by the use of tonics; and, in cases of great debility, by stimulants and a nourishing diet.

These measures may cause the absorption of the effused fluid; but when the quantity is large, and especially when it consists chiefly or wholly of pus, absorption rarely occurs, and the disease now takes the name of *Hydrothorax* or *Empyema.*

HYDROTHORAX and EMPYEMA.

The former term signifies a collection of serum, the latter a collection of pus, in one or both cavities of the pleura. The physical symptoms are the same whether the fluid be pus or serum. At first it is impossible to say positively which of these two fluids is present.

The *general symptoms* are those of chronic pleurisy. When the effusion into one side of the chest is considerable, there is dyspnœa, increased by exertion; and, on lying down, a painful sense of weight and oppression at the chest; the face is pale or dusky, and expressive of anxiety, and palpitation is often a distressing symptom. There is a dry, harassing cough, with expectoration sometimes tinged with blood. In describing his sensations, the patient frequently speaks of breathing through water. There is inability to lie on the sound side; but when the disease exists in both pleural cavities the patient cannot lie down at all.

When the effusion is purulent, ulceration is apt to occur in some of the surrounding textures, and an opening is formed into the lungs, through the walls of the chest, or through the diaphragm. The bones may also become carious. When the matter points externally, fluctuation is perceived in the part, and the integument becomes tense during expiration. When an opening takes place into the lungs, a large quantity of offensive matter is discharged during a fit of coughing, and this is followed by great relief to the breathing. When the opening forms externally, the discharge of matter is increased by coughing.

The *local signs* are as follows:—Enlargement of the diseased side, proportioned to the extent of the effusion; the ribs raised as in full inspiration; the intercostal spaces bulged, level with the ribs, and sometimes perceptibly fluctuant. When the effusion is great, universal dullness on percussion in all postures, with absence of vocal fremitus and respiratory murmur, and displacement of the heart. When moderate, the dullness on percussion, and the respiratory and vocal sounds shift with the position of the body. Puerile respiration on the sound side, proportioned to the degree of compression on the lung of the diseased side. When the effusion is slight, ægophony, generally most distinct about the angle of the scapula.

TREATMENT.—Having failed to produce absorption in the course of a week by the general and local treatment above mentioned, it will be necessary to remove the fluid, if there be sufficient to impede the breathing. In no case must paracentesis be delayed too long, else the lung will become completely collapsed and incapable of re-expansion.

If we have positive indications that the fluid is pus we evacuate it at once. If the matter point in any part of the chest, a large orifice should be made there, with a scalpel, for its free evacuation; but if not, we select a spot midway between the spine and sternum, above the upper margin of the fifth rib on the left side, of the fourth on the right side, and if the effusion be not very great, a small incision being previously made through the skin with a scalpel, a full-sized trocar should be pushed horizontally inwards, perpendicular to the median plane. When the effusion is great, we may operate above the fifth right rib, and the sixth left rib. Before the introduction of the trocar, the skin should be drawn upwards, *so that the external* and internal opening may not coincide. To prevent the introduction of air during the operation, the canula should be attached to an indiarubber tube, filled with water, and its free extremity suspended in water. By means of a stop-cock the fluid should be allowed to flow *very slowly* from the chest; and meantime we should ascertain, by the stethoscope, whether the lungs are proportionately expanding. As long as they continue to do so, we may allow the fluid to flow slowly; but as soon as they cease to expand, the flow should be stopped, or air will be admitted into the pleural sac. The more slowly the fluid is removed, the less chance is there both of the admission of air and of renewed effusion. Simultaneously with the withdrawal of the canula, and while the patient is holding the breath, or *expiring*, the integument should be slipped over the orifice in the chest wall, and retained there by means of collodion and a pad of lint.

If we discover the fluid to be pus, the canula may be withdrawn, a free incision made, and a drainage-tube inserted.

Pressure by broad bands of adhesive plaster may be advantageously employed both during and after the operation.

In many cases the removal of the fluid, whether brought about by internal remedies or by operation, cannot take place without more or less affecting the shape of the chest; the lung may be either permanently condensed by the pressure, or bound down by firm adhesions. As the fluid then is absorbed, the ribs fall in, the chest shrinks, the shoulder falls, and remains more fixed than that of the sound side, the scapula approaches the spine and is more prominent, and the spine itself is often concave towards the same side. The lung of the sound side, expanding beyond its usual limits, displaces the heart. These changes are accompanied by appropriate physical signs of collapsed lung, namely, dullness on percussion, impaired respiratory murmur, bronchophony, and vocal fremitus. When the effusion is partial and confined by adhesions, the contraction is also partial, and the physical signs are more limited in extent.

Pleurisy may occur in young people, and lead to great deformity, without much impeding the breathing; but when it attacks the adult, it generally leaves behind it some dyspnœa, with a strong tendency to recurrence.

PNEUMOTHORAX.—AIR IN THE CHEST.

Air may find its way into the cavity of the pleura in two ways: 1. By an opening in either the pulmonary or parietal pleura. 2. By secretion. The first is the more common cause.

Sʏᴍᴘᴛᴏᴍs.—These vary with the circumstances under which the opening takes place, and the previous condition of the pleura. When a superficial ulcer of the lung opens into a previously healthy pleural sac, the entrance of air gives rise to dyspnœa, acute pain, dry cough, spasms of the intercostal muscles, a frequent, feeble, and sometimes irregular pulse. These symptoms, which are more or less sudden, according to the size of the opening, are soon followed by those of inflammation of the pleura. When inflammation pre-exists, the presence of air not only tends to increase it, but converts the otherwise inodorous pus into a fœtid fluid.

PHYSICAL SIGNS.—Unusually clear tympanitic sound on percussion, with great indistinctness or total absence of respiratory murmur on the affected side; the breathing has an *amphoric* or *metallic resonance*, most distinct at the root of the lung behind, and during expiration; the voice and cough are attended by a metallic ringing echo, like that produced by speaking under a stone arch. There is increased distinctness of the respiratory murmur on the sound side. When there is liquid as well as air in the pleural sac, the physical signs are, dulness on percussion as high as the level of the fluid, which shifts with change of posture; *metallic tinkling*, and splashing on succussion.

PROGNOSIS.—Unfavourable, but life is often prolonged for months.

TREATMENT.—This depends upon the stage of the disease, and the state of the patient. The sudden rupture of the lung is generally followed by symptoms of collapse and irritation, requiring stimulants and opium; when inflammatory symptoms come on, antiphlogistic measures are required. It may be necessary to resort to local depletion by cupping or leeches, and to counter-irritation. Tartar-emetic may be given in nauseating doses, and the bowels should be kept free by gentle aperients.

When extreme dyspnœa is present, an opening must be made with a fine trocar to give exit to the air, and this should be done at a part of the chest below the level of any liquid it may contain. The operation may be repeated if necessary.

CHAPTER IV.

DISEASES OF THE DIGESTIVE CANAL AND ABDOMINAL VISCERA.

1. Diseases of the Mouth, Fauces, and Gullet.
2. Diseases of the Stomach.
3. Diseases of the Intestines.
4. Diseases of the Stomach and Intestines.
5. Diseases of the Peritoneum.
6. Diseases of the Liver, Pancreas, and Spleen.

DISEASES OF THE MOUTH, FAUCES, AND GULLET.

Stomatitis	Inflammation of the Mouth.
Gingivitis	Inflammation of the Gums.
Glossitis	Inflammation of the Tongue.
Tonsillitis	Inflammation of the Tonsils.
Parotitis	Inflammation of the Parotid Gland.
Cynanche Thyroidea .	Bronchocele.
Œsophagitis	Inflammation of the Gullet.
Other Diseases of the Œsophagus.	

STOMATITIS.—INFLAMMATION OF THE MOUTH.

Varieties.—1. Stomatitis erythematosa; 2. S. follicularis; 3. S. fungosa (aphthæ); 4. S. mercurialis; 5. S. gangrenosa.

1. Stomatitis Erythematosa seu Vesicularis.

Symptoms.—This is a disease of early infancy, characterized by redness and heat, and sometimes by dryness, of the mouth and of the tongue, and the eruption of groups of minute vesicles upon it and around its edges. It often coexists with inflammation of the stomach and bowels. In infants from the seventh to the ninth month fever is often superadded. The inflammation may extend to the whole mouth, and even to the lips, which swell, excoriate, and sometimes become the seat of *herpes*. The chronic form is often attended by profuse salivation.

Treatment.—If the mouth and tongue be dry, lint or fine sponge moistened with thin barley-water should be frequently passed over them. The diet should be of milk combined with a little fluid magnesia, given, if the bowels be irritable, in small quantities at short intervals.

2. STOMATITIS FOLLICULARIS.

SYMPTOMS.—Large, roundish, elevated, white, thick-walled, distinct vesicles, on the inner surfaces of the lips and cheeks, the sides of the tongue and the gums. The vesicles usually present a depressed centre and a minute point, the sealed orifice of the follicle. They soon break, and discharge a little glairy fluid. A minute superficial ulcer, bounded by a red margin and apt to spread a short distance, follows.

The disease attacks children about the time of the first teething. Old people are also liable to it.

CAUSES.—Inflammation of the mucous follicles, and simple racemose glands, sympathetic with some disorder of the alimentary canal.

TREATMENT.—For infants ʒj doses of solution of bicarbonate of magnesia, and solution of nitrate of silver locally applied. In adults attention to the disordered function of the alimentary canal.

3. STOMATITIS FUNGOSA.—THRUSH.

Under the specific name *fungosa* are included all the aphthous affections known to be due to the presence of fungi.

DEFINITION.—Mouldiness of the mucous membrane of the mouth.

SYNONYMS.—S. membranosa. Aphthæ. Muguet. Millett.

SYMPTOMS.—White, opaque, conical, irregularly-rounded or ring-like, elevated patches, appearing alone or simultaneously on the inner surface of the lips and cheeks, on the gums, palate, and tonsils, and on both surfaces, but especially the sides, of the tongue. Sometimes the disease extends down the œsophagus into the stomach, and along the respiratory passages into the bronchi. In aggravated cases the patches become confluent, and form a loose, ragged membrane of a dirty white or greyish colour, extending over a considerable portion of the tongue or cheek. They soften down and become ragged on their surfaces, and after a variable time (from ten hours to several days) separate, and leave either a smooth, red, unbroken surface, or a superficial excoriation. The abraded surface may now become covered with healthy epithelium, or the diseased condition may be reproduced. This affection is a frequent accompaniment of gastro-intestinal irritation in weakly infants. There is increased difficulty of sucking and swallowing. If the disease extend into the alimentary canal, it will produce vomiting and diarrhœa, with mucous stools. Coughing and mucous expectoration, mixed with grey aphthous threads, mark its extension into the air-passages. When the child is in a low state of health, the aphthæ sometimes produce unhealthy sores, the surrounding parts become swollen, soft, and livid, there is profuse salivation; and the child, refusing food, becomes pale and cold, and at last dies of inanition.

CAUSES.—Predisposing. A tender epithelium as in infants, and after desquamation, resulting from local or general disease. The disease affects persons of all ages.—*Exciting*. The development of a parasitic fungus (Oidium albicans) in the epithelial covering of the mucous membrane. The plant consists of minute tubular jointed filaments, and of bright spherical or oval spores developed at the joints and extremities of the filaments. The spores and the joints of the thread-like stems contain one or two bright rounded granules. (Fig. 74). The filaments (*g*, *k*, *l*,) grow in between the epithelial cells in every direction, and form a network, into the meshes of which the spores (*c*) are poured, disturbing and loosening the epithelium, which becomes swollen, opaque, and friable. The disease rarely extends below the cellular layer; but as the deepest growing portion of this layer is frequently invaded, the disease is not thrown off when the superficial parts are separated. Sometimes the disease extends to the corium itself, producing unhealthy ulceration. The racemose glands are a favourite seat of the fungus, their little open-mouthed ducts allowing of its ready introduction to the softer cells within them.

Fig. 74.



Contagion.—As the disease is due to the growth of a fungus, its presence, and a favourable condition of the mucous membrane will always result in its development. The fungus is probably derived, in the first instance, from some mouldy article of diet. When once established, it may spread from one child to another throughout a foundling hospital. The disease may be conveyed from the child's mouth to the nurse's nipple, and from the latter to the mouths of other children; and by the use in common of cups, spoons, towels, baths, and other domestic articles.

Treatment.—Gastric irritation and diarrhœa, which frequently attend this disease, must be treated on general principles. The mouth should be frequently washed with a saturated solution of borax, or smeared with borax and honey. Under this treatment the disease soon yields.

Aphthous ulcers of the mucous membrane of the lips and tongue are frequent concomitants of skin disease caused by vegetable parasites. I have frequently observed them in persons affected with dermmycosis circinata (herpes circinatus). The fungus represented in Fig. 75 is from a case in which the external ase was confined to two large semicircles on the upper lip.

On the tongue were two aphthous ulcers, both near the tip; one was quite depressed, as if partially cicatrised, and extended into the vascular corium. The epithelium forming the margins of the ulcers was opaque and thick and contained the fungus. All parts of the mucous membrane are liable to be affected by vegetable parasites, and especially when the vital powers of the individual are depressed, as in the last stages of lingering diseases. The specimen of Oidium albicans represented in Fig. 76 is from the kidney of an aged patient who came under my care in King's College Hospital. She was admitted in the last stage of pulmonary consumption; her nervous power was much depressed, as was indicated by apathy and low temperature of body. The parasite had invaded the vascular tissue of the mamilla for the distance of about a line between the terminations of the tubules. The patient had no cutaneous disease. The vulva and nipples are very liable to the aphthous affection. Israel (Virch.: Archiv. B. lxxiv.) has recorded a case of general mycosis.

Fig. 75.



Fig. 76.



4. Stomatitis Mercurialis.—Mercurial Salivation.

Symptoms.—A disagreeable brassy taste, looseness of the teeth, tenderness of the gums, a peculiar fœtor of the breath, and a constant profuse discharge of saliva, with shreds of epithelium; shooting pains in the face, stiffness of jaw, and swelling of the parotid and submaxillary glands. The gums are first marked by a distinct red line, and then become generally red and swollen; little ashy superficial ulcers appear upon them, and they are apt to bleed; after a few days, pus oozes from their margins here and there, and they are more or less separated from the teeth. The inflammation may extend to the interior of the cheeks and to the tongue, which becomes swollen, indented, and furred; and it sometimes leads to ulceration of the gums and cheeks, and, in rare cases to gangrene. These local symptoms are attended by slight irritative fever.

The duration of mercurial salivation, in slight cases, is two or three days; in severe cases, ten days or a fortnight, and if ulceration or gangrene ensue, still longer. Several weeks may elapse before the gums are restored to their healthy state.

Causes.—The accumulation of mercury in the system from internal administration or external application of some of its compounds.

Some persons are exceedingly susceptible of mercury, while others are with difficulty brought under its influence. Great vigilance is, therefore, required in its use. In one case severe stomatitis, with slight ulceration and bleeding of the gums, swelling of the salivary and cervical glands, and severe pain in the jaws, has been induced in three days by the infriction of 100 grains of mercurial ointment into the groins, and the internal administration of gr. iii ss. of calomel in divided doses. In another the repeated application of the ung. hyd. oxidi rubri to an extensive ulcerated surface caused the same effect.

Diagnosis.—In most cases, mercurial salivation is distinguished from that of pregnancy, that produced by antimony, copper, arsenic, and gold, jaborandi, digitalis, prussic acid, iodide of potassium, and several other substances, by the excessive fœtor of the breath.

Treatment.—Gargles of alum or zinc with carbolic acid, chlorides of soda or lime, tannic or hydrochloric acid, acetate of lead, or brandy and water. In more severe cases, and when the gums are ulcerated, a strong solution of nitrate of silver applied by a brush, or nitrate of silver, or sulphate of copper in substance. If much swelling of the glands be present, leeches to the jaws, followed by blisters behind the ears, and warm fomentations: and if much irritation, opium. Saline aperients, and moderate doses of quinine with acid, complete the treatment.

5. Stomatitis Gangrenosa.—Gangrene of the Mouth.

Synonyms.—Cancrum oris; Noma.

Symptoms.—The attention is often first called to a circumscribed indolent, hard, shining swelling on one cheek (generally the left), without pain, heat, or redness. On examining the mucous membrane of the mouth, one or more ulcers, blisters, or white eschars, will be found on the internal surface of the cheek, lips, or gums. These gradually increase in size, and discharge a dirty, sanious, offensive fluid; at the same time the saliva, increased in quantity, flows from the mouth mixed with membranous shreds. The swelling of the cheek increases till it involves the eyelids and lips. A dark livid spot now occupies the centre of the swelling, enlarges, softens, and sloughs. Gangrene having set in, makes rapid progress both within the mouth and on the surface, and at length involves the cheek, lips, and gums, and in extreme cases, the nostrils, eyelids, neck, and pharynx; the teeth fall out, and the bones of one or of both jaws, and even the cheek and frontal bones, are ultimately involved. The constitutional symptoms by no means keep pace with the severity of the local affection. In most cases there is no fever, no loss of appetite, and little impairment of strength. The little patient often continues to run about and play, to sit up, and to amuse himself till within a short period of his death, the faculties of the mind remaining intact. Less frequently there are febrile symptoms, and still more rarely delirium. Local reaction affords hope of recovery. In fatal cases, death results from asthenia.

COMPLICATIONS.—Pneumonia (58 cases in 63); pleurisy; enteritis; gangrene of the lungs, pharynx, œsophagus, and stomach; gangrene of the extremities, and of the vulva: scrofulous affections.

CAUSES.—*Predisposing*. Childhood, and all causes of debility. Inflammation of the lungs or intestines.—*Exciting*. Overcrowding, and impure air.

DIAGNOSIS.—*Cutaneous* swelling of a gangrenous character distinguishes this affection from Anthrax, and is attended by acute pain and inflammatory symptoms. Anthrax is very rare on the cheek. *Scurvy* is usually confined to the gums. The effects of *mercury* are known by the history of the case, the swollen gums and tongue, the abundant flow of saliva, the peculiar odour of the breath, and the numerous superficial ulcerations. The diagnosis is very difficult when the illness is of some standing, and the previous history obscure.

PROGNOSIS.—Extremely unfavourable. Mortality about 75 per cent. An early age, previous great exhaustion, and treatment postponed till the gangrene has fairly set in, are unfavourable circumstances.

TREATMENT.—I. The *local* treatment consists in the use of stimulant applications. Previous to the appearance of the livid spot, the linimentum camphoræ compositum, or the linimentum ammoniæ to the cheek, or lunar caustic; should gangrene have set in, strong acetic or nitric acid. The mouth should be washed out frequently with an aqueous solution of carbolic acid, or gargle (Form. 63).

II. The *general* treatment consists in the use of light nourishing diet, wine, ammonia and bark, or perchloride of iron in large doses.

GINGIVITIS.—INFLAMMATION OF THE GUMS.—PAINFUL DENTITION.

SYMPTOMS.—Dentition is generally accompanied by salivation, and by hot, painful, red and swollen gums. The infant puts the fingers, or whatever it can grasp, into the mouth, and presses the gums upon it. But when the true inflammation is present, he cannot bear even the pressure of the nipple. This inflammation of the gums may extend to the lining membrane of the mouth, and be followed by aphthæ, ulceration, or gangrene.

The general symptoms are feverishness, fretfulness, disturbed sleep, flushing of face and head, often accompanied by inflammation of the brain or its coverings, and diarrhœa. In extreme cases, water in the head, with convulsions, inflammation of the lungs, or laryngismus stridulus. Skin diseases are also common complications, especially lichen and strophulus.

TREATMENT.—In mild cases, gentle friction of the gums; in more severe cases, scarification. The warm bath, simple diet, and a strict attention to the state of the bowels, complete the treatment. Opium and hemlock are most valuable to calm irritation.

Incision of the gums ought not to be practised unless they are swollen, hot, and painful from the pressure of the teeth. When the incision is made prematurely, dentition, so far from being accelerated, is retarded. The incisions should be deep and free, one parallel to the alveolar margin, and a second at right angles to it.

GLOSSITIS.—INFLAMMATION OF THE TONGUE.

SYMPTOMS.—Inflammation of the whole tongue is rare, except as the sequel of profuse salivation, or of strong irritant applications. Abscess appears at first as a hard tumour on the upper surface, it slowly suppurates, and leaves a deep penetrating ulcer.

Inflammatory œdema of the whole tongue is often a severe and dangerous disease, marked by heat, swelling, and pain, difficult speech and deglutition, dyspnœa, salivation, swelling of the veins of the neck, and determination of blood to the head, with inflammatory fever. It arises, in most instances, from gastric or intestinal irritation, and is cured by purgatives and the application of nitrate of silver.

TERMINATIONS.—In resolution, suppuration, or gangrene. In extreme cases it threatens suffocation or apoplexy.

CAUSES.—Mechanical injuries; strong irritants; the sting of insects; salivation; extension of disease from the tonsils, gums, and cheeks.

TREATMENT.—In the early stage, brisk purgatives and antiphlogistic remedies, with ice to the surface of the tongue. In a more advanced stage, incisions. If suffocation threaten, tracheotomy must be performed.

Ulceration sometimes takes place on the side of the tongue, from the irritation of a decayed tooth, which must be filed or removed.

Epithelial cancer of the tongue is known by its peculiar hardness, the irregular ulceration, the acute lancinating pain, and the cachectic state of the patient.

Syphilitic ulcers of the tongue, with foul surface and irregular hard margins, occupying chiefly its edges, require a course of mercury or iodide of potassium, with the application of solid sulphate of coper, or nitrate of silver. Ichthyosis of the tongue is due to syphilis, and known by a bare serpiginous thickening and opacity of the epithelium with a tendency to abrasion and cracking.

TONSILLITIS.—INFLAMMATION OF THE TONSILS.

1. ACUTE TONSILLITIS.

SYNONYMS.—Cynanche tonsillaris. Angina tonsillaris. Amygdalitis. Quinsy. Inflammatory sore throat.

SYMPTOMS.—After rigors, followed by flushes, pains in the back and limbs, and a full, frequent, and compressible pulse,—a sense of fulness, heat, and dryness in the throat, pain and difficulty in swallowing and speaking. The throat presents a diffused redness, of a deeper tint over the tonsils, which are swollen, and sprinkled with greyish yellow spots, consisting of secretion from the gland blocking up the mouths of its follicles. The tongue is coated with a white creamy fur. As the disease advances, the swelling of the tonsils increases; the mouth is almost closed; the acts of swallowing and speaking become more difficult and painful; liquids return through the nostrils, there is a constant discharge of viscid saliva, the respiration is affected, and there is a painful sense of tension, with acute darting pains in the ears. The febrile symptoms increase, and the pain in the back and limbs become more acute; but in a more advanced stage, the fever often subsides, or changes its character from inflammatory fever during the first stage, to mild hectic during the stage of suppuration.

DURATION.—From five to seven days.

TERMINATION.—By resolution, suppuration, ulceration or gangrene; or in chronic enlargement.

PROGNOSIS.—The disease usually terminates by resolution. Suppuration is to be feared when the disease does not yield to remedies, when the local pain is acute and throbbing, or when there are rigors or cold shiverings. An abscess is indicated when there is much swelling, a sense of fluctuation on pressure with the finger, a whiteness of some part of the tumour, and, finally, purulent expectoration. Gangrene is to be dreaded, if the fever be intense, and the pain extremely violent, without any sign of resolution or suppuration. A pinched and sunken countenance, the extremities cold and covered with a clammy perspiration, a small, frequent, weak, and intermittent pulse, and a very fœtid odour issing from the mouth, are signs of its existence.

CAUSES.—*Predisposing*. Youth, debility, syphilis, previous attacks.—*Exciting*. Cold; cold drinks while the body is heated; the deglutition of caustic or irritating fluids.

TREATMENT.—When the disease is slight, the treatment proper to catarrh. When more severe, the tonsils should be scarified and leeches applied below the angles of the jaws, followed by a poultice to the throat, and a brisk aperient. When, however, the gland suppurates and feels tense and yielding, a lancet should be thrust directly backwards into the most prominent part, and the pus evacuated. The mouth should then be gargled repeatedly with warm water. When the tonsils are so swollen as to impede the breathing, emetics sometimes give relief. If the skin be hot and the pulse strong, saline diaphoretics should be given; but if the patient is very weak, quinine, beef-tea, and wine must be prescribed.

2. CHRONIC TONSILLITIS.

SYMPTOMS.—Enlargement and induration of the tonsils, which, projecting towards the middle line, impede swallowing, speaking, and hearing. The mouth is often kept partially open; the breathing is audible and the voice sibilant.

CAUSES.—*Predisposing*. Syphilis, scrofula, and chronic dyspepsia. —*Exciting*. Acute inflammation of the gland.

TREATMENT.—*General*. Chalybeate tonics with iodine, change of air, warm clothing.—*Local*. Strong solution of nitrate of silver, astringent gargles (Form. 60), the occasional application of a leech or small blister to the angles of the jaws. Iodine unguents and liniments. When these remedies are unavailing, and the tonsils are so large as to impede deglutition or respiration, or to affect the voice, excision may be practised.

Ulceration of the tonsils may occur in disordered states of health, but it is generally a secondary effect of syphilis. The disease is slow in its progress; but, if not checked, it extends into the nostrils and fauces, and ultimately attacks the larynx itself. A gargle of chloride of soda may be used with advantage, and the ulcers may be frequently touched with nitrate of silver. The general health must be carefully attended to, and the strength supported by a nourishing and generous diet. *Syphilitic ulceration of the tonsils* requires the same treatment as other secondary diseases.

The disease known as *Clergyman's sore throat*, or *dysphonia clericorum*, consists at first in a chronic enlargement of the tonsils and lengthening of the uvula, with a relaxed and congested condition of the mucous membrane of the fauces, which gradually extends to the pharynx and the upper part of the larynx. In the most severe cases of the disease, there is also ulceration of the mucous follicles of the parts affected, and the mucous membrane, especially about the pillars of the fauces, is coated with a tenacious secretion. The *symptoms* are dryness and tickling of the throat, constant hawking, and spitting, and hoarseness increased after reading or speaking, and attended sometimes with pain in the upper part of the windpipe. The disease is generally traceable to a bad method of reading and speaking in unhealthy persons. The treatment consists in the exhibition of alteratives and tonics to improve the general health, the particular remedies employed being determined by the state of the system ; and in local measures directed to remove the relaxed and congested state of the mucous membrane. The best local remedy is a strong solution of nitrate of silver (gr. v to ʒj) applied by means of a camel's hair brush or a piece of sponge to the whole of the inflamed surface. If this mode of application should prove insufficient, the solution of nitrate of silver may be applied to the upper part of the larynx by means of a whalebone probang tipped with sponge. When there is great enlargement of the tonsils of long standing, excision may become necessary, as in simple chronic tonsillitis. Clergymen suffering in this way should acquire the habit of taking a full breath very frequently while reading or preaching, so as to speak from the lungs and not from the throat; and take lessons in elocution.

PAROTITIS.—CYNANCHE PAROTIDEA.—THE MUMPS.

Symptoms.—After slight febrile symptoms, fulness and soreness at the angle of the jaw, with pain on moving the part. The swelling extends by degrees upwards to the space between the cheek and ear, and downwards to the submaxillary gland, occasioning great deformity. On the fourth day it begins to subside. It is generally confined to one side, but sometimes it attacks the other afterwards; it rarely attacks both at once. The disease is sometimes accompanied, and sometimes followed, by painful swelling of the breast, or testicles. It generally terminates in resolution.

Suppurative inflammation of the parotid is a frequent concomitant of the latter stage of typhus and enteric fevers, and is often developed with remarkable rapidity. Without any premonitory indication, a large congested, hard and painful swelling forms round the ramus of the jaw in a few hours; and the inflammation rarely stops short of suppuration.

Causes.—*Predisposing.* The period of childhood.—*Exciting.* Exposure to cold ; scarlatina, and other febrile diseases.

Contagion.—A medical student had mumps in London, while his mother was staying with him. They remained in town until the swelling disappeared, and then went 100 miles into the country. There was no mumps in the neighbourhood; but a fortnight after their arrival one of the children was taken ill with it, and it afterwards successively affected at regular intervals of a fortnight, each member of a large family.

Treatment.—Warm fomentations, with the application of flannel in the intervals; gentle aperients, and farinaceous diet. If much inflammation be present, leeches may be applied. The secondary affection of the breasts or testicles must be treated in the same way. Should any swelling remain after the inflammation has subsided, friction with stimulating liniments may be prescribed.

BRONCHOCELE.—CYNANCHE THYROIDEA.—GOÎTRE.

Symptoms.—A swelling affecting the entire thyroid gland, or a single lobe of it; at first firm and elastic, but after a time soft, with small, flabby portions of a denser consistence. It grows slowly at first, but after a time rapidly, extending upwards towards the jaw, sometimes beyond the limits of the neck, and even hanging over the chest. It sometimes attains an enormous size, and then causes serious inconvenience by its pressure on the trachea and vessels of the neck.

Morbid Anatomy.—Hypertrophy of the gland, partial or entire, with enormous enlargement of its vesicles, so as to present, when cut into, cavities often of considerable size, and containing serous fluids of various consistence.

Fig. 77.



Causes.—*Predisposing.* Female sex; puberty; hereditary tendency. *Exciting.* Unknown. The disease is endemic in localities differing widely from each other in all respects. But the most common characteristic of the spots in which it prevails is want of due movement of the air. It is very common in deep valleys shut in by mountains. Combined with every degree of idiocy and imbecility it is the *Cretinism* of the Vallais. It is so common in Derbyshire as to be called the "Derbyshire neck." It is also common in the valley of the Teme, and the dale of the Corve, N.W. of Ludlow, particularly in the vicinity of the calcareous beds of the Silurian and Devonian formations.

Treatment.—Iodine externally. Iodide of potassium internally. Burnt sponge, which contains minute quantities of iodine, was formerly in great repute for the cure of this malady. Removal from the district in which the disease originated.

When other means fail, and the tumour, by its pressure, causes great inconvenience, ligature of the thyroid arteries.

A condition known as *Exophthalmic goître*, is occasionally met with in females near the climacteric periods of life; rarely in males. Associated with a general irritability of the heart and vascular system, there is special dilatation, with throbbing of the thyroid and ophthalmic arteries, causing enlargement of the thyroid gland, and protrusion of the eyeballs. These effects were well marked in the patient delineated in Fig. 77. The disease appears to be due to more or less complete paralysis of the vasomotor nerves of the parts affected, and it is sometimes accompanied by local sweating and dilatation of the pupils. Palpitation and functional bruits are common. The treatment consists in stimulation of the sympathetic, and for this purpose belladonna and ergot have proved most successful.

ŒSOPHAGITIS.—INFLAMMATION OF THE ŒSOPHAGUS.

Symptoms.—Pain, or a burning sensation, in the act of swallowing, either in a part of the œsophagus, or through its whole extent. This pain is sometimes increased on pressing the larynx firmly towards the spine. When the inflammation extends to the mucous membrane of the stomach, there is pain in the epigastrium, with vomiting, leading, in some instances, to the expulsion of tenacious casts of the tube. In cases produced by swallowing hot water or corrosive poisons, large flakes of epithelium are often discharged.

Causes.—Stimulant and corrosive applications to the tube itself, such as hot water, and the several corrosive poisons. The extension of inflammation from the mouth, fauces, or tonsils; wounds.

Treatment.—The frequent use of ice or iced water, and a farinaceous, liquid diet. So long as the difficulty of swallowing remains very great, the patient must be supported by nutritious injections. After the first or second week a large well-oiled bougie should be carefully passed daily, in order to prevent constriction during cicatrization.

OTHER DISEASES OF THE ŒSOPHAGUS.

The gullet is subject to other functional and structural diseases; among the former, rheumatism and spasmodic stricture; among the latter, hypertrophy of the submucous tissue, and various malignant degenerations, such as scirrhus and medullary sarcoma. It is also liable to pressure from aneurism of the aorta or carotid artery, from enlargement of the cervical glands, and from diseases of the spine.

Rheumatism of the gullet is a rare disease, characterised by painful deglutition distinctly referred to some part of its course, accompanied by rheumatism of other muscles, and yielding to the treatment proper to muscular rheumatism.

Spasmodic stricture of the gullet is characterized by difficulty of swallowing, accompanied by a sense of choking, the food either passing into the stomach after many efforts to swallow, or being rejected. It is generally associated with other symptoms of hysteria, and is amenable to the treatment proper to that disease. It is distinguished from organic stricture by the circumstance of its not being constant, but subject to intermissions; by the result of an examination with a bougie; by the history of the case; and the presence of other hysterical symptoms. It requires no local treatment; but in obstinate cases the daily introduction of a bougie may be attended with benefit.

Dysphagia, a fixed pain at the root of the neck or sternum, and corresponding to the site of obstruction; rumination of light solid food, such as bread and butter, with the discharge of mucus, sometimes tinged with blood, declare the early stage of *cancer*. In this disease the use of bougies should be avoided.

DISEASES OF THE STOMACH.

CONGESTION	Of the Stomach.
HÆMATEMESIS	Vomiting of Blood.
GASTRITIS	Inflammation of the Stomach.
ULCER	Of the Stomach.
PERFORATION	Of the Stomach.
CARCINOMA	Of the Stomach.

OTHER FORMS OF STOMACH DISORDERS.

CONGESTION OF THE STOMACH.

SYMPTOMS.—The mucous membrane of the stomach is an extended and highly vascular glandular surface, and when it becomes congested the secretion of gastric juice takes place slowly, and in diminished quantity. Anorexia, dyspepsia, with a dryish tongue and thirst, some pain and tenderness in the epigastrium, and constipation are the usual symptoms.

The distended capillaries are sometimes relieved by an oozing of blood. The effused blood, acted on by the acid secretion of the stomach, forms black coagula, which may be rejected by vomiting, constituting *hæmatemesis*; or the clots undergo disintegration in the stomach, and are rejected as "coffee-ground" or "black" vomit; or they may pass along the alimentary canal, and, after further alteration, be ultimately evacuated as a black grumous or pultaceous stool, constituting *melæna*.

CAUSES.—1. Obstruction to the flow of blood through the liver and thoracic viscera. If a ligature be placed around the portal vein, or the vena cava inferior at the under surface of the diaphragm, blood will ooze from the stomach. Some diseases of the liver cause an obstruction to the portal circulation almost tantamount to a ligature round the main trunk; and obstructions to the flow of blood through the lungs and heart are nearly equivalent in their effects on the stomach to obliteration of the inferior cava above the liver. Hence congestion of the stomach is sooner or later a prominent symptom in cirrhosis of the liver; in atrophy from long-continued obliteration of the bile ducts; and in diseases, such as cancerous tumours, which involve and press on the portal vein. Acute suppression of bile, such as occurs in yellow and relapsing fevers, commonly produces severe congestion of the stomach, resulting in vomiting of altered blood. The disease of the lungs which most frequently leads to congestion of the stomach is emphysema; and disease of the mitral valve, which both contracts its orifice and permits regurgitation, is the condition of the heart which most commonly produces the same result.

Congestion of the stomach may also be due to functional disorder, such as suppressed menstruation, in which the stomach sometimes assumes a vicarious office, and a monthly hæmatemesis takes the place of the catamenia. In some cases this happens during the whole natural term of menstruation.

Treatment.—The congestion of the portal circulation may be relieved by free watery purgation induced by the non-irritating saline purgatives, such as potassio-tartrate of soda. The abdominal vessels may also be relieved, though less effectually, by copious diuresis, for which acetate and nitrate of potash may be prescribed. To prevent the congestion from degenerating into inflammation and ulceration, irritating food and medicine, strong alcoholic drinks, and even fermented liquors, must be avoided, and the diet must consist chiefly or exclusively of eggs, milk, and farinaceous articles. If there be much pain in the epigastrium, mustard poultices may be applied, and a few leeches to the anus. In cirrhosis of the liver it is better to avoid leeching, for the bleeding is liable to be too free.

Hæmatemesis, if present, must be treated as recommended below.

HÆMATEMESIS.—VOMITING OF BLOOD.

Symptoms.—Vomiting of dark-coloured clotted or grumous blood, in greater or less quantity, often mixed with food, and preceded by a sense of weight and obtuse pain in the region of the stomach. If the oozing be slow, the countenance becomes blanched; but if rapid and considerable, the patient becomes pale, faint, and sick, and the vomited blood may be bright-coloured. In hepatic disease the complexion is sallow, and the conjunctiva tinged with bile. Melæna often co-exists.

Causes.—Those of congestion of the stomach; ulcer of the stomach; rupture of an aneurismal tumour into the stomach.

Morbid Anatomy.—Congestion, ulcers, or malignant diseases of the stomach; congestion or chronic disease of the liver.

Diagnosis.—The blood is vomited, and not coughed up as in *hæmoptysis*. In hæmoptysis the blood is usually bright, in hæmatemesis commonly dark, often grumous, and, being altered by the action of gastric juice, like coffee grounds. Food may also be present. But in certain rare cases, the diagnosis of the source of the hæmorrhage is not easy. If, for example, an ulcer of the stomach erode a large arterial trunk, the blood vomited may be fluid and scarlet. Again, the blood in hæmoptysis may come up into the mouth without the effort of coughing, so as to seem to be vomited rather than coughed up. It may also be unmixed with sputa; and when discharged from old cavities of the lungs, may have lost its bright vermilion hue. But the discharge of a very large quantity, such as a pint, or a quart, of dark grumous blood, even though unmixed with food, may be held to be conclusive of its having come from the stomach; for when such large quantities are expelled from the lungs, the blood is always of a bright scarlet colour. The state of the liver and lungs will serve to confirm the diagnosis.

Treatment.—Rest, abstinence from all food for some hours, and afterwards, for many days, only unirritating slops.

When the hæmorrhage is excessive, the patient may be made to drink freely of iced water, or to swallow rough ice, and an ice bag may be applied to the pit of the stomach. The vegetable and mineral astringents (Form. 158). When the hæmorrhage has been stayed, gr. v. pilulæ hydrargyri, followed by a saline aperient, should be given, and the disease subsequently treated according to its cause.

If there be suppression of the hæmorrhoidal or catamenial flux, leeches should be applied to the anus or vulva.

GASTRITIS.—INFLAMMATION OF THE STOMACH.

1. Acute Gastritis.

Symptoms.—An acute fixed pain and sense of burning heat in the pit of the stomach, increased by pressure, deglutition, and the movements of respiration; frequent vomiting of clear viscid mucus streaked or not with blood, attended with increase of pain: intense thirst; great restlessness, and extreme anxiety; the tongue red; the pulse quick, small, and hard; the bowels confined.

The disease generally extends to the gullet and intestines, and is attended by pain and dysphagia, diarrhœa, and abdominal tenderness.

Terminations.—*In resolution*, when the pulse becomes more soft and full, and the other symptoms gradually disappear. *In chronic gastritis*. *In gangrene*, marked by a violent exacerbation of the symptoms, followed by a sudden cessation of pain, a rapid and intermitting pulse, the utmost prostration of strength, cold extremities, delirium, hiccough, and death. *In perforation*, characterized by sudden and acute pain, with extreme prostration, and symptoms of peritonitis.

CAUSES.—Drinking ardent spirits or hot water; irritant poisons, and indigestible diet. Idiopathic acute gastritis is exceedingly rare. Prolonged abstinence from food. The gouty excitant in the blood.

DIAGNOSIS.—From *enteritis*, by the epigastric heat, tenderness, and pain, and by the more severe vomiting.

PROGNOSIS.—*Favourable.* The pulse becoming softer, fuller, and less frequent; and the pain and tenderness gradually ceasing.—*Unfavourable.* No alleviation of symptoms. Extreme and general tenderness of the abdomen. Symptoms marking the accession of gangrene or perforation.

MORBID ANATOMY.—The mucous membrane of the stomach red, universally or in patches, especially around the cardia and pylorus; deep redness of the rugæ; abrasion, ulceration, or "hæmorrhagic erosions," occurring as brown or soot-black spots, in size from a pin's head to a pea; or softening of the membrane; gangrene; also dark patches resembling gangrene, but arising from the effusion of blood into the sub-mucous cellular tissue; the blood-vessels full of dark blood. Gangrene and ulceration are rare, but softening is common.

TREATMENT.—I. Six to twelve leeches to the pit of the stomach, and iced water or ice, externally and internally. Free action of the bowels in the absence of diarrhœa, by the use of emollient clysters. The free and frequent use of mucilaginous diluents, such as gruel, linseed-tea, or barley-water.

II. The sickness, restlessness, and pain are best relieved by soda-water and small doses of dilute hydrocyanic acid (♏iii to ♏v) combined with opium.

2. SUB-ACUTE GASTRITIS.—DYSPEPSIA.—INDIGESTION.

SYMPTOMS.—Anorexia; nausea; flatulence; heartburn; occasional pain in the epigastrium; sick headache; a sense of fulness and oppression after eating, or a feeling of languor and depression relieved by taking food. These symptoms, variously combined, and generally accompanied by constipation, diarrhœa, or the two conditions alternately, and with defective or immoderate secretion of bile, constitute the most common form of dyspepsia. A dry cough; cold extremities; headache; furred tongue, with red prominent papillæ; a bitter taste; dimness of vision; bright spots before the eyes; palpitation; shooting or fixed pains in the region of the heart, and under the scapulæ, varying with the degree of flatulence, are occasional consequences of dyspepsia. In the more severe cases the epigastric pain is considerable, and is increased by pressure and by food. Sometimes the smallest quantity of food gives pain, and is rejected as soon as it is swallowed, or after a short interval.

Pain in the stomach (*gastralgia*) may be produced by flatulent distension, and by the presence of hard indigestible food, or of excess of acid. When the pylorous contracts upon masses of hard undigested food as it is passing into the intestines, violent crampy pain in the epigastrium is produced.

CAUSES.—*Predisposing.* Debility; want of exercise; depressing passions; amenorrhœa; imperfect mastication; irregular intervals between meals; the abuse of drastic purgatives; close study, or exercise immediately after food; diseases of the liver, pancreas, or spleen; the gouty diathesis. Dyspepsia is a frequent precursor of phthisis, and a common accompaniment of asthma and bronchitis. —*Exciting.* Inactivity of the liver producing constipation; unwholesome and indigestible food; the abuse of spirituous liquors, especially at the dinner-table; liquids in excess, especially hot tea and coffee.

DIAGNOSIS.—From ulcer of the stomach, by the absence of a fixed and limited seat of pain, and of hæmatemesis or melæna.

TREATMENT.—*Indications.* I. To correct bad habits, and to regulate the diet. II. To restore the stomach to a healthy condition. III. To palliate urgent symptoms.

The habits which commonly require correction are the following: —Eating too much at one time; eating too often or too seldom; taking too great a variety of food at the same meal; drinking too much liquid before or with the meals; imperfect mastication; resuming bodily or mental occupation directly after eating; indolent and sedentary habits; the injudicious use of purgatives; drinking, smoking, chewing tobacco, opium-eating, and tea and coffee in excess. If any particular article of food seem to disagree, it should be carefully avoided. Flatulence is frequently increased by green vegetables and fruit. Wine and ale will sometimes require to be exchanged for weak brandy and water, or for brandy with soda-water, or Seltzer water.

II. A regular action of the bowels should be secured by mild cholagogue purgatives. Stomachic tonics (gentian, calumba, cascarilla, cinchona), combined, according to the state of the secretions, with alkalies or the mineral acids, should be persevered in. In mild cases a few grains of compound rhubarb-pill may be given as a dinner-pill.

III. If there be tenderness, half a dozen leeches or a mustard poultice may be applied to the epigastrium. Acidi hydrocyanici diluti, ♏v, tincture opii, ♏v, given in effervescence, with a few grains of carbonate of soda and citric acid will generally allay the vomiting. The diarrhœa will usually yield to a few doses of the pulvis cretæ aromaticus cum opio.

An acute attack of indigestion is best treated by an emetic, followed by rest and an aloetic purge.

ULCER OF THE STOMACH.

Symptoms.—Pain in the pit of the stomach, referred to a small spot, coming on immediately or soon after food, continuing for an hour or two, and then slowly abating as the stomach becomes empty. Pressure usually gives rise to a slight feeling of uneasiness in some part of the epigastrium, sometimes accompanied by a like sensation in the corresponding part of the back. It is increased by indigestible food, hot fluids, and alcoholic liquids, and in young females on the approach of the menstrual period. There is nausea and vomiting of food, of a clear, sour liquid, of bile, or of blood. Sometimes the blood is discharged by the bowels, which are generally constipated. The patient loses flesh, has an unhealthy aspect, and wears an expression of weariness and suffering.

Usually the disease causes very little constitutional disturbance, and in some cases the local symptoms are so slight, that severe hæmatemesis, or even perforation of the stomach, may be the first indication of its existence. In some instances the process of ulceration is rapid, and perforation may occur within a few weeks of the formation of the ulcer. In other cases the ulcer remains open for many years, giving rise to its ordinary symptoms, and now and then to an alarming hæmorrhage; and at last leads to perforation.

Terminations.—In recovery; in perforation (see p. 501); by hæmorrhage and fatal syncope, or collapse; by marasmus from constant vomiting.

Causes.—*Predisposing*. The female sex; intemperance; fatigue; anxiety. The influence of age may be thus briefly stated:—From 16 to 20 years of age, 20 cases; for each decade from 20 to 60, about 50 cases; for the two decades from 60 to 80, about 80 cases; and for the ten years from 80 to 90, 100 cases. In this country it is most frequent in female cooks.—*Exciting*. Obscure; probably raw spirit.

Diagnosis.—From *dyspepsia*, *sub-acute gastritis*, *pyrosis*, and *gastralgia*, by the limited pain on pressure in the epigastrium; by the pain in the back, the more frequent vomiting, and the discharge of blood; from *cancer* of the stomach, by the absence of the marked cancerous diathesis, the lancinating pain, the hard and movable tumour in the pit of the stomach, the less abundant hæmorrhage, and the presence of cancer-cells in the vomit. The diagnosis of ulcer of the stomach is often difficult and uncertain.

Prognosis.—Favourable but guarded. Most guarded with young females in whom perforation is a common event. About one in five cases prove fatal in one of the ways mentioned above.

Morbid Anatomy.—Of 10,203 bodies examined in the hospital at Prague, there were 126 open ulcers, and 224 cicatrices of the stomach and duodenum, = 3·4 per cent. In more than a third of the cases the ulcer occupies the posterior surface of the stomach, and in more than three-fourths the posterior surface, the lesser curvature, or neighbourhood of the pylorus. In about one-fifth of the cases there is more than one ulcer, and there may be two, three, four, five, or more. "The ulcer is rarely much smaller than a fourpenny piece, or larger than a crown piece, but it may attain a diameter of five or six inches. Its shape is usually round or oval, and it presents the appearance of "a shallow but level pit, with a sharp, smooth, vertical edge, as though it had been punched out" (Brinton); but as the circular opening in the sub-mucous areolar tissue is smaller, and the aperture in the peritoneum, if the ulcer perforate, still more minute, the ulcer has a conical form. The surrounding mucous membrane and areolar tissue are somewhat thickened, and sometimes inflamed. Perforation takes place in about 1 case in 8; this result being often prevented by adhesion to the pancreas, liver, spleen, mesentery, or diaphragm.

In attributing death to ulceration of the stomach, it is important to be aware of the fact that, under certain circumstances, the coats of the stomach undergo *self-digestion*, resulting in pulpy or gelatinous softening, irregular abrasion, and even perforation. The mucous membrane is converted into a thin, pasty, mucous layer; the blood-vessels are blackened; and if all the coats of the stomach are removed, a ragged aperture results, through which the contents of the stomach escape. This self-digestion is due to the action of the gastric juice; it is met with in those who have died suddenly during digestion, and in those who have died from disease (such as phthisis), in which chronic irritation of the vagus nerve had induced excessive secretion of gastric juice.

TREATMENT.—I. We must try to promote the healing of the ulcer, by preventing irritation or distension of the stomach. With this view the diet must be strictly regulated. Solid food must be rigidly avoided, and its place supplied by milk, eggs in the form of emulsion, light broths, and farinaceous diet, given at short intervals, and in quantities not exceeding a teacupful. Spirituous liquors and hot fluids should be forbidden.

II. If there be much *tenderness on pressure*, mustard poultices or blisters should be used; if constant *pain*, solid opium may be given; if *gastrodyne* and *pyrosis*, nitrate of bismuth; if distressing *vomiting*, hydrocyanic acid, and farinaceous food in small quantities often repeated; if *vomiting of blood*, ice, and the remedies recommended under hæmatemesis; if *constipation*, castor oil is the most suitable aperient; if *diarrhœa*, compound kino powder.

III. If the patient be *anæmic*, the preparations of iron, of which the ammonio-citrate is most suitable. (In this disease it may be given dissolved in glycerin.) If there be much debility present, the citrate of iron and quinine in glycerin is to be preferred. In intemperate persons, full doses of opium are indicated.

PERFORATION OF THE STOMACH.

Symptoms.—After a longer or shorter duration of symptoms of ulcer of the stomach, intense pain in the epigastrium occurring suddenly, spreading rapidly over the whole abdomen, and soon followed by tympanites and collapse. The disease assumes all the characters of peritonitis, and usually proves fatal in from twenty-four to thirty-six hours; but in some cases the fatal event is postponed in consequence of the peritonitis being limited in extent, or sub-acute in character. In most cases the rupture takes place during the distension of the stomach by a full meal, but it is sometimes caused by vomiting, straining at stool, coughing, or sneezing; by pressure, shocks, or blows.

Terminations.—In acute peritonitis and rapid death; in chronic peritonitis, and death after a longer interval; in abscess of organs bordering on the stomach; in gastric fistula.

Causes.—*Predisposing*. Those of the gastric ulcer. The female sex from the fifteenth to the twenty-fifth year.—*Exciting*. Gastric ulcer; irritant poisons.

Diagnosis.—From ordinary peritonitis by the sudden attack.

Prognosis.—In the highest degree unfavourable, especially when the perforation takes place after a full meal.

Treatment.—The patient should be placed in the recumbent posture at perfect rest. A full dose of opium should be given every three or four hours. Complete abstinence from food must be enjoined, the patient being allowed merely to moisten the mouth from time to time. If the inflammation run high, leeches should be applied to the abdomen, followed by hot simple fomentations. The lower bowel should be relieved by enemata, and nourishment be supplied by the same channel. Should the patient survive the immediate consequences of the rupture, milk and farinaceous food must be given by the spoonful at short intervals, and a return to the usual diet must be made slowly and cautiously. When convalescent, castor oil should be used as an aperient.

CARCINOMA.—CANCER OF THE STOMACH.

Symptoms.—In the early stage the symptoms are very obscure. They are usually those of dyspepsia (sub-acute gastritis). But, after a longer or shorter interval, during which the patient loses flesh, and obtains little or no relief from his dyspeptic symptoms, a circumscribed tumour may be discovered in the epigastrium, and now the pain becomes burning, gnawing, or lancinating; and there are nausea, acid and fœtid eructations, with vomiting of ingesta, mucus, blood, or a dark grumous or sour frothy matter containing sarcinæ (Fig. 78, p. 503); complete constipation, and retraction of the belly, which becomes hard and flat; great emaciation, and the cancerous complexion and expression.

When the cancer involves the pylorus, as is most frequently the case, the passage of food into the intestine is impeded; it accumulates in the stomach, which becomes enormously dilated, ferments, and is discharged at intervals of 24 or 48 hours by copious vomiting.

MORBID ANATOMY.—The disease may take the form of scirrhus, or of medullary or colloid cancer. But the most common form is scirrhus, and its usual seat the pylorus. Forms of cancer cells are given p. 77, Fig. 10. The stomach is generally contracted when the disease occupies the cardiac end; greatly expanded and hypertrophied when the pylorus is affected.

DIAGNOSIS.—An epigastric tumour can occasionally be felt. Lancinating pain; constipation and retraction of the abdomen; cachexy and emaciation; persistent vomiting of decomposed food; and the rapid progress of the malady, serve to identify this disease. Cancer rarely occurs before forty. The part of the stomach attacked may be generally inferred from the symptoms. When the cardia is affected there is obstruction to the entrance of food, the pain and vomiting come on immediately after taking food; when the pylorus is attacked, there is obstruction to the exit of chyme, and pain and vomiting come on later.

CAUSES.—*Predisposing.* The cancerous diathesis.—*Exciting.* Chronic dyspepsia, and any irritation of the stomach.

TREATMENT.—A bland and nourishing diet, such as new milk; gruel; milk with arrowroot; strong soups, thickened with vermicelli; jellies, and light farinaceous puddings; and tripe boiled in milk. The food to be taken often, and in very small quantities. Excessive acidity may be checked by combining lime-water or bicarbonate of soda with the milk. Nutritive enemata may be given once or twice a day; and cod-liver oil rubbed into the abdomen. Narcotics and anodynes to allay pain; an occasional blister; anodyne plasters, fomentations and embrocations externally; and rest.

OTHER FORMS OF STOMACH DISORDER.

1. ATONY OF THE STOMACH. — ATONIC DYSPEPSIA.

SYMPTOMS.—Anorexia and slowness of digestion, with occasional severe crampy or spasmodic pain some hours after meals, due to the presence of undigested food and its passage through the pylorus. Headache, flushing after meals, and other symptoms of dyspepsia are occasionally added.

CAUSE.—Defective secretion of gastric fluid.

TREATMENT.—Brisk exercise and the avoidance of sedentary occupations and excessive mental labour and anxiety. A light nutritious diet, taken in small quantities and often. The use of salt, mustard, pepper, a pill composed of gr. v each of mastic or myrrh and extract of rhubarb taken daily half an hour before dinner, or a carminative tonic (Form. 243). In many cases the mineral acids are of much service (Form. 122), in some, small doses of ipecacuanha.

2. Pyrosis.—Water-brash.

Symptoms.—In the morning or forenoon, two or three hours after a meal, when the stomach is empty, pain and tension at the pit of the stomach, lasting some time, and followed by vomiting of a thin watery fluid, in considerable quantity, sometimes acid, but often insipid. This generally relieves the pain, and puts an end to the attack. It may occur only occasionally, or last, with intermissions, for years. The fluid, which may vary from an ounce to a pint or more, is rejected by a sort of rumination and not by ordinary vomiting.

Causes.—*Predisposing.* Middle age. The female sex.—*Exciting.* Reflex irritation of the abdominal and pelvic viscera, especially the uterus. Hence pyrosis is common in pregnancy. A poor diet.

Treatment.—Improve the diet, and avoid an undue proportion of farinaceous substances. If the liquor ejected from the stomach be highly acid, alkalies (Form. 123), or bismuth (Form. 75). In other cases the vegetable astringents in combination with opium such as gr. x pulveris kino compositi.

3. Excessive Formation of Lactic Acid in the Stomach.

Symptoms and Treatment.—"This disorder is most common in nervous persons with feeble digestion, in whom it not unfrequently happens that acid collects in great quantities after meals. They often familiarly tell us that almost everything they eat turns to an acid." (Budd.) Severe heartburn comes on soon after eating, to be relieved after two or three hours by vomiting of very sour fluid, the acidity being due to lactic acid produced by conversion of the starchy constituents of food into that compound. The alkalies afford temporary relief; and the mineral acids more lasting benefit.

4. Formation of Acetic Acid by Fermentation of the Saccharine Constituents of the Food.

Symptoms.—Heartburn, pain in the stomach, and sour eructations after meals; and eventually vomiting of sour frothy fluid containing much acetic acid with or without a little alcohol. Very frequently it is associated with the development of the peculiar vegetable organisms which have been called by Goodsir *Sarcinæ ventriculi* (Fig. 78). The sarcinæ are found in a brownish scum on the surface of the vomited matters. They are often associated with the common yeast fungus, *Torula cerevisiæ* (Fig. 30, p. 132).

Fig. 78.



Treatment.—This form of stomach disease is often very obstinate, and may continue, with greater or less severity, for years. Alkalies only give temporary relief. The fermentative process may be prevented by kreasote given in ii or iii ♏ doses in the form of pill, thrice a day. Sulphurous acid is still more effectual; it may be given in ʒss doses diluted with a little peppermint-water twice or thrice a day.

5. Sympathetic Vomiting.

Causes.—Sympathetic disorder of the stomach resulting in vomiting may be produced by irritation of the brain, lungs, liver, intestines, kidneys and ureters, uterus and ovaries. That cerebral and uterine irritation are most prone to induce it, is seen in cerebral concussion and in pregnancy.

When the irritation is prolonged, reflex vomiting becomes a constant and distressing symptom. In the latter stage of tubercular disease of the lungs the irritation leads to the secretion of much sour fluid.

The treatment must be directed to remove the source of the irritation. In the vomiting associated with phthisis, the alkalies and subnitrate of bismuth, combined with hydrocyanic acid and the vegetable astringents, are of much service. In other cases, such as the passage of a gall-stone, large doses of opium, in the solid form, may be required.

DISEASES OF THE INTESTINES.

Enteritis	Inflammation of the Intestines.
Dysenteria	Dysentery.
Diarrhœa	Looseness of the Bowels.
Melæna	Hæmorrhage from the Bowels.
Torpor Intestinorum . .	Constipation.
Obstructio Intestinorum .	Obstruction of the Bowels.
Intus-susceptio	Invagination of the Bowels.
Colica	Colic.
Colica Pictonum	Painters' Colic.
Tympanites	Drum Belly.
Hæmorrhoides	Piles.

ENTERITIS.

Definition.—Inflammation of the mucous membrane of the small intestine.

1. General Interitis.

Synonyms.—*Enteria. Enteritis erythematoidea. Diarrhœa mucosa*, or *catarrhosa*.

Symptoms.—At first, chilliness or slight rigor; nausea and loss of appetite ; if the duodenum be especially affected, vomiting; thirst; a white furred tongue with prominent papillæ and a red tip; heat and soreness in the belly, but chiefly about the epigastrium and umbilicus; a dull diffused pain on pressure; and frequent diarrhœa. The nature of the evacuations depends on the cause of irritation. They are always fluid; contain at first much undigested matter, but after a time watery mucus occasionally streaked with blood. After the diarrhœa has lasted some hours, the intestine is liable to become distended with flatus, causing gurgling and griping pain.

Unless the patient be judiciously treated, these symptoms may continue for several days or even weeks, to the serious impairment of his health.

CAUSES.—Imperfect stomach digestion; the passage of vitiated or imperfectly formed chyme into the intestine. A vitiated condition of the bile. Drastic purgatives:—the symptoms of enteritis may be well studied in the effects produced by a large dose of jalap. Mineral poisons, such as arsenic, antimony, and corrosive sublimate. Exposure to cold inducing congestion of the internal organs.

TREATMENT.—Warmth to the surface; rest of the inflamed part, by quietude, light diet, such as may be digested in the stomach, or, if passed into the intestine, cannot irritate the inflamed surface. Eggs, milk, beef-tea, arrowroot, answer to this description. Milk and arrowroot, mixed, if the patient be weak, with a little brandy, is generally the most appropriate food. The inflammation and its most prominent symptom, diarrhœa, will be relieved by Form. 148, 83. Hot fomentations, or stimulant poultices, may be simultaneously applied to the abdomen. If the diarrhœa persist, and the evacuations be bloody, the treatment proper to dysentery is indicated.

2. PARTIAL ENTERITIS.

This disease is caused by specific inflammation of the glands of the small intestine. The solitary and agminated glands are invariably affected in enteric fever (see p. 294). They also frefrequently become the seat of tubercular deposit, inducing local inflammation and subsequent ulceration. The symptoms of tubercular ulceration of the small intestine resemble those of well-marked ulceration in enteric fever—viz., fever, persistent purging, light-coloured watery stools, griping pain in the abdomen, gurgling and tenderness about the right iliac fossa. In both diseases hæmorrhage to an alarming extent is liable to occur. The general treatment is the same in both diseases. Bismuth (Form. 75) is very serviceable in the diarrhœa of phthisis.

MORBID ANATOMY.—Of the ulceration of enteric fever (see p. 294). Of tubercular ulceration of the intestine:—Large patches of ulceration throughout the ileum, separated by intervals of four or six inches, commencing as small round discrete ulcers at the upper part of the bowel, gradually become confluent below into large irregular patches, extending round the whole circumference of the canal. From a description of a single ulcer the appearance of all *may be inferred*:—Ulcer irregularly circular, limited by a thick, round, elevated, angry-looking border: within the margin is irregular and continuous, with less distinct granulations, between which little yellow masses of tubercular deposit, firmly attached to the base of the ulcer, may sometimes be seen; the contiguous parts of the intestinal wall are much thickened, so that on spreading the ulcerated bowel on a flat surface, the patches form considerable elevations. Some of the ulcers extend quite down to the peritoneal coat. Their position is known before opening the intestine, by corresponding vascularity of the peritoneum, and a feeling of irregular thickening.

DYSENTERIA.—COLITIS.—DYSENTERY.—BLOODY FLUX.

Definition.—**A specific inflammation of the mucous membrane of the colon, accompanied by tenesmus, and by mucous, bloody, or purulent stools.**

Symptoms.—At first cold shiverings, followed by fever; or bilious diarrhœa, which after continuing for a few days, without causing much pain or uneasiness, becomes an incessant flux, with discharge of pure blood, of mucus, or of a white glairy matter, like white of egg, mixed with blood. Masses of indurated fæces often form part of the discharges. At the same time there are severe griping pains in the abdomen; frequent inclination to go to stool; tenesmus; dysuria; and cramps in the thighs. The patient is restless, sleepless, and anxious. The pulse is quick and hard, the tongue clean, the skin warm and moist, the face flushed, and the eye bright.

In this, the first stage of dysentery, the disease sometimes proves fatal by collapse; but it more commonly assumes the chronic form, the purging becomes persistent, pus and blood appear in variable quantity in the stools, which are semifluid and pultaceous, mixed with shreds of lymph, and excessively offensive.

Under appropriate treatment the blood and pus disappear, the motions become more healthy, the diarrhœa decreases, and after some months the patient recovers. But recovery is in many cases very slow, and in many more incomplete, and the purging sets in again and again on exposure to cold, or after improper food. The patient preserves a good appetite, and does not lose flesh; but if, as is sometimes the case, the disease involve the ileum also, emaciation, in proportion to the extent of surface affected, results.

Complications.—The disease may accompany, precede, or follow ague, or remittent fever, and land or sea scurvy; and it may be complicated with inflammation of the liver, spleen, or pancreas.

Terminations.—In incessant vomiting; in aphthous inflammation of the mouth; in abscess of the liver; in ascites; in fatal hæmorrhage; in perforation of the intestine; in gangrene; in collapse.

Morbid Anatomy.—In the *acute stage*, the mucous membrane of the colon inflamed in patches of a deep red colour, or throughout its whole extent; sometimes black, as if gangrenous; sometimes softened. The intestine itself contracted. The follicles enlarged and transparent, or hard and opaque. In the *advanced stage* of the disease, small round ulcers, which commence in the first instance in the solitary glands, thence spread, and subsequently (becoming confluent) form large ragged patches. The neighbouring tissues are much thickened. In some cases, similar appearances in the lower part of the small intestines, and occasionally even in the stomach. The mesenteric glands often red, swollen, and soft. The intestines, in the early stage, contain mucus, blood, and a watery lymph; in the advanced stages, pus mixed with blood.

In cases of long-standing disease the ulcers are found contracted and surrounded by tissue of almost cartilaginous hardness. Tough cicatrices mark the position of ulcers which have ultimately healed.

A large majority of the fatal cases of dysentery present abscess in the liver. The purulent deposits in this organ may be due to concomitant hepatitis, or (as Dr. Budd has suggested) the pus may be derived from the ulcerated intestine (see Pyæmia).

Causes.—*Predisposing.* A high temperature. Unwholesome food, especially salt meat and unripe fruit; fatigue, privation, and exposure. Intemperance.—*Exciting.* Marsh miasma; impure water; exposure to wet and cold, especially at night after a hot day. A debauch.

Duration.—From a few days to several weeks, months, or years.

Mortality.—In acute dysentery from 1 in 8 to 1 in 50; in chronic dysentery, from 1 in 4 to 1 in 6.

Diagnosis.—From inflammation and ulceration of the small intestines; by the absence of anorexia, vomiting, and emaciation. From ordinary diarrhœa; by the presence of sloughy membrane, blood, and pus, and by the persistence of the purging.

Prognosis.—*Favourable.* Moderate diarrhœa, and the absence of hectic. *Unfavourable.*—Violent and distressing tenesmus and tormina; vomiting; hiccough; cold extremities; cold and partial sweats; the tongue præternaturally red and dry: great prostration; the motions extremely fœtid; petechiæ; involuntary evacuations; intermitting pulse; complications with diseases of the liver, and intermittent or remittent fever.

Treatment.—In the *acute stage*. It is of the first importance to free the bowels of irritant matter, and with this view simple enemata and one or two doses of castor oil with ♏x tincturæ opii should be prescribed. Simultaneously we may use the hot bath; leeches to the anus or to the tender spots of the abdomen, followed by hot fomentations, turpentine stupes, or mustard poultices.

At the same time a diet should be prescribed free from solid *ingredients*, but more or less nourishing according to the state of the patient, with an allowance of port wine in cases of great debility. Tender spots in the abdomen should be treated with a few leeches, followed by warm fomentations: and tenesmus and dysuria by suppositories of the compound soap-pill, or small injectious of gruel, containing laudanum. From the favourable effect of nitrate of potash in doses of ten grains frequently repeated in a very troublesome and intractable form of diarrhœa, I should be disposed to recommend ten grains of this salt with a grain of opium and a grain of ipecacuanha three or four times a day. (G.)

Chronic dysentery is a most intractable disease; a fact explained by the pathological condition of the diseased intestine. Alterations in the calibre of the intestine and the passage of undigested food, or of irritating fluids, are sufficient to prevent the ulcers from healing. The diet must therefore consist of bread, eggs, and milk; and such other food as will leave no indigestible residue. Vegetables must be prohibited, except when the dysentery is complicated with scurvy.

The diarrhœa will only yield to the mineral astringents, of which sulphate of copper, in ⅙ grain doses, combined with ¼ grain of powdered opium, is the most effectual. The bowels should be washed out every day with a cold-water clyster.

Prophylaxis.—Pure water, warm and dry clothing; cleanliness; a mixed and wholesome diet; avoidance of exposure to wet, cold, and fatigue; in the case of armies, a frequent change of the site of the camp.

DIARRHŒA.—LOOSENESS, OR PURGING.

Definition.—Frequent discharges of semi-solid, or fluid-stools, with more or less gastro-intestinal irritation.

Varieties.—1. Intestinal dyspepsia. 2. Bilious diarrhœa. 3. Mucous diarrhœa. 4. Serous diarrhœa. 5. Diarrhœa with fibrinous exsudation. 6. Sympathetic diarrhœa.

The *first form* is very common in the autumn and latter part of summer. It is due mainly to the high temperature, but may be caused or increased by excess in fruits, and in such vegetables as the cucumber and melon. The treatment consists in the removal of the offending matter by a full dose of castor oil, combined, if there be much griping, with ♏x or xv of tincture of opium.

Bilious diarrhœa is very common in the European inhabitants of tropical climates. It is caused by the use of a larger quantity of animal food than is required in hot climates, under which circumstances the diminished respiratory function is compensated by the elimination of the hydro-carbonaceous constituents of the bile in excessive quantities.* (See Billiary Congestion.) The secretion is [illegible]dly poured out into the duodenum, and sets up bilious diarrhœa. [illegible] treatment consists:—1. In relieving the distended condition [illegible] liver, by allowing the diarrhœa to continue unchecked for a time. If there be pain, gr. xv–xx of bicarbonate of soda may be given in combination with ♏v–x of tincture of opium.—2. By adapting the diet to the altered conditions of existence, substituting vegetables and ripe fruits for animal food, and avoiding the use of spirituous liquors.

Mucous diarrhœa, or intestinal catarrh, sometimes co-exists with, and sometimes follows upon, catarrh of the bronchial mucous membrane. The slightest exposure to cold and damp will induce it in many delicate people. It is this form which accompanies enteritis and the acute stage of dysentery.

The appropriate remedies are sulphuric acid, and the vegetable astringents, such as catechu and gallic acid, together with the general treatment recommended in enteritis.

Serous or *watery diarrhœa* often occurs spontaneously in ascites and general dropsy, in which conditions it appears to be a natural curative process, caused by the direct exsudation of the watery constituents of the blood from the congested membrane. It should therefore be encouraged, and only controlled when excessive by the vegetable astringents. This form of diarrhœa follows the administration of the hydragogue purgatives. Sometimes it alternates with profuse perspiration, as in colliquative diarrhœa. In Asiatic Cholera it occurs to an intense degree.

Fibrinous diarrhœa is very rare. The discharges in the form of shreds or tubular membranes, resemble those of croup, or of plastic bronchitis. In the treatment the astringent mineral salts are very serviceable.

Sympathetic diarrhœa.—In place of morning sickness, many women experience diarrhœa during the early months of pregnancy. It frequently occurs in children during teething; emotional excitement quickly induces it in persons of nervous temperament. It readily yields to small doses of opium.

From the foregoing it appears that there is no single treatment for diarrhœa. Before prescribing remedies we ought, from the previous history, or from the nature of the evacuations, to determine the precise cause.

CAUSES.—Cold applied to the surface; suppressed perspiration; mental emotions; pregnancy; teething; the heat of the summer and autumn seasons; indigestible food; unripe fruits, or ripe fruits in excess; putrid substances; the abuse of active purgatives; previous constipation; worms; retrocedent gout or rheumatism; phthisis; enteric fever. Diarrhœa is a frequent precursor of Asiatic cholera; and it occasionally adds to the distress of sea-sickness.

MELÆNA.—HÆMORRHAGE FROM THE BOWELS.

DEFINITION.—The discharge from the bowels of dark coloured, or more or less altered, blood, often in appearance resembling *coffee grounds, tar,* or blacking.

Causes.—Melæna is symptomatic of diseases of the liver, heart, and lungs, obstructing the general venous and portal circulations (see Hæmatemesis); of ulcer of the stomach, or duodenum; tubercular ulceration of the small intestine; enteric fever; dysentery; intussusception; or of rupture of an aneurismal sac into the bowel.

Diagnosis.—From *hæmorrhoids* by the darker colour and larger quantity of the blood, and by the absence of soreness and tenesmus.

Treatment.—That of the condition producing it. (See the several diseases above enumerated.)

TORPOR INTESTINORUM.—CONSTIPATION.

The causes of constipation are either structural or functional.

The *structural* causes either narrow the intestines or obliterate the passage. In the one case, purgative medicines act with difficulty; in the other case, action of the bowels is impossible.

Among the *functional* causes of constipation are the absence of stimulant matter from the diet, a deficiency of bile, want of proper exercise, spasmodic action, or paralysis of some part of the gut.

The *treatment* of constipation, due to alteration of function, will depend on the character of that alteration. If the food be deficient in indigestible or irritant matter, we must supply it by brown or whole meal bread, or ripe fruits; if the bile be wanting, we must stimulate the secretion of the liver by mercurial preparations in small doses; if the habits be sedentary, we must enjoin proper exercise. Where spasms exist, belladonna or henbane is very useful—a small dose of the extract every four hours.

Habitual constipation is best treated by rhubarb in powder or infusion (Form. 243). When the torpor of the bowels is still greater, and especially when there is a large accumulation of hardened fæces, purgative enemata are required (see Formulæ): aided by castor oil by the mouth.

A stream of cold water poured from a height on the abdomen has sometimes relieved obstinate constipation. Electricity is serviceable in some cases, one of the conductors being inserted within the rectum.

OBSTRUCTION OF THE BOWELS.

It sometimes happens that all our remedies fail to relieve the bowels. If, in such a case, there be tenderness in any particular part of the abdomen, accompanied by vomiting, we may be sure that there is obstruction, more or less complete, to the passage of of fæcal matter, and it becomes a matter of the most urgent necessity to ascertain the cause and situation of the obstruction. The causes are:—

1. Strangulation or incarceration of a portion of intestine; a small knuckle of intestine may, after careful examination, be found

at the femoral opening, or in the scrotum or labium, and no other symptom of hernia but constipation be present. The strangulation may be internal, and caused either by intussusception (see below), or by the entanglement of a portion of intestine in a band of the mesentery or in some old adhesion.

2. Fæcal accumulations, forming large, hard, dry masses, filling up the cells of the colon, are liable to form around biliary calculi, cherry and plum stones, and other foreign bodies. These accumulations feel like hard, irregular tumours, and may be mistaken for adventitious growths. Fæcal accumulations are very apt to form in the cæcum, where they often set up violent inflammation, with symptoms of complete obstruction. If the inflammatory symptoms be not subdued, perforation and pelvic abscess may result. The inflamed cæcum sometimes becomes adherent to the anterior abdominal wall, an abscess forms and points, and at length pus and fæcal matter discharge themselves through an opening communicating with the interior of the intestine.

3. Cancerous growths, chiefly of the rectum; and cicatrized ulcers of the bowel, are other causes of obstruction.

Treatment.—Reduce the hernia, and give a copious clyster of gruel. If the strangulation be internal, and the symptoms urgent, a careful diagnosis of the exact seat of strangulation should be made; the abdomen should be opened without delay, and the bowel disengaged. If the obstruction be due to accumulation in the cæcum and large intestines, copious castor oil or soap enemata should be thrown up, and hot fomentations simultaneously applied to the abdomen. If there be symptoms of inflammation, leeches must be freely applied over the inflamed part. The vomiting may be allayed by iced soda-water, and the pain by large doses of opium. When the scybala reach the rectum, it may be necessary to assist their discharge by a forceps or scoop. In cases of unrelieved obstruction, perforation is liable to occur.

It is important to distinguish simple constipation from the mechanical obstructions of the bowels mentioned above. (See Colic, p. 512.)

The symptoms and treatment of Perforation of the Intestines are the same as those of perforation of the stomach. (See p. 501.)

INTUSSUSCEPTIO.—INVAGINATION.

Symptoms.—As a consequence of the action of strong purgatives, or after severe colic, a constant desire to go to stool, acute pain and tenesmus, discharge of blood, or of scanty bloody mucus, and the symptoms of enteritis. The existence of the disease becomes more probable after the failure of attempts to evacuate the bowels, and the supervention of hiccough and stercoraceous vomiting afford a strong probability of mechanical obstruction and a presumption in favour of this form of it.

Morbid Anatomy.—One portion (from a few lines to more than a foot in length) of the intestines received within another. In most cases there is only one of these invaginations, but in some instances there are several. The most common seat of the obstruction is the junction of the small and large intestines; but it may take place in any part of the small intestines, and in the arch of the colon. A natural cure is sometimes effected by adhesion, suppuration, gangrene, and separation of the enclosed gut, the presence of which may be looked for in the stools.

Diagnosis.—Sudden obstruction of the bowels, followed by a perceptible tumour in the abdomen, and the passage of blood, would give reason to suspect the existence of this disease. The discovery of a portion of the intestinal tube in the stool is conclusive.

Prognosis.—Very unfavourable. In a few cases recovery takes place after sloughing of the constricted portion of intestine.

Treatment.—I. If there be marked tenderness in any part of the abdomen, leeches must be applied to the spot, followed by warm poultices, or hot fomentations.

II. The distressing vomiting is best relieved by iced soda-water. Solid opium, or its tincture, should also be given at short intervals, so as to moderate the pain and control the disordered peristaltic action.

III. To relieve the obstruction, a large quantity of warm water should be thrown up into the bowel by the long elastic tube; if this fail, air may be injected. After the failure of these attempts, the sac of the peritoneum may be opened, and the intestine unravelled.

COLICA.—COLIC.

Definition.—Painful contraction and disordered peristaltic action from the presence of hard fæces or air, in the intestines.

Symptoms.—Severe twisting pain in the abdomen, occurring in paroxysms, with retraction of the umbilicus and troublesome flatulence. The pain is relieved by pressure; the pulse is little, if at all, affected.

Causes.—The presence of undigested hard substances, such as unripe fruit and uncooked vegetables in the intestines; hardened fæces (scybala), or other accumulations; flatulent distension; obstruction of some part of the intestinal canal from impacted fæces; stricture or strangulation; worms; certain metallic poisons; *e.g.*, lead.

Diagnosis.—From *peritonitis*, by the peculiar twisting pain and retraction of the navel; by the absence of fever; and by the pain being alleviated by pressure.

Rheumatism of the abdominal muscles is distinguished at page 352.

Treatment.—Having ascertained that there is no concomitant inflammation, and no mechanical obstruction, and that the pain is not merely muscular—the bowels should be freely relieved by a full dose of castor oil with ♏x to ♏xv of tincture of opium.

If the colic be due merely to flatulent distension give ʒj spiritûs chloroformi with ℥ss tincturæ rhei co. and ♏x tincturæ opii.

If there be symptoms of obstruction, we must avoid active purgatives, and trust to enemata. A large clyster of thin gruel containing ♏xx of tincture of opium may be thrown into the bowel. Should the bowels continue unrelieved, and there are still no symptoms of inflammation, the patient should be kept under the influence of opium till a free evacuation takes place. Meanwhile, the pain may be relieved by applying flannels wrung out of hot water or poppy fomentation; or by steady pressure.

It is not unusual in cases of colic to find, on inquiry, that one of the first symptoms was the discharge of a quantity of gelatinous mucus from the bowels. In such cases there is commonly more or less tenderness in some part of the abdomen, especially in the right iliac fossa, and from six to twelve leeches, followed by a warm bread-and-water poultice, should be applied to the tender spot. (G.)

Flatulence may be relieved by the introduction of the long flexible tube, which may also be used to convey warm water into the gut.

In spite of the persevering employment of these means, six or seven days will sometimes elapse before the bowels are relieved. Patients commonly evince undue anxiety to obtain this relief, and aggravate the difficulty by the repetition of strong purgatives.

COLICA PICTONUM.—LEAD COLIC.

Synonyms.—Colic of Poitou. Painters' colic. Devonshire colic.

Symptoms.—Those of colic from other causes, the pain generally coming on more gradually, and being often accompanied with pains in the limbs, or with weakness, or complete paralysis of the hands or forearms. The abdomen is generally retracted.

Diagnosis.—From common colic, by the history of the case and the employment of the patient; and generally by the blue line along the margin of the gums indicating the presence of lead in the system.

Prognosis.—Favourable. Five fatal cases in 500. (Andral.)

Treatment.—Sulphated aperients (Form. 244); enemata of warm water; hot fomentations or the warm bath. When the urgent symptoms have been relieved, iodide of potassium.

Prophylaxis. (See Lead Palsy, p. 397.)

TYMPANITES.—METEORISMUS.—DRUM BELLY.

Symptoms.—The abdomen distended, tense, elastic, and painful, and sounding, on percussion, like a drum. The air is, in almost all cases, contained in the stomach and intestines, its most common seat being the arch and sigmoid flexure of the colon. In very rare instances air passes into the sac of the peritoneum, in consequence of ulceration of the bowels. Tympanites is a painful symptom in severe cases of enteric fever, and in the latter stages of peritonitis.

Causes.—Loss of tone in the intestinal canal; indigestible food: abuse of purgatives; hysteria.

Diagnosis.—From *ascites*, by the clear sound and absence of fluctuation.

Treatment.—In mild cases of flatulent distension of the bowels, the remedies usually resorted to are the peppermint lozenge, essence of ginger with hot water, or brandy and water swallowed as hot as it can be borne. In severe cases large doses of opium with ʒj of spirit of chloroform, or iii–v drops of cajaput oil may be necessary. Stimulant enemata (Form. 64) often give great relief. If the distension be very great, it may often be relieved by the passage of a long wide elastic tube into the bowel. If this be ineffectual, and the movements of the diaphragm be dangerously impeded, the imprisoned air should be liberated by a capillary trocar thrust into the distended bowel.

The use of food known to occasion flatulence should be carefully avoided.

HÆMORRHOIDES.—THE PILES.

1. External Piles.

Definition.—Small round tumours, situated at the verge of the anus, and covered with skin or mucous membrane, or painful folds of integument. The tumours either discharge blood, when they are called *bleeding piles*, or they do not bleed, when they are called *blind piles*. When free from pain they are called *indolent*.

Symptoms.—When piles are in an inflamed state they occasion heat, itching, and pain, with a sense of weight and tension, increased upon going to stool, which generally occasions a discharge of blood. The inflammation sometimes runs on to suppuration. In mild cases piles appear and disappear, and are often absent for long periods of time.

2. Internal Piles.

Symptoms.—A sensation as of a foreign body in the rectum, with frequent desire to relieve the bowels, and painful strainings, accompanied by discharges of blood. In the more severe cases, dysuria, pain in the back and down the thighs, and, in females, uterine irritation.

Causes.—Luxurious and sedentary habits; habitual costiveness; phlethora; hard riding; excesses of various kinds; the suppression of some habitual discharge; the frequent use of strong aloetic purgatives; varicose condition of the hæmorrhoidal veins; pregnancy.

Prognosis.—The discharge of blood by piles is often salutary, especially in persons advanced in life, and their suppression may be followed by more serious hæmorrhage, such as apoplexy.

Treatment.—I. *General.* II. *Local.*

I. The circulation of blood through the abdominal vessels must be promoted, and the regular action of the bowels maintained by active exercise, abstemious living, and suitable aperients (Form. 239 and 242), confections of senna, pepper, and of sulphur, compound liquorice powder.

II. The *local* treatment consists in the strict observance of cleanliness, washing with cold water after each motion, and the careful return of the piles, if, being internal, they protrude during the evacuation of the bowels; in the use of astringent washes or ointments (such as the liq. plumbi subacetatis, or unguentum gallæ cum opio). When the piles are inflamed, the application of leeches, followed by cooling lotions.

Bleeding piles also require the use of cold astringent applications and injections. Daily injections of cold water are highly beneficial. When the hæmorrhage is profuse, astringents may be given internally. The best is the perchloride of iron. The hæmorrhage, when very profuse, must be treated by astringent injections of alum and tannic acid.

Piles strangulated by the spasm of the sphincter, must be compressed with the finger, and passed back; the operation being facilitated by the use of the warm bath and oil. A T-bandage may become necessary.

When the tumours become chronic they should be removed.

Prophylaxis.—Patients with piles should sit and ride as little as possible, pursue their avocations, if inactive or literary, in an erect posture, and use cane-seated or wooden chairs.

DISEASES OF THE STOMACH AND INTESTINES.

Gastro-Enteritis Mucosa . .	English Cholera.
Cholera Maligna	Asiatic Cholera.

GASTRO-ENTERITIS MUCOSA.—ENGLISH CHOLERA.

Symptoms.—Nausea, pain, and distension of the stomach and intestines, succeeded by vomiting, and by purging of bilious or fæculent matter, and, when this has been discharged, of mucus. The tongue is furred; the pulse frequent, small, and sometimes unequal; and there is much thirst. In rare cases death takes place within twenty-four hours, after hiccough, cold sweats, great anxiety, blueness of the surface, and painful cramps of the extremities.

Causes.—Excessive heat, or sudden transitions from heat to cold: the summer and autumnal seasons; indigestible food; unripe fruit, or an excessive quantity of ripe fruit; putrid meat; decayed vegetables; violent purgatives; irritant poisons; catarrh.

Diagnosis.—From enteritis by the co-existence of gastric symptoms. The disease in its most severe form is not distinguishable from Asiatic cholera.

Prognosis.—*Favourable.* Cessation of the vomiting, tendency to sleep, warmth and moisture of the skin. The disease, when protracted to the third or fourth day, seldom proves fatal.—*Unfavourable.* Painful cramps of the extremities; convulsions; great prostration; cold, clammy sweats; anxiety; short, hurried respiration; continual hiccough; intermitting pulse.

Treatment.—A farinaceous diet, and the entire exclusion of solid food. A scruple of the compound chalk and opium powder, or a mucilaginous mixture, with twenty drops of tincture of hyoscyamus, may be given three or four times a day. When there is great prostration of strength, full doses of opium, with stimulants, are indicated, with warmth to the surface, and mustard sinapisms to the extremities.

When the disease has subsided, the usual diet must be gradually resumed, and tonic medicines given if there be much debility.

CHOLERA MALIGNA.—ASIATIC CHOLERA.

Synonyms.—Cholera morbus; epidemic, spasmodic, Indian, Asiatic, blue, and pestilential cholera. Cholerine—a diminutive term. Cholera asphyxia—a term indicative of the state of collapse in fatal cases.

Definition.—An epidemic malady characterized by profuse vomiting and purging with symptoms of collapse allied to asphyxia.

Symptoms.—In a few cases (rarely seen out of India), the attack is sudden; the patient vomits once or twice, or passes one or two loose motions, complains of giddiness, blindness, or deafness, falls down, and expires in a few minutes. In another and larger class of cases the disease shows itself after two or three days of slight indisposition, with depression of spirits, loss of appetite, oppression at the præcordia, rumbling in the bowels, giddiness, noise in the ears, and twitchings in the limbs. In a still larger class the fully-formed disease sets in after a preliminary attack of diarrhœa of some hours' or days' continuance.

In the majority of cases, both in India and in England, the following is the order of the symptoms: after a preliminary attack of diarrhœa, of greater or less severity, and lasting for some hours or days, the patient is seized with symptoms of collapse, accompanied, in most cases, by vomiting. The acts of vomiting and purging are generally unattended by pain or tenderness in the abdomen; and the matters rejected from the stomach and bowels are free from bile and colourless, have a faint, fishy smell, and resemble yeast; or they consist of a thin colourless serum, or bear a close resemblance to rice water, being familiarly known as "*rice-water evacuations.*" Sometimes they have a pink colour, or the deeper hue of port wine. Severe and painful cramps commence in the fingers and toes, and rapidly extend to the calves of the legs, to the thighs, and muscles of the abdomen; the eyes are sunk, and surrounded by a dark circle; the features contracted and sharpened; the expression indifferent and apathetic; the face, extremities, and sometimes the whole surface of the body, assume a leaden, bluish, or purple hue; the limbs are shrunken and contracted; the nails blue; the hands clammy and sodden; the surface covered with a profuse cold sweat; the pulse thready or imperceptible at the wrist, arm, axilla, temple, and neck; and if a vein or artery be opened, the blood trickles away, thick and dark. In spite of the extreme coldness of the surface, the patient complains of heat, throws off the bedclothes, and suffers from great restlessness and incessant jactitation, complains of a burning heat in the epigastrium, and is tormented with thirst; the respirations are below the number in health, the inspiration difficult, and the expiration short and convulsive; the voice is plaintive, the patient speaking in a hoarse whisper; the breath feels cold; the tongue is white or of a leaden colour, cold and flabby; the temperature often as low as 79° or 77° and even 72°. The secretion of urine is partially or entirely suppressed, and the body exhales an earthy or cadaverous odour. In this state of collapse the disease often proves fatal, the patient dying without a struggle, and retaining his faculties to the last. In other cases he gradually rallies, the pulse rises, the blueness of the surface disappears, the body resumes its warmth, the cramps and vomiting cease, bile appears in the motions, the secretion of urine is restored, and a rapid and complete recovery takes place. But in a third class of cases the improvement is partial and temporary, and the patient falls into the typhous condition, from which he may possibly recover after several days.

TERMINATIONS.—In sudden death; in death after severe primary or secondary symptoms; in recovery; in prolonged gastric irritation; in secondary fever of the typhous character, often accompanied by a rash resembling urticaria febrilis.

PATHOLOGY and MORBID ANATOMY.—The disease appears to consist in a sudden rejection of the fluid parts of the blood through the mucous membrane of the alimentary canal; the intestines are *filled with* a white flaky liquid; the mucous membrane is swollen, and greatly congested in patches; all the glands of the intestines are large and prominent; the veins and arteries loaded with dark blood; the lungs congested in some cases, extremely contracted in others; the liver and gall-bladder gorged with bile; the kidneys congested; the urinary bladder contracted and empty. In patients who survive the stage of collapse, and die after the secondary fever, the morbid appearances are those present in enteric fever.

DURATION.—In fatal cases, from a few minutes to twelve hours or more. More than half the fatal cases die within twenty-four, and nearly a sixth within six, hours. The average duration is about two days. The duration of the cold stage varies from a few minutes to forty-eight hours or more, while that of the febrile stage may extend from four to ten days or more.

MORTALITY.—At the onset of the epidemic nine-tenths of the cases; on the average about one-half; at the decline a small fraction. Deaths from cholera in England and Wales, in 1831–32, 30,924; in 1848–49, 54,398; in 1853–54, 24,516. Deaths in London, in a million of inhabitants, 6209 in 1849, and 4269 in 1854.

CAUSES.—*Predisposing.* Debility; impaired health; intemperance; impure air; impure water; low and damp situations; the summer and autumn seasons.—*Exciting.* A peculiar poison contained in water arising from the decomposition of animal matter.

DIAGNOSIS.—From *English cholera*, by the greater severity of the symptoms; the complete suppression of urine, the intense blueness of the surface, the hoarse, feeble voice, and the shrunken appearance of the countenance. But these marks will not serve to distinguish the disease from the more severe cases of English cholera. The premonitory diarrhœa of cholera is distinguished from ordinary diarrhœa by the absence of pain.

PROGNOSIS.—*Favourable* in the early stage before collapse has set in, and in the secondary stage when the febrile symptoms are slight; *unfavourable* during the stage of collapse, and in the secondary fever when it assumes the typhous character.—*Favourable Symptoms.* Cessation of cramp; subsidence of vomiting and purging, and the reappearance of bile in the motions; voiding of urine; return of the pulse; restoration of heat in the extremities and surface of the body; disappearance of the blueness of the skin and of the facies Hippocratica.—*Unfavourable Symptoms.* Extreme collapse; absence or cessation of vomiting and purging in the stage of collapse; deafness; the evacuations of the colour of port wine. Advanced age, previous debility, ill health, or habits of intemperance. The disease is somewhat more fatal in females than in males.

TREATMENT.—I. Of the preliminary diarrhœa. II. Of the stage of collapse. III. Of the stage of reaction.

I. The preliminary diarrhœa requires the treatment of common diarrhœa. A scruple of the compound chalk and opium powder may be given three or four times a day, the diet being at the same time restricted to gruel or arrowroot, made with milk. In more severe cases, grain-doses of opium, in combination with ½ grain of sulphate of copper, may be given every hour, or every two or three hours. When the patient is weak and exhausted, brandy may be administered from time to time. In epidemics of Asiatic cholera, patients suffering from diarrhœa should be promptly treated and carefully watched.

II. The stage of collapse is best treated by large draughts of cold water, or water holding a little chlorate of potash in solution. The most hopeful means of restoring the circulation and of contracting the intestinal vessels, is the hypodermic injection of the $\frac{1}{50}$ of a grain of atropia at intervals of an hour. At the same time reaction should be promoted by warm blankets, bottles of hot water to the feet and epigastrium, and assiduous friction. The patient may be allowed to drink freely of warm brandy and water. The cramps may be relieved by rubbing, and the forcible extension of the parts affected.

III. Reaction having been established, the treatment may be guided by the symptoms actually present. The thirst may be assuaged by large draughts of water; diarrhœa, if it exist, may be met with opium in doses of one grain, repeated at short intervals, or by a strong decoction of logwood in combination with laudanum and aromatic spirit of ammonia; and the warmth of the skin may be kept up by frictions and warm applications. In the absence of diarrhœa, the bowels should be relieved by occasional doses of castor oil.

If the reaction be excessive, and assume the form of fever, the case must be treated as one of enteric fever; and if it assumes the typhous type, by the remedies appropriate to that condition.

Prophylaxis.—Temperate habits; wholesome diet; and *pure boiled and filtered water;* moderate use of wholesome vegetables and ripe fruits; the early treatment of diarrhœa. Those who are able to do so, should remove from low-lying districts to high grounds. On the approach of cholera, the authorities should provide a supply of water of ascertained purity, and prevent access to pumps and sources liable to contamination. They should organize means for the treatment of diarrhœa, and also adopt measures for insuring personal and household cleanliness; for the early removal of all refuse matters; and for the suppression of nuisances. Armies attacked by cholera in low situations should be encamped on high ground, and draw their supply of water from pure springs or rivulets.

Remedies.—Castor oil in the dose of a tablespoonful repeated at short intervals, so as "to produce vomiting and purging sufficient to insure, from time to time, the evacuation of the stomach and intestines, and to prevent the accumulation of morbid secretions" as practised by Dr. George Johnson. Saline medicines. Injections *of warm water* or of warm saline solutions (sodii chloridii, ʒss., sodæ bicarb., ℥iss aquæ callidæ Ox.) into the veins (a mode of treatment followed by the most prompt and marked relief of all the symptoms, but not to be commended as curing cholera); transfusion of blood; calomel, in scruple or half-drachm doses every hour; cajeput oil; galvanism; large doses of opiates; camphor; acetate of lead in combination with opium. A drachm of laudanum and a scruple of calomel administered at the onset, and repeated at a short interval, if necessary; chloroform; chloroform and brandy; quinine in large doses; Indian hemp.

DISEASES OF THE PERITONEUM.

Peritonitis . . .	Inflammation of the Peritoneum.
Ascites	Dropsy of the Belly.

PERITONITIS.—INFLAMMATION OF THE PERITONEUM.

Varieties.—1. Simple. 2. Tubercular.

1. Simple Peritonitis.

Symptoms.—After rigors, but, in some cases, without any preliminary symptoms, pain commencing in any part of the abdomen, and soon extending over the whole, increased by pressure, and often so acute that even the weight of the bedclothes is intolerable. The skin of the abdomen is hot; the pulse is in general small, hard, and contracted, though sometimes full and soft; the countenance is expressive of great suffering; the patient lies on the back with the thighs flexed on the abdomen; the bowels are constipated; the urine scanty and high coloured, and perhaps passed with pain; the tongue is white and covered with mucus, and soon becomes dry and brown; the breathing is thoracic, short, each inspiration causing an increase of pain. The disease often terminates fatally within twenty-four or forty-eight hours by great prostration, death being preceded by sudden cessation of pain, sharpened countenance, distension of the abdomen by liquid or gas, vomiting of a coffee-coloured fluid, cold extremities, and torpor.

Morbid Appearances.—Injection of the vessels of the peritoneum; coagulable lymph spread over the surface, or flakes of lymph floating in serum or pus; the folds of the intestines adherent by coagulable lymph to each other and to the contiguous viscera. In chronic cases the adhesions are organized, binding the intestines so firmly together as to greatly hinder peristaltic movement.

Causes.—Cold and fatigue; constipation; contusions; wounds, surgical operations; parturition; rupture of any of the abdominal viscera.

Prognosis.—*Favourable*, in peritonitis from common and transient causes.—*Unfavourable*, in that produced by mechanical injury, organic disease, parturition, or rupture of the abdominal viscera.

Diagnosis.—From *rheumatism* or *neuralgic pains* of the abdominal muscles, by the pain being increased by pressure, and by the presence of *severe* constitutional symptoms. From colic, by the character of the pain. (See p. 512.) In colic the patient writhes about and changes his position. In peritonitis even the abdominal respiratory movements are avoided. From ovarian inflammation (see Oophoritis). From hysterical tenderness and pain, by the severe constitutional symptoms. The disease, in its early stage, may be distinguished by a feeling of crepitation under the hand, and a *to-and-fro* sound on applying the stethoscope while the abdominal parietes are in motion, in the act of respiration.

Treatment.—In recent and acute cases bleeding from the arm, followed by leeches and warm fomentations, and the internal use of tartar emetic with calomel and opium in full doses, and at short intervals, so as speedily to affect the system. In very severe cases, mercurial inunction may be added. If the stomach be irritable, the tartar-emetic must be omitted. In less severe cases, leeches to the abdomen, followed by warm fomentations, and calomel and opium internally.

The large intestines may be relieved by enemata of warm water or warm gruel.

If there be painful tympanites, turpentine enemata are required, or the long elastic tube may be introduced so as to allow the accumulated gas to escape.

When effusion has taken place, and the febrile symptoms have abated, the treatment will be that of ascites.

Chronic peritonitis must be treated by the repeated application of leeches, blisters, and stimulant embrocations to the abdomen. If the intestines become adherent from organization of the plastic lymph thrown out around them, such food only should be taken as is readily absorbed. The resulting constipation must be treated by enemata and very mild laxatives, such as castor oil and confection of senna.

2. Tubercular Peritonitis.

Symptoms.—These come on very insidiously. The abdomen slowly enlarges until it at last attracts the notice of the patient; and when he first comes under treatment, ascites to a considerable extent is present. The general health now begins to fail; emaciation, sweating, and diarrhœa, alternating with constipation, set in; the abdomen becomes tense, painful, and tender (the pain is at first deep seated); hectic, and gastro-intestinal irritation, resulting in vomiting and more severe diarrhœa, sooner or later supervene, the food is rejected, and the patient dies of asthenia. Sometimes the mesenteric glands and the folds of the mesentery are the chief seat of the tubercular deposit, and hard nodular tumours may be felt *through the abdominal walls*; and the chief, and it may be, the only other symptoms present, are emaciation and swelling of the belly. This variety of the disease is called *Tubercular mesenteritis* and *Tabes mesenterica.* It is only in the latter stages of this variety that ascites becomes a prominent symptom. When the tubercular matter is deposited simultaneously in the mesenteric and intestinal glands and upon the general peritoneal surface, the emaciation is very rapid, and the pallor of surface extreme.

Morbid Anatomy.—If the disease kill speedily, the peritoneal cavity will be found distended with clear serum, and the peritoneal covering of the intestines uniformly granular with miliary tubercles the size of hemp seeds. The mesenteric glands are more or less enlarged and hardened. In the more chronic form the mesenteric glands are greatly enlarged, forming hard nodular matted masses. When opened the centres of many will be found softened. When persistent and intractable diarrhœa has been a prominent symptom, we may expect to find tubercular ulceration of Peyer's glands. (See p. 505.)

Diagnosis.—From ascites, caused by hepatic disease, by the absence of jaundice and hepatic enlargement or inequality. From enteric fever (see p. 298). The disease is often accompanied, sooner or later, by symptoms of pulmonary phthisis.

Treatment.—Iodide of iron alone or combined with cod-liver oil. Alternate infrictions of cod-liver oil and iodine unguents into the abdomen. Chalybeate tonics. The gastro-intestinal symptoms must be treated as directed under Phthisis and Partial Enteritis.

ASCITES.—DROPSY OF THE BELLY.

Symptoms.—A progressive and uniform enlargement of the abdomen, accompanied, when the quantity of fluid is large, by tension of the parietes; dulness on percussion over the whole abdomen, when the fluid is abundant; and when small, over the part to which the position of the patient causes it to subside, the rest of the abdomen being tympanitic; and a sense of fluctuation becoming more distinct as the quantity of fluid increases.

The general symptoms of ascites are due to pressure of the accumulated fluids, and when it is merely a symptom of some other disease, to the particular disease present. The symptoms arising from pressure are difficulty of breathing; suffusion of the countenance, and injection of the eyes; and distension of the superficial veins of the abdomen. Thirst, a dry skin, scanty urine, and torpid bowels, are among the most common accompaniments of ascites.

The disease seldom continues long without inducing, or being accompanied by, an anasarcous state of the lower extremities.

Causes.—The general causes of dropsy (see p. 268). Disease of any organ obstructing the portal circulation, and especially obstructive diseases of the liver, cirrhosis in particular; cancerous [illegible] of the pancreas, involving the portal vein, is an occasional cause. Diseases of the spleen and mesenteric glands; of the heart, lungs, and kidney; scarlatina; loss of tone in the peritoneum after pregnancy; chronic or sub-acute inflammation of the peritoneum; and local injury.

Diagnosis.—From *ovarian dropsy,* by the uniform enlargement and greater width of the abdomen, which sways from side to side according to the position of the patient. From *tympanites,* by the dulness on percussion over the seat of fluid, or over the greater part of the abdomen. When the intestines are distended with air they float on the surface of the fluid, giving a tympanitic resonance to the upper parts of the abdomen. The pregnant uterus forms a defined rounded tumour, which contracts under the hand; moreover, we may feel the fœtal movements, and hear the pulsations of the fœtal heart. A distended bladder causes a uniform pyriform enlargement above the pubes, and is associated with constant dribbling of urine.

Prognosis.—*Favourable.* The ascertained absence of organic disease of the viscera of the chest and abdomen. The urine healthy, in quality and quantity, and not coagulating by heat; moist skin; the swelling of the abdomen diminishing; the respiration becoming free; the strength little impaired.—*Unfavourable.* Organic disease of the viscera of the chest and abdomen, especially of the liver; great emaciation; sympathetic fever; coma; an impaired constitution.

Treatment.—If pain and tenderness exist, leeches to the abdomen, followed by mercury so as to affect the mouth. If both are absent, the treatment must vary with the disease, of which the ascites is the effect. If disease of the liver, heart, lungs, or kidney be present, the remedies appropriate to that disease. The remedies for the dropsy itself, irrespective of the causes which may have produced it, are diuretics, and drastic purgatives, unless contra-indicated. The choice of diuretics must be partly determined by the cause of the dropsy, and partly by the existing state of the patient.

If, after a fair trial, these remedies are unavailing, and the pressure becomes insupportable, recourse must be had to tapping.

Ascites is often combined with anasarca.

DISEASES OF THE LIVER.

Congestio	Congestion of the Liver.
Hepatitis	Inflammation of the Liver.
Abscess	Of the Liver.
Acute Atrophy . . .	Of the Liver.
Biliary Concretions, or	Gall Stones.
Icterus	Jaundice.
Other Diseases . . .	Of the Liver.

CONGESTION OF THE LIVER.

VARIETIES.—1. Sanguineous. 2. Biliary.

1. SANGUINEOUS CONGESTION.

SYMPTOMS.—A sense of fulness and weight in the right hypochondrium, rarely amounting to dull pain; enlargement of the liver, so that the lower edge can be felt two or three fingers' breadth below the margin of the ribs; sallowness of the complexion, with sometimes distinct yellowness of the conjunctiva. In severe congestion, complete jaundice; anorexia; tongue coated with a white fur; bowels torpid.

Fig. 79.



Fig. 80.*



Fig. 81.



MORBID ANATOMY.—Increase in the size and weight of the liver, which is dark-coloured and gorged with blood. If the congestion affect the hepatic and portal veins unequally, the liver has a distinct mottled appearance. When the congestion affects only the hepatic vein, the lobules have a light border (C) and a dark centre (A); the congestion is chiefly intralobular (Fig. 79). When the portal vein is alone congested, the outer portions of the lobules are darker than their centres, and the congestion is said to be interlobular (Fig. 81).

CAUSES.—Diseases of the heart and lungs, and tumours within the chest, obstructing the thoracic circulation; functional derangement of the liver itself, with diminished activity of the secreting function; intermittent fever; purpura; impurity of the blood from improper diet and excess of alcoholic fluids.

---

* Fig. 80 illustrates a diffuse form of intralobular congestion spreading from lobule to lobule.

Treatment.—When due to heart or lung disease, the same treatment must be adopted as for congestion of the stomach arising from the same causes. In all other cases, gr. v pilulæ hydrargyri, or gr. iv calomelanos, followed, after twelve hours, by a brisk saline purgative, should be prescribed, and a light farinaceous diet, and abstinence from fermented or spirituous liquors enjoined.

2. Biliary Congestion.

Symptoms.—"A bilious attack," viz., vomiting and purging of matters highly charged with bile, usually preceded by constipation, and accompanied by pain in the hepatic region, some enlargement of the liver, and a biliary tinge of the conjunctiva.

Causes.—Biliary congestion is the effect of excessive functional activity of the liver, from overfeeding or indolent habits, or a combination of the two. The functions of the liver and lungs are to a considerable extent vicarious. The digestion and assimilation of animal food implies the separation of a large quantity of hydrocarbon from the blood. If the respiratory function be sufficiently active, this is consumed in the lungs, and excreted as carbonic acid and water; but if, as in tropical climates, the respiratory function be insufficient, the hydro-carbon is separated by the liver as fatty acids of the bile. This secretion becomes immoderate, the liver is congested with it, and occasional relief is afforded by bilious diarrhœa. This result happens both to those natives of cold climates who, when resident in or near the tropics, do not adapt their diet to the altered conditions of their life, and to those who, in any climate, feed heartily and take little exercise.

Biliary congestion is of course an immediate consequence of closure or obstruction of the common bile duct.

Treatment.—After a dose of calomel or blue pill, free saline purgation; abstinence from fermented and spirituous liquors; and plain diet, consisting chiefly of farinaceous substances.

HEPATITIS.—INFLAMMATION OF THE LIVER.

1. Acute Hepatitis.

Symptoms.—Pain in the right hypochondrium, increased by pressure, by deep inspiration, by coughing, or by lying on the left side; dry cough; difficulty of breathing; shooting pains in the chest resembling pleurisy; sympathetic pain in the right shoulder; yellow tinge of the conjunctiva, and sometimes actual jaundice; high coloured urine; vomiting; hiccough; rigidity of the right rectus muscle; costiveness or diarrhœa. There is also more or less pyrexia. In some cases the fæces are of a clay colour, owing to a deficiency of bile: in others, the bile is in excess, and is rejected by vomiting and stool.

When the *concave* surface is affected, the pain is more obscure, and is referred to the back: the breathing is less affected; but the functions of the stomach are more disturbed. The same disturbance takes place when the left lobe adjacent to the stomach is inflamed; and when the posterior and inferior portion of the organ is implicated, there is more or less pain and disturbance of function in the kidney.

TERMINATIONS.—In resolution; in diffused or circumscribed abscess; in gangrene; in chronic disease.

CAUSES.—All the common causes of inflammation; external injury; intemperance; protracted biliary congestion; dysentery; pneumonia; phlebitis of the portal vein or its tributaries.

DIAGNOSIS.—From *pneumonia*, by the absence of the local signs of that disease; by the pain in the shoulder; by the local pain, increased by pressure; by the yellowness of the skin and conjunctiva; by the colour of the urine and fæces; and in many cases by the absence of cough and expectoration.

From *gastritis*, by the seat of the tenderness, and by the colour of the eye and skin, of the urine and fæces.

PROGNOSIS.—*Favourable*. About the third, fifth, or seventh day, bilious diarrhœa; universal free perspiration; hæmorrhage from the hæmorrhoidal veins; an abatement of fever.—*Unfavourable*. Intense pain and fever; the pain confined to a point; continual hiccough; cold extremities; obstinate constipation; rigors and hectic fever, indicating the formation of abscess.

TREATMENT.—Local depletion by cupping or leeches; or, when the hæmorrhoidal or catamenial evacuations are suppressed, the abstraction of blood from the anus; blisters over the seat of the pain; brisk saline aperients; saline and antimonial diaphoretics; mercurial inunction; especially during the inflammatory stage of the disease; a low diet, consisting chiefly of farinaceous food.

2. CHRONIC HEPATITIS.—CIRRHOSIS.

SYNONYMS.—Hepatitis chronica, diffusa, adhesiva; interstitial hepatitis; hob-nailed liver; gin-drinkers' liver; chronic atrophy.

SYMPTOMS.—The early symptoms are very obscure. There is a sense of weight with obtuse pain in the region of the liver, increased by deep pressure or by lying on the left side, with enlargement and preternatural hardness of the organ, obvious to the touch. During the progress of the disease, symptoms of more acute hepatitis, and sometimes jaundice, are occasionally present. There is a sense of fulness and distension of the stomach, with flatulence, and loss of appetite. The countenance is sallow, and the skin harsh and dry: the patient is torpid, inactive, desponding, [illegible] grows thin; the bowels are obstinately costive; the stools deficient in bile; and the abdomen enlarges imperceptibly at first, and well-marked ascites is usually present when the attention of the physician is first called to the case. The ascites increases; the legs become œdematous; the veins of the abdomen are prominent; the urine is scanty, and deposits lithates, but rarely or never contains albumin. Symptoms of congestion of the alimentary canal appear:—the tongue is furred, there is much thirst, and hæmorrhage from the bowels or stomach is very liable to occur. The blood becomes much impoverished, and slight wounds bleed profusely; minute capillary aneurisms occasionally form in the skin, burst, and bleed freely. Under careful treatment the patient may improve for a time, but sooner or later the digestion fails, he becomes anæmic, weak, and emaciated, the liver shrinks, the dropsy increases, a copious hæmorrhage from the bowels, or profuse diarrhœa, causes great debility, and ultimately the patient dies exhausted.

PATHOLOGY.—Diffuse inflammation of the connective tissue of the portal canals and interlobular spaces, with effusion of the solid products. These subsequently undergo organization and contraction, and form a dense fibrous network of new connective tissue throughout the liver. The contraction of the new material causes obliteration of the smaller branches of the portal vein and bile ducts, resulting in atrophy of the lobules. Great obstruction of the portal circulation thus gradually results, ending in the most irremediable form of ascites and anasarca.

MORBID ANATOMY.—The liver reduced in size, of a light yellow colour like bees'-wax, presents a coarse tubercular appearance, its surface being studded over with rounded elevations of various sizes, projecting from the interior. Capsule thickened and opaque; tissue harder than normal, sometimes cutting like gristle; the cut surface presents intersecting lines of opaque connective tissue, forming a coarse network in which the yellow nodular masses are contained. The walls of the portal vein are thickened, surrounded by condensed connective tissue, and their calibre is much diminished. The gall-bladder is collapsed, and contains a little transparent golden yellow or light ochre-coloured grumous fluid. On minute examination, a large portion of the hepatic cells are found to be destroyed, and their places occupied by masses of light-yellow pigment, scattered through a network of newly-formed connective tissue. In other places the cells are shrunken, and are in a state of fatty degeneration. The capillaries of the lobules are degenerated, and their place supplied by a few narrow vessels which serve to convey the blood into the radicles of the hepatic vein. The bile ducts are atrophied, and many of the smaller branches, as well as most of the tubular network within the lobules, obliterated. Great enlargement of the spleen, and congestion of the portal system.

CAUSES.—The acute form; the abuse of ardent spirits; the disease is very common amongst cabmen, who drink much neat spirits.

DIAGNOSIS.—Sallowness of the skin, never amounting to jaun-

[illegible] tongue, and thirst, preceded or accompanied by a [illegible] tenderness in the right hypochondrium, coming on after [illegible] is strong presumptive evidence of cirrhosis. If [illegible] occur in a person who has indulged [illegible] the case is quite clear. In *tubercular peritonitis* there is diffused pain and tenderness over the whole of the belly, and the sallow look of cirrhosis is absent; the ascites moreover is not so great as in cirrhosis, and the fluctuation is less distinct, because the fluid is retained in pouches formed by the adherent intestines. In *cancer* of the liver the ascites is never very great, the [illegible] uneven enlargement, and there is the characteristic cachexia, emaciation, and eventually jaundice. The [illegible] enlargement, known as the "hobnail liver," may be perceived through the parietes, and distinguished from the [illegible] caused by a collection of *hydatids*, and from the smooth round tumour near the margin of the liver caused by a *distended gall bladder*.

PROGNOSIS.—Extremely unfavourable.

TREATMENT.—I. In the early stage leeches to the region of the liver as often as it is tender [illegible] and mercurial preparations [illegible] often repeated, with mercurial inunction, so as slightly to affect the gums.

II. The portal [illegible] may be relieved by saline aperients, given every morning so as to keep the bowels loose. When the intestinal canal is healthy, drastic purgatives are often more effective than any other remedies. If the digestive powers are much impaired, a course of bitter tonics, such as the infusion of gentian, quassia, or calumba, with soda, or some preparation of steel, if the patient be anæmic. The nitric or nitro-muriatic acid internally (Form. 122) or as a bath (Form. 39). Partial tapping is never followed by permanent improvement; and if the whole of the fluid be withdrawn, there is danger of fatal exhaustion. Still, when the action of the diaphragm is impeded, we are bound to have recourse to tapping, and some patients bear a frequent repetition of the operation.

ABSCESS OF THE LIVER.

SYMPTOMS.—If in a case of hepatitis severe rigors occur, followed by well-marked hectic fever, and the previous continued pain, whether dull or acute, be exchanged for distinct throbbing, there is reason to believe that suppuration has taken place. Rigidity of the right rectus muscle usually accompanies abscess of the liver.

The abscess may burst into the stomach, and be emptied by vomiting into the colon or duodenum, and be evacuated by the bowels; through the diaphragm into the cavity of the chest, giving rise to empyema; into the lung or bronchial tube, and be expectorated; or, it may open externally, between the ribs, or below them through the muscles of the abdomen or back. In very rare cases, the abscess discharges itself into the pericardium, into the pelvis of the kidney, into the ascending vena cava, or into the cavity of the abdomen.

Causes.—*Predisposing*. Those of the inflammation of the liver which precedes it.—*Exciting*. Phlebitis (leading to purulent deposits in the liver and lungs). Dysentery. Operations on the rectum, bladder, or vagina. Ulceration of the stomach and intestines. Animal parasites.—Echinococcus, Distomum, and Bilharzia.

Complications.—Ascites. Inflammation of the organs contiguous to the abscess, and through which it ultimately discharges itself.

Diagnosis.—The nature of the disease will be inferred from the colour of the discharged matter, and from the rigors, throbbing pain, and hectic fever attending the process of suppuration.

Prognosis.—This will depend, in great measure, on the direction in which the abscess discharges itself, and on the degree of inflammation which follows. The prognosis is most favourable when the opening is in the parietes of the chest or abdomen. It is extremely unfavourable when the abscess bursts into the peritoneum. If it become encysted, the health may remain unimpaired for years.

Treatment.—If the abscess point externally, it must be brought forward by poultices and fomentations, and the matter must be discharged by a trocar and canula. Such an operation should not be performed unless we have reason to infer that there is adhesion between the sac of the abscess and the abdominal wall. A generous diet, and tonics, especially quinine and the mineral acids, must be prescribed.

HEPATITIS DIFFUSA.—YELLOW OR ACUTE ATROPHY.

Definition.—Acute disease of the liver, probably of an inflammatory nature, leading to total suppression of bile and degeneration of the secreting structure.

Symptoms.—For a variable period of a week or more before any positive symptoms appear, there are usually indications of hepatic derangement; the bowels are irregular, sometimes purged and sometimes constipated; the abdomen is slightly tender, the tongue coated; there is loss of appetite, and headache. Sooner or later the skin presents a slight jaundiced tint. After the jaundice has existed for a week or fourteen days, or even longer, severe symptoms of biliary suppression manifest themselves, and the disease runs a rapid course, terminating fatally in twelve or twenty-four hours, or more rarely in a week. The skin, which was at first cool and dry, now becomes hot, and of a deeper yellow colour; the pulse rises to 110–120; the head is hot and painful; severe vomiting comes on, first of grey mucus, afterwards of blood, clotted, or grumous like coffee-grounds; hæmorrhage from the bowels, uterus (with abortion), and nose, is liable to occur. There is pain in the right hypochondrium, and the hepatic dulness is found on percussion to have diminished or disappeared, while that of the spleen has increased: the bowels are confined, and the stools firm, dry and clay-like, from deficiency of bile; occasionally they are tinged with bile. The urine is normal in quantity and specific gravity, of a dark brown colour, and gives the reactions of bile pigment. Spontaneous evaporation on a glass slide yields microscopical yellowish crystals of leucin and tyrosin in fine needles, and bundles of dense opaque stellate masses (see *a*, Fig. 82), consisting of crystals of tyrosin. The pain in the head increases in severity, violent delirium sets in, and is succeeded by convulsions, stupor, and deep coma; hiccough and diarrhœa are often present at this stage; the skin becomes deeper coloured and frequently covered with petechiæ and ecchymoses, and the motions are tar-like, from the presence of blood. In this condition the patient usually dies. Rarely after free evacuation of the bowels, consciousness returns, the jaundice diminishes, and recovery takes place.

Fig. 82.



MORBID ANATOMY.—Liver shrunken, shrivelled, and flabby. Sections present a smooth, shining surface, of an ochre yellow colour; but no division into lobules is visible. When minutely examined, no trace of hepatic cells can be found; the atrophied hepatic tissue is composed of fine yellow or pale molecules; a little oil in fine spherules; here and there irregular masses of a dark-brown colour, and bundles of radiating crystalline masses of tyrosin; the biliary ducts are everywhere pervious, and their lining pale. The gall-bladder nearly empty, containing only a small quantity of grey mucus or grumous pale yellow fluid, neutral, and giving the ordinary reactions of bile. The blood of the hepatic vein is rich in crystals of tyrosin, but this compound is absent from the blood both of the portal vein and hepatic artery; decoction of the wasted liver deposits much tyrosin and leucin. Leucin and urea are accumulated in the blood of the heart. The urine is deficient in phosphate of lime and urea, and contains large quantities of leucin, tyrosin, and extractive matters of a peculiar nature. The spleen is enlarged and congested; and extravasations of blood between the folds of the mesentery are occasionally found. (Frerichs.)

CAUSES.—*Predisposing.* Youth; irregular and dissolute habits; syphilis; pregnancy; certain miasmata (?)—*Exciting.* The symptoms and morbid anatomy both point to diffuse inflammation of the hepatic tissue:—"hyperæmia and grey exsudation in parts not yet broken down" have been noticed. (Frerichs.) The obstruction to the portal circulation, causing the splenic enlargement and the gastro-intestinal congestion, are accounted for by the loss of function of the hepatic cells and the consequent collapse of the liver.

Diagnosis.—Acute atrophy may be mistaken for typhus, pyæmia, and yellow fever. There appears to be a close relation between yellow fever and acute atrophy of the liver, but whether such be really the case is uncertain. Acute atrophy is known by the shrinking of the liver, and by the presence of the leucin in the urine.

Prognosis.—Exceedingly unfavourable.

Treatment.—At first a powerful emetic, and afterwards a large dose of calomel, followed by a strong saline aperient; hot baths; leeching and cupping over the liver. An occasional dose (v grains) of quinine.

BILIARY CONCRETIONS.—GALL-STONES.

Symptoms.—Biliary calculi give rise to no pain or inconvenience till they become impacted in the gall-ducts. The passing of the gall-stone is accompanied by the following symptoms:—Usually after a hearty meal excruciating pain in the epigastrium, extending to the right hypochondrium and back, occurring in severe paroxysms, with intervals of comparative ease, during which there is a dull heavy pain in the epigastrium, generally relieved by firm pressure. Nausea, frequent vomiting of a clear sour fluid, and constant hiccough, are also often present, and jaundice commonly supervenes in the course of the attack. The urine generally contains bile, and the motions are pale from its absence. The pulse is frequent and full, or the reverse; there is profuse perspiration; or, if inflammation be present, febrile symptoms. As soon as the calculus reaches the intestine, there is a sudden cessation of pain.

Termination.—In death from exhaustion on the second or third day. In inflammation, followed by suppuration and the discharge of the calculus externally, or through some internal organ, as in ordinary abscess of the liver. After the escape of the gall-stones into the intestines, constipation or obstinate obstruction of the bowels, either immediate, when the stones are large, or remote, when they have become the centres of intestinal concretions. Sometimes a large number of calculi are found in the gall-bladder and gall-duct, after death, though no sign of their presence existed during life. Complete obstruction of the common bile-duct, and deepest jaundice may exist for several months, or even years, without preventing the patient from following heavy manual work; but after a time he lapses into the anæmic state, and ultimately dies of inanition.

Morbid Anatomy.—After long retention of bile from closure or obliteration of the common bile duct, the ducts in the liver are found enormously dilated, while the gland itself is shrunken and atrophied and of a deep olive colour; the secreting cells are destroyed, and their place occupied by free oil globules and dark biliary granules.

Diagnosis.—The pathognomonic sign is the excruciating pain relieved by pressure. When the gall-stones are numerous, their presence may sometimes be detected by a rough crepitation under the finger. By watching the evacuations, and diluting them with water, they may sometimes be seen floating on the surface. If the gall stone be round and smooth, there is presumption in favour of its being the only one; but if it present a flattened surface, it may be inferred that there are several. The calculi may be as small as a pea or larger than a walnut, and they have been found in the intestines of great size, and moulded so as to fill and obstruct the canal. They are commonly of a dark yellow-brown colour, of soft consistence, and have several flat surfaces. They consist of cholesterin and the colouring matter of the bile, sometimes blended with carbonate or phosphate of lime.

Treatment.—I. Opium, chloroform, the hot bath, hot fomentations or emetics to relieve the pain and spasm. The *opium* may be given in doses of a grain, or twenty drops of laudanum, every hour, and the enema opii every six hours.

II. In plethoric persons, or in those prone to suffer from inflammatory diseases, bleeding will do good. It may be followed, in the absence of vomiting, by nauseating doses of tartar-emetic.

ICTERUS.—JAUNDICE.

Synonyms.—Morbus arquatus; aurigo; morbus regius.

Symptoms.—Languor; inactivity; nausea; loss of appetite, and bitter taste; and sense of uneasiness or pain in the right hypochondrium. The eye and the whole surface of the body are of a yellow colour; the urine is high-coloured, and tinges linen yellow; the stools are clay-coloured, but in some cases light yellow; the bowels are usually costive, but diarrhœa is sometimes present; in extreme instances the sweat and saliva are yellow, and all objects seen by the patient are tinged of the same colour. The pulse is generally slow, yet sometimes, especially when the pain is acute, becomes quick and hard, and there is a feverish heat and dryness of the skin. In some cases, also, the skin is the seat of troublesome heat and pricking. Should the disease be long protracted, petechiæ and maculæ sometimes appear in different parts of the body; the skin turns brown or livid; passive hæmorrhages and ulcerations break out, and the disease has in some instances assumed the form of scurvy.

Causes and Pathology.—Jaundice is directly produced by the transudation of bile through the walls of the distended bile ducts and the contiguous capillaries, into the blood. The ultimate cause of jaundice is therefore retention of the bile within the liver. The retention may be complete or incomplete. *Complete retention* is caused by the impaction of biliary calculi in the hepatic duct or its main branches, or in the common bile duct, by the pressure of cancerous tumours of the pancreas, duodenum, pylorus, and of the liver itself; by the pressure of fæcal accumulations, and of the enlarged uterus; by inflammation of the lining membrane of the ducts causing their occlusion.

Inflammatory occlusion of the duodenal orifice of the common duct may probably be sufficient of itself to cause complete retention.

Spasmodic closure of the bile ducts was formerly regarded as a frequent cause of jaundice. It may be a transient cause, but it is highly improbable that jaundice of some days' standing is due to spasm.

Incomplete retention may result from biliary congestion; from the effect of certain poisons, especially the poison of serpents; and from mental emotion.

Jaundice is a prominent symptom of the severer forms of intermittent and relapsing fevers; it occasionally appears in a milder degree, during attacks of typhus fever, pneumonia, and pyæmia.

Both congestion of the liver and hepatitis may produce the jaundice occasionally present in these diseases; and both of these conditions, the one as a consequence and the other as an accident, accompany pneumonia; and suppurative hepatitis is one of the commonest results of pyæmia. Nor, when we consider analogous changes, does the sudden production of jaundice from fear, or other intense mental emotion, involve any special difficulties. Sudden fright, we know, will often cause an immediate exsudation from the skin and alimentary canal, leading, in the latter case, to profuse diarrhœa; and if we imagine a similar relaxation of the biliary ducts, allowing of transudation of bile into the equally relaxed capillaries, we shall at once understand how the Abbé, as mentioned by Villermi ("Dict. des Scienc. Médic.," p. 420), became suddenly yellow when a mad dog rushed against him. Jaundice is frequently attributed to grief and other depressing passions, nor do we deny that it may be so produced; but we believe that if such cases were carefully investigated, in nine out of ten a much more palpable cause would be discovered, viz., alcohol, which is so often taken to blunt and dispel grief. The identical history of numerous cases has convinced me that this agent acts locally by producing inflammatory occlusion of the orifice, or of the orifice and of some portion of the duodenal end of the bile duct. One history will serve for all these cases, so similar were the circumstances attending them. A young robust labouring man in perfect health, to allay a sudden vexation, intoxicated himself by drinking three or four glasses of neat rum. The next day there was anexoria, nausea, and some pain and tenderness in the epigastrium. On the morning of the third day, the skin was moderately jaundiced, the urine contained much bile, the fæces none, and the bowels were constipated. The jaundice increased during the next three or four days, and then, under the influence of free saline purgation, gradually diminished, and disappeared at the end of twelve days. The most obvious explanation of such cases is, that the gastro-duodenal inflammation caused *by the raw spirit* involved the duodenal end of the common bile duct and closed it, thus preventing the flow of bile into the intestine. The mineral irritants appear to act in the same way. A patient of mine, took at once, by mistake, five doses of strong solution of acid muriate of iron. It produced epigastric pain and tenderness, followed by deep jaundice.

DIAGNOSIS.—The characteristic symptoms which distinguish this from every other disease are, the yellow colour of the skin, conjunctiva, and urine; and, in most cases, the white or clay-coloured fæces.

PROGNOSIS.—*Favourable.* The disease having arisen from a cause that admits of easy removal; such as violent mental emotion, accumulated fæces, or temporary pressure during pregnancy; the strength and appetite little impaired, the disease appearing suddenly, cessation of local pain, followed by bilious diarrhœa. The disease, even in mild cases, runs a chronic course, the skin rarely recovering its proper colour under two or three weeks.—*Unfavourable.* Deep and persistent jaundice with anæmia, acute atrophy, cirrhosis, and cancer of the liver.

TREATMENT.—Jaundice from inflammation of the liver, or from obstruction of the duct, requires the treatment of hepatitis or of biliary concretions. (See those diseases.) When, however, there is no pain in the right hypochondrium, no fever, and the paroxysms of acute pain due to the passage of gall stones are absent, the treatment will consist in the use of emetics, and of gentle aperients to keep the bowels free. In the more strongly marked cases, we may begin the treatment by administering an emetic (Form. 201); and afterwards x to xx grs. of calomel, followed within two or three hours by half an ounce of castor oil. In cases of less severity, the treatment having been commenced by an emetic, the bowels may be kept free by some saline aperient (Form. 240).

ICTERUS NEONATORUM.—The jaundice of new-born children usually appears a few hours after birth, attains its maximum in three days, and disappears in from seven to fourteen days. The urine contains bile pigment, and the motions are pale; the general health is unaffected.

Causes.—A congested condition of the hepatic ducts. The jaundice of new-born infants is occasionally caused by constriction, an impervious condition, or congenital absence of the hepatic or common bile ducts; inspissated bile obstructing these ducts is another cause. In these cases life may be prolonged for several weeks.

Treatment.—Mild laxatives, such as syrupus sennæ, preceded by gr. i to gr. ii hydrargyri cum cretâ.

OTHER ORGANIC DISEASES OF THE LIVER.

The liver is subject to several organic diseases besides those already described: namely, to fatty and waxy degeneration, cancerous, syphilitic, and tubercular deposits, serous cysts, and hydatids.

1. Fatty Degeneration.—The *symptoms* are, a smooth, rounded margin felt three or four fingers' breadth below the margin of the ribs, increased dulness of the hepatic region, pale fæces, liability to profuse pale diarrhœa. Skin pale, anæmic, waxy and smooth to the touch: in drunkards greasy. As there is no impediment to the flow of blood through the liver, there is no dropsy or hæmorrhage.

Morbid Anatomy.—Bile ducts empty; liver enlarged, pale and greasy, or (in drunkards) dark dirty brown, and rotten (the nutmeg liver). Cells invaded with fat, and deficient in pigment granules. (Fig. 12, p. 78.)

Causes.—Phthisis; habits of intoxication, and a sedentary life; Bright's disease. The disease admits of no direct amelioration.

2. Syphilitic Disease of the Liver occurs in two forms:—1. Simple interstitial hepatitis. 2. Hepatitis gummosa. These forms may co-exist in the same liver.

The *symptoms*, *pathology*, and *morbid anatomy* of simple interstitial hepatitis are those of cirrhosis; the syphilitic variety of the disease, however, more frequently results in simple induration without the formation of the nodules characteristic of cirrhosis. *Hepatitis gummosa* consists in the formation of white depressed deposits, having a radiated form, on the surface of the liver, and extending to a variable depth into the interior of the gland. In this opaque deposit, whitish or yellowish nodules, varying in size from a hemp-seed to a walnut, are found. They are composed of oil globules, cells loaded with fat, and fibres of connective tissue, being identical in structure with the common syphilitic node.

3. Albuminoid, Waxy, Lardaceous, or Amyloid Degeneration of the Liver is associated with a similar degeneration of other organs. It occurs in syphilitic, rickety, and strumous individuals, and is often associated with fatty degeneration and cirrhosis. The *symptoms* are anæmia associated with albuminuria and uniform enlargement of the liver, sometimes to an enormous extent.

Morbid Anatomy.—In the early stage the lobular structure is unusually distinct, the centres of the lobules are reddish yellow, translucent, firmer than natural, and sharply defined from the dull grey peripheral parts. As the disease advances the whole of the lobule is invaded, and when this has occurred they are no longer distinct, and the section of the gland presents a smooth, homogeneous, yellowish red, glistening, semi-translucent surface. In advanced stages the liver has a waxy lustre, the molecular contents of the normal hepatic cells gradually disappear, and give place to a homogeneous clear substance, which fills up the cavity of the cell, and the individual cell membranes can be no longer distinguished, so completely is the tissue transformed. The walls of the blood-vessels and ducts undergo the same degeneration. On moistening the section with solution of iodine, all the parts which have undergone the waxy degeneration are coloured deep red, and when subsequently treated with sulphuric acid, the red colour is changed to a dirty violet or blue, similar to that produced in cellulose with the same reagents. These reactions have led some observers to the opinion that the degeneration is "*amyloid*." It is as distinct from starch as white of egg, being in fact a form of albumin.

4. HYDATID TUMOURS are more common in the liver than in any other organ.—*Symptoms*. A globular tumour in the hepatic region having a tense elastic feel and history of slow, painless growth, and unaccompanied by any considerable derangement of health, is indicative of hydatid tumour of the organ. The tumour may have its seat on the under surface of the liver, and by pressure on the portal vein or bile duct cause ascites or jaundice. An abscess is always preceded by some marks of inflammation. An aneurism of the abdominal aorta may be distinguished by strong heaving pulsation, bellows murmur, palpitation in the belly, and sympathetic pains in various parts of the body. Hydatid tumours sometimes attain to an enormous size. They may burst into the abdominal cavity, causing severe peritoneal pain, collapse, and death in a few hours; into the intestine, and be evacuated per anum ; into the lungs, when their contents are expectorated. These tumours may remain in a state of quiescence for a whole lifetime, but they are a source of constant danger, because they may be ruptured by any accidental blow or fall.

Structure of the Hydatid Tumour.—The tumour (*echinococcus veterinorum*) is formed of a restricted development of a species of tape worm, the Tænia echinococcus of Siebold. It is composed of a delicate thin-walled cyst, called the parent cyst, surrounded by a

Fig. 83.



a, Echinococcus with circlet of hooklets retracted. *b*, hooklets. *c*, *d*, E. expanded. *e*, E. imperfectly developed. *f*, E. showing suckers.

thick-walled dense sac, formed partly of an exsudation from the parent cyst, and partly by a condensation of the hepatic tissue enclosing it. The parent cyst is filled with a clear salt fluid, in which are floating multitudes of delicate spherical secondary cysts varying in size from a pea to an egg. These secondary cysts are called *acephalocysts;* the larger contain fluid and another brood of acephalocysts. The inner surface of many of the acephalocysts presents a finely granular appearance; these granules are readily detached; they are echinococci, and have the appearances represented in Fig. 82.

The parent cyst and its progeny are very liable to calcareous degeneration, their delicate walls becoming thickened and hardened by milk-white earthy matter.

Treatment.—Hydatid tumours should be tapped as soon as they come near enough to the surface, their contents completely evacuated, and means taken to effect a radical cure. (See "Med. Chir. Trans." vol. xlix.)

MALIGNANT DEGENERATIONS of the liver assume the several forms of scirrhus, medullary sarcoma, and melanosis; and like malignant degenerations of other important viscera are necessarily fatal. They generally occasion a great increase in the size of the organ, and sooner or later produce obstinate jaundice and chronic ascites. The most common of these malignant diseases is the medullary cancer, in the form of tumours varying in size and scattered throughout the substance of the liver. They project from the surface, and can be felt through the attenuated walls of the abdomen.

The treatment is palliative, and varies with the symptoms, and the existing state of the system.

DISEASES OF THE SPLEEN.

The Spleen is very liable to congestion; is sometimes the seat of inflammation, acute and chronic, usually resulting in simple enlargement; is also liable to waxy degeneration, to fibrinous, tubercular, and syphilitic deposits. These diseases may be treated under the single head of

ENLARGEMENT OF THE SPLEEN.

SYMPTOMS.—Dull pain in the left side; dyspnœa; dry cough; inability to lie on the right side; loss of flesh; anæmia.

COMPLICATIONS.—Disease of the liver, an unusual tendency to hæmorrhage, dysentery, and scurvy, and to the anæmic or cachetic state, known as *leucocythæmia* (see p. 260).

CAUSES.—Previous attacks of ague; morbid degeneration, especially the deposit of tubercle; morbid softening; diseases of the liver obstructing the hepatic circulation; enteric fever.

DIAGNOSIS.—By the situation of the tumour in the left hypochondrium, extending, in extreme cases, to the epigastrium, the um-bilious, and the hypogastrium; by the tumour being solid and smooth, generally of an oblong shape, lying beneath the integuments, movable and presenting a notch on the right edge. The previous occurrence of ague always affords a probability that the tumour "ague-cake" is situated in the spleen.

Treatment.—The use of iodine, externally, and iodide of potassium, with tonics, internally; friction, in the absence of pain; gentle aperients, alteratives, and moderation in diet. If the disease have been preceded by ague, bark or quinine.

DISEASES OF THE PANCREAS.

Symptoms.—The symptoms are still more obscure than those of disease of the spleen. Hard cancer is the disease to which this gland is most liable. The enlargement of the pancreas is not readily distinguished from that of the adjoining viscera; and is very liable to be confounded with organic disease of the pylorus or duodenum. Usual symptoms: a deep-seated pain in the epigastrium, nausea, sickness, and emaciation. Constipation or diarrhœa, salivation, and jaundice, occur occasionally.

Diagnosis.—When the whole gland is diseased, by fatty stools (see p. 38).

Treatment.—The treatment must be so shaped as to meet urgent symptoms. Fat should be omitted from the diet.

CHAPTER V.

DISEASES OF THE URINARY ORGANS.

1. Diseases of the Kidney.
2. Diseases of the Bladder.

DISEASES OF THE KIDNEY.

NEPHRITIS	Inflammation of the Kidney.
OTHER DISEASES	Of the Kidney.
LITHIASIS	Gravel. Calculus.
HÆMATURIA	Bloody Urine.
CHYLURIA	Milky or Fatty Urine.
ISCHURIA RENALIS	Suppression of Urine.
DIABETES	Saccharine Urine.
DIURESIS	Immoderate flow of Urine.

NEPHRITIS.—INFLAMMATION OF THE KIDNEY.

VARIETIES.—1. Acute Suppurative Nephritis. 2. Acute Desquamative Nephritis. 3. Chronic Desquamative Nephritis.

1. ACUTE SUPPURATIVE NEPHRITIS.

SYMPTOMS.—Deep seated pain and tenderness in one or other loin; numbness in the thigh; frequent nausea and retching; irritability of the bladder, and pain on micturition; considerable pyrexia; urine presenting a white finely granular deposit, which, on examination is found to consist of pus cells, free or contained in casts of the uriniferous tubes. (See Fig. 38, p. 136.) If an abscess form, it may burst into the pelvis of the kidney, and be discharged by the urethra; or it may point in the loin or groin, which parts previously become full and tender. Free suppuration is accompanied by hectic fever, under which the patient often sinks.

CAUSES.—Morbid conditions of the blood. External violence. Retention of urine. Renal calculi.

MORBID ANATOMY.—Kidneys enlarged, congested, with scattered abscesses varying in size from a walnut to a hemp-seed. Tubes stuffed with epithelial cells or pus corpuscles. If a calculus have been the cause of the disease, the kidney will probably be found destroyed, and its outer portions converted into the sac of a large abscess which occupies its interior. Calculi usually lie in the pelvis of the kidney, and are the cause of suppurative inflammation of its mucous membrane (pyelitis). They ultimately lead to ulceration of the mamillæ, and degeneration of the entire kidney.

Diagnosis.—Pus, derived from the kidneys, is moulded into tubes. The symptoms of inflammation of the pelvis are great renal pain and irritation, and the passage of large quantities of *free* pus.

Treatment.—In the early stage, cupping or leeches to the loins. Hot baths. A brisk saline purge followed by full doses of compound ipecacuanha powder, and acetate of ammonia. In the latter stages, quinine alone or with the mineral acids. If the inflammation be due to calculi, we must treat it accordingly. (See Renal Calculi.)

2. Acute Desquamative Nephritis.

Symptoms.—After a chill, or slight feeling of chilliness, or merely after a pain in the loins and legs; headache; vomiting; rigor and pyrexia. In the course of a few days the face becomes pallid and swollen, and the legs œdematous. Ultimately there is general anasarca.

During the first few days the urine is very scanty, or even suppressed. It is of a dark-brown or red colour from admixture of blood, and loaded with albumin. The pain in the loins persists, and on deep pressure there is much tenderness. Sometimes the pain is severe, and extends down the ureter to the bladder and thence to the testicles and down the inside of the thighs. Nausea and vomiting accompany these symptoms. Inflammation of the serous membrane is very liable to occur during the existence of the febrile symptoms. Sometimes convulsions and coma (symptoms of suppression) suddenly supervene.

If the case progress favourably, the quantity of urine increases, and deposits a little cloud of flocculent matter, and the blood disappears. After a week it may become quite clear, and remain of a pale colour and low specific gravity; it constantly contains albumin, the quantity of which is variable, but as convalescence approaches, diminishes to a mere trace. Sometimes as much as 120 ounces of urine are voided in the twenty-four hours. The anasarca now gradually disappears, and the patient is ultimately left very thin and weak. If the disease terminate fatally, death is preceded by diminution of the urine, and at last total suppression. Death more frequently occurs in the latter stages from dropsy and chest complications, resulting in apnœa.

Causes.—Scarlatina, measles, erysipelas; abuse of alcoholic liquors; suppression of the cutaneous excretions from exposure to wet and cold.

Pathology.—Excessive functional activity of the kidney, induced by suppression of the cutaneous excretion. This leads to active congestion and excessive growth of secreting epithelium, the cells of which, being changed, become at last inadequate for the performance of their own special function—the elimination of the urinary constituents. These, in part, remain in the blood, and give rise to the characteristic symptoms of the disease. Meanwhile the capillaries of the kidney become dilated or even ruptured, and the constituents of the blood escape into the renal tubuli. The blood becomes much impoverished; the albumin and red corpuscles diminish, and the specific gravity of the serum falls from 1030 to as low as 1020 in some cases. But what is of more serious import still, urea accumulates in such quantities in the blood, that its presence may be detected in effusions in distant parts of the body.

The fatal symptoms of urinary suppression are due to the presence of urea in the blood. At first the stomach endeavours to eliminate it, and hence the vomiting, but this vicarious function is insufficient: the poison accumulates, and its action is manifested in the convulsions and coma which terminate life. It is thought by some that urea, as such, has no poisonous influence, and that the terrible symptoms of suppression only come on when this is converted into ammonia.

Morbid Anatomy.—After death during an acute attack. Both kidneys involved. They are enlarged and congested, and of a dark red or chocolate colour; the structure as firm or a little firmer than natural; the cortex mottled with spots of anæmic and ecchymosed tissue; the medullary cones uniformly congested.

On minute examination the uriniferous tubuli are found, some crowded with epithelial cells, others filled with blood, giving rise to the ecchymosed spots observed on the capsular surface and in the interior of the gland; in others the clot has become colourless. Here and there blood may be observed effused into the capsule inclosing the Malpighian tufts. The walls of the capillaries themselves are thickened and opaque. The pelvis of the kidney, the ureters, and sometimes the bladder are congested; and there is general congestion of the internal organs and effusion into the serous cavities. The bladder is usually empty. If the disease have continued for a month or more, the kidneys will be found in one or other of the stages of degeneration described under chronic Desquamative Nephritis.

Diagnosis.—Œdema commencing in the delicate areolar tissue of the eyelids, nymphæ, or scrotum, followed by puffiness of the face and general anasarca; the dark, smoky colour of the scanty urine, which is found to deposit blood corpuscles and casts of the uriniferous tubules filled with epithelial cells (Fig. 34, p. 136), are the signs by which acute desquamative nephritis, and its attendant dropsy, may be distinguished from other renal affections, and dropsies dependent on hepatic, pulmonary, or cardiac diseases.

Prognosis.—*Favourable* if the secretion of the urine be free, and contain comparatively little blood and albumin. *Unfavourable* if the urine be very scanty and bloody, and if difficulty of breathing come on.

TREATMENT.—1. *Reduce the inflammation*, either by the use of cupping-glasses, or the application of numerous leeches to the region of the kidney, followed by mustard poultices.

If there be much febrile action, tartarated antimony, in diaphoretic doses, is indicated. A few grains of Dover's powder may be combined when there is pain, but it must always be remembered that the effects of opium are greatly intensified in renal disease.

II. *Restore the action of the skin.*—The hot bath, or, still better, a hot-air bath, should be given, and acetate of ammonia simultaneously administered, in order to secure copious diaphoresis.

The temperature of the room should be kept above 70° Fahr.

III. *Relieve the action of the kidneys.*—Purgatives of senna or jalap should be given, so as to keep the bowels freely open. The diet must be restricted to gruel and farinaceous substances; and toast or barley-water may be freely taken.

IV. If symptoms of *suppression* appear, the treatment recommended under Ischuria Renalis (see p. 554).

3. CHRONIC DESQUAMATIVE NEPHRITIS.

SYMPTOMS.—These are insidious, and may long remain unobserved. The disease is a frequent consequence of a slight attack of the acute form, and we may generally trace back its origin to an indisposition caused by exposure to wet or cold. In many cases it appears to be the consequence of gradual degeneration of the kidney. Many patients present the gouty diathesis, or are actually suffering from an attack of gout when the renal symptoms first appear. Anæmia, with an inclination to swelling of the eyelids and ankles, are the symptoms which induce the patient to apply for relief. On inquiry we shall probably find that the urine is copious and frequent, and that the patient is disturbed several times in the night to void it. In gouty subjects the urine is usually scanty and loaded with lithates, and contains a variable quantity of albumin and casts of the uriniferous tubules resembling those already described as characteristic of acute desquamative nephritis. The patient may remain in this state for months or even a few years, but at last dropsy comes on and becomes general, the urine decreases, the casts show great degeneration of the epithelial cells, and have a granular appearance (Fig. 35, p. 136); sometimes the cells are altogether absent, the cast itself looking like a film of wax, to which spherules of oil in the latter stages occasionally adhere. (Fig. 37, p. 136). The dropsy suddenly increases with ascites and œdema of the lungs; or the urine becoming scanty, urea accumulates in the blood, the patient is seized with successive epileptic fits, finally becomes comatose, and so dies. Death from cerebral hæmorrhage (apoplexy) is a common result of chronic renal disease, and this may happen before dropsy has appeared, or even a suspicion of renal disease been entertained.

MORBID ANATOMY.—The kidneys are more or less atrophied, shrunken, and red, weighing sometimes not more than 1½ ounce; the tubuli in part completely denuded of epithelium, and atrophied; the cortex contracted and reduced to a narrow layer covering the bases of the cones, and the Malpighian bodies more closely approximated. Some of the tubuli present dilatations, which, by becoming isolated and further distended, are converted into cysts containing a clear albuminous and often a jelly-like fluid. The intertubular tissue has a fibrous appearance, and the walls of the bloodvessels are thickened. The capsule is generally firmly adherent, and the surface from which it is removed granular. The granulations are composed of aggregations of degenerated tubules lying between the small branches of the renal vein. This condition closely resembles that of cirrhosis of the liver. If the disease have had its origin in gout, the kidney will be small and atrophied, as in the last stage of chronic desquamative nephritis, but they will often present the characteristic appearance described at p. 354.

If the chronic disease follow the acute, we may meet with two other morbid conditions of the kidney—viz., the "large white" and the "red coarse mottled" kidney, both of which may be regarded as intermediate stages between the swollen congested kidney, characteristic of the *first* stage of *acute desquamative nephritis*, and the small contracted kidney, the *last* stage of *chronic desquamative nephritis*. The coarse red mottled kidney is found in those who have abused spirituous liquors: it is a mixture of congestion and fatty degeneration, the white spots which mottle the enlarged cortex, and the white lines which streak the pyramids being composed of fat.

PATHOLOGY.—COMPLICATIONS AND TERMINATIONS.—In consequence of the destruction of the secreting epithelium of the kidneys, the blood becomes contaminated with the constituents of the urine. The effects of the circulation of this impure blood are:—1. The affinity between the growing and secreting structures and the blood is diminished, the capillary circulation is feeble and sluggish, and the heart and bloodvessels, in their endeavours to overcome the impediment, become hypertrophied and dilated. These efforts failing, general anasarca results.—2. The gastro-intestinal and pulmonary mucous membranes take on an action vicarious of that of the kidney, and endeavour to eliminate the urinary constituents: vomiting, diarrhœa, and bronchitis are the consequences.—3. The impure blood tends to produce low forms of inflammation in various parts of the body; peritonitis, pleuritis, pneumonia, and if the skin be slightly wounded, erysipelas, may arise as complications at any time. The brain itself is often implicated, the diseased vessels allowing serous exudation, and fluid containing urea poured out into its ventricles:—the ultimate result when death occurs from suppression of urine. Apoplexy, from the same cause, may be looked for at any time.

DIAGNOSIS.—For that of Dropsy, see p. 268. Renal dropsy is known from other varieties:—1. By the absence of long standing pulmonary, cardiac, or hepatic disease;—2. By the mode of access, appearing first on the face, particularly the eyelids, on rising in the morning, and by slight puffiness of the ankles and scrotum towards evening; and 3. By the condition of the urine, from which the several stages of renal degeneration may be safely inferred. If the tubular casts be composed of epithelial cells in a state of granular degeneration, we may assume that the kidney is in the second stage of degeneration. If the casts be large, and wholly denuded of cells, the degeneration is still further advanced. If these denuded casts contain oil globules, the organ may be regarded as in the last stage of atrophy. (See p. 136.)

PROGNOSIS.—The prognosis will depend on the evidence furnished by the microscope as to the state of the kidney, indicated by the casts of the uriniferous tubules just described under diagnosis. In the early stage of chronic as well as of acute desquamative nephritis, in the absence of any serious complications, recovery may be hoped for. In the later stages the prognosis is unfavourable.

CAUSES.—*Predisposing.* The scrofulous diathesis. It occurs in both sexes, and at all ages. Of seventy-four fatal cases recorded by Dr. Bright, nineteen were under thirty; thirty-eight under fifty; thirteen above fifty; and four above sixty.—*Exciting.* Those of the acute forms of the disease. The impure air, and other unwholesome influences to which the poor inhabitants of large towns are exposed; intemperance; mechanical injuries; cold; a previous attack of scarlatina, followed by dropsy; rheumatism; gout.

TREATMENT.—*Relieve the congestion of the kidney, and the attendant dropsy,* by purgatives and diaphoretics, diuretics being inadmissible. In the absence of diarrhœa, a drastic purgative, such as a full dose of the compound jalap powder, may be given every morning. When there is much debility, stimulant diaphoretics, such as the liq. ammon. acet. in doses of ʒii to ʒiv three or four times a day, are indicated. The warm bath, or the hot-air bath, may be used at intervals of one, two, or three days. The skin should be kept warm.

To improve the health.—A nourishing diet should be prescribed; and preparations of steel, of which the tinctura ferri perchloridi (in doses of ♏x or ♏xx) is the best. I have given this with advantage in combination with belladonna, the object being to promote contraction of the renal blood vessels.

In the treatment of complications, the pathology of the disease must be duly regarded; vomiting may be checked, but purging, we must remember, is a natural safety-valve, and we must merely restrain it, if it become immoderate. If the œdema of the legs increase, and the skin become painfully tense, much relief will be afforded by acupuncture, or slight incisions made on the outside of the legs, or we may insert a capillary trocar with a long dependent india-rubber tube dipping into a vessel of water. The syphon action thus established will aid the flow of serum from the cellular tissues.

PROPHYLAXIS.—Temperance; pure air; a warm, dry climate; plain and wholesome diet, and regular exercise, are needful for persons who have had nephritis, or who seem liable to it.

OTHER DISEASES OF THE KIDNEY.

The kidney, in common with other vascular organs, is liable to many other forms of disease. Some of these may affect the kidney alone; others are associated with similar disease of the neighbouring viscera. So long as one kidney only is affected, the urinary function is unimpaired, the healthy organ becoming hypertrophied and performing double duty. The following are the diseases most commonly met with:—

I. *Cystic diseases.*—Cysts in the kidney, varying in size from a mustard seed to a marble, and of very frequent occurrence in the cortical part of the kidney. The atrophied kidney of chronic nephritis very commonly presents a large number of minute cysts. It is sometimes enlarged and lobulated, and converted into a few large cysts filled with glairy fluid, the intervening secreting structure being destroyed. There can be little doubt that these cysts are formed by obstruction and obliteration of one part of the denuded uriniferous tubules, while other portions are distended into cysts by the secretion of albuminous fluid.

When an ureter becomes obstructed or obliterated, at first urine, and then a watery fluid, continues to accumulate in the pelvis of the kidney, the secreting structure being slowly absorbed by the pressure, and the whole organ finally converted into one large cyst. A similar change may result from an impediment to the flow of urine from the bladder, the ureter becoming dilated in extreme cases to the diameter of the small intestine. The term *hydro-nephrosis* has been employed to indicate the presence of such cystic tumours.

The kidney is liable to morbid changes resembling those which, in the ovary, give rise to ovarian dropsy. In one case which came under my notice, the symptoms were so precisely similar that the case was treated throughout for ovarian disease, the abdomen being uniformly and excessively enlarged, dull, and distinctly fluctuant on percussion. After death both ovaries and the other genital organs were found perfectly healthy, and had contracted no adhesions with the tumour. This, which weighed forty-five pounds, was contained within a smooth walled cyst; the ureter and upper end of the left kidney were directly continuous with the smooth wall of the tumour. There were two principal cysts, which contained together nine pints of fluid,—colourless in one of the cavities, and dark brown in the other. The right kidney was healthy and hypertrophied. This patient was 34 years of age; and had had two children. Another case, presenting exactly the same symptoms, and generally the same morbid appearances, also in connection with the left kidney, occurred at the Stockport Infirmary during my residence there. The subject was a little girl about seven years of age. The abdomen was greatly distended as if by the gravid uterus. The age of the patient simplified the diagnosis: a tumour of the uterus it could hardly be, and ovarian disease seemed just as improbable; still from the uniformity of the swelling which had commenced in one iliac region, its fluctuation, and the absence of any urinary symptoms, most of those who formed a positive diagnosis concluded that it was ovarian.

II. *Fatty degeneration (the granular kidney).*—This is the condition to which the atrophied kidney of desquamative nephritis tends. The kidneys are large and pale, the cortex is anæmic, and mottled with opaque granulations of a yellowish-white colour, giving to the organ a granular appearance. On minute examination the granulations are found to be composed of fat, and the convoluted tubuli are lined with dark opaque cells, composed of fatty molecules and drops of oil (Fig. 12, p. 78).

The early symptoms are those of desquamative nephritis; afterwards the pale albuminous urine is rather scanty and quite clear, occasionally depositing a little cloud of small waxy casts, in which minute globules of oil are found adhering.

III. *Albuminoid (waxy, lardaceous, amyloid) degeneration.*—The kidney, in common with other glands, is liable to this form of disease. It is usually increased in size; it is hard, and cuts firm; the surface of the section is smooth, homogeneous, and of a waxy appearance. The minute structure of the degenerate tissue is that described under Albuminoid Degeneration of the Liver. (See p. 535.) This condition appears to be derived from the "large white kidney," found in the second stage of acute nephritis. Perhaps the scrofulous diathesis, with which the albuminoid kidney is most frequently associated, determines the particular pathological condition in which the large white kidney may issue. The term "*albuminoid*" is selected to designate this form of degeneration because the morbid material is of the nature of albumin. "*Lardaceous*" and "*waxy*" are only appropriate in so far as they refer to appearances. The term *amyloid* is exceedingly inappropriate.

The symptoms are those of chronic desquamative nephritis.

IV. *Tuberculous* and *cancerous* deposits occur in the kidney, associated with similar disease elsewhere, rarely or never alone. They form at first isolated rounded masses, which tend to become confluent and soften in the centre, and being discharged with the urine, may be identified, and the condition of the kidney inferred.

V. *Hydatid tumours* of the kidney are uncommon.

LITHIASIS.—GRAVEL AND CALCULI.

SYMPTOMS.—Dull or acute pains with a sense of heat and heaviness in the loins; with more or less pain or difficulty in voiding urine, increased by sudden and violent motion, with occasional pain behind the pubes; irritation at the neck of the bladder, and itching or pain at the end of the penis. Sometimes there is retraction of the testicles, with discharge of bloody urine, or clots of blood. The urine, even while warm, contains a sandy powder, crystalline grains, or small calculi. It is generally rather scanty, high-coloured, of high specific gravity, acid, of a strong odour, and becomes turbid on cooling. The digestive organs are deranged, and the patient suffers from acidity, flatulence, and frequent eructation; constipation; furred tongue and dry skin; and is restless and feverish.

The most common form of gravel consists of urate (lithate) of ammonia, with or without free uric acid (*red gravel*). Next in frequency is pure uric acid. The ammoniaco-magnesian phosphate, or a mixture of this with amorphous phosphate of lime (*white gravel*), comes next in order; then oxalate of lime. These deposits may co-exist or alternate with each other. When the deposits become aggregated to form small calculi, the symptoms are much more severe. (For the mode of distinguishing these several varieties see pp. 123, *et seq.*)

The symptoms of *calculus in the kidney* are those of gravel in its most severe form, viz., pain in the loins, extending to the groin, testicle, or extremity of the penis, retraction of the testicle, painful and frequent micturition, and bloody urine; nausea and vomiting, restlessness, and slight fever. These symptoms are often suddenly removed by the discharge of a small calculus, accompanied, perhaps, by a large deposit of gravel. If the calculus remain in the kidney, the pain becomes fixed and increased by exercise, and especially by jolting or descending a staircase or steep hill. Hæmaturia and suppurative inflammation (*pyelitis*) and its complications (p. 539) are the consequences.

The symptoms of *calculus in the ureter.*—When a calculus is passing along the ureter, there are paroxysms of intense pain (a fit of the gravel), or a dull pain along the affected ureter and spermatic cord on the same side, extending to the penis, the testicle, or the inside of the thighs. There is frequently great tenderness in a circumscribed part of the abdomen, corresponding to the seat of the calculus. The patient is troubled with constant and often ineffectual calls to pass urine, which is tinged with blood. There are severe nausea and vomiting, and intense suffering. These symptoms may pass off suddenly as soon as the calculus reaches the bladder, followed in some cases by its discharge from the urethra. In other instances, the calculus remains impacted in the ureter, leading to disease of the kidney, or giving rise to large accumulations of urine, with distension of the ureter, of the pelvis, and even of the walls of the kidney itself. The kidney thus enlarged has grown to such a size as to fill the abdomen (*hydro-nephrosis*) and be mistaken for ascites.

The symptoms of *calculus in the bladder* are, frequent desire to pass water; during its passage a burning sensation at the orifice of the urethra; sudden interruptions of the stream, accompanied by great forcing and intolerable pain; after lying on the back the urine again flows; the discharge of the last ounce is attended with excruciating pain, caused by the contraction of the bladder upon the stone; frequently there is numbness and tormenting pain down the inside of the thigh. After violent exercise, or long continuance of the symptoms, the urine becomes purulent and bloody, from inflammation of the mucous membrane of the bladder.

Causes.—*Predisposing.* High living; sedentary habits; rheumatic and gouty diathesis.—*Exciting.* Cold; blows and injury to the loins; parasites (p. 550–3); dyspepsia; the use of water containing much calcareous matter. In the case of the oxalate of lime gravel, an excess of saccharine matters, and of vegetables and fruits containing oxalic acid; organic disease of the kidney or bladder.

Treatment.—This varies with the species of gravel discharged.

In *uric lithiasis* a diet chiefly vegetable, and in extreme cases entirely so, with total abstinence from fermented liquors and wines. Diluents; the bicarbonate of potash, and salts of lithia, taken in a tumbler of cold water an hour before meals, three or four times a day, so long only as the urine has an acid reaction. The alkaline aërated waters of Vichy and Carlsbad.

In *phosphatic lithiasis* a more generous diet is admissible, with a moderate allowance of wine, and the mineral acids (the nitric, muriatic, or nitro-muriatic acid) should be given at short intervals. When the phosphatic diathesis has been brought about by exhaustion of mind or body, opium usually proves very serviceable.

In *oxalic acid lithiasis* mineral acids (Form. 122). Henbane is appropriate for the relief of pain, or irritability of any part of the urinary tract. All articles of food containing oxalic acid should be avoided and saccharine substances taken in moderation or in extreme cases, disallowed; and soft water alone should be used.

In all forms of gravel, strict attention must be paid to the general health; and to the functions of the skin, stomach, and bowels. Warm bathing is beneficial by promoting the action of the skin. Our efforts must be directed to relieve pain and facilitate the passage of the calculus. When there is positive evidence of the existence of a calculus in the kidney, the pain being so frequent and severe as to render life a burthen, the question of removing the calculus through the loin should be entertained. The result of the operations is such as to promise a successful issue in healthy subjects. The medical treatment of *calculus in the bladder* will depend on the nature of the gravel voided by the patient.

HÆMATURIA.—BLOODY URINE.

Symptoms.—An evacuation of blood in the urine.

Causes.—Congestion of the kidney, or of any part of the mucous membrane of the urinary organs, idiopathic, or produced by cantharides, turpentine, &c.; nephritis; calculus in the kidney, ureter, bladder, or urethra; blows on the loins; diseased prostate; chronic inflammation or ulceration of the mucous membrane of the bladder; villous tumours or malignant fungous growths from the mucous membrane. Sometimes hæmaturia occurs in the course of purpura, variola, typhus, and scarlet fever. In certain aguish subjects, and in some other conditions, this symptom is *intermittent*. The strongylus gigas, a nematoid worm, is a rare cause of hæmaturia. In Brazil, the West Indies, Egypt, Mauritius, Natal, and Cape of Good Hope, hæmaturia is *endemic*, and is due to animal parasites resident within the urinary organs (see p. 550).

DIAGNOSIS.—Bloody urine is of a bright-red or dark-brown colour, and if the quantity of blood be considerable, a dark brown deposit, or distinct coagula are formed. For the chemical and microscopical characters, see p. 133. When the secretion is acid, and the blood in very small quantity, the urine has a smoky appearance, like weak tea or coffee.

The source from which the blood flows may sometimes be inferred from the accompanying symptoms, and a careful examination of the urine. If the hæmorrhage be preceded by pain in the region of the kidney, the blood be equally diffused through the urine, and contains casts of the uriniferous tubules (see p. 136), the blood is from the kidney. When the urine first discharged from the bladder is little, or not at all, tinged with blood, and the remainder is highly charged with it, there is a strong presumption that the hæmorrhage is from the bladder, especially if symptoms of stone are present. When the blood flows without discharge of urine, it is derived from the urethra.

TREATMENT.—Must be determined by the probable cause of the hæmorrhage. If the disease arise from injury, or the patient be of a full habit, cupping of the loins, rest, and gentle aperients will be required. If irritation of the kidney by calculus be the cause, frequent draughts of mucilaginous liquids, as thick barley water, solution of gum acacia, decoction of marsh-mallows sweetened with honey; opium; henbane; and copious emollient clysters; together with the remedies proper for that disease, should be prescribed. When the blood coagulates in the bladder, and gives rise to dysuria, the catheter must be used.

When the hæmorrhage is excessive, cold water, or a cold solution of alum (℥j-Oij) may be injected into the rectum. At the same time the vegetable astringents (Form. 155, 154) may be given by the mouth. Acetate of lead with opium forms a useful combination. The tinctura ferri perchloridi is suited to the anæmic.

INTERMITTENT OR PAROXYSMAL HÆMATURIA.

SYMPTOMS.—The excretion of dark red, or reddish brown albuminous urine, after exposure to the outer air on a cold—and especially *a damp, windy* day. There is an inability to resist cold owing to an undue sensitiveness of the skin, which is either very pallid, or sallowish, and in some cases becomes on exposure quite livid. The patient experiences occasional chills, or distinct aguish attacks. In most cases the general health is but little affected, in others there is much depression and discomfort, the coldness of the surface recurring every morning, recovery gradually taking place towards evening and continues until the next day.

PATHOLOGY.—In some cases, intermittent congestion of the kidneys from temporary contraction of the cutaneous capillaries; in others, renal congestion or irritation dependent on the oxalic diathesis. In all cases the urine deposits a large quantity of chocolate-coloured matter composed of disintegrated blood corpuscles, occasionally moulded into casts of the uriniferous tubules. In one class of cases, crystals of oxalate of lime are always present (Fig. 39, p. 136). The term *Hæmatinuria* has been given to this symptom, as implying an escape of blood colouring matter by the kidneys; but it is inappropriate, since the urine contains the whole of the constituents of the blood, and occasionally the corpuscles are entire.

CAUSES.—1. Severe congestion of the kidneys from prolonged exposure to cold immediately following profuse sweating. 2. The irritation of crystalline matter in the kidneys.

TREATMENT.—Those suffering from the aguish variety need a warm dry climate, the precautions requisite for keeping the skin warm and moist, and ague-doses of quinine. In the oxalic variety nitric, or nitro-hydrochloric acid, in combination with henbane is very serviceable.

ENDEMIC HÆMATURIA.

One of the above-mentioned causes of hæmaturia prevails so widely among the inhabitants of certain regions as to require separate consideration. It is known to be endemic in the West Indies, in Egypt, in the Mauritius; and some years ago I called attention ("Med. Chir. Trans." 1864, *et seq.*) to its existence in Natal and the Cape of Good Hope, at Uitenhage, Port Elizabeth, &c.

Dr. T. Bilharz, of Cairo, has shown that the hæmaturia and gravel (lithiasis) so common in Egypt is due to the presence of a nematoid worm, variously termed Distomum hæmatobium, Gynæcophorus hæmatobius, and Bilharzia hæmatobia. It is a minute white worm, less than half an inch long. In Fig. 83, the female, (A B C D), is represented partly lying within the gynæcophoric canal of the male (C); the eggs (E) are considerably magnified. The parasite inhabits the veins of the urinary and portal systems, but more commonly those of the former, causing much congestion and hypertrophy of the mucous membrane of the bladder, ureter, and pelvis of the kidney.

The hæmaturia of the south-east coast of Africa and Mauritius is due to the same parasite.



Fig. 83.

SYMPTOMS.—The symptoms of the disease prevalent in South Africa and Mauritius are the following:—The passage, with the last ounce of urine, of a little blood, rarely exceeding a teaspoonful; or bloody, or colourless mucus, moulded so as to resemble "veins," which sometimes cause a little obstruction, and give rise to straining. When the parasite inhabits the kidney, an occasional smart twinge of lumbar pain is felt. The urine is clear and pale, the blood being rarely or never diffused through it. After exertion the quantity of blood is increased. During the earlier years of the disease no other pain or inconvenience is experienced. The disease attacks both sexes at about the age of ten. My friend, the late Mr. Dunsterville, of Port Elizabeth, informs me that two out of every three schoolboys were affected, and their linen was commonly blood-stained like that of the other sex from the menstrual discharge.

Adults, and occasional residents of certain localities in the Cape and Natal, are also liable to the attacks of the parasite, and a person may acquire it on merely passing through the infected district.

After a few years the hæmaturia gradually declines, and, as a rule, entirely disappears at the age of puberty; but the cause, as manifested by the presence of ova in the urine, persists, and sooner or later gives rise to severe symptoms of gravel. The urine abounds in salts; and crystalline deposits, chiefly composed of oxalate of lime, form around the ova which the parasite produces in great abundance. The eggs may thus become the nuclei of renal or vesical calculi.

DIAGNOSIS.—The presence in the urine of the characteristic ova, *a b* (Fig. 84). They measure the $\frac{1}{170}$th of an inch long, and the $\frac{1}{400}$th broad, and are sharp-pointed. The colourless or bloody mucus casts, *a*, frequently contain scores of these ova. Occasionally the ciliated embryo, *c*, may be observed escaping from the egg, *d*.

CAUSE.—The introduction of the parasite into the stomach by means probably of water, or of certain water plants or salads, or possibly into the blood by hypodermic puncture or cutaneous ulceration—almost all of my patients show scars on the legs, the result of some peculiar boils.

Prophylaxis.—The use of filtered or boiled water, and prevention of the contamination of the streams by the urinary products of individuals suffering from the disease.

Fig. 84.



Treatment.—This must be directed: I. To kill or expel the adult sexual parasites. II. To secure the continuous expulsion of the ova which, so long as they remain in the body, may at any time become the nuclei of urinary calculi. To destroy the parasite, which is not simply attached to the surface, but contained within burrows of the mucous membrane, we must introduce into the blood a remedy poisonous to the parasite. Iodide of potassium is such a remedy, and we may daily inject from ten to twenty grains dissolved in ℥iv of infusion of quassia into the bladder. Ten to fifteen grains of extract of male fern may be occasionally substituted for the iodide, to induce strong expulsive efforts, whereby the worm may be dislodged from the mucous membrane. As atropia and hyoscyamia are wholly eliminated by the kidney, it is probable that a persevering use of belladonna and henbane may retard the development of the parasite, even if it do not cause its destruction. These remedies are at the same time most beneficial in allaying the irritation arising from crystalline deposits.

The hæmaturia of Brazil, the West and East Indies is, as far as the evidence goes, due to a different parasite. See the following Article.

CHYLURIA.—CHYLOUS OR FATTY URINE.

Symptoms.—The passage of opalescent, or milk-like urine. Sometimes it has a faint pink tinge from the presence of blood. Occasionally the urine coagulates in the bladder and gives rise to retention. Otherwise the symptoms are very slight. In aggravated cases, debility, loss of flesh, and pain in the loins constitute the general symptoms.

The urine is generally abundant, of a milky appearance, and varying in density from 1010 to 1020. After this discharge it sometimes coagulates into a white gelatinous substance, like blancmange, taking the form of the containing vessel. It more frequently retains the liquid condition, and separates after some time into a clear yellowish fluid and a white clot; at other times a white flaky matter is deposited; or a white cream rises to the surface. The opalescence is due to fatty matter in the molecular condition; small granular cells resembling chyle corpuscles, and sometimes a few red blood corpuscles are also observed. On analysis, the urine furnishes, in addition to its normal constituents, fat and albuminous matter.

The disease is rare in temperate regions; but prevails endemically in the East and West Indies, Brazil, Mauritius, and Bourbon.

Treatment.—Does not admit of removal; but it may be palliated by gallic acid, and the astringent chalybeates.

Pathology.—Dr. H. V. Carter ("Trans. Med. and Physiol. Soc." Bombay, 1861) concludes that the chyle, by rupture of the walls of dilated lymphatic vessels, obtains direct entrance into some part of the urinary passages. In three of his cases there was an accumulation of milky chyle in the enlarged inguinal glands. A very close connection appears to exist between hæmaturia and chylous urine. The diseases frequently coexist. Further, hæmaturia and chylous urine are both endemic, *and both prevail in the same localities*. The late Dr. Wucherer, in the *Gazeta da Bahia*, 1869, was the first to demonstrate the existence of living *filariæ* in the recently voided urine. Dr. J. Crevaux confirmed this observation in a native of Guadaloupe. Subsequently Mr. T. R. Lewis has established the same fact in connection with the chylous urine of India. His observations were made 'on upwards of fifteen cases, all of which were associated with hæmaturia. He very properly regards the chylous urine as a mere accident attending the presence of vast numbers of these minute worms in the blood, and probably in the lymphatics also. He says, that in certain individuals numbers of the worms can be obtained day after day by pricking any part of the body. On one occasion, he obtained six excellent specimens in a single drop of blood from the lobule of the ear. Fig. 85 (after Dr. A. Corre) represents the parasite: the average length is the $\frac{1}{75}$ of an inch, and the breadth that of a red blood corpuscle: A gives the appearance of the living, and B that of the dead, animal. No organs can be distinguished, but Dr. Corre regards a slight constriction of the anterior extremity as characteristic. Its movements are very active.

Fig. 85.



ISCHURIA RENALIS.—SUPPRESSION OF URINE.

Symptoms.—Languor, restlessness, weariness and weight in the loins and legs, frequent pulse, hot skin, flushed face, headache, nausea, and vomiting. About the third day drowsiness and œdema of the face, or general anasarca follow. Some hours afterwards epileptiform convulsions, often very violent and frequent, come on, and after three or four attacks the patient falls into a state of profound coma, and dies. At the onset, a small quantity of muddy urine may be voided; but when the disease is fully formed, there is anuria, or complete suppression.

In some cases, there is neither pain in the loins nor fever, but only slight nausea and drowsiness. During the second or third day the patient becomes comatose, and dies in from 24 to 30 hours. In some cases, the suppression is a consequence of retention of urine in the kidney from obstruction of the ureters, and in these the disease sets in with excruciating pain, which at length subsides; and the patient becomes drowsy and dies comatose.

Causes.—Chronic disease of the kidney, aggravated by exposure to wet and cold. The action of certain poisons, as digitalis, arsenic, corrosive sublimate, and cantharides. Acute inflammation of the kidney. Mechanical obstruction in the ureters. The infectious fevers.

Diagnosis.—From *retention of urine* by the empty state of the bladder as ascertained by the hand, or the catheter.

Prognosis.—*Unfavourable* in chronic disease of the kidney; *more favourable* when it occurs in acute disease.

Treatment.—*Indications.* I. To promote the elimination of urea by copious purging and diaphoresis; gr. i of elaterium, or ♏ii of croton oil should be given immediately, and a hot-air bath. The function of the kidney may be aroused by the injection of the [illegible] of a grain of atropia beneath the skin.

II. If acute nephritis be present, ℥x or ℥xx of blood may be taken from the arm, or the loins may be cupped or leeched, and hot stimulating fomentations subsequently applied.

III. The head symptoms must be treated by blisters to the forehead and nape, and if the head be hot, by a bladder of ice to the vertex.

DIABETES.—IMMODERATE FLOW OF SACCHARINE URINE.

Symptoms.—That which first attracts attention is frequent micturition. The urine is excessive in quantity, of a pale straw colour, [illegible] a peculiar faint odour resembling hay, has a sweet taste, and contains more or less sugar. There is inordinate appetite, excessive [illegible] and constipation, the stools being dry and hard. The tongue is clammy, and red at the edge, or clean, or white with a brown streak down the middle; the gums are red and tender; the throat dry; the breath has often a sweetish odour, like that of hay; and the skin is dry and harsh. The patient is weak and loses flesh; and becomes anxious, sad, and irritable. After the disease has continued for some months, or even for several years, the symptoms continuing to increase, the emaciation becomes extreme, and the patient either dies of exhaustion or phthisis. Death often comes suddenly, and therefore unexpectedly.

In some cases the sugar disappears from the urine and reappears after a variable interval. Sugar is frequently present in small quantity in the urine of old people, without producing injurious effects

PATHOLOGY.—The following facts have been established:—I. Sugar invariably exists in minute quantity in the blood of the hepatic veins, and rapidly increases after death. II. A substance (*glycogen*) may be artificially separated from the liver, which under the influence of saliva, pancreatic fluid, blood, liver tissue, &c., gives the reaction of grape sugar. III. Glycogen is formed with equal facility and abundance when the food consists of nitrogenized matter only, saccharine or starchy articles of diet being unnecessary for its production.

From these facts Bernard infers that sugar is formed in the liver during healthy assimilation; that it passes out of it into the blood of the hepatic veins; and is carried to the lungs, where it undergoes oxidation and conversion into carbonic acid and water, which are eliminated as such from the lungs.

According to this theory, the liver and lungs have a reciprocity of function in the generation and destruction of sugar; and the most obvious explanation of the appearance of sugar in the urine is, that the reciprocal action of these two great glands have become disproportionate the one to the other. Thus, under certain abnormal conditions, the liver may generate a larger amount of sugar than could be destroyed in a single circulation through the lungs, and sugar enters the general circulation, and is separated by the kidneys. Again, when only a normal quantity of sugar is separated by the liver, disease or functional derangement of the lungs may render these organs inadequate to perform their sugar-destroying function, and thus also the saccharine matter would pass into the general circulation.

But according to Dr. Pavy, glycogen is not normally converted into sugar in the liver. He supposes that it ought to be converted into fat, and that it is only when the function of the liver is disturbed, as in diabetes, that it undergoes metamorphosis into sugar. He believes that this metamorphosis is the result of the changes which commence immediately after the death of the animal. He bases this conclusion upon a frequently repeated observation, that the blood of the right side of the heart of a living animal contains *only that trace of* sugar (about one grain in 1000 parts) which can be detected in the blood of the left side of the heart. It appears, then, that we must regard the generation of sugar in the liver as a result of derangement or perversion of its function. Amongst the causes of this specific derangement are irritations of the pneumogastric nerve and brain. Thus, Dr. Bernard induced diabetes by irritating the pneumogastric nerve at its origin in the floor of the fourth ventricle. Dr. Goolden observed that diabetes was a frequent result of blows on the head; and we have had several opportunities of convincing ourselves of the accuracy of his observations.

Morbid Anatomy.—The kidneys vascular and hypertrophied; rarely presenting granular degeneration. Tubercular deposit in the lungs; shrunken condition of the brain.

Complications and Secondary Disorders.—Pulmonary phthisis (the most common complication); granular degeneration of the kidney; peritoneal inflammation; anasarca; apoplexy.

Prognosis.—*Favourable.* The intermittent form of the disease; a short previous duration; urine not exceeding 12 pints in quantity and 1036 in density; the emaciation inconsiderable; the appetite and thirst not excessive; the skin still soft and moist; and the mind tranquil. When the patient is under treatment, the signs of improvement are a decrease in the quantity of the urine and of solids discharged, increase of weight, strength, and activity, moderate appetite and thirst, the mind becoming clearer and more cheerful.—*Unfavourable.* Prolonged duration of the disease, great emaciation, and rapid diminution of strength, the supervention of pulmonary or renal disease, great and sudden prostration of strength.

Causes. — *Predisposing.* Hereditary tendency. — *Exciting.* Phthisis; injuries of the head.

Diagnosis.—Excessive diuresis; 8 gallons of urine are sometimes voided in the 24 hours; 2 gallons being about the usual quantity. The specific gravity ranging between 1030 and 1070. It has a sweet taste, and on evaporation leaves a white powder or sticky residue—sugar. The quantity of sugar passed in the 24 hours varies from half a pound to three pounds. For the mode of detecting sugar in the urine, and of ascertaining its quantity see p. 130.

Treatment.—I. The diet should consist chiefly of animal food, broiled or roasted, with a small quantity of stale and well-fermented bread; and liquids in moderate quantity, of which the best are weak beef or mutton tea, milk, pure spring water, or water holding calcareous salts in solution. Gluten and bran bread may be substituted with advantage for common bread. The liver, indeed, readily converts albuminous substances into sugar; but when the diet is restricted to azotized food, the sugar decreases.

II. The quantity of fluid should be limited, and spirituous liquors, saline aperients, and all articles of diet or medicine which have diuretic properties, avoided. The secretion of the skin may be stimulated by warm baths, friction, and warm clothing; and by opium in small and repeated doses, as v to x grains of Dover's powder two or three times a day. I have found ergot (♏ x to xxx of the liquid extract twice a day), most valuable in the treatment of diabetes.

III. The intense thirst is best relieved by iced water acidulated with phosphoric acid. Claret is a suitable drink.

IV. The strength must be supported, and the disease kept in check by the administration of ♏xx-♏xl tincturæ ferri perchloridi twice or thrice a day, and a full dose of opium at bedtime every other night. Constipation should be relieved by resinous purgatives; and debility, when extreme, by tonics and stimulants.

In one case that was under my care, a young female continued for months to pass large quantities of saccharine urine without losing flesh or suffering in health. She took no medicine, except a simple tonic infusion, and continued, though not very strictly, a diet containing an excess of animal food. It is evident that no part of the sugar was formed at the expense of the structures of the body. So long as a patient does not lose flesh, it is probably inexpedient to adopt any other treatment. (G.)

DIURESIS.—IMMODERATE FLOW OF URINE.

The passage of large quantities of watery urine is a direct result of the excessive use of fluids, especially of spirituous liquors. It also occurs during functional irritation of the kidney, at the end of the hysterical fit, and after other mental agitation.

The term chronic diuresis is used by Dr. Watson to designate the condition which has been wrongly named *Diabetes insipidus*. The disease, or rather symptom of disease, consists in the excretion of large quantities of urine only differing from that of health in containing more water, or more or less urea than normal. These variations have been significantly termed by Dr. Willis, *hydruria*, *azoturia*, and *anazoturia*, respectively. When the urea is in excess the specific gravity of the urine is unusually high. In the other varieties it is exceedingly low. The diuresis is commonly associated with thirst, and some disorder of the digestion.

The treatment must be directed to the regulation of the cutaneous and gastric functions.

DISEASES OF THE BLADDER.

CYSTITIS	Inflammation of the Bladder.
ENURESIS	Incontinence of Urine.
DYSURIA	Difficulty in voiding the Urine.
IRRITABLE BLADDER.	

CYSTITIS.—INFLAMMATION OF THE BLADDER.

1. ACUTE CYSTITIS.

SYMPTOMS.—Pyrexia; acute pain, swelling, and tension in the *region of the bladder*; pain and soreness, increased upon pressure above the pubes, or in the perineum; frequent micturition; painful discharge of urine, in small quantities, or complete obstruction to its passage; tenesmus; vomiting.

Causes.—Mechanical injury; falls on the abdomen when the bladder is distended; local irritation by calculi; gonorrhœal inflammation extending along the urethra; spasmodic or permanent stricture; all the usual causes of inflammation; cantharides; stimulant urethral injections; cold (*catarrhus vesicæ*).

Treatment.—Leeches to the perineum, followed by a hot bath and fomentations, and a brisk saline purgative combined with a full dose of opium.

The condition of the urine must be carefully determined. If it be hyperacid, alkalies; if alkaline, acids, with opium, should be given.

When ammoniacal, the bladder should be washed out daily with carbolic acid water (1 part to 40).

2. Chronic Cystitis.—Cystorrhœa.

Symptoms.—The discharge of an increased quantity of mucous with the urine, with slight symptoms of inflammation of the bladder.

Causes.—Diseases of the prostate, urethra, ureters, or kidney. Stone in the bladder. Ulceration of the mucous membrane. Retention of the urine in cases of paralysis due to spinal disease. Obstruction to the flow of urine out of the bladder.

If the urine remain long in the bladder it undergoes decomposition; the urea assimilates four equivalents of water, and is converted into carbonate of ammonia, which sets up chronic inflammation, and the urine becomes bloody, and highly offensive.

Prognosis.—*Unfavourable* in the aged and intemperate, especially when associated with paralysis, or renal disease.

Treatment.—In simple cystorrhœa the use of uva ursi, buchu, pareira, cubebs, copaiba, black pepper, combined with mineral acids. The irritability of the bladder is relieved by emollient injections, such as decoction of marsh-mallows with laudanum, and by hot fomentations. The feet should be kept warm, and the patient protected against cold.

If the urine be ammoniacal, bloody, offensive, and loaded with mucus, the bladder should be frequently washed out by the double-channeled catheter, with warm water slightly acidulated with hydrochloric or nitric acid, or carbolic acid water (1 pt. in 40). In cases of paralysis, the urine should be drawn off at least twice a day.

ENURESIS.—INCONTINENCE OF URINE.

Incontinence of urine may arise from mechanical causes, or from functional derangements of the bladder. The latter class comes within the province of the physician.

Causes.—Incontinence of urine, without organic defect, may arise from one of two causes; violent contraction of the bladder, the sphincter possessing its usual power; or relaxation of the sphincter, the bladder retaining its normal contractile power. In the first case, there is generally some source of irritation within the bladder, the urine being hyperacid, or containing acicular crystals of uric acid; but in rare instances the muscular fibres are thrown into spasm without obvious cause. The first form is most common in males; the second in females and children.

Treatment.—In incontinence arising from spasm the most effectual remedy is henbane combined with carbonates of the alkalies, or with acid, according as the urine is hyperacid or alkaline. A grain of solid opium as a suppository, or half a drachm of laudanum in a wineglassful of mucilage of starch, injected into the rectum, will generally succeed in relieving the spasm. If lithiasis be the cause of the incontinence the appropriate remedies must be employed. (See p. 548.)

In incontinence arising from debility of the sphincter, two or three drops of tincture of cantharides, with ten drops of tincture of perchloride of iron, rarely fails to relieve the symptoms. I have had several cases of this kind, which have received immediate benefit and a speedy cure from this mode of treatment. In one case, occurring in a young adult, after cantharides had failed, tinctura ferri perchloridi in the dose of ʒss three times a day effected a speedy cure. (G.)

In many cases the urine is perfectly retained during the day, and voided only at night. These require the same treatment.

DYSURIA.—DIFFICULTY IN VOIDING URINE.

Dysuria may exist in every degree, from slight and momentary arrest of the flow of urine, with or without pain, to complete retention. Some degree of pain generally attends the abortive attempts to discharge the urine, and in severe cases the suffering is intense.

Causes.—Long retention or acidity of the urine; irritation or inflammation of the coats of the bladder. Gonorrhœa, inflamed prostate, gravel, urinary calculus, cystitis and nephritis, inflamed hæmorrhoids, inflammation or irritation of the rectum, uterine affections, pregnancy, &c. *Strangury*, an aggravated form of dysuria, is produced by cantharides and other strong irritants. Dysuria is also a symptom of hysteria, and may occur in nervous persons of both sexes. The mechanical causes are stone in the bladder, stricture of the urethra, abscesses in the perineum, prostatic tumours, displacements of the uterus.

Treatment.—This must depend on the cause. Of causes external to the bladder, constipation is the most common; and a brisk purgative, or a proper course of aperients, will soon remove the disease.

Spasm of the muscular coat requires the use of the warm bath with opiate suppositories or enemata. When the spasm is of frequent occurrence, tincture of the muriate of iron in repeated doses.

When the urine is scanty and acid, alkaline diuretics, and diluents will be required. Dysuria following long retention of urine is best relieved by the warm bath.

IRRITABLE BLADDER.

Some persons are subject to constant calls to void urine, as others are troubled with diarrhœa. They suffer much when confined in churches, courts of law, railway trains, &c., &c., and much more (as a rule) early in the day than in the evening. It is natural that such persons should have their sufferings increased by nervous apprehension. The treatment will consist in the scrupulous avoidance of spirituous liquors and all known diuretics, and of liquids in excess, on the eve of travelling or of detention. When opium is borne well, a small dose of the tincture may be taken by way of precaution. Those who suffer most from this cause should wear habitually, or as occasion requires, a suitable flexible and water-tight apparatus, to be had of surgical instrument makers.

CHAPTER VI.

DISEASES OF THE ORGANS OF GENERATION.

AMENORRHŒA.
DYSMENORRHŒA.
MENORRHAGIA.
LEUCORRHŒA.
METRITIS.
DISEASES OF THE OS AND CERVIX UTERI.
CANCER OF THE UTERUS.
FIBROUS TUMOURS.
PELVIC HÆMATOCELE.
UTERINE DISPLACEMENTS
OOPHORITIS.
OVARIAN TUMOURS.
GONORRHŒA.
SYPHILIS.
SPERMATORRHŒA.

AMENORRHŒA.—ABSENCE OF MENSTRUAL DISCHARGE.

SPECIES.—1. Amenorrhœa from organic deficiency. 2. Amenorrhœa from functional derangement.

1. ORGANIC AMENORRHŒA.

CAUSES.—Absence of the ovaries; disease or defective development of the ovaries; absence or defective development of the uterus or vagina. Treatment, with a view to the establishment of the function, is of course useless in such cases.

2. FUNCTIONAL AMENORRHŒA.

VARIETIES.—(*a.*) Primary suppressed menstruation. (*b.*) Amenorrhœa with plethora. (*c.*) Amenorrhœa with anæmia or chlorosis.

(*a.*) PRIMARY SUPPRESSED MENSTRUATION.

The age at which menstruation begins is very variable. In this country it may be as early as the tenth, or as late as the twentieth, year. In most cases it comes on between the ages of fourteen and fifteen. (See p. 80, last edition, Dr. Guy's For. Med.)

The discharge is usually preceded by the following symptoms:—A little languor, flushing of the face, throbbing headache, and aching pain in the loins. In some cases there is also well-marked pyrexia. After a few hours an oozing of thin non-coagulable dark-coloured blood of acid reaction appears, continues for a variable period, usually three or four days, and then ceases, the whole quantity discharged being usually about six ounces.

In many cases the menstrual nisus occurs and recurs with increasing severity every month without any sanguineous discharge. Such are cases of primary suppressed menstruation.

TREATMENT.—When the above-mentioned symptoms come on, a brisk aloetic purge, followed by Form. 285, and a hot hip-bath. Strict attention must be paid to the general health in the intervals. Moderate exercise should be taken, and fatigue and exposure to cold and wet avoided.

In the *chronic* form the menstrual nisus is absent, and the general health is delicate. In such cases we may give chalybeate tonics, combined with stimulants, to improve the general health, and at suitable periods we may endeavour to elicit the menstrual flow by the exhibition of emmenagogues. (Form. 286.) If these fail, we may try electricity. The best emmenagogues are the remedies and modes of treatment which tend to restore the health and strength of the patient.

(*b.*) AMENORRHŒA WITH PLETHORA.

The general symptoms and constitutional treatment are those of plethora. (See p. 251.) When blood is abstracted, it should be taken away at the approach of the menstrual period.

(*c.*) AMENORRHŒA WITH ANÆMIA OR CHLOROSIS.

For a description of the constitutional symptoms and treatment of anæmia and chlorosis, see p. 255 *et seq*. Amenorrhœa is often the first symptom of anæmia and chlorosis; or it may make its appearance after these states have existed for a considerable period.

In addition to the general treatment of anæmia, it is sometimes necessary to prescribe the measures for the restoration of the menstrual discharge mentioned under the first variety of the disorder.

Amenorrhœa is sometimes attended by vicarious or supplemental discharges of blood, or of blood slightly altered, from the nose, lungs, stomach, or rectum, and from ulcers, or even from the skin itself. These discharges, if occurring in important organs, require medical interference, and are best treated by leeching and purging, a little before they are expected.

The catamenia are normally absent during gestation and lactation. Some women, however, menstruate during pregnancy only; and others during lactation.

The *complications* of amenorrhœa are extremely numerous, and must be treated by remedies appropriate to them, combined with such as restore strength, and tend to re-establish the menstrual discharge.

DYSMENORRHŒA.—PAINFUL MENSTRUATION.

SYMPTOMS.—Pain in the loins preceding the menstrual period by a few hours or days; tenderness in the hypogastric region; and sometimes over a considerable extent of the abdomen; soreness or acute darting pains, resembling those of colic, and occurring mostly in paroxysms; vomiting; diarrhœa with tenesmus; dysuria.

Hysteria is often present. These symptoms increase in severity until the appearance of the catamenia, and then cease suddenly or gradually. Severe cramp, with rigors and coldness of the surface, almost amounting to collapse, precede the flow in some cases. The discharge is often scanty, and is sometimes accompanied by a membranous formation (decidua) moulded to the internal surface of the uterus.

CAUSES.—*Predisposing.* The rheumatic diathesis; the nervous temperament.—*Exciting.* Sudden and violent emotions; increased determination of blood to the uterus; sexual intercourse immediately before the expected flux; constipation; spinal irritation; exposure to cold; mechanical obstruction from organic or spasmodic constriction of the cervical canal, or from retroflexion of the uterus.

PROGNOSIS.—*Favourable.* Most cases admit of cure, or relief, by the improvement of the health, and proper local treatment.

TREATMENT. — I. When there is plethora, the application of leeches to the vulva, or cupping-glasses to the loins; tepid, hot, or vapour baths; opium and henbane alone, or with small doses of tartarated antimony frequently repeated.

II. Careful attention to the functions of the stomach and bowels, moderate depletion to meet any irregular determination of blood, and strict attention to the general health.

Organic impediments must be removed, if possible. Stricture of the cervical canal may be relieved by graduated bougies carefully introduced. Those made of the *Fucus Laminaria* are objectionable.

MENORRHAGIA.—EXCESSIVE MENSTRUATION.

The menstrual flux is excessive, when the intervals are less than three weeks, or when it continues longer than six days, and is abundant during the whole time. It may be the effect of plethora (*active m.*); or of general relaxation or debility (*passive m.*).

SYMPTOMS.—Menorrhagia, from plethora, is usually preceded by acute pains in the head and loins, a sense of heat, fulness, and throbbing in the pelvis, turgid flushed countenance, universal heat, and a strong, hard pulse; when, on the contrary, the symptoms of debility prevail, the pulse is small and feeble, the face pallid; there is dull aching pain in the back and loins, and in nervous persons the group of symptoms described under Mimosis Inquieta. (See p. 261.)

CAUSES.—*Predisposing.* Plethora; laxity of the womb from frequent parturition; displacement of the womb; difficult and tedious labours, or repeated miscarriages; a sedentary and inactive life; heated apartments, and all causes of debility.—*Exciting.* Violent exercise; blows or concussions; straining at stool; tight lacing; sexual excess, particularly during menstruation; exposure to wet and cold; congestion or ulceration of the mucous membrane; uterine tumours. Menorrhagia is common in women at or shortly after the change of life.

Prognosis.—*Favourable*, if it be not of very long standing, or dependent upon organic disease.

Treatment.—The treatment of menorrhagia consists in—

1. Reducing the febrile symptoms and the plethoric condition of the pelvic circulation by free purgation, gr. x of colocynth and blue pill, followed by a saline (Form. 242) with ♏xx tincture of henbane.

2. When the febrile symptoms are subdued, astringents (Form. 149).

If the hæmorrhage be profuse, cold water should be injected into the rectum and vagina. If this does not suffice, injections of alum or tannic acid should be used. Plugging the vagina is to be avoided on hygienic grounds.

The patient should keep the horizontal posture on a hard mattress. The clothing should be light, and the regimen cooling.

3. When symptoms of debility are present, tonics or stimulants, in combination with sedatives, are required.

LEUCORRHŒA.—THE WHITES.

Definition.—Discharge of a milk-white or glairy mucous fluid from the orifice of the vagina.

Varieties.—1. Vaginal. 2. Uterine.

1. Vaginal Leucorrhœa.—Vaginitis.

Symptoms.—Pain and soreness, with heat and fulness of the vagina; vesical and urethral irritation, resulting in frequent micturition, pain, and dysuria; soreness and itching of the vulva; a thin colourless acid discharge becoming, in the chronic form of the disease, more or less creamy or purulent. The vagina is swollen and tender, and the mucous membrane, which is naturally of a pale rose tint, is uniformly dark red, and inflamed. This is an uncommon form of the disease.

Diagnosis.—There are no characters by which simple vaginitis may be distinguished from the gonorrhœal variety. The character of the patient and of her husband, if she be married, must decide the diagnosis. Some observers are of opinion that simple leucorrhœa may, by contact, induce both urethral discharge and preputial sores in the male. From the uterine variety, it is distinguished by the absence of inflammation of, and discharge from, the os uteri, by the thinner and more acid nature of the discharge, and by the circumstance that vaginal leucorrhœa is not increased before or after the time of menstruation. There is also an absence of uterine symptoms, and the health suffers less.

Causes.—Simple vaginitis usually results from direct irritation:

e.g. pessaries in the vagina; violence in sexual intercourse; irritation of the rectum from piles or ascarides. It is often associated with excessive acidity of the urine.

Treatment.—*General,* saline alkaline aperients, and the hip-bath.—*Local,* the removal of any sources of irritation which may be present; injections of warm water, and afterwards of astringents, (Form. 172, 176.)

In the chronic form the most scrupulous cleanliness is required. Zinc or alum injections should be used twice a day; and quinine or the astringent chalybeates should be prescribed.

2. Uterine Leucorrhœa.—Inflammation of the Cervical Canal.

Symptoms.—The discharge of an inodorous white creamy fluid varying in quantity from a slight increase of the natural secretion to several ounces in the day, increased largely immediately before and after menstruation, and sometimes taking its place. Pain and weakness of the loins, excessive debility, and a sense of bearing down in the pelvis; the vagina is relaxed, and the os uteri lower than normal; the cervix uteri is swollen, and the os red, congested, patulous, and occupied by a glairy secretion like white of egg. As this passes down the vagina, it becomes altered by its acid secretion into a creamy fluid. The general health suffers in a marked degree; the appetite is lost or impaired; the bowels are constipated, or irritable. Spinal irritation is often present, and the symptoms described under Mimosis Inquieta (p. 261).

Causes.—Inflammation of the os and cervix uteri; the discharge is derived from the extensive glandular surface which Dr. Tyler Smith has shown to line the canal of the cervix uteri. Debility, suppressed menstruation, abortion, frequent parturition, lactation, and congestion of the cervix uteri, all predispose to this condition.

Treatment.—I. Must be directed to improve the general health by the judicious use of saline aperients and tonics, moderate exercise, rest of the sexual organs, cold bathing, and, if need be, change of air. II. The local treatment will consist in the use of cold water or astringent injections (Form. 174). When much irritability is present, opiate injections may be required; and if there be much congestion, or signs of local inflammation, a few leeches may be applied to the neck of the uterus.

The remedies which act on the mucous membrane through the general system are given in the Formulæ.

METRITIS.—INFLAMMATION OF THE UNIMPREGNATED UTERUS.

1. Acute Metritis.

Symptoms.—Pain, increased by pressure, in the region of the uterus, and in the cervix on examination per vaginam; pain extending to the loins and thighs; dysuria; a sense of weight and bearing down; swelling of the abdomen and tympanites. These local symptoms are generally accompanied by fever, with nausea and vomiting. In the most severe cases, there are slight delirium, drowsiness, extreme prostration of strength, diarrhœa, and subsultus tendinum. At first there is no vaginal discharge, but after a day or two, an abundant and often offensive purulent, or muco-purulent, discharge, occasionally tinged with blood, appears. The uterus is slightly enlarged, and very tender to the touch, and the arteries of the cervix pulsate strongly.

Morbid Anatomy.—The substance of the uterus inflamed and enlarged, œdematous, and softened: in severe cases, pus is infiltrated through its tissue; or an abscess is formed in it. Purulent matter may also be found in the veins of the pelvic areolar tissue, and in the folds of the broad ligament. Swelling and redness of the mucous membrane.

Causes.—*Predisposing*. Those of inflammation generally.—*Exciting*. Suppression of the menstrual discharge from cold; extension of gonorrhœal inflammation; physical injuries; blows and falls.

Treatment.—Leeches to the vulva or groins; a free saline aperient followed by calomel and opium (Form. 295), hot fomentations, turpentine stupes, or sinapisms, a hot-hip bath. Dysuria may be relieved by mucilaginous drinks, and the bowels should be kept free by gentle saline aperients, or by castor oil.

2. Chronic Metritis.

This is a common consequence of the acute form, when neglected or badly treated. It may lead to severe structural lesions of the uterus, such as ulceration, suppuration, membranous inflammation, and enlargement and induration of the mucous follicles and muscular structure of the organ.

INFLAMMATION OF THE OS AND CERVIX UTERI.

1. Simple Congestion and Ulceration.

Symptoms.—Uterine leucorrhœa, occasionally tinged or streaked with blood; pricking, darting, or throbbing pain in the situation of the os uteri; great irritability of the bladder; a sense of bearing down. Action of the bowels, sitting, and sexual intercourse produce pain. The pain increased before the appearance of the catamenia, and usually absent for a short time afterwards. The menses unusually profuse.

The os uteri is low down, swollen, and tender, and the hard and painful glandular tissue can be felt through the mucous covering. The cervix is enlarged, congested, and presents superficial ulceration of variable extent on one or other side of the os. The ulcerations are depressed, and usually present healthy granulations. In chronic cases the granulations are angry-looking, and the edges of the ulcer thickened.

Treatment.—The *general* treatment will be the same as that for inflammation of the os and cervix uteri. (See Uterine Leucorrhœa.)

The *local* treatment consists in the use of mild zinc injections, and the repeated applications of nitrate of silver, solid, or as in Form. 163. When the cervix is within the patient's reach she may occasionally apply the Unguentum hydrargyri nitratis.

2. Corroding Ulceration.

Symptoms.—Pain and weakness in the loins; with pelvic pain and uneasiness, sometimes of an acute burning or cutting nature, excited and increased by the passage of hardened fæces. At first there is leucorrhœa, subsequently a thin watery yellowish discharge, occasionally tinged with blood; as the ulceration spreads, attacks of profuse hæmorrhage, which sometimes recur so often as to endanger life. The finger detects a loss of substance; the cervix is shorter or altogether absorbed, but the eroded surface is soft and rarely very uneven; there is no induration about the edges or base of the ulcer, the whole surface of which has a pulpy feel. Pressure with the tip of the finger does not produce pain, but merely a sensation of soreness. The ulcer has a ragged excavated appearance, and is covered with ashy-grey débris; when these are removed a raw bleeding surface is exposed. In severe cases the ulceration extends to the contiguous parts of the vagina. The fundus of the uterus is unaffected, and easily moved.

The patient becomes anæmic and exhausted by the repeated hæmorrhage due to the erosion of bloodvessels; and if the disease be not speedily checked, she dies of asthenia.

Diagnosis.—From cancerous ulceration by the absence of induration, of acute pain on pressure, and of paroxysms of darting pelvic pain, by the *mobility* of the uterus and the limitation of the disease.

Prognosis.—*Unfavourable*, but if we can treat the disease early, we may arrest, and in some cases cure it.

Treatment.—Must be directed to improve the health by astringent tonics and nutritious food; and to check the erosion by the application of strong nitric acid, the acid nitrate of mercury, nitrate of silver, or the actual cautery. The most efficacious is the actual cautery. When the eschar separates the caustic should be again applied if the surface does not present a granular appearance. When healthy granulations appear, we may expect a permanent cure. The vagina should be frequently injected with astringent lotions.

CANCER OF THE UTERUS.

Varieties.—1. Medullary. 2. Epithelioma (cauliflower excrescence.)

1. Medullary Cancer.

Symptoms. Paroxysms of deep-seated pain in the pelvis readily induced by evacuation of the bowels or bladder, menstruation or sexual intercourse. The paroxysms gradually lengthen, the pain assumes a sharp neuralgic or lancinating character, and the menstruation becomes irregular. Menorrhagia is an early and prominent symptom. There is a sense of weight and fulness in the pelvis. The cervix is enlarged and hard, the os uteri patulous, and its margins hard and deeply notched; pressure produces acute pain; the body of the uterus is enlarged, and loses much of its mobility. The os and cervix appear swollen, tense, and of a mottled red, or purplish colour; in many cases the mucous membrane retains its natural appearance. The indurated tissue soon begins to ulcerate and break down, and a watery, greenish, very fœtid discharge, occasionally tinged with blood, appears; with frequent hæmorrhage. The enlarged cervix becomes soft and ragged, and the finger may be readily passed into the uterus, the walls of which feel partly pulpy and partly nodular. The fundus is firmly fixed in a solid mass which surrounds it. The degeneration and ulceration slowly extend backwards, involving the rectum; or forwards, implicating the bladder. The walls of both these cavities are sometimes destroyed, and the contents mingle in the vagina with the uterine discharges, and are in part evacuated through the vulva. The health rapidly declines, the stomach sympathises and food is rejected, the cachexia and emaciation are extreme, and the patient dies, worn out by excruciating pain and excessive discharges.

Diagnosis.—Hæmorrhage, and in the intervals a watery fœtid discharge; deep-seated paroxysms of lancinating pain; indurated enlargement of the os and cervix uteri; *immobility* of the fundus; emaciation and a sallow cachetic appearance are positive indications of the cancerous nature of the disease.

Treatment.—In the early stage when the disease is limited to the vaginal portion of the cervix, its removal by means of the écraseur. Later on the treatment must be palliative only—the application of caustics does harm. The general treatment will consist in the exhibition of chalybeate tonics, iodide and bromide of potassium, combined with tonic infusions. The pain and irritability of the stomach may be relieved by alkalies in a state of effervescence, combined with hydrocyanic acid. When the stomach [illegible] bear it, cod liver oil may be given to counteract the emacia[illegible]. The strength should be sustained by wine and light nu[illegible]ious diet administered frequently in small quantities. Sleep must [illegible] procured, and the uterine pain alleviated by occasional doses of opium. Opiate suppositories and injections may be employed with the same view. The vagina must be frequently washed out with warm water, to which a little carbolic acid has been added, to destroy the fœtor of the discharges. The most scrupulous attention to cleanliness will be required; especially when the disease opens the rectum or bladder.

2. Epithelioma (Cauliflower Excrescence).

Symptoms.—A copious watery offensive discharge, occasionally streaked with blood, from the vagina; occasionally profuse florid hæmorrhage, induced by sexual intercourse, straining at stool, or any other direct cause of congestion or irritation; a rough villous insensible mass of a florid colour, and a granular or villous structure; bleeding freely when handled, is felt attached to the os uteri at some part of its circumference. Its growth is rapid, and it sometimes attains such a size as to occupy the whole of the vagina and protrude between the labia. The disease is limited to the uterus, and if removed is speedily reproduced. The patient rapidly becomes anæmic, and dies of asthenia.

Diagnosis.—The structure and appearance of the tumour and its origin, by a broad base from the os uteri, are conclusive as to its nature.

Treatment.—The *general* treatment will consist in the exhibition of the astringent chalybeates combined with the mineral acids; the only efficient *local* treatment is removal of the tumour and contiguous part of the cervix uteri by the écraseur or galvanic cautery; followed by astringent injections.

FIBROUS TUMOURS OF THE UTERUS.

These occur, I. As interstitial growths within the muscular walls. II. As isolated fibrous or fibro-cartilaginous masses developed within the walls, and projecting more or less from them. As pedunculated growths attached to the outer, or more frequently, to the inner surface of the uterus (*Uterine polypi*).

The *first* and *second variety* often form enormous growths, sometimes weighing more than fifty pounds, and are accompanied by hypertrophy of the uterus and enlargement of its cavity. They are composed of white fibrous or of fibro-cartilaginous tissue, and have very little vascularity. They are of gristly, and occasionally of bony hardness. Their colour is greyish-white, and the section is pervaded by intersecting or concentric bands of white fibrous tissue. The first variety of tumour is continuous with the uterine tissue; the second, which is almost always composed of fibro-cartilage, is surrounded by a distinct areolar investment, which, by limiting it, allows of its ready separation from the contiguous uterine tissue. Usually there are more than one of these tumours. In projecting outwards towards the peritoneal cavity, or inwards towards the mucous surface, they sometimes become almost completely invested, in the former case with peritoneum, in the latter with mucous membrane, and so come to form large pedunculated growths. Cysts are occasionally formed in the interior of these tumours.

The *symptoms* which attend the development of the first and second variety are precisely similar. They are usually so obscure that the tumour attains a considerable size before it attracts attention, and then the patient supposes that she is pregnant or dropsical. When the rectum or bladder are pressed upon, there will be frequent desire to evacuate the fæces and urine, and more or less difficulty will probably attend these acts. The menstrual function is sometimes interfered with, sometimes not. In the majority of cases the discharge is more profuse than usual, and it comes on at irregular intervals; occasionally there is dysmenorrhœa. The os and cervix uteri are felt to be natural; but around and above the latter there is a hard rounded mass, filling up the sacral cavity. If the other hand be placed upon the lower part of the abdomen, a large hard nodular mass may be tilted against it, by pressing the tumour upwards with the finger. The uterine sound readily passes, sometimes in one direction, sometimes in another, an unusual distance within the uterine cavity, proving that it has undergone considerable enlargement.

The health is unaffected so long as the pressure of the tumour does not produce derangement of the contiguous viscera or blood vessels.

Treatment.—The treatment of the first variety must be purely constitutional. With a view of reducing the tumour and preventing its further development, chloride of calcium, iodide or bromide of potassium, and the Kreuznach waters have been recommended.

Enucleation has been proposed for the second variety; but the operation has been attended with so large a proportion of deaths that we deem it unjustifiable. When self-enucleation of the tumour has been nearly effected, we may facilitate its expulsion from the uterine cavity by dilating the os and cervix and administering ergot.

The *third variety* of fibrous tumours (*uterine polypi*) give rise to much more serious *symptoms*. These are leucorrhœa and hæmorrhage, which increase in severity and endanger the patient's life. At first the menstrual periods are protracted, then the discharge becomes more profuse. In the intervals there is profuse leucorrhœa. After a time the sanguineous discharge becomes continuous, and is attended by constant bearing down or dragging sensation. On examination, the os uteri is felt low down and patulous, and on passing the finger within the orifice a firm rounded projection may be felt, which can only be mistaken for the inverted fundus. The *diagnosis* is readily effected by means of the uterine sound; in the case of the pedunculated tumour, the cavity is enlarged, while in inversion of the fundus it is diminished. If the cervical canal be contracted it must be dilated with a sponge tent in order to ascertain the existence of a tumour.

Treatment.—The only efficient treatment consists in the removal of the tumour. The os uteri having been dilated, the tumour must be seized with a hooked forceps and pulled downwards, and a ligature passed round the pedicle. Whenever it is practicable, the pedicle should be severed by the écraseur, or blunt scissors; for the putrefactive process which follows ligature without subsequent removal of the tumour, is very liable to set up putrid fever and endanger the patient's life.

PELVIC HÆMATOCELE.

Synonyms.—Uterine, peri-uterine, and recto-uterine hæmatocele.

During the intense vascular excitement of the menstrual periods, the congested vessels of the ovary or fibrated extremity of the Fallopian tube may break and lead to effusions of considerable quantities of blood into the recto-uterine pouch. This accident of menstruation is most frequent between the ages of twenty and thirty, the period of greatest sexual vigour.

Symptoms.—Usually after sudden suppression of the menstrual discharge, severe abdominal pain, undergoing increase at intervals, tenderness of the lower parts of the abdomen, difficulty and pain in micturition and defæcation; usually pain in flexing one or other thigh; increased fulness of the abdomen. The pelvic tumour differs much in size and situation; but it usually bulges the posterior wall of the vagina, tilts the body of the uterus forwards, and feels hard and solid. If all go on well, the pain and fever subside, and the blood begins to be absorbed. During the process, which is a slow one, there remains some difficulty in evacuating the contents of the bladder and rectum; there is weight and bearing down in the pelvis, and walking causes pain or inconvenience. The effused blood sometimes sets up pelvic inflammation, and the clot, becoming imperfectly encysted, breaks down into pus. The abscess may burst into the vagina, rectum, bladder, intestine, or into the peritoneal cavity.

Treatment.—At the time, complete rest, a drastic purgative (Form. 253), followed by a full dose of opium, and subsequently Form. 194, with a little sulphate of magnesia.

The absorption of the blood tumour may be facilitated by iodine infrictions, and the internal administration of iodide of iron. The menstrual function should be regulated, and the circulation relieved, before each catamenial period by the administration of a brisk hydragogue purgative.

DISPLACEMENTS OF THE UTERUS.

The unimpregnated uterus is liable to downward, backward, and forward displacements, known respectively as *prolapsus*, *retroversion*, and *anteversion*.

Prolapsus may be *partial;* or *complete*, when the womb protrudes entirely out of the vagina.

Symptoms.—A sense of bearing down; dragging pain in the loins; leucorrhœa. If the uterus be displaced suddenly, acute pain, fainting, and hæmorrhage.

Diagnosis.—From protruded pedunculated tumour, by the arrest of the uterine sound when passed aside of the tumour into the vagina. The finger or sound cannot be introduced beyond the prolapsed uterus, because the vagina is pushed down with it and inverted. The prolapsed uterus forms a pear-shaped tumour, the small end being directed downwards and presenting the orifice of the cervix. These characters distinguish it from the inverted uterus.

Causes.—Leaving bed too soon after parturition; debility and leucorrhœa; severe chronic cough; straining; injuries to the perineum.

Treatment.—Tonics, astringent injections, and sponge pessaries are usually sufficient for the relief of partial prolapse; a T bandage and suitable pessaries are needed in addition, when the prolapse is complete.

Retroversion.—I. When the womb is completely displaced, the fundus is directed backwards against the rectum, and the os forwards towards the symphisis, and the organ lies horizontally across the pelvis. II. The position of the os and cervix may not be greatly altered, while the fundus is bent downwards and backwards at the upper part of the cervix, so as to descend as low as the os and lie in the recto-uterine pouch; this condition is known as retro*flexion*.

Symptoms.—Sacral pain, aggravated at the menstrual periods, sense of dragging in the groins and down the inside of the thighs, irritability of the bladder; dysmenorrhœa; menorrhagia. The os uteri is swollen, congested, low down, and directed more or less forwards; behind it a firm round tumour can be felt through the posterior wall of the vagina, filling up the hollow of the sacrum and pressing on the rectum. On tracing the cervix upwards from the posterior lip, the finger comes upon the angle formed by the body and neck of the uterus. The uterine sound passes but a short way if its curve be directed forwards, but on rotating the handle, the instrument readily passes into the uterine cavity, and its point can be felt, by the finger in the rectum, occupying the interior of the retroflexed fundus.

Causes.—Predisposing. Abortion, constipation, retention of urine, laxity of the uterus, and of the round and broad ligaments. *Exciting.* Straining; a false step.

Treatment.—Replacement with the uterine sound, after which the patient should lie in the prone position for some hours daily, for a time; astringent injections; the bowels to be kept free, and all straining avoided.

Anteversion may occur as a *malformation;* but as a *displacement* in an unenlarged uterus it is anatomically impossible, so long as the bladder is properly formed, and rightly placed.

)PHORITIS.—INFLAMMATION OF THE OVARY.

'PTOMS.—A dull, sickening, deep-seated pain in the groin, enderness of the iliac region. So long as the inflammation is ;d to the ovary the pain is local, but frequently it involves the uous peritoneum, and becomes diffused over the lower part of domen, which is swollen and tender; the pain becomes more , and radiates down the inside of the thigh, being increased :ension of the leg; nausea and vomiting come on, and the oms much resemble simple peritonitis; but on manipulation ve no difficulty in tracing the pain to its source deep in one or of the iliac fossæ. The os and cervix uteri are usually very l to the touch, owing to the transmission of the pressure to flamed ovary. On passing the finger alongside the cervix, the iitely tender ovary may be felt through the wall of the vagina, in the direction of the sacro-iliac articulation. Whether we ıe ovary or not, pressure in this direction causes intolerable ing pain.

JSE.—Suppression of the menses, from exposure to cold.

ɛATMENT.—A full dose of opium; leeches, applied to the groins, or, still better, to the upper part of the vagina on the painful a hot hip bath and a brisk purgative; hot fomentations to ıdomen. If there be signs of peritoneal inflammation, calomel)ium must be administered, so as slightly to affect the gums. e menstrual flow can be re-established, the patient will bly do well. If the acute inflammation be neglected or imrly treated, the disease becomes chronic, and ovarian dysmen:a, or cystic disease of the ovaries, will result.

OVARIAN TUMOURS AND DROPSY.

arian tumours are almost invariably cystic growths.

ım the nature of the changes which attend the development ischarge of the ovum, no other organ is so liable to cystic ıeration as the ovary. All the elements of this morbid process resent at every menstrual period.

e following varieties of ovarian tumour are found to occur:—

The *simple cystic tumour*.—The ovary being distended into a ɜ cyst containing several gallons of fluid, which is usually a watery serum, but, in some cases, a thick brown grumous which, when heated, becomes solid.

Compound ovarian cysts.—In these the proportion of solid luid constituents varies; sometimes the cysts are very large, ıeparated by thin partitions; sometimes small, and surrounded ıick walls of firm fibrous or vascular tissue (*Cystosarcoma.*)

Alveolar or *colloid tumour*.—In this form the enlarged ovary is oped into innumerable minute cells, not exceeding an inch in eter, filled with a glutinous jelly-like material.

4. *Cysts containing developed tegumentary organs*—teeth and hair.

Symptoms.—At first obscure, so as to attract little or no notice. Suppression or irregularity of the menses, is one of the earliest symptoms; pain, referred to the side where the disease begins, is present in one-third of the cases; retention of urine, or difficult micturition, in about one-ninth; in one-third of the cases the tumour is discovered unexpectedly. (West.) It is always at first seated on one side. When it has attained such a size as to attract the patient's notice, there is pain or numbness extending down the corresponding leg; and when the left ovary is affected, the passage of fæces may be hindered. Usually there is more or less complete suppression of the catamenia.

As the tumour grows it distends the abdomen equally, and may then be mistaken (if mostly solid) for the pregnant uterus; a fibrous tumour of that organ; cystic disease of the kidney (see p. 545); or, if it be fluctuant, for ascites.

Ovarian Dropsy.

The first two varieties of ovarian tumour (the monocystic and the polycystic) are those that give rise to ovarian dropsy. A distinction can generally be made by the extent of the fluctuation. In the case of the single cyst, a tap on one side of the belly produces distinct fluctuation on the other. When the cyst is compound, the partitions interrupt the fluctuation generated in any one cyst, and it can be only felt within its own limits. In either variety the most protuberant parts of the abdomen are dull on percussion, while the sides are more or less resonant. The belly does not swag to the sides when the patient lies in this position; the upward development of the tumour causes great divergence of the false ribs, and if the fingers be insinuated between their margin and the tumour, its tense rounded outline may be felt.

Diagnosis of Ovarian Dropsy.—From the *pregnant uterus*, by the absence of fœtal sounds and movements, and by the unaltered state of the uterus. From *ascites*, by the history of the case, which shows that the tumour commenced in the side; in ascites the tumid abdomen sways from side to side according to the position of the patient; and its most prominent parts are resonant from air in the floating intestines, the pelvic viscera are pushed down, and the uterus is low: and some cause of ascites, such as an enlarged nodular liver, may also be discovered. In ovarian disease, the tumour rises out of the pelvis, and drags the uterus a little way with it.

The *distended bladder* has been mistaken for ovarian dropsy. As it forms a symmetrical pyriform tumour, this can only occur through gross carelessness; but there is some excuse for mistaking for it an asymmetrical multilocular bladder. I have myself seen half a pint of urine drawn, by the trocar and canula, through the abdominal walls, from a distended bladder of this description.

Treatment.—If the tumour come under treatment early, increases, and is movable, it should be extirpated forthwith. From the results of the operation of spaying in quadrupeds we infer how safely the removal may be effected in the early stages of the disease. When the tumour has attained a great size, removal should not be attempted if, from manipulation and the history of previous attacks of pain and pyrexia, we infer that the tumour is adherent. In such cases, if the tumour be fluid we must resort to tapping as often as the pressure of the tumour interferes with the respiratory or digestive functions. Excision of a portion of the cyst wall, and the injection of solutions of iodine have been successfully employed to procure inflammatory adhesion of the cyst walls and obliteration of the cyst in those cases in which the tumour cannot safely be removed.

With a view of arresting the growth of the tumour we must seek to improve the health of the patient by astringent tonics.

GONORRHŒA.

Definition.—A specific inflammation of the genito-urinary mucous membrane from impure sexual connection.

Symptoms.—In men, about seven days after contagion, a tickling sensation at the orifice of the urethra and scalding pain along the passage in micturition; the orifice is red and swollen, and in the course of a few hours a thin discharge, quickly becoming thick, puriform, and of a yellowish white colour, appears. The passage becomes much swollen, and the stream of urine is diminished. Painful erections occur, and occasionally a little bleeding takes place after micturition. The prepuce is usually much inflamed and swollen, giving rise to phymosis or paraphymosis. If the body of the penis be implicated in the swelling, painful curving of the organ (chordee) takes place during erection. In severe cases the inflammation extends backwards, to the seminal ducts, and thence along the vas deferens to the testicle, or to the bladder, producing severe inflammation of these parts. When orchitis supervenes, the puriform secretion is altogether suppressed. When suppression occurs, febrile symptoms set in, often attended by severe ophthalmia or swelling of the joints (gonorrhœal rheumatism).

In women the inflammation is usually confined to the vagina, and unless the urethra is implicated, little pain or inconvenience is experienced. When it extends to the uterus, symptoms of severe metritis (p. 565.) apppear.

Fig. 86.



Diagnosis.—From simple urethritis and vaginal leucorrhœa, by the violence of the inflammation. Donné considers the presence of the ciliated animalcule, the Trichomonas vaginalis (Fig. 86), to be diagnostic of the specific vaginal inflammation; but it is formed with other morbid conditions of the vaginal mucus.

Treatment.—In mild cases the administration of saline purgatives: and injections of warm water, followed by a mild lead or zinc injection. If the discharge do not cease after the pain and inflammatory symptoms have disappeared, copaiba or cubebs are required.

If there be much swelling and chordee, hot fomentations and the use of lint soaked in the Linimentum belladonnæ; to prevent the latter condition, a grain of opium with camphor may be given.

In many cases the discharge degenerates into a colourless glairy secretion, very difficult to remove, known as *gleet;* due to a congested and relaxed condition of the mucous membrane of the urethra. In such cases cubebs, copaiba, and cantharides are often efficacious.

SYPHILIS.

Definition.—A specific disease, arising from contact with a specific animal poison.

Symptoms.—After a period of incubation, varying from three to five days, the appearance of a pimple, pustule, crack, or abrasion on the skin or mucous membrane of the genital organs. In the male the glans or the under surface of the prepuce, and in the female the inner surface of the labia, are the parts usually affected. The pimple enlarges, and the base becomes red; usually the summit softens down into a thin purulent fluid; the cuticle gives way, and a minute excavated sore, without granulations, is formed. The sore now enlarges, and in two or three days attains the size of a pea; it is perfectly circular, deeply and smoothly concave, and covered with a smooth ashy layer of sloughy tissue, and limited by a smooth, round, narrow, red ring, barely or not at all elevated above the surrounding surface. As the ulcer grows, the red edge becomes broader and is raised, and the surrounding tissue is indurated: minute raw or pale granulations, partly covered with ashy *débris*, spring from the bottom of the ulcer and yield a little ichorous, watery, or thin purulent discharge. This is the *soft chancre.* In a certain proportion of cases the induration and elevation increase, and a well marked "Hunterian" chancre is thus formed. Cracks and abrasions, if left to themselves, tend to the same condition. In some cases the pimple never becomes pustular, but undergoing enlargement and induration, passes into a characteristic red tubercle.

After a variable interval, secondary symptoms occur, showing that the virus has been absorbed. The earliest and most constant of these is bubo. One or more glands in the groin become enlarged, hard and tender. At first they are not inflamed, their surface is smooth, and they readily move under the finger. They may remain in this condition for months; but usually inflammation, acute or chronic, supervenes. The gland enlarges, and, the surrounding areolar tissue being implicated, loses its mobility. If the inflammation be acute, the integument becomes tense and red, and sooner or later there is fluctuation.

Among the earliest and most common of the secondary symptoms, is ulceration of the membrane of the soft palate and mouth. The ulcers are usually superficial, and appear as mere abrasions surrounded by slightly elevated rounded smooth margins, about which the epithelium has an opaque appearance. They occur on the inner surfaces of the lips, at the angles of the mouth, on the sides of the tongue, but chiefly on the arches of the soft palate and surfaces of the tonsils. In this last situation they are apt to become excavated and ragged. Frequently the mucous membrane and submucous tissue of the larynx is similarly affected, and the voice becomes gruff and husky.

This condition of the mucous membrane is almost always associated with one or more of the following forms of cutaneous disease.

Syphilitic roseola.—After slight constitutional disorder, with headache, and frequently tenderness of the scalp, the trunk, limbs, and face become mottled with light mulberry-coloured blotches, not elevated, and disappearing on pressure. The epidermis is unaffected, and the spots are distinct, and shade off into an indistinctly circular margin. This rash is slow in disappearing. It is, doubtless, the first stage of the leprous affection. Its appearance is usually followed by rapid shedding of the hair, sometimes leaving the scalp almost bald.

S. impetigo.—The favourite seat of this eruption is the scalp. It is preceded by pain and tenderness, and commences as distinct red circular spots, which become slightly raised; a muco-purulent exsudation next takes place beneath the epidermis, and the spots are subsequently covered with greenish scales. If these be removed, a little depressed, irritable sore is exposed, on which the scab reforms again and again. Ultimately they heal and leave minute scars. The eruption often appears on the face and other parts of the body.—*S. ecthyma* and *rupia* are but increased developments of this form in debilitated constitutions.

S. lepra appears first as roseola. The injected derm subsequently becomes thickened and elevated into a round copper-coloured "*S. tubercle,*" or, if less elevated, a slightly tumid base, on which the epidermal cells become dry and silvery, constituting *S. lepra* and *psoriasis*. Occasionally the rash is much congested, and shows a tendency to ulcerate. When this occurs we have either *S. tubercle, lupus*, or a characteristic *serpiginous ulceration.*

S. lichen.—Small, hard, conical, copper-coloured elevations, formed of the hypertrophied papillæ of the skin, appearing over all parts of the body, and being often intensely irritable. Usually they remain dry, and covered with scaly epidermis; but in persons of feeble constitution they suppurate, and may then be described as

S. varioloid eruption.—The lichenous rash may have existed for weeks, or have preceded the pustular eruption but a short time. The papules exhibit first a little milky serum; but in about a week they are converted into pointed, thick-set but discrete pustules, resting on an inflamed, slightly raised, bright rose or copper-coloured base. They appear earliest, and in greatest numbers, on the face; later and more thinly scattered on the trunk. A fortnight or three weeks may elapse before the whole of the pustules on the body maturate. The subsequent history of the pustule is much the same as that of variola; but the processes of squamation, desquamation, and the absorption of the inflammatory products around the bases occupy a much longer time. Minute cicatrices stained for a long time with a dusky brown colour, remain. When the eruption is extensive and well-marked, the patient presents the appearance of one covered with small-pox; but on closer examination, the small size of the pustules offers a ready distinction.

S. tubercle.—Indolent fiery-red, or coppery, flat tubercles, from a mere pimple to a nut in size, occupying the face, nape, and shoulders. The nose and forehead are perhaps the commonest situations. The tubercles are liable to ulcerate and form, in debilitated subjects, ill-conditioned ulcers, surrounded by dusky red areolæ. The tubercles may persist for a long time and ultimately degenerate into lupus, and invade and destroy the parts on which they are formed.

Such is the relationship which careful observation leads me to establish between the principal syphilitic skin diseases.

But the skin and mucous membranes are not the only structures affected by the syphilitic virus. The serous and fibrous tissues may be involved. The iris, retina, dura mater, and periosteum, and, worse than all, the bloodvessels are each and all, at a later period, liable to be affected. The resulting iritis, retinitis, epileptic convulsions, periostitis, and cerebral symptoms, are usually classed as tertiary symptoms. The periostitis, if chronic, results in severe neuralgic pains, and nodes; if acute, it ends in necrosis. The same poison induces similar morbid processes in the viscera. (See Diseases of the Liver.)

Syphilitic inflammation in or around the bloodvessels of the brain and spinal cord, produce every variety of nerve affection. Severe neuralgia, epilepsy, cerebral hæmorrhage with hemiplegia, mental aberration, muscular paresis, local paralysis—the third and seventh nerve being especially liable to suffer—and paraplegia.

If personal cleanliness be neglected, and the discharges from the primary sores be allowed to excoriate the contiguous parts, condylomatous growths result. It is not uncommon in young females, ignorant at first of the nature of the disease, and when informed, ashamed to apply for advice, to find the vulva, perineum, and margin of the anus covered with condylomatous growths, and the labia and clitoris themselves converted into large misshapen pendulous masses, exuding an offensive ichorous fluid. Warts, and probably elephantiasis, have the same origin.

PATHOLOGY.—The syphilitic poison, when introduced into the blood, causes a low sluggish form of adhesive inflammation, accompanied by the effusion of solid unorganized matter. Unlike the solid products of common inflammation, this material seems little sceptible of absorption or of conversion into fibrous tissue. Like tubercular matter, its tendency is to break down and to produce unhealthy ulceration.

CONTAGION.—A person may become infected with syphilis in three ways:—1. By *absorption*. 2. By *inoculation of the discharge* from a chancre. 3. By *inoculation of the blood* of a person in whom secondary symptoms are present. The disease is commonly propagated by the first mode, the poison being absorbed during sexual intercourse through the delicate cuticle into the capillaries of the mucous membrane; and more readily if the cuticle be abraded.

With regard to inoculation, M. Ricord has shown that if matter from a chancre be taken on the point of a lancet and introduced into the skin of a person *free from constitutional syphilis*, a similar infecting chancre is produced there. The following is a description of its development. During the first twenty-four hours, a little redness round the puncture; second to third day, a papular elevation seated on an inflamed areola or base; fourth day, a vesicle due to the effusion of turbid fluid beneath the cuticle covering the papule; fifth day, the effusion increases and becomes more or less purulent; the centre of the pustule is depressed, and the areola redder and swollen; sixth day, the tissue surrounding the base of the pustule hardens and feels elastic like fibro-cartilage. Subsequently the swelling, induration, and effusion increase, the cuticle gives way, a scab forms, and when this is detached the indurated chancre above described presents itself. If, however, the syphilitic virus have been previously absorbed into, *and be actually present* in the blood of an individual, inoculation of matter from an infecting sore on his own person, or on that of another, produces no effect. This non-production of a chancre around the point of inoculation is accepted as proof that the syphilitic poison already pervades the constitution. It would appear that the constitution is infected on or about the fifth or sixth day of the development of a primary chancre, that is, at the time when the specific induration appears. If, then, the individual be inoculated before the fifth day with syphilitic matter from his own developing chancre, or from any other source, an infecting chancre will be produced around the point.

As to the third mode of propagation, it has been proved that inoculation with the blood of a person affected with secondary syphilis will produce an infecting chancre. The disease has been transmitted in this manner by vaccination, and the blood of a child suffering from secondary syphilis having mingled with the vaccine matter derived from it, imperfectly developed vaccine vesicles have resulted, and passed into the condition of indurated chancres—a result the more remarkable since the infecting child itself never had the primary disease.

Hereditary transmission of syphilis.—Just as the *fœtus in utero* participates in small-pox affecting the mother, so may it be with syphilis. Hundreds of sickly infants attest this painful fact.

Several good observers consider it to be well-established that the infection of the infant may take place independently of the existence of a chancre or syphilitic bubo in the mother during gestation.

Origin.—Some authors are of opinion that syphilis has its origin in some very remote age, and that it has been transmitted by successive contact with infected persons to the present generation. When it has been proved that certain conditions, or combinations of circumstances, happened in remote ages, which are never repeated now, we may accept this hypothesis. At present it is more philosophical, and more in accordance with what we know of the origin of other contagious diseases, to assume that the virus is every day generated anew.

Diagnosis.—The primary sore may be known by the ashy excavation or pale warty granulations of the surface, and by the elevated, rounded, circumscribed induration which borders and surrounds it.

Treatment.—I. *Local.* Before the end of the fifth day, the primary sore admits of arrest and cure by the application of nitrate of silver, strong nitric acid, or caustic potash. When the slough has separated, the ulcer may be dressed with black wash or calomel ointment. If the disease come under notice after induration, local treatment will be of no service. The sore must be kept clean and free from irritation, and constitutional treatment adopted.

II. *Constitutional.*—This consists in the exhibition of mercury in the form of calomel or pilula hydrargyri in small and repeated doses, combined, if bubo be present, with the infriction of mercurial ointment into the groins until the gums become red, slightly swollen, and tender. No disease has a remedy more efficacious than syphilis has in mercury, and if the patient be carefully watched, even stomatitis need not result from its use. Under its influence, the hard effused products melt away, the bubo disappears, the ulcer assumes a healthy aspect and heals. When the constitutional effects have been thus induced, they should be kept up for a time by the occasional use of a little mercurial ointment.

When it is desirable to affect the system speedily, gr. xv to gr. xxx of calomel should be sublimed and the vapour retained in contact with the person by means of a blanket.

If the primary disease have been treated by mercury, secondary and tertiary symptoms, such as the cutaneous and periosteal affections and ulceration of the larynx, very readily yield to iodide of potassium, given in doses of from gr. iii to gr. xxx thrice a day. If mercury have not been used in the treatment of the primary disease, it must be given in combination with iodine. Gr. i to gr. iii hydrargyri iodidi viridis, or gr. $\frac{1}{16}$ to gr. $\frac{1}{4}$ hydrargyri iodidi rubri may be given in the form of pills thrice a day; or the latter may be combined with an excess of iodide of potassium, in solution of which it is soluble, and thus given in the form of mixture.

Two other forms of syphilis remain to be described—viz. Infantile Syphilis and Local Syphilis.

Infantile Syphilis.—The child may be born apparently healthy. The first symptom which usually appears is inflammation of the nasal passages, resulting in a muco-purulent discharge, causing obstructed nasal breathing. This is popularly known as the *snuffles*, and the child is supposed to have a cold. It now becomes pallid and fretful, and rapidly emaciates. After about a fortnight an eruption of copper-coloured blotches appears round the anus, the adjacent parts of the buttocks, and lower extremities, and after a time on other parts, particularly about the folds of the neck and joints. The eruption consists of circular spots slightly raised and subsequently covered with thin dryish cuticle (S. lepra), and on the folds of the groin, and about the perineum it is apt to become moist and excoriated, leading, perhaps, to the formation of condylomata. As the disease progresses, the intervening skin usually becomes copper-coloured, superficial ulcers appear on the inside of the mouth, the infant presents an extremely cachectic and emaciated appearance, and, if the specific remedy be not applied, soon dies of asthenia.

Treatment.—Gr. i to gr. ii hydrargyri cum cretâ twice or thrice a day, continued until the snuffles and rash have disappeared, and for two or three weeks afterwards.

Local Syphilis.—Mr. Henry Lee recognizes four forms of primary syphilis: viz. 1st, The indurated chancre. 2nd, The suppurating sore. 3rd, Ulcerative syphilitic inflammation. 4th, Destructive syphilitic inflammation.

The first two forms are those which have been already described as producing constitutional syphilis. Some deny that the soft chancre can produce secondary symptoms, but this does not accord with my experience. The other two forms are purely local, and, as such, never give rise to secondary symptoms, but they require specific constitutional treatment. The secretion of each of these three latter forms may be artificially inoculated.

SPERMATORRHŒA.

Symptoms.—Involuntary seminal discharges, occurring either during sleep, or in the day-time, and, in extreme cases, on the slightest friction or irritation of the genital organs. The constitutional symptoms are out of proportion to the loss of fluid sustained, and are due in part to the intimate relation subsisting between the sexual function and nervous system. They are those of Mimosis Inquieta (p. 261), and Hypochondriasis (p. 415). The patient is restless, listless, timid, and desponding. He is subject to flushings of the face, headache, giddiness, noises in the ears, disordered vision, dilated pupil, and other symptoms of cerebral congestion, to palpitation and shortness of breath. He is easily startled by noises and readily irritated, and has various nervous feelings, as of cold water trickling down the back, or of ants crawling over the skin; or weakness and numbness of the hands. The memory fails, and the intellect grows weak; the patient hesitates, and often stammers. In the most severe cases, his mind is still more seriously affected. His spirits are depressed; he is addicted to silence and solitude; is timid and morose; believes himself to be the object of plots and persecutions; grows weary of life, and is tempted to commit suicide; and, at length becomes the confirmed victim of monomania or dementia. In some cases the state of mind may be fitly described as one of intolerable discomfort or *malaise*. Such a condition of mind existed in a young man who had been successful at school and college, possessed an intellect of rare clearness, was free from any ascertainable illusion or delusion, but referred with great grief to habits of self-abuse commenced early and abandoned at the age of twelve. After attempting suicide three times on one day, being placed in an asylum and discharged as cured, he succeeded in destroying himself within a day or two of his release. (G.) Among the occasional symptoms and consequences of this affection are impotence, rigid contraction of the limbs, chorea, epilepsy, strabismus, amaurosis, bulimia, and nervous asthma.

CAUSES.—Sexual excesses; masturbation, pruritus scroti, ascarides, hæmorrhoids, fissures of the anus, and stricture of the rectum; blisters and cantharides taken internally; sleeping on the face.

DIAGNOSIS.—The fluid is identified as coming from the vesiculæ seminales by the physical and microscopic characters of the semen (see Fig. 32, p. 134). In one case which came under my notice, the patient mistook an abundant pale sediment of urate of ammonia (Fig. 21, p. 127), completely dissolved by heat, for semen. (G.) The urine alleged to contain semen should always be submitted to examination.

PROGNOSIS.—*Favourable* in those cases in which the discharge is nocturnal, and always preceded and accompanied by the usual sexual phenomena. Less favourable in those cases in which the discharge is diurnal, and produced by slight causes. Most favourable when traceable to irritation in the rectum, urethra, or scrotum.

TREATMENT.—The patient often requires comfort more than medicine. As a general rule, cases in which the emissions are nocturnal, and accompanied by the usual sexual phenomena, admit of cure by abstinence from any bad habits which may have caused them. In all cases aperients regularly administered, to secure a free state of the bowels, are required (aloetic aperients and hypercatharsis are contra-indicated). If nervous symptoms predominate, the treatment prescribed under Mimosis Inquieta; if the patient be pale and anæmic the treatment proper to Anæmia. If ascarides be present, the remedies for the removal of the same. Piles require the treatment recommended at p. 515. If cutaneous eruptions near the parts of generation be the cause of irritation, these will have to be treated according to their form and character. The careful avoidance by patients suffering from this disease, of advertising quacks cannot be too strongly insisted upon.

CHAPTER VII.

DISEASES OF THE EYE AND EAR.

DISEASES OF THE EYE.

1. CONJUNCTIVITIS.
2. SCLEROTITIS.
3. CORNEITIS.
4. IRITIS.
5. DISEASES OF THE CHOROID.
6. DISEASES OF THE RETINA.
7. DISEASES OF THE CHOROID AND RETINA.
8. DISEASES OF THE LENS.
9. STAPHYLOMA POSTICUM.
10. GLAUCOMA.
11. OTHER DISEASES AND DEFECTS OF THE EYE.

INFLAMMATION OF THE CONJUNCTIVA.

VARIETIES.—1. Catarrhal Ophthalmia. 2. Purulent Ophthalmia of Infants. 3. Purulent Ophthalmia of Adults. 4. Gonorrhœal Ophthalmia. 5. Strumous Ophthalmia.

1. CATARRHAL OPHTHALMIA.

SYMPTOMS.—Redness and itching of the conjunctiva, lachrymation, slight intolerance of light, and stiffness of the globe of the eye, followed by pricking pain, the sensation of a grain of sand beneath the eyelid, and adhesion of the eyelashes, on first waking in the morning. The inflammation begins in the conjunctiva of the lids, and gradually extends towards the cornea. In the acute form, the whole eye except the cornea is covered with a vascular network, the secretion becomes puriform or muco-purulent, and patches of blood are sometimes effused beneath the conjunctiva. If the disease extend to the cornea, vision is obscured. There is no constitutional disturbance, beyond the slight feverishness attendant on the catarrh.

CAUSES.—Catarrh; a draught of cold air directed on the eye; foreign bodies in the eye; over-exertion of the sight; the glare of a strong light; all the causes of inflammation in other mucous membranes.

DIAGNOSIS.—From *purulent ophthalmia,* except in severe cases, by its milder character, and by not being contagious. From *inflammation of the sclerotic,* by the brighter colour, larger size, and tortuosity of the vessels, which are obviously superficial, and shift their place with the motions of the lids; by the abundant secretion: by the absence of acute pain in and around the orbit; and by the slight intolerance of light, existing chiefly at the onset of the attack.

PROGNOSIS.—*Favourable.* The disease readily yields to treatment, and, when confined to the conjunctiva, does not threaten the loss of vision. In chronic cases, or after repeated attacks, the lids may become thickened, and that part of the membrane which covers the cornea may be rendered opaque, so as to impair the sight.

TREATMENT.—That of catarrh. Dover's powder may be given at night, with a saline aperient in the morning; or small doses of tartar-emetic, in combination with a saline aperient, two or three times a day.

Local treatment. In severe cases, the application of a blister, or a few leeches to the temple, with fomentations of warm water or warm decoction of poppies. When the inflammation has in some degree subsided, and in mild cases from the first, collyria (Form. 33) will be needed; a large drop or two being placed between the lids at the outer angle twice or thrice a day. Adhesion of the eyelids must be prevented by spermaceti or zinc ointment placed between them at bedtime.

2. PURULENT OPHTHALMIA OF CHILDREN.

SYMPTOMS.—Inflammation in the conjunctiva covering the lids, commencing generally on the third day after birth, and extending over the entire surface of the eye, accompanied by intolerance of light, swelling and firm adhesion of the lids, and a copious discharge of purulent matter, which issues in large quantities on their separation. The membrane is of a bright crimson colour. The discharge is generally yellow, but sometimes greenish, or tinged with blood; or ichorous. The disease may continue for eight or ten days, without involving the transparent parts of the eye; but if it be not properly treated, ulceration occurs at the circumference of the cornea, which first becomes hazy, then opaque, and finally sloughy and infiltrated with pus. Sooner or later it gives way, and the iris protrudes. If the inflammation of the cornea stop short of ulceration it becomes opaque and usually adherent to the iris.

The constitutional symptoms are restlessness, sleeplessness, and disordered bowels,—results of the prolonged local irritation.

DIAGNOSIS.—There is no other disease of the eyes occurring at this early period with which it can be confounded.

PROGNOSIS.—*Favourable*, so long as the cornea retains its transparency.

CAUSES.—The application of leucorrhœal or gonorrhœal discharges to the eye, during parturition; contagion.

TREATMENT.—Few diseases require more assiduous attention, and few so rapidly yield to treatment; neglect for a single day may [redacted]ion. Six times a day the [redacted] separated, and the [redacted]ly syringed with warm water and one or two drops of solution of nitrate of silver (gr. ii to gr. iv to ℥j), or of alum (gr. x to ℥j) dropped into the eye just within the outer canthus. The lids should then be smeared with a little olive oil; and lint wetted with water be kept constantly applied to them. In chronic cases, when the lids present a granular appearance, they may be touched with the solid nitrate of silver or sulphate of copper.

The bowels should be kept free by gentle aperients of castor oil, magnesia, or manna.

PROPHYLAXIS.—The greatest care should be taken to prevent the application of the matter to the eyes of other persons.

3. PURULENT OPHTHALMIA OF ADULTS.

SYNONYM.—Ægyptian ophthalmia.

SYMPTOMS.—The disease generally attacks both eyes, and sets in with the sensation of a foreign body beneath the eyelids, speedily followed by injection of the conjunctiva, effusion of serum beneath it, and a thick puriform discharge. The conjunctiva is of a bright red colour, the lids and anterior surface of the eye are swollen and granular, and the cornea is sunk, as it were, into a deep pit formed by the projecting conjunctiva. There is, here and there, extravasated blood. So long as the conjunctiva alone suffers, the pain is inconsiderable; but when the deep-seated textures are involved, it is extremely severe. In the globe itself, it is a sensation of painful tension, and around the orbit, a pain like that of hemicrania. It is intermittent, or aggravated at intervals, and attains its greatest intensity at night, the sleep being disturbed by paroxysms of pain. There is little intolerance of light in any form of the disease. Rupture of the cornea sometimes takes place with permanent or temporary relief to the pain. The constitutional symptoms are slight.

TERMINATIONS.—In resolution; chronic inflammation; granular conjunctiva; opacity, ulceration, or sloughing of the cornea; staphyloma; prolapsis of the iris. The disease is very apt to recur.

CAUSES.—Contagion. The common causes of inflammation.

DIAGNOSIS.—From *catarrhal ophthalmia* by its greater severity, and greater tendency to attack the deeper seated parts. From diseases of the deeper seated tissues alone, by the severe inflammation of the conjunctiva.

PROGNOSIS.—*Unfavourable*, when very severe, or neglected at its outset. From its tendency to attack the deeper seated structures of the eye, loss of vision, or at least injury to the sight, may be anticipated.

TREATMENT.—Leeches round the orbit, or blisters to the temples. *Strong astringents* (Form. 163). In chronic cases, the vinum opii.

[illegible] place with the motions of [illegible] cleansed by a sy[illegible] acute pain i[illegible] outset; the patient should be p[illegible] [illegible] to take gentle exercise in the open air. When the deeper seated textures of the eye are implicated, the remedies appropriate to the inflammation of those textures should be employed; such as the belladonna ointment in threatened adhesion of the iris; puncturing the cornea to prevent rupture of the membrane; the application of nitrate of silver to ulcers on the cornea, or to the protruding iris.

PROPHYLAXIS.—Great care should be taken to prevent the application of the matter to the eyes of healthy persons.

4. GONORRHŒAL OPHTHALMIA.

SYMPTOMS AND TREATMENT.—Those of purulent ophthalmia of adults; but more severe and much more rapid: a few hours may suffice for its complete development. In order to arrest it, we may pass solid nitrate of silver rapidly over the inflamed conjunctiva.

CAUSE.—Inoculation of the eye with gonorrhœal matter.

5. STRUMOUS OPHTHALMIA.

SYNONYMS.—Scrofulous, pustular, and phlyctenular ophthalmia.

SYMPTOMS.—This disease attacks children from the period of weaning to eight or nine years of age, and sometimes up to puberty. There is slight and partial redness of one, or of both eyes, sometimes confined to the eyelids, and caused by groups of enlarged vessels running from the circumference of the eye to the edge of the cornea, where they terminate in small pustules, which break and form minute ulcers. Sometimes the injection extends to the conjunctiva covering the cornea, and pustules form on its surface. There is great intolerance of light, the eyebrows are contracted, and the nostrils and upper lip drawn upwards. Whenever the eye is exposed to light, there is a profuse discharge of scalding tears, which, flowing over the skin, irritate and inflame it. The symptoms remit towards evening. The constitutional symptoms are those of scrofula, such as glandular enlargements, eruptions on the head and face, sore ears, general debility, tumid belly, disordered bowels, offensive breath.

CAUSES.—*Predisposing.* The scrofulous diathesis, and all the conditions which are known to excite it.—*Exciting.* The common causes of inflammation; catarrhal ophthalmia; the exanthemata.

DIAGNOSIS.—From catarrhal ophthalmia, by the more partial injection of the vessels, the greater intolerance of light, the formation of distinct pustules, and the presence of other symptoms of scrofula. From purulent ophthalmia, by the profuse watery discharge.

PROGNOSIS.—*Favourable*, when the scrofulous taint is slight.—*Unfavourable*, when it is strongly marked.

[illegible]—In resolution; in the formation of a "vascular [illegible]nus; in ulceration of the cornea; followed in some [illegible]n of the iris, and its adhesion to the cornea; in in[illegible]n of the cornea.

Treatment.—I. *General.* That recommended for scrofula (p. 341). Quinine is a most valuable tonic in this disease. II. *Local.* Warm fomentations to the eye; the instillation of vinum opii with $\frac{1}{20}$ part of liq. atropiæ, two or three times a day, or the use of astringent collyria; a little red precipitate or citrine ointment, placed between the lids at bed-time; and by counter-irritation—blisters behind the ears, an issue in the arm, or a ring or thread passed through the lobe of the ear. Ulcers on the cornea should be touched with nitrate of silver. When there is much spasm of the orbicularis oculi, conium in efficient doses is extremely useful.

SCLEROTITIS.—INFLAMMATION OF THE SCLEROTIC.

Synonym.—Rheumatic ophthalmia.

This disease is sometimes limited to the sclerotic, but more frequently co-exists with inflammation of the conjunctiva (*catarrho-rheumatic ophthalmia*), or of the iris. (See Specific Iritis.)

Symptoms.—A deep seated and dusky redness of the globe of the eye, especially round the cornea, where the fine radiating straight vessels of the sclerotic are seen abruptly terminating a short distance from its margin. There is an abundant flow of tears, extreme photophobia, and a sensation of fulness and tension, with darting pain in the globe, extending round the orbit, in the course of the branches of the fifth nerve, increasing towards evening, attaining its greatest intensity at midnight, and subsiding towards morning. There is generally some degree of haziness of the cornea, and vision is more or less impaired.

Termination.—In recovery, or in chronic disease. If the disease extend to the cornea or iris, the results of inflammation of those parts.

Causes.—*Predisposing.* Middle age; the male sex; a previous attack; the rheumatic or gouty diathesis.—*Exciting.* The common causes of inflammation. The disease is simply local rheumatism.

Diagnosis.—From inflammation of the conjunctiva by the deep-seated redness, radiated arrangement, and hair-like fineness of the vessels; by the secretion of tears in the place of mucus; by the deep-seated pain of the orbit, extending to the surrounding parts; by the intolerance of light; in some cases by its complication with iritis.

Prognosis.—*Favourable*, if the disease be promptly treated. It is very liable to assume a chronic form, and to return.

Treatment.—That of catarrhal inflammation of the conjunctiva, combined with the remedies proper for rheumatic inflammation of their place with the motions of the lids; by the abundant secretion cleansed by a [illegible] acute pain in and around the [illegible]ered at the outset; the patient should be put on a spare diet, and enjoined to take gentle exercise in the open air. When the deeper seated textures of the eye are implicated, the remedies appropriate to the inflammation of those textures should be employed; such as the belladonna ointment in threatened adhesion of the iris; puncturing the cornea to prevent rupture of the membrane; the application of nitrate of silver to ulcers on the cornea, or to the protruding iris.

PROPHYLAXIS.—Great care should be taken to prevent the application of the matter to the eyes of healthy persons.

4. GONORRHŒAL OPHTHALMIA.

SYMPTOMS AND TREATMENT.—Those of purulent ophthalmia of adults; but more severe and much more rapid: a few hours may suffice for its complete development. In order to arrest it, we may pass solid nitrate of silver rapidly over the inflamed conjunctiva.

CAUSE.—Inoculation of the eye with gonorrhœal matter.

5. STRUMOUS OPHTHALMIA.

SYNONYMS.—Scrofulous, pustular, and phlyctenular ophthalmia.

SYMPTOMS.—This disease attacks children from the period of weaning to eight or nine years of age, and sometimes up to puberty. There is slight and partial redness of one, or of both eyes, sometimes confined to the eyelids, and caused by groups of enlarged vessels running from the circumference of the eye to the edge of the cornea, where they terminate in small pustules, which break and form minute ulcers. Sometimes the injection extends to the conjunctiva covering the cornea, and pustules form on its surface. There is great intolerance of light, the eyebrows are contracted, and the nostrils and upper lip drawn upwards. Whenever the eye is exposed to light, there is a profuse discharge of scalding tears, which, flowing over the skin, irritate and inflame it. The symptoms remit towards evening. The constitutional symptoms are those of scrofula, such as glandular enlargements, eruptions on the head and face, sore ears, general debility, tumid belly, disordered bowels, offensive breath.

CAUSES.—*Predisposing.* The scrofulous diathesis, and all the conditions which are known to excite it.—*Exciting.* The common causes of inflammation; catarrhal ophthalmia; the exanthemata.

DIAGNOSIS.—From catarrhal ophthalmia, by the more partial injection of the vessels, the greater intolerance of light, the formation of distinct pustules, and the presence of other symptoms of scrofula. From purulent ophthalmia, by the profuse watery discharge.

PROGNOSIS.—*Favourable*, when the scrofulous taint is slight.—*Unfavourable*, when it is strongly marked.

Terminations.—In resolution; in the formation of a "vascular speck," or of *pannus;* in ulceration of the cornea; followed in some cases by protrusion of the iris, and its adhesion to the cornea; in infiltration of the cornea.

Treatment.—I. *General.* That recommended for scrofula (p. 341). Quinine is a most valuable tonic in this disease. II. *Local.* Warm fomentations to the eye; the instillation of vinum opii with $\frac{1}{20}$ part of liq. atropiæ, two or three times a day, or the use of astringent collyria; a little red precipitate or citrine ointment, placed between the lids at bed-time; and by counter-irritation—blisters behind the ears, an issue in the arm, or a ring or thread passed through the lobe of the ear. Ulcers on the cornea should be touched with nitrate of silver. When there is much spasm of the orbicularis oculi, conium in efficient doses is extremely useful.

SCLEROTITIS.—INFLAMMATION OF THE SCLEROTIC.

Synonym.—Rheumatic ophthalmia.

This disease is sometimes limited to the sclerotic, but more frequently co-exists with inflammation of the conjunctiva (*catarrho-rheumatic ophthalmia*), or of the iris. (See Specific Iritis.)

Symptoms.—A deep seated and dusky redness of the globe of the eye, especially round the cornea, where the fine radiating straight vessels of the sclerotic are seen abruptly terminating a short distance from its margin. There is an abundant flow of tears, extreme photophobia, and a sensation of fulness and tension, with darting pain in the globe, extending round the orbit, in the course of the branches of the fifth nerve, increasing towards evening, attaining its greatest intensity at midnight, and subsiding towards morning. There is generally some degree of haziness of the cornea, and vision is more or less impaired.

Termination.—In recovery, or in chronic disease. If the disease extend to the cornea or iris, the results of inflammation of those parts.

Causes.—*Predisposing.* Middle age; the male sex; a previous attack; the rheumatic or gouty diathesis.—*Exciting.* The common causes of inflammation. The disease is simply local rheumatism.

Diagnosis.—From inflammation of the conjunctiva by the deep-seated redness, radiated arrangement, and hair-like fineness of the vessels; by the secretion of tears in the place of mucus; by the deep-seated pain of the orbit, extending to the surrounding parts; by the intolerance of light; in some cases by its complication with iritis.

Prognosis.—*Favourable,* if the disease be promptly treated. It is very liable to assume a chronic form, and to return.

Treatment.—That of catarrhal inflammation of the conjunctiva, combined with the remedies proper for rheumatic inflammation of the sclerotic. An alterative purgative followed by a full dose of sodæ et potassæ tartras combined with ♏xv vini colchici. Quinine with the vegetable acids. Gr. x pulv. ipecacuanhæ comp. at bed-time. In obstinate cases, arsenic (Form. 292) is sometimes beneficial.

A solution of extract of opium occasionally dropped into the eye, which should be protected by a shade, or the patient remain in a darkened room. Warm opium fomentation. Unguentum belladonnæ should be rubbed into the forehead, and smeared over the eyelid and brow. If the inflammation be very acute, leeches to the temple or behind the ears.

CORNEITIS.—INFLAMMATION OF THE CORNEA.

Symptoms.—The disease begins with irritation of the eye, slight vascularity of the sclerotic, and a soaked appearance of the cornea, the haziness of which increases. One or more minute ulcers now form on the surface, and the vessels of the conjunctiva and sclerotic become injected; those of the conjunctiva ramifying over the surface of the cornea, and those of the sclerotic being arranged in the characteristic radiated form round the margin of the cornea. Depositions of lymph between the layers of the cornea are also of frequent occurrence; and the secretion of the aqueous humour being augmented, the convexity of the membrane is increased. During the progress of the disease pus may form within the layers of the cornea, appearing as a yellowish white spot; the posterior lamina may give way, when the pus is discharged into the anterior chamber and sinks down to the lower part, forming a yellow crescent (*hypopyon*); or the fibres of the anterior elastic lamina may be destroyed and a minute ulcer result. Such ulcers readily heal; but the cicatrix always remains opaque. There is generally considerable lachrymation and intolerance of light. The pain is usually slight, except occasionally in the first stage, when there is a sense of tension in the eye, with darting pains in the forehead.

Diagnosis.—From other chronic affections of the eye, by a plexus of very fine vessels arranged in the form of a crescent at the edge of the cornea. Sometimes these vessels form an almost complete circle.

Prognosis.—*Unfavourable*, when the general health is impaired.

Treatment.—That recommended under Sclerotitis. A solution of nitrate of silver (gr. v–℥i) should be daily dropped into the eye. Quinine is particularly useful in this, as in strumous ophthalmia. Should inflammation of the surrounding textures, and of the iris, take place, the treatment proper to iritis will be necessary.

IRITIS.—INFLAMMATION OF THE IRIS.

Varieties.—1. Idiopathic. 2. Specific.

1. Idiopathic Iritis.

Symptoms.—The disease begins by the formation of a red zone of small, straight, parallel vessels, arranged as radii round the circumference of the cornea, and terminating abruptly near its edge, the redness after a time extending to the conjunctiva. The iris loses its brilliancy, becomes muddy, and of a tint formed by blending a red with its original hue; its texture is at the same time impaired or destroyed, and lymph is largely effused into its substance. The movements of the iris are at first impeded, and then suspended; the pupil contracts, and becomes irregular in shape, from effusion into its substance and adhesion to surrounding parts. There is dimness, and at length complete loss, of vision; and generally severe pain in and round the orbit, darting to the cheek and temple, and worse at night.

Diagnosis.—By the change of colour of the iris, the irregular pupil, and the effusion of lymph behind the cornea.

Prognosis.—*Unfavourable*, when the treatment has been delayed. A contracted pupil, great vascularity, acute and deep-seated pain, dimness of vision, or insensibility to light.—*Favourable*, in mild cases, and in acute cases, promptly treated.

Causes.—Mechanical injuries, surgical operations, over-exertion of the eyes, and the common causes of inflammation.

Treatment.—*Indications*. I. To subdue inflammation. II. To prevent effusion, and promote the absorption of lymph. III. To dilate the pupil and prevent the formation of adhesions.

I. Leeches to the temple, brisk aperients, a strict antiphlogistic regimen, the exclusion of light, and perfect rest.

II. To fulfil this indication, calomel and opium must be given from the outset, in doses of gr. ⅓ to gr. i, with from a quarter to half a grain of opium, every three, four, or six hours, according to the severity of the symptoms; combined in very severe cases with mercurial inunction. The calomel and opium may be combined with tartar-emetic (⅛ to ¼ gr.) if there be much general excitement of the circulation.

III. This indication is best fulfilled by occasionally dropping a little liquor atropiæ into the eye.

2. Specific Iritis.

Varieties.—Syphilitic; Rheumatic or Gouty; Strumous.

1. Syphilitic Iritis.—The *symptoms* resemble those of idiopathic iritis, but generally come on slowly and insidiously. When fully established, the disease may prove highly destructive. The *cause*, as the name implies, is the syphilitic virus. The disease may *occur alone; or in* combination with other secondary symptoms;

and it may make its appearance during the primary disorder. The *diagnosis* turns on the position in which the lymph is effused, and on its appearance. It is thrown out on the margin of the iris in the form of globules or distinct masses, of a reddish, brownish, or brownish yellow colour, sometimes described as tubercles. At the same time the pupil is displaced upwards and inwards, the sclerotic zone is of a cinnamon colour, and small brown spots form on the cornea. The *treatment* consists in inducing the constitutional effects of mercury, as quickly as possible, by means of calomel and opium internally, and the infriction of mercurial ointment into the armpits or groins. Atropia must be used to dilate the pupil.

2. RHEUMATIC OR GOUTY IRITIS.—The *symptoms* are usually associated with those of sclerotitis (see p. 587). The sclerotic, however, has a peculiar purplish hue, and the radiating vessels stop within one or two lines of the margin of the cornea, leaving a bluish white ring around it,—appearances characteristic of this affection. Bloodvessels become visible in the iris. Deposition of fibrin is rare; and when it does occur is small in quantity, and surrounds the pupillary margin.

CAUSE.—Exposure of the eye to a draught of cold air.

TREATMENT.—That of sclerotitis (see page 587), care being taken by the use of liquor atropiæ to prevent adhesion of the iris to the capsule of the lens. Mercury is of no use in this form of disease.

3. STRUMOUS IRITIS.—This form generally results from the extension of strumous ophthalmia to the deeper-seated structures, and is chronic and obstinate. The constitutional treatment is that of scrofula; the local treatment being determined by the degree and extent of inflammation. Solution of atropia must be used as in other forms of iritis.

USE OF THE OPHTHALMOSCOPE.

To ascertain the state of the deeper structures of the eye, the ophthalmoscope is indispensable, and a few words on the use of it will not be out of place here.

To explore the whole fundus of the eye, the pupil must be dilated by instilling a few drops of solution of atropia. But as the pupil does not regain its contractility for some time, we must use the solution as seldom as possible, and we may even dispense with it when a glance at the optic nerve and the parts immediately surrounding it is all that is wanted. Let the patient be seated in a dark room, and place an argand gas-light, or moderator lamp, just behind his shoulder and close to the side of his head, so that the light is on a level with the eye, and so far behind it that the face is in the shade. Stand or sit opposite the patient, apply the ophthalmoscope to your own eye, at a distance of eighteen inches from the eye of the patient, and, looking attentively through the sighthole, direct the rays from its mirrored surface so as to fall on the patient's eye. Next interpose the lens at the distance of about an inch in front of him, and by a slight backward and forward movement of your own head bearing the speculum, catch the proper focal distance, and the image of the fundus of the eye will appear as a reddish glow. On careful examination the following parts will distinctly appear:—

NORMAL APPEARANCE OF THE FUNDUS OF THE EYE.—Figs. 87 and 88.—The *entrance of the optic nerve* (optic disc, or papilla) is seen as a white or rosy-tinted circular spot limited by a sharp, well-defined, circular line, formed internally of the margin of the choroid, externally of the margin of the sclerotic. The margin is slightly raised above the general concavity of the fundus, while its central parts are slightly depressed below it. A little to the inside of the optic entrance the *yellow spot* may be seen: it is the darkest part of the fundus, forming a dusky oval or roundish patch, as large as, or smaller than, the optic entrance. In the centre may be distinguished a small bright dot, the *fovea centralis.* The optic entrance and yellow spot are surrounded by an orange-red field, varying in intensity of colour according to the complexion, and pervaded by the retinal vessels. The *retinal artery* and *vein*, in obtaining entrance into the eye, perforate the optic entrance, where each consists of from one to three trunks; the artery is distinguished from the vein by its smaller size, its scarlet colour, and its dichotomous ramifications. The veins are more tortuous, and receive branches at considerable angles. Leaving the optic entrance, these vessels are seen to ramify freely over the surface of the retina, diverging above and below the yellow spot so as to avoid it, and spreading their fine terminal branches towards the anterior edge.

Fig. 87.*



The different parts of the fundus are successively brought into view as the patient moves his eye outwards or inwards, downwards or upwards. The yellow spot, being in the axis of the eye, will be seen when it is directed straight forward; the optic entrance, which is $\frac{1}{12}$ of an inch internal to and a little below the yellow spot, will be visible when the eye is rolled a little inwards. During the examination of a particular part of the fundus, the patient should be directed to fix his eye on a number, marked in large characters on a screen.

---

* Fig. 87 represents the parts of natural size, and the retina spread open. The yellow spot, and a little below and to the inner side, the optic nerve *entrance* and the retinal vessels are seen.

In dark complexioned persons the *choroid vessels* cannot be distinguished; but in those who have light hair and blue eyes, they may be readily seen, and even the arrangement of the *vasa vorticosa* observed. In Albinos it is possible to see the ciliary arteries in the *sclerotic* through the choroid.

Fig. 88.*



DISEASES OF THE CHOROID.

This membrane, consisting of a fine network of delicate blood vessels, is liable, not only to participate in several constitutional diseases, but also to implicate in its own disorders those important parts of the eye which depend on it for nutrition, or are otherwise connected with it. Lying between the sclerotic and retina, and forming anteriorly the choroid body and the iris, every change of the choroid must, more or less, affect those continuous and contiguous parts also.

1. **Congestion of the Choroid.**—*Morbid Appearances.* Increased redness of the fundus, and enlargement, with more or less tortuosity of the blood vessels. As the colour of the fundus varies in intensity in different people, we can only diagnose the condition satisfactorily by a comparative examination of the two eyes.

Symptoms.—Pain, or aching fulness, intolerance of light, lachrymation.

2. **Inflammation.**—*Morbid Appearances.* Those of congestion in a higher degree, with effusion, either between the choroid and sclerotic, or between the choroid and retina, or bursting through the

---

* Fig. 88 represents the healthy fundus magnified by the ordinary lens: the optic nerve entrance, and the distribution of the retinal artery and nerve.

latter and escaping into the vitreous humour. The choroid itself may be swollen and opaque from interstitial effusion. In the disseminated and syphilitic varieties white patches or rounded spots of effusion, and black spots, composed of masses of pigment epithelium, are seen on the surface of the choroid. Capillary hæmorrhage is not common; when it does occur the extravasation is more extensive and less defined than when it takes place in the retina. The effused serum in front of the choroid may be deeply stained with blood. If the inflammation continue, it soon affects the vitreous humour, which becomes hazy. If the effused products have been limited to the substance of the choroid, they may be absorbed, and the eye recover. If the inflammation take on the suppurative form it may rapidly spread and disorganize the whole eye. Recovery is generally incomplete, for as the exsudation is removed, the choroid undergoes *atrophy*, the pigment cells are destroyed at the points where the inflammation developed itself, and corresponding parts of the surface of the white sclerotic are exposed. The fundus therefore presents yellowish-white patches with ragged margins, bounded by, and dappled over with, the black unaltered choroidal epithelium. If the inflammation have been more diffuse, only small black islands of unaltered pigment are left scattered over the pale fundus. The retinal vessels are seen undisturbed in front of this mottled field. (Fig. 89.)

Fig. 89.



Symptoms.—Those of congestion of the choroid, but more intense. The external symptoms are usually little marked. In some cases there is no external indication of disease. When the ciliary processes are involved, there is vascularity of the corresponding part of the sclerotic, and fulness of the veins. The pupil is usually inactive.

Terminations.—Staphylomatous protrusions of the sclerotic, forming blue tumours close to the margin of the cornea. Glaucoma is no doubt a frequent result of choroiditis.

Treatment.—In congestion of the choroid the patient should avoid bright light, read little, and use large type. The cold douche should be frequently applied to the eyes, and occasionally to the whole head. If debility be present, quinine with mineral acids or the astringent chalybeates. When inflammation occurs, leeches or blisters to the temples; calomel and opium given to slightly affect the gums; and exclusion from light.

DISEASES OF THE RETINA.

1. Anæmia may arise from a general anæmic condition, or from the obstruction of the retinal artery by an embolus. In the first case there is simple pallor of the optic disc, rendering the veins very conspicuous. The *symptoms* are fatigue and dimness of vision. When it arises from blockade of the retinal artery, its branches are seen empty and contracted and the veins collapsed. Sudden blindness is the result.

2. Atrophy of the Optic Disc and Retina.—Optic disc atrophied, sunken, pearly white, and very conspicuous; retinal vessels contracted. Retina, near optic disc and yellow spot, opaque and white. This condition is indicative of atrophy of the intercranial portion of the optic nerve constituting the so-called "cranial amaurosis."

Symptoms.—Obscurity of vision coming on gradually or suddenly, followed by insensibility of the greater portion of the retina. The fingers can be dimly seen only in a certain limited position.

3. Imbibition and Swelling of the Optic Nerve, with Fatty Degeneration of the Retina.—*Morbid Appearances.* Spots of an intense white colour streaking the optic disc, indicating commencing induration of the nerve fibres; small white points grouped in the form of a star near the yellow spot, resulting from fatty degeneration of the anterior extremities of the radial fibres of the retina. Numerous minute linear extravasations of blood lie between the altered fibres, and give a more decided appearance of radiation to the diseased patch. In a more advanced stage, the swelling of the optic disc almost disappears, and the fundus is occupied by a patch of pearly whiteness, spotted and striated here and there, with minute extravasations, and limited by an irregular dotted margin. The degenerate arteries and tortuous veins appear very distinct as they radiate over this mottled white field.

Symptoms.—Dimness of vision gradually increasing to complete blindness, without pain or external symptoms.

Cause.—"This condition of the retina is so characteristic of Bright's disease that it allows one, by ophthalmoscopic examination alone, to recognize with certainty the affection of the kidney." (Liebreich, "Atlas der Ophthalmoscopie," p. 25.)

4. Retinitis.—*Morbid Appearances.* Redness of the optic disc, becoming intense, obscuring its outline, and gradually increasing until it is lost to view; retinal veins enlarged and varicose. Sometimes the fundus is dotted over with red spots of blood; thickening of the

retina by serous infiltration, and diminution of its transparency, so that the deeper portions of the veins cannot be seen, and so wear the appearance of being interrupted. In proportion to the quantity and density of the opaque inflammatory products, the red colour of the choroid becomes dimmed, and at last obscured, so that the retina is alone seen, of a dull drab or grey colour, and presenting patches of ecchymosis.

In the *syphilitic variety* the affected portion of the retina is rendered opaque by solid effusion forming a white patch, stretching from the obscure margin of the optic disc round the yellow spot, and thence spreading as a streak towards the circumference. It is distinguished from the degeneration occurring in Bright's disease, by the absence of the sharp definition and vivid whiteness.

Symptoms.—Dim and distorted vision, lines appear zigzagged, and vertical objects out of the perpendicular; occasionally fiery flashes are noticed; there is considerable pain in the head.

Causes.—Strong light; the heat and light of large fires; light reflected from snow or sand; lightning; overstraining the eye in examining very minute objects; syphilis.

Treatment.—That of local inflammation. Quinine should be given early. If there be syphilitic taint, the treatment given p. 590.

5. RETINAL HÆMORRHAGE (Retinal apoplexy).—*Morbid appearances.*—Extravasation of blood in spots, streaks, or patches. The effusion may take place between the layers of the retina; upon its surface, between it and the lining membrane; or it may rupture the latter, and pass into the vitreous humour. When recent, the colour of the effusion is crimson, afterwards black or brown.

Symptoms.—More or less imperfect vision coming on suddenly after exertion in a stooping posture, or a blow on the globe of the eye. Only the half of an object may be seen. The pupils are usually dilated, sluggish or motionless. Small objects cannot be distinguished; but light, and large objects often appear of a deep red tint. Except in case of violence, there is no pain or intolerance of light.

Causes.—Violent straining, congestion of the retina; suppression of the menses; degeneration of the coats of the retinal vessels; blows on the eyeball; convulsions; apoplexy; Bright's disease.

Prognosis.—Dependent on the cause. *Favourable* if the patient be young and the effusion small. *Unfavourable* in proportion to the amount of direct violence, to the imperfection of vision, to the inactivity of the iris, and to the presence of pain within the eye or brain.

Treatment.—Leeches to the temples, a brisk hydragogue purgative, and the constant application of cold to the eye. If pain be present, opium may be given. If light be intolerable, the patient must be kept in the dark; and in any case direct light must be avoided. The sound eye must not be used in reading or fine work.

Under the most favourable circumstances, the effusion is slowly absorbed and the function of the retina tardily restored.

DISEASES OF THE CHOROID AND RETINA.

Choroido-retinitis Pigmentosa.—*Morbid Appearances.* Those of atrophy. The choroid and retina are atrophied, speckled with pigment, and adherent. The disease is characterized by commencing in a more or less complete circle at the ora serrata (ant. margin of retina), and spreading backwards towards the optic disc, which ultimately becomes implicated in the atrophy.

Symptoms.—A general contraction of the field of vision, while the central parts retain their clearness; in two words—circumferential blindness. When the disease has made considerable advance towards the centre, night blindness occurs. The progress of the disease is often very slow, and there are no external evidences of its presence. As the fundus becomes affected, blindness creeps on, and the pupil becomes large and inactive. At length there is total blindness.

Causes.—Chronic inflammation and defective nutrition.

Detachment of the Retina from the Choroid (Floating Retina).—*Morbid Appearances.* If the displacement be extensive, it is readily observed; not so if it be slight. It is first seen at the lowest part of the fundus, probably in consequence of the gravitation of the effused fluid. If this be serum, the detached retina projects into the vitreous humour as a tense vesicle, or folded membrane, which vibrates or undulates with every movement of the eyeball. The limit of detachment is marked by the sudden bending of the vessels, and by a diminution in the colour of that part of the fundus which is detached. In the earlier stages, the colour of the choroid is transmitted through the retina, which still retains its transparency. In long-standing cases the detached retina becomes pearly white and opaque, and the colour of the choroid is no longer apparent. The separation of the retina may be partial, or it may increase until it is wholly disunited from the choroid. It is then pushed forwards in the form of an irregular hollow cone, the apex of which is formed by the optic disc. In extreme cases it is reduced to a mere translucent cord traversing the posterior part of the axis of the globe.

Symptoms.—The disease comes on so insidiously, that the blindness which it causes is often discovered accidentally; for there is no pain, and the appearance of the eye is quite natural. When the disease is developed, the field of vision is obliterated in a degree corresponding to the limited detachment of the retina. If the *lower* half [illegible] the nervous layer be detached, the field is terminated by an [illegible]gular horizontal line, above which is darkness.

[illegible]iagnosis.—Cancerous tumours of the choroid may coexist, and be overlooked, in this condition of the retina. Effusions into, and opacities of, the vitreous membrane may be mistaken for it; the absence of these latter conditions is known by the appearance of the retinal vessels in the projection.

Cause.—Inflammation of the retina or choroid.

Treatment.—If the retina be wholly detached, the sight will never be regained. In cases of partial separation, the absorption will be promoted by the repeated application of blisters to the temple, and a prolonged course of iodide of iron.

DISEASES OF THE SCLEROTIC AND CHOROID.

STAPHYLOMA POSTICUM (SCLERECTASIA. SCLEROTICO-CHOROIDITIS POSTERIOR).

DEFINITION.—A conical protrusion backwards of a portion of the sclerotic, in the neighbourhood of the optic nerve, usually on its outer side, involving the choroid and retina.

MORBID APPEARANCES.—A clear zone surrounding the optic nerve (Fig. 90), caused by removal of pigment from the atrophied choroid, which no longer prevents a view of the white sclerotic behind. The zone grows whiter as the disease advances, and greyish streaks or spots are observed in it. At first the zone is incomplete, and in the form of a crescent joined by its concave edge to the optic nerve. As the atrophy of the choroid proceeds farther outwards, the white or mottled zone spreads in a more or less circular form. (Fig. 91.)

Fig. 90.



In more advanced stages the circular outline is lost, the atrophied choroid extending into rounded or oblong processes. (Fig. 92.)

The white crescentic figure so characteristic of this disease is the inner surface of the protruded sclerotic. When the staphyloma is deep, the adjacent portion of the sclero-choroidal ring bounding the optic nerve is obliterated, and the corresponding side of the optic nerve entrance is pulled down into the hollow. When this has happened the nerve entrance is seen in perspective, and its figure becomes elliptical in proportion as it slopes into the hollow. When the staphyloma is to the side of the optic nerve, the major axis of the ellipse will of course be vertical. This condition is well represented in Fig. 92.

Fig. 91.



Fig. 92.



Symptom.—Posterior staphyloma is the most frequent cause of myopia (short sight). When the yellow spot is involved in the disease, amblyopia results.

Diagnosis. — The white crescentic figure near the optic nerve; distinctness of the retinal vessels ramifying in front of a white ground; and their undulatory course from the nerve entrance across the depression, are sure marks of posterior staphyloma.

Cause. — According to Von Ammon there exists in an early stage of fœtal life a protuberance of the sclerotic on the outer side of the optic nerve which communicates with the anterior cerebral vesicle means of an oval opening. There is therefore a natural tendency this defect, and a very slight accident or arrest of development cause it. Atrophy of the choroid, resulting in wasting, and a of the sclerotic, may produce it in after life.

Treatment.—The defect of vision to be remedied by the use of concave glasses, of suitable power.

DISEASES OF THE LENS.

Every morbid process that affects the lens results in more or less irremediable opacity, and bears the name of "cataract." It is conveniently divided into *lenticular* and *capsular*, according as it affects the lens or its capsule.

Congenital Cataract.—Four varieties. I. A minute chalky-white dot, deposited in the most superficial part of the lens within the capsule, and occupying the centre of a clear dark pupil (*C. centralis*). II. A more extensive deposit, occupying nearly the whole area of the pupil; it has a conical shape, with the apex directed forwards (*C. pyramidata*). III. A greyish white opacity composed of faint striæ, terminating in a little opaque white dot. IV. Irregular fatty or earthy patches, affecting either the anterior or posterior surface of the capsule.

These opacities are circumscribed, the rest of the lens remaining perfectly clear: they do not extend, and when small do not cause blindness. When large they require surgical interference. They are distinguished from diseases of deeper structures by their brilliant white colour and comparatively superficial position. Morbid deposits in the fundus of the eye have a yellow colour. Congenital cataract, as a rule, affects both eyes. The *symptoms* attendant upon these conditions are, more or less cloudiness of vision and inability to distinguish type; but when the pupil is dilated with atropia, perfect and minute vision.

Cataract in Adults and Old Persons.—Complete opacity of lens (except from injury) is rare before forty. After fifty it is the commonest cause of failing sight. The *hard* variety spreads inwards from circumference to centre. Opaque streaks first appear at the extreme edge of the lens; then gradually coalesce into patches and spread in a radiating manner, first and chiefly over the posterior surface, and at length involve the anterior surface. After a year or more the whole lens becomes a little hazy, and opaque streaks begin to appear within the margin of the pupil, converging to the central line of vision; and slowly the pupil changes from black to milk white, and the opacity is complete. In rare instances the opaque lens becomes deep brown.

In the *fluid* form of cataract, no converging streaks are seen; the morbid process is one of softening, which goes on till the whole lens become a white, bluish white, or dirty grey pultaceous matter.

GLAUCOMA.

Varieties.—Acute and chronic.

Definition.—Inflammation of the interior of the eye leading to effusion of fluid within the eyeball, and destructive distension.

Symptoms.—These come on between the ages of fifty and sixty, and both eyes are usually affected. In the *acute* form the disease begins with sudden and violent pain in the eyeball and temple, followed by rapid extinction of vision; the pupil is widely dilated, motionless, sometimes transversely oval, and of a greenish tint; the iris bulges forward, and its veins are often distinctly enlarged; the lens is hazy or even milky, and advanced almost to the posterior surface of the cornea, which is dull; the sclerotic and conjunctiva behind the margin of the cornea are congested. The globe feels very hard, and is tender.

The *chronic* form begins very insidiously; dimness of sight, dull aching pain in the eye or head, and flashes of light across the field of vision, sooner or later indicate internal disease. The patient becomes gradually blind, the pupil enlarged and insensible, and the eye ultimately assumes the appearances above described, but the distended globe is not painful on pressure. Chronic iritis and cataract appear sooner or later, and large dark purple veins appear on the sclerotic.

When the eyeball is distended by effusion, the termination of the optic nerve losing the support of the sclerotic, yields to the pressure, and, as it is pushed backwards, there is a corresponding depression of the optic disc. This condition is distinctly marked by the appearance of the blood vessels in the optic disc and at its margins. At the bottom of the depression the main trunks are spread out, and appear smaller and quite unconnected with the larger prolongations at the margin of the excavation. By focussing the vessels at the bottom of the depression, and then gradually advancing the lens, so as to advance the focus, we may trace the continuity of the central and peripheral trunks, and, at the same time, measure approximately the depth of the depression. Extravasations of blood in the retina are very common.

Cause.—Inflammation, probably commencing in the choroid.

Prognosis.—Extremely unfavourable.

Treatment.—Mercurial salivation does not appear to arrest the progress of the disease. In the *acute* form leeches, and subsequently blisters, to the temples; the removal of fluid by the insertion of a fine grooved needle; cold affusions to the head; opium, and quinine in full doses; an occasional brisk purgative.

The *chronic* disease has been much alleviated, and sight partially restored, by extraction of the lens and excision of a portion of the iris.

OTHER DISEASES AND DEFECTS OF THE EYE.

1. Specific Disease of the Eye.

The internal tunics of the eye are often the seat of cancerous and tubercular deposits, and the lens, vitreous humour, and anterior and posterior chambers are sometimes occupied by parasites (Cysticercus tenuicollis, Filaria oculi, and Distomum ophthalmobium). It is important to be able to recognise a *melanotic growth* in the earliest stages of its existence, in order that the eyeball may be extirpated, and the disease thus removed before it has involved other structures behind the globe. Dull pain, increasing dimness of vision, or dilated and sluggish pupil, a bright metallic reflection from the fundus, and the appearance of a vascular tumour projecting into the vitreous humour, are the symptoms of the disease.

The diagnosis of cancer mainly rests on the presence of blood-vessels different in their arrangement, or distinct from those of the retina. But medullary and melanotic cancer often have their seat in the choroid, and then the retina is pushed forwards and the ophthalmoscopic indications are not diagnostic.

Tubercular deposit forms a bright yellowish *non vascular* tumour.

Entozoa may be distinguished by their form and movements.

2. Amaurosis.—Gutta Serena.

Although this indefinite term is well-nigh obsolete, we may conveniently use it here for the purpose of enumerating all causes of blindness, except those which are discoverable by the unaided eye, such as opacities of the cornea and lens.

Amaurosis may be subdivided into two kinds: 1. Temporary or functional. 2. Permanent or organic.

Temporary amaurosis is due to the following causes:—Exposure to intense light, loss of blood, diphtheria.

Permanent amaurosis may be due either to interocular or to intercranial disease. In the former case it is caused by fatty degeneration of the retina, as in Bright's disease; retinitis; retinal hæmorrhage; choroiditis with effusion of serum or blood, causing detachment of the retina; scrofulous or melanotic tumours, immediately behind or in front of the retina; glaucoma.

Intercranial amaurosis may be caused by pressure upon or atrophy of any portion of the optic nerves, or of those parts of the optic thalami and corpora geniculata in which they have their origin.

The ophthalmoscope will generally enable us to discover the cause of the blindness. If the disease be intercranial, the optic nerve entrance will afford characteristic indications. (See Atrophy of Optic Disc, p. 594.) The treatment must be determined by the cause.

3. Defects and Disproportion of the Refractive Media.

Such defects as the following are very common; and since some are remediable, while others occasionally give rise to alarm, it is necessary that the practitioner should be familiar with them.

Astigmatism.—Under this title, Donders, "Accommodation and Refraction," includes those phenomena which result from inequality of the refractive media. The error chiefly lies in the cornea, which, on account of variation in thickness or density, produces the same effect on vision as a rough pane of crown glass interposed between the eye and a distant object. The rays of light being unequally refracted as they pass through the several parts of the unequal cornea, straight lines become zigzagged and broken, and circles lose their even outline.

Myopia.—*Short sight.* An inability to distinguish near objects at the usual distance from the eye. It is caused by undue convexity of the refracting media, whereby the image of an object held at the usual distance is brought to a focus at a point in front of the retina; and in order to throw the image further back upon the retina, the object must be approximated to the eye.

Anything which causes a prolongation of the visual axis must result in myopia. According to Liebreich, Donders, and others, posterior staphyloma (see p. 597) is the most frequent cause of this defect.

Myopia is remedied by the use of biconcave glasses of such a focus that distant objects shall appear distinct and undiminished.

Presbyopia.—*Old* or *long sight.* Inability to discern near objects. This is caused by flatness of the refracting media, whereby the image of an object held at the usual distance from the eye is brought to a focus at a point behind the retina, and in order to advance it, it is necessary to remove the object to an unusual distance.

This defect is compensated by the use of biconvex glasses of suitable convexity.

Muscæ Volitantes.—Some persons are annoyed and alarmed, by minute dark specks or beaded filaments, which, by floating in front of the retinal image, puzzle and constantly threaten to obscure vision. "If the eye be directed towards a clear sky, and then kept steadily fixed, the spots appear to sink slowly downwards. A brisk movement of the eye instantly whisks the little bodies about in various directions, and then as soon as the eye is steadied, they again slowly sail across the field of vision." (Dixon on Diseases of the Eye.) They are not sympathetic of any organic disease, and need not excite alarm.

DISEASES OF THE EAR.

1. Otitis Externa . . .	Inflammation of the External Ear.
2. Otitis Interna . . .	Inflammation of the Internal Ear.
3. Surditas	Deafness.

OTITIS EXTERNA.—INFLAMMATION OF THE EXTERNAL EAR.

Symptoms.—In the *acute* stage, pain in the passage, gradually increasing and augmented by cold, pressure, and the motions of the jaw; deafness; noises in the ear; redness and swelling of the lining membrane; and after a few hours, or one or two days, a thin acrid fœtid discharge, often tinged with blood, and becoming puriform. The inflammation is followed by enlargement of the follicles, and terminates by suppuration, ulceration, and sometimes a painful granular condition of the mucous membrane, when the discharge becomes *chronic*.

Causes.—*Predisposing*. Childhood; the scrofulous diathesis.—*Exciting*. Cold; the introduction of foreign bodies; extension of inflammation from surrounding parts; the exanthemata, especially scarlatina.

Treatment.—Hot poultices and fomentations; the injection of warm water, alone or containing from five to ten grains of acetate of lead to the ounce; in severe cases, leeches behind the ear, blisters over the mastoid process; aperients. If an abscess form, it must be punctured. In the *chronic* form, astringents, injections of alum, sulphate of zinc, and nitrate of silver. If granulations of the mucous membrane have formed, tents of lint or cotton, dipped in zinc ointment, may be introduced into the meatus. The general treatment will consist in the steady use of aperients and alteratives, nourishing diet, pure air, and cleanliness; and if there be much debility, chalybeate tonics. If the discharge should suddenly cease, and symptoms of head affection occur, the treatment for inflammation of the internal ear will be required.

OTITIS INTERNA.—INFLAMMATION OF THE INTERNAL EAR.

1. Acute Inflammation of the Internal Ear.

Symptoms.—Acute, deep seated pain in the ear, and in the head and face of the same side, increased by mastication; a sense of tension in the ear; loud noises; deafness; sometimes swelling of the tonsils, with dull pain or itching at the back of the throat. There is a frequent, quick, and hard pulse, hot skin, anxious countenance, furred tongue, general febrile excitement, restlessness, and, in very severe cases, delirium and convulsions.

Terminations.—In resolution, with gradual subsidence of the symptoms. In suppuration, with throbbing pain and great tension, followed by discharge of matter from the external meatus (the membrana tympani having been ruptured), through the Eustachian tube into the throat, or through an opening in the mastoid process.

Causes.—Those of inflammation of the external ear; the extension of inflammation from the throat through the Eustachian tube.

Diagnosis.—From inflammation of the external ear by the deeper seated pain, and in the early stage the absence of discharge from the external meatus. The rupture of the membrana tympani may be recognized by the speculum; and if the patient expire forcibly, the mouth and nostrils being closed, air will issue from the ear.

Prognosis.—Deafness is the increasing effect of this disease; and inflammation of the membranes of the brain, an occasional result.

Treatment.—Leeches behind the ear, followed by blisters: aperients. If suppuration have taken place, and there be extreme tension, with throbbing pain, and violent headache or delirium, instantaneous relief may be afforded by puncturing the membrana tympani, washing the ear out repeatedly with tepid water, and facilitating the discharge of matter, by causing the patient to lie on the affected side. If there be swelling or inflammation of the fauces, astringent gargles or the inhalation of steam. If, after the pain has subsided, the Eustachian tube be obstructed, the air douche or the ear catheter, should be used.

2. Chronic Inflammation of the Internal Ear.

Symptoms.—The principal symptom of chronic inflammation of the ear, whether external or internal, is an intermittent discharge of offensive, muco-purulent, or purulent matter (otorrhœa), from the external meatus, with deafness more or less complete. The tympanic membrane will be found more or less completely destroyed, exposing the ossicula; or these may have been discharged, when the tympanic cavity will be found in a granular condition.

Treatment.—The same as in chronic inflammation of the external ear, combined with the use of gargles, the air douche, or the ear catheter, in order to keep the Eustachian canal open. The purely medical treatment will be regulated by the existing state of the constitution. If it be connected with scrofula or syphilis, the remedies proper to those diseases. Tonics and alteratives are requisite in all forms of the disease.

SURDITAS.—DEAFNESS.

Causes.—Congenital absence, or excessive contraction of the external meatus. Accumulation of wax; inflammation and swelling of the meatus; polypi; osseous tumours; foreign bodies, such as wool and hairs in the meatus. Inflammation, calcareous degeneration, extreme relaxation or destruction of the membrana tympani. All these causes are readily observed, and the treatment is obvious. The following causes are more obscure: inflammatory thickening of the Eustachian tube at its faucial orifice or elsewhere, collections of pus, mucus, or blood in the tympanum; anchylosis of the ossicula, and disease of the auditory nerve.

Diagnosis.—To find which of these obscure causes is present, we must ascertain the condition of the membrana tympani, the Eustachian canal, the tympanum, and the auditory nerve.

1. Examined by the speculum, the drum head, directed downwards and forwards, appears as a delicate grey or yellowish grey, shining membrane with a whiter ridge (handle of the malleus) com-

mencing as a smooth rounded tubercle above, and running downwards and very little backwards, to the centre, which is drawn a little inwards, so as to make the outer surface slightly concave. The outer and lower quarter, however, is a little convex, and reflects a cone of light, spreading from the centre forwards and downwards. As the membrane is bulged outwards or inwards by variation of the tension of the air in the tympanum, so the cone of light varies, the apex taking the place of the base, and *vice versâ*. In acute inflammation of the middle ear, the drum head is streaked with blood vessels, or uniformly red; and the concavity is increased (from absorption of portions of the air now imprisoned by swelling of the lining membrane of the Eustachian canal), unless there be an accumulation of fluid, when the membrane is of course pushed outwards.

2. In a state of rest of the muscles of the palate, the air in the tympanum is shut off from that of the throat, but in every act of swallowing, the faucial extremity of the Eustachian tube is opened by the contraction of the levator and tensor palati. Variation of the cone of light on the drum head in swallowing is proof of a healthy state of the Eustachian canal. If the drum head be perforated, air from the throat passes readily into the outer passages of the ear, when the patient expires forcibly with the mouth and nostrils closed; and fluids, on the other hand, thrown into the external meatus, pass readily into the pharynx.

3. Auscultation of the tympanum is thus performed:—one end of an elastic tube is placed in the patient's ear, and the other in one of the operator's. The patient takes some water into his mouth, and when the mouth is closed, and the air douche fixed on the nostrils, he swallows a portion of the fluid from time to time. At the same moment air is forced into the tympanum by moderate pressure of the air bag. When the air enters the tympanum, the patient hears an explosive noise, and the operator a thud or crackling. If the cavity be healthy, he hears a rustling noise like the pattering of fine rain; if the lining membrane be abnormally dry, a harsh snapping sound; if the Eustachian canal be thickened, a sibilant sound: gurgling indicates excess of fluid; and a whistling sound, perforation of the membrana tympani: in which case the speculum will show an oozing of pus through the aperture.

4. A healthy state of the auditory nerve is readily known by the tuning-fork, which is distinctly heard when brought into *contact* with the teeth or bones of the head, and is more distinctly heard on the *deaf* side. This will be the case when neither watch nor tuning-fork, brought as near to the deaf ear as possible, without touching, can be heard. Diseases of the auditory nerve generally implicate the portio dura, and facial palsy of one side results.

Functional deafness may result from concussion, sudden and loud noises, poisons, or fever.

TREATMENT.—Apart from inflammation and accumulations in the tympanum already treated of, this will chiefly have reference to obstruction or occlusion of the Eustachian canal; and to perforation of the membrana tympani. To relieve the former condition, the frequent use of the air douche, as described under 3, is invaluable. When we fail to open the canal by this means, recourse must be had to the ear catheter. The effect of perforation of the drum head may be temporarily relieved by a little pellet of moistened cotton wool, or Toynbee's artificial membrana tympani placed against the aperture.

CHAPTER VIII.

CUTANEOUS DISEASES.

1. Parasitical. 2. Non-Parasitical.

Parasitical.

1. Dermatozoa	Animal Parasites.
2. Dermatophyta	Vegetable Parasites.

Non-Parasitical.

1. Exanthemata	Rashes.	5. Papulæ	Pimples.
2. Vesiculæ	Vesicles.	6. Squamæ	Scales.
3. Bullæ	Blebs.	7. Tuberculæ.	Tubercles.
4. Pustulæ	Pustules.	8. Maculæ	Spots.

9. Other Diseases.

GENERAL OBSERVATIONS ON CUTANEOUS DISEASES.

In order to take a proper view of diseases of the skin, the complexity of its structure and function must be duly considered. It forms a most extensive vascular and exhalent surface, the nature and functions of which bring it into direct reciprocal relation both with the lungs and the kidneys. It has a proper glandular apparatus—the sebaceous. It contains the organ of touch, and is the seat of common sensation. It is furnished with hairs and nails, which share every derangement of the part of the skin to which they are attached, and of which they are but modified processes. A surface so richly supplied with blood vessels, nerves, and glands, must necessarily be very liable to derangement from variations of temperature and moisture; and while its vascular surface sympathises with every derangement of the circulation in the internal organs, its protective cellular covering, and glandular orifices are exposed to the invasions of parasites.

The classification of skin diseases is difficult and unsatisfactory. In this work something has been done towards the attainment of simplicity by separating the diseases due to parasites, and subdividing them into two orders.

The subdivision adopted for the other orders is convenient; but it must be borne in mind that there are no abrupt lines of demarcation between them. An exanthem may pass through the successive stages of papule, vesicle, pustule, and scale in the natural sequence of morbid action and without any new exciting cause.

A few diseases are placed by themselves, as not admitting of classification; lupus, furuncle, hæmorrhage, and abnormal perspiration.

T
ap
te
st
tymp
tacili
the a
astrin
has s
the ea

SYMP
the ear.
of offen
external
tympani
exposin
the tymp

TREAT
ternal ea
ear cath
purely m
the const
remedies
requisite

CAUSES.
ternal mea
of the mea
wool and h
tion, extrem
All these ca
The followin
the Eustachi
pus, mucus,
and disease

GNOSIS.
st asc
tian ca
xamin
and forw
g memb

purulenta), or they are destroyed by friction, and leave
und dark spots. The pimples or vesicles are either single
all groups; rarely in patches of any size. The disease is
l throughout by most distressing itching.

s.—*Predisposing.* Neglect of personal cleanliness.—*Ex-*
Contagion; the *Acarus* (Sarcoptes, Cheyletes) *scabiei*
3) is common to man and the
animals. Half an hour after it
l on the skin it bores perpendi-
through the cuticle, and then
r through the softer cells beneath
tis, in a little circular depression
it lodges itself.

Fig. 93.



IOSIS.—The vesicular and pustular
s distinguished by a little black
ich can usually be traced from the
f the itch vesicle outwards for a
tance. This is the tunnel formed
carus. When scabies assumes the
orm, and the summits of the pimples
ched off, so as to leave round dark
is difficult to distinguish from
senilis. Advanced age affords a probability in favour of
r; while the fact of more than one member of the same
eing affected is conclusive as to the former.
hen, by the latter being papular, more clustered,
situated on the hand, being on the back, and
reen the fingers. From *herpes* and *eczema*,
vesicles being more isolated and in smaller
by the intense itching and by their contagious
and often by their situation. Scabies very
tacks the face.

MENT.—Sulphur ointment, or an ointment of
and carbonate of potash; sulphur baths; sul-
f lime, with olive oil; a strong alcoholic
f stavesacre. Cleanliness and the warm bath,
le aperients if required, are useful auxiliaries.

Fig. 94.



ACARUS FOLLICULORUM.

YM.—Demodex folliculorum. Steazoon follicu-

parasite (Fig. 94) was discovered by Henle
tave Simon, in 1842. In England it is un-
r very rare. It sometimes occurs singly,
s in groups of as many as thirteen in a follicle;
lly occupy the duct near the orifice, towards which the
is directed, the head lying deeper in the gland.

DEFINITIONS.

1. *Exanthemata. Rashes.*—Superficial red patches or points variously shaped, circumscribed or diffused, disappearing on pressure, rarely passing into vesicles, and terminating by resolution or desquamation.

2. *Vesiculæ. Vesicles.*—Small, round, pointed elevations of the cuticle, containing a colourless, transparent, or opaque, pearly lymph. They break and discharge their contents, and are succeeded by scurf, scales, or sores. Sometimes their contents are absorbed.

3. *Bullæ. Blebs.*—Vesicles of larger size.

4. *Pustulæ. Pustules.*—Circumscribed elevations of the cuticle containing pus, and terminating in thick crusts or scabs.

5. *Papulæ. Pimples.*—Small, solid, pointed elevations of the skin, usually terminating in scurf; rarely by ulceration of the summit.

6. *Squamæ. Scales.*—Hard, opaque layers of cuticle, covering papulæ or inflamed surfaces; continually detached and renewed.

7. *Tuberculæ. Tubercles.*—Small, hard, persistent tumours of the skin, larger than papulæ, with or without an inflamed base, and terminating in resolution, partial suppuration, or ulceration.

8. *Maculæ. Spots.*—Permanent discolorations, or decolorations, of the skin, often accompanied by change of structure.

PARASITICAL SKIN DISEASES.

ORDER I.

DERMATOZOA.—ANIMAL PARASITES.

ACARUS SCABIEI . . .	The Itch.
ACARUS FOLLICULORUM.	
PHTHIRIASIS	Lousiness.
FILARIA MEDINENSIS . .	Guinea Worm.

SCABIES. PSORA.—THE ITCH.

SYMPTOMS.—The usual seat of this eruption is between the fingers, on the wrists, inside the forearm, and at the bends of the joints; but it may affect any part of the body. It generally appears a few days after exposure to the contagion, and is preceded for one or two days by itching, increased towards evening and at night, and by all causes which excite the circulation. The eruption consists either of pale rose-coloured or greyish pimples, or of pointed vesicles, containing serum, raised slightly above the surface. In severe cases these vesicles enlarge, and become filled with pu

(Scabies purulenta), or they are destroyed by friction, and leave small round dark spots. The pimples or vesicles are either single or in small groups; rarely in patches of any size. The disease is attended throughout by most distressing itching.

Causes.—*Predisposing.* Neglect of personal cleanliness.—*Exciting.* Contagion; the *Acarus* (Sarcoptes, Cheyletes) *scabiei* (Fig. 93) is common to man and the domestic animals. Half an hour after it is placed on the skin it bores perpendicularly through the cuticle, and then obliquely through the softer cells beneath to the cutis, in a little circular depression of which it lodges itself.

Fig. 93.



Diagnosis.—The vesicular and pustular forms are distinguished by a little black line which can usually be traced from the centre of the itch vesicle outwards for a short distance. This is the tunnel formed by the acarus. When scabies assumes the papular form, and the summits of the pimples are scratched off, so as to leave round dark spots, it is difficult to distinguish from *Prurigo senilis.* Advanced age affords a probability in favour of the latter; while the fact of more than one member of the same family being affected is conclusive as to the former. From *lichen,* by the latter being papular, more clustered, and, if situated on the hand, being on the back, and not between the fingers. From *herpes* and *eczema,* by the vesicles being more isolated and in smaller clusters, by the intense itching and by their contagious nature, and often by their situation. Scabies very rarely attacks the face.

Fig. 94.



Treatment.—Sulphur ointment, or an ointment of sulphur and carbonate of potash; sulphur baths; sulphuret of lime, with olive oil; a strong alcoholic solution of stavesacre. Cleanliness and the warm bath, and gentle aperients if required, are useful auxiliaries.

ACARUS FOLLICULORUM.

Synonym.—Demodex folliculorum. Steazoon folliculorum.

This parasite (Fig. 94) was discovered by Henle and Gustave Simon, in 1842. In England it is undoubtedly very rare. It sometimes occurs singly, sometimes in groups of as many as thirteen in a follicle; they usually occupy the duct near the orifice, towards which the abdomen is directed, the head lying deeper in the gland.

According to Erasmus Wilson the animal varies in length from the $\frac{1}{135}$ to the $\frac{1}{81}$ of an inch. Much difference exists in the length and development of the abdomen. As represented in Fig. 95 it is much elongated. In the other varieties there are four pairs of legs, and the abdomen is shorter.

Symptoms.—This parasite usually causes no disturbance, and appears to be compatible with a perfectly healthy state of the sebaceous follicles; sometimes, however, it produces pustular and indurated acne of rather an inveterate form.

Treatment.—The follicles should be emptied by pressure, and unguentum sulphuris, or a solution of sulphur and camphor in spirit of turpentine, rubbed in.

PHTHIRIASIS.—LOUSINESS.

Three species of louse take up their abode on the human body. They are the following:—Pediculus capitis, Fig. 95; P. corporis, Fig. 96; and P. pubis, Fig. 97.

Symptoms.—They run about and bite the skin, producing intolerable itching, and occasionally pustular eruptions; their eggs (popularly called *nits*) are readily observed attached to the hairs.

Fig. 95.



Fig. 96.



Fig. 97.



Treatment.—Mercurial ointment, well rubbed in, is an effectual remedy against the *P. pubis*. The unguentum hydrargyri ammoniati is equally efficacious against the other two species. When the use of mercurial preparations is objectionable, stavesacre ointment may be substituted.

FILARIA MEDINENSIS.—GUINEA-WORM.

Synonyms.—Dracunculus. Hair-worm.

Symptoms.—An itching is felt in the skin of some part of the arms or legs; most frequently in the legs, and especially in the feet. This is soon followed by a small vesicle, succeeded by an indolent inflamed swelling like a boil, which breaks and discharges. The head of the worm gradually protrudes through the opening, so as to be easily seized; but unskilful attempts to withdraw it are apt to be followed by acute inflammation, extensive suppuration, and, in some cases, mortification.

Diagnosis.—The length of the worm varies from half a foot to twelve feet. Its form and size are shown in the subjoined engraving (Fig. 99) of a worm extracted from the heel of a negro, and preserved in the Museum at King's College. The form of the tail is seen at *a*. The head is of a darker colour than the body.

Fig. 98.



Causes.—*Predisposing.* The rainy seasons in the tropical regions of Asia, Africa, and especially Upper Egypt, Nubia, and Guinea.—*Exciting.* The worm in an embryo state pierces the skin (usually the feet and hands), immersed in, or otherwise brought into contact with, the water which it inhabits.

Treatment.—The worm to be cautiously extracted, by rolling a fresh portion each day round a quill strapped in the intervals to the adjoining skin. Suppuration to be promoted by poultices.

Prophylaxis.—When the disease prevails among bodies of men, separation from the sound, and scrupulous cleanliness. (Consult Sir James Mc Grigor's "Medical Sketches of the Expedition to Egypt from India.")

ORDER II.

VEGETABLE PARASITES.

*EPIDERMMYCOSIS VERSICOLOR .	Chloasma.
EPIDERMMYCOSIS DECALVANS .	Baldness.
EPIDERMMYCOSIS TONSURANS .	Ringworm of the Scalp.
DERMMYCOSIS CIRCINATA . .	Ringworm.
DERMMYCOSIS SYCOSIS . . .	Parasitic Chin Welk.
DERMMYCOSIS FAVOSA . . .	Scall Head.
PLICA POLONICA	The Polish Plait.
FUNGUS FOOT OF INDIA.	

EPIDERMMYCOSIS.—MOULDINESS OF THE EPIDERM; AND DERMMYCOSIS.—MOULDINESS OF THE SKIN.

Under these generic terms are included all diseases of the skin and its appendages, which are known to be due to vegetable parasites.

The confusion in the nomenclature of skin diseases is so complete, that an apology for employing new terms which are at once significant and descriptive is scarcely needed. In applying these new terms, we shall associate them with the names in common use, in order that the diseases to which these refer may be the more readily recognized.

EPIDERMMYCOSIS VERSICOLOR.

SYNONYMS.—Tinea and Pityriasis versicolor. Chloasma, Pannus hepaticus. Liver spots.

SYMPTOMS.—Delicate pinkish, greyish, or light yellowish-brown, round spots, varying in diameter from the ⅛th of an inch to an inch or more, in the axillary, pubic, and inguinal regions, gradually extending and becoming confluent, so as to form continuous patches with sinuous margins, covering the greater part of the chest, abdomen, and shoulders, leaving here and there a small island of healthy skin. Its favourite seat is under the hairs about the pubes. It never affects parts exposed to the light. The colour varies much; in most persons of dark complexions, it has a light dirty-brown colour, and is separated from the surrounding healthy skin by a sharp line; in others the colour is fainter, and resembles sunburnt skin. Occasionally only a few small circles of skin are unaffected, forming, perhaps, a single cluster, not larger than the hand, on some part of the trunk. The hue of the diseased skin corresponds so closely to that of the exposed parts of the body that I have known the few pearl-like spots of healthy skin to be mistaken, under the name of *albinism*, for the diseased skin.

Usually there is no breach of surface, and the disease is apparently nothing more than a spreading discoloration; but on examining the discoloured skin attentively, the cuticle is observed to be minutely wrinkled, and on scraping it with a scalpel we find that the discoloured portions may be separated as minute silvery scales, whereas the healthy cuticle is not readily detached.

---

* See Glossary.

The disease being entirely confined to the epidermis, is unaccompanied by irritation; so that in some cases, when the patient's attention is first called to it, he doubts whether or not the discoloration is congenital. When the disease is of long standing, the cuticle becomes loose, and a minute silvery desquamation takes place continuously.

Cause.—A fungus, called Microsporon furfur, composed of minute jointed filaments forming a close network among the cells of the cuticle, and developing vast numbers of bright spherical, nearly equal-sized spores, in patches of various sizes (Fig. 99).

Contagion.—The fungus may be easily transplanted to the healthy skin by lying between sheets previously used by one affected with the disease. The fungus never attacks persons before the age of puberty. According to my own observations it is more frequently found in men than in women, and in those who lead a dissolute life. Robust health and cleanliness confer no protection whatever. The gentleman from whom the specimen delineated in Fig. 100 was obtained, was of the most scrupulously cleanly habits; yet the disease spread unchecked for two years. Indeed daily baths appear to facilitate its development.

Fig. 99.



Diagnosis.—The characteristic appearance under the microscope. The cuticle should be scraped off with a scalpel, placed on a glass slide, and wetted with weak solution of ammonia, which renders the cells transparent. So minute is the fungus that a ⅛ object glass, at least, is necessary. Epidermmycosis versicolor is frequently mistaken for syphilitic eruptions, and the patient subjected to treatment accordingly.

Treatment.—Solution of chloride of mercury (gr. i–iii to f℥j); or hyposulphite of soda (gr. xxx to f℥j); sulphurous acid daily applied to the skin, or a saturated solution of biborate of soda. The disease rapidly yields, and the skin resumes its healthy colour under this treatment.

EPIDERMMYCOSIS DECALVANS.

Synonyms.—Tinea and Porrigo decalvans. Alopecia areata. *Phyto-alopecia.*

Definition.—Mouldiness of the roots of the hair, resulting baldness.

Symptoms.—The hair becomes dry, withered, and faded; fa off, and is not regenerated, leaving more or less circular patches smooth apparently healthy skin.

Cause and Pathology.—The development of the fungus Mic sporon Audouini in the roots of the hair, within the follicles, a for a little distance beyond. The plant is composed of minut round and oval spores, and short branched filaments. It forms uniform layer round the roots of the hair, and invades the cutic and cortex, rendering the hair opaque and brittle. The pla develops very rapidly.

This form must be carefully distinguished from non-parasi Alopecia, which is usually a much more general affection (see p. 64

Contagion.—The disease is readily communicated by the spo of the fungus.

Treatment.—That recommended for Epidermmycosis versicol

EPIDERMMYCOSIS TONSURANS.—RINGWORM OF THE SCALP.

Synonyms.—Tinea tonsurans. Porrigo scutulata. Herpes t dens. Trichosis furfurans. Rhizo-phyto-alopecia.

Definition.—Mouldiness of the roots of the hairs of the he resulting in their breaking away nearly on a le with the surface of the skin.

Fig. 100.



Symptoms.—The hairs are thickened, bent at th junction with the skin, have a withered appearan become very brittle at the roots, and ultimately bre off at a distance of one or two lines from the surfa The stumps present a ragged, split appearan and readily break if an attempt be made to remo them from the follicle. The disease affects the h in dry, scaly, circular patches, varying from half inch to four inches in diameter; the contiguous cuti sharing in the disease, and forming characteristic sc fringes round the orifices of the hair follicl Vesicles and dry scabs are occasionally formed duri the progress of the disease.

In some cases the hair follicles become inflam and thickened, giving a prominence to the affect patch. After a time the follicles gape and exu a clear viscid fluid. The part feels boggy and the neighbouri glands become swollen. To this variety the term *Kerion* is appli

The nails are occasionally affected in Favus and Ringworm (*Onychiomycosis*); they become coarsely striated, thickened and arched the edges are friable and lamellated, and the bed of the nail becomes atrophied and invaded by an accumulation of dry scales in which the spores of the fungus may be detected.

Fig. 101.



Cause and Pathology.—The roots of the hair are found to be completely pervaded and split up by the Tricophyton tonsurans (Figs. 100, 101), a fungus composed of minute round or oval spores, destitute of granules, and short curved filaments.

Contagion.—The disease is readily communicated by the spores. Cats are especially liable to this disease, and in London are certainly the chief means of its dissemination. Fig. 102 represents one of the broken hairs of the nearly bald face of a young cat. The fungus has almost severed the hair at the junction 2, of the shaft, and root *d*; at *d*, the soft cells of the hair bulb are represented.

Treatment.—That recommended for Epidermmycosis versicolor.

DERMMYCOSIS CIRCINATA.—RINGWORM.

Synonyms.—Tinea circinata. Herpes circinata.

Definition.—Mouldiness of the skin, chiefly of the epidermis, spreading in the form of rings.

Symptoms.—At first a number of very small vesicles arranged in circles on a red, inflamed base. The breadth of the ring is usually about a quarter of an inch; the base itself varying from a few lines to one or two inches. The vesicles crack, and the secretion dries and forms scales which are readily detached. External to these scales a fresh ring of vesicles is developed, which also become converted into scales, and thus the process goes on, the patch constantly widening by centrifugal growth, and leaving the parts previously affected inflamed and covered with dry scales. The disease chiefly attacks the young, and usually appears on the face, neck, chest, and arms. When it affects the scalp, it takes on the same form and produces the same effect as Epidermmycosis tonsurans, with which it is probably identical. The disease is highly *contagious*.

The development of the fungus is greatly favoured by the he and warmth of the axilla or the fork, and it is here that we see t most luxuriant development of the disease. The rings are of gr size, the margins very distinct, the whole patch of a deep red colo and there is much irritation. This is the so-called *Ezcema m ginatum*.

The *cause*, *mode of propagation*, and *treatment*, are th described under Epidermmycosis tonsurans.

DERMMYCOSIS SYCOSIS.—PARASITIC SYCOSIS.

Synonyms.—Tinea sycosis. Mentagrophyte. Chin Welk. Trich mycosis.

This form must be distinguished from that described p. 631.

Symptoms.—Redness, tension and smarting of the skin of t chin, lower jaw, or upper lip, followed by an eruption of small r points, which, in a day or two, ripen into distinct pointed pustul traversed by a single hair. After five or six days more, the pustul discharge their contents, and form thin brownish scabs, which f off, and are sometimes not renewed, the disease terminating in fr ten days to a fortnight; but usually successive crops are develop and, in extreme cases, the skin is cover with a thick, yellowish-brown crust, which the hairs are matted. When t disease has continued some time the bea falls off. In chronic cases, the skin of t parts affected is covered with tuberck The disease may attack any part whe the hairs are strong. It is often ve obstinate.

Fig. 102.



Cause and Pathology.—The disea is due to the development of the Mic sporon mentagrophytes (Fig. 102), whi invades the hair follicles and forms a shea round the roots of the hairs. The fung luxuriates in the epithelial layer of t hair follicle, and sets up inflammation the subjacent vascular parts.

Diagnosis.—A friable and loose con tion of the hairs, and the presence of t fungus. The spores are very minute, a the filaments branch at acute angles a are annulated.

Treatment.—The hair should be removed from the affect follicles by pincers, and a solution of corrosive sublimate (gr. x ℥j) should be applied with a camel hair brush. Epilation is usua easy and painless, for the tendency of the disease is to loosen t hair.

DERMMYCOSIS FAVOSA.—FAVUS.

Synonyms.—Tinea favosa, annularis, et rugosa. Porrigo lupinosa, et scutulata. Scall head. Honeycomb scall.

Varieties.—Porrigo favosa; porrigo scutulata; porrigo decalvans.

Symptoms.—Small round pustules, usually seated on the hairy scalp, and containing a yellow matter, which hardens into a prominent scab with a central depression (*favus*). The disease generally attacks children, but is not confined to them. The primary seat of the disease is in the hair follicles.

It is not confined to the scalp, but may attack the chin, eyebrows, or forehead, and, in rare instances, the trunk or extremities. The scabs have an offensive mousy odour. When the pustules are closely set, the yellow crusts become confluent, and present a honeycombed appearance. If few pustules only appear, and their development be not interfered with, the favi become greatly enlarged, sometimes to the diameter of 1¼ inch; and form circular, yellow, dry elevations, depressed in the centre, and with smooth, rounded, varnished margins. These large crusts may become confluent, and then form the variety known as *Porrigo lupinosa.* When the disease is of some duration, it may be seen at the same time in all its stages—the red patches, the cluster of yellow pustules, crusts of various thickness, and bald spots. If the scabs be removed by poultices, the favi are reproduced on the clean raw surface. When the disease disappears, the hair is slowly reproduced, but sometimes there is permanent baldness. The nails are occasionally affected.

Fig. 103.



Causes and Pathology.—The disease is due to the development of the Achorion Schönleinii (Fig. 103), in the deeper layers of the epidermis, and on the surface of the cutis. At first the deeper epithelial cells are disturbed. The cuticle, and subsequently the whole epidermis, becomes raised into a circular, yellowish-white spot, which increases in size, assumes a sulphur yellow colour, and becomes a favus. When, as is commonly the case, the parasite attacks the hair follicles, the depressed centre of each favus is occupied by a hair, which becomes thickened, opaque, non-elastic, and may readily be removed. When the crusts are separated, soaked in ammonia, and examined, they are found *to be chiefly* composed of the spores and large-jointed spore—containing filaments of the fungus.

Diagnosis.—The presence of the fungus distinguishes the disease from eczema and impetigo; and the scabs of eczema have never the characteristic alveolar depressions. The pustules of impetigo are prominent and convex, seated on an inflamed base, and the purulent contents have no trace of fungi.

Prognosis.—The disease is often obstinate and of long duration.

Treatment.—The hair must be cut close with sharp scissors, and well washed, and the scabs must be softened with warm fomentations or poultices. The best local applications are the iodide of sulphur ointment and a saturated solution of sulphurous acid.

PLICA POLONICA.

A disease of the hair allied to the present class, but almost unknown in this country. It consists in an inflamed and tender state of the scalp, and a swollen condition of the hairs, which are glued together into a compact mass by a viscid and offensive secretion. Two parasitic plants—the Tricophyton tonsurans and Tricophyton sporuloides—are said to accompany it, and are thought to be the cause of it. Nothing is known of the proper treatment, but the disease seems to be aggravated by cutting the hair. Stimulants, such as the mixed vapour of iodine and sulphur appear to be the most hopeful means of cure.

FUNGUS FOOT OF INDIA.

Synonyms.—Madura foot. Podelkoma. Mycetoma. Ghootloo. Mahdeo. Kirudeo. Dr. H. V. Carter, of Bombay, has given a full description of this disease, and an elucidation of its cause, in the "Trans. of the Medical and Physical Society of Bombay," 1860. The following is a brief summary of the principal facts:—

Symptoms and Pathology.—The disease appears as a flattened swelling of the integument, from which the cuticle is thrown off, leaving a white surface, which presents numerous pinkish spots, and on making sections of the cutis these are found to be the extremities of pink, red, or orange-brown streaks radiating through the corium. This deposit is composed of minute bright globules, measuring $\frac{1}{4000}$ to $\frac{1}{8000}$ of an inch in diameter. Occasionally spherical groups of spores are seen. After a time the whole foot becomes swollen, and greyish depressed spots appear, composed of a thin layer of cuticle, which finally breaks and discloses the orifice of channels, allowing the passage of a probe for a greater or less distance. Numerous depressions and circular apertures form over the surface of the dorsum, sides, and heel of the foot; they are large enough to admit a pea or a shot, and numbers of small round ıles like fish-roe or poppy-seeds are discharged with an ichorous ıive fluid from the orifices. The foot continues to enlarge, and ıes much misshapen. The surface dled with numerous round holes of ıs sizes, leading to canals and es which pervade all the textures of ot, including the bones. The lower of the tibia and fibula are often ated into numerous communicating es, some large enough to lodge a nut. The sinuses and excavations lled with mahogany-brown or pink les. A section of the diseased presents great indistinctness of the tissues being everywhere ex- ed, changed, and in places infiltrated the coloured granules. The disease ıs its maximum development in four years. It may continue for e years. No acute pain attends its ess, but merely a deep-seated ach- The health suffers considerably, he patient becomes emaciated and

Fig. 104.*



one case the disease has been ob- l to attack the hand.

USE.—The development of a fungus, named by Mr. Berkeley, ıyphe Carteri. It occurs in globular masses, varying in size

Fig. 105.



ı pin's head to that of a bullet (*a b c*, Fig. 104), friable and upon the surface, where they present numbers of minute tuber-

---

A globular mass of the fungus, natural size. *a*. Another in section. A fourth of *a* slightly magnified. Spherical granules from outer surface of *b* magnified; *e* and *f*, beaded :ts and spores highly magnified.

cles (*d*). Sections show a radiated arrangement (*a*). Minutely examined, they are found to be composed of radiating tubular fibres, which branch and unite towards the circumference (*c*). Near the surface they become beaded (*e*). Interspersed among these fibres are the spores (*f*). Dr. Carter believes that the fungus is introduced from without, the spores gaining admission through the orifices of the sweat ducts, or any slight abrasion of the surface. The disease has occasionally followed a prick from a thorn. Farm labourers between the ages of 17 and 50, who go about with their feet uncovered, are most liable to its attacks.

Distribution.—The disease is endemic in the Bombay and Madras Presidencies, and N. W. Provinces. "Kattiawar, Kutch, Gujerat, Sind, the Deccan, Lower Concan, are known localities in the Madras Presidency. On the Madras side, Guntoor, Bellary, Madura, and Cuddapah are well-known localities; parts of Mysore, and, it is said, Trichinopoly." (Carter.) "In the Dependencies of the Punjaub (N. W. Provinces), the greater number of cases come from Igepore and the Bicaneer territories. It prevails also in the Bhuttuana, Harrianah and Bhawalpore districts." (Hon. Asst. Surgeon Peter A. Minas, to whom we are also indebted for the sketch from which Fig. 105, representing the disease in one of his patients, has been made.)

Treatment.—In the later stages, amputation of the foot is the only remedy. In the earlier ones, the application of a strong solution of corrosive sublimate or hyposulphite of soda.

NON-PARASITICAL SKIN DISEASES.

Order 1.

EXANTHEMATA.—RASHES.

Rubeola . . .	Measles (p. 313).
Scarlatina . .	Scarlet Fever (p. 316).
Erysipelas . .	St. Anthony's Fire (p. 270).
Erythema . . .	Inflammatory Blush.
Urticaria . . .	Nettle-rash.
Roseola . . .	Rose-rash.

ERYTHEMA.—INFLAMMATORY BLUSH.

Symptoms.—Red patches of variable form and extent disappearing on pressure, with little or no swelling, heat, pain, or fever. Not contagious, nor dangerous.

Varieties.—1. *Erythema papulatum*, occurring in young persons of both sexes, on the trunk and upper extremities, in small, round, and slightly-prominent patches, which disappear entirely in the course of a few days.—2. *E. tuberculatum*, in which the patches are larger, more prominent, and more permanent.—3. *E. nodosum*, which occurs chiefly in children and young persons of both sexes, on the extremities, especially the forepart of the leg, its form rounded or oval, its size varying from half an inch to an inch in diameter, at first slightly raised above the surface, but in a few days assuming the form of red, painful tumours, which disappear in a week or fortnight. It is generally preceded by debility.—4. *E. centrifugum*, appearing mostly on the cheek, as small round raised patches, which gradually spread from a small pimple till they cover a considerable surface.—5. *E. intertrigo*. The blush and irritation caused by prolonged contact or friction of two surfaces of skin.

TERMINATIONS.—In resolution, with or without desquamation (E. fugax and E. læve); or in an offensive sero-purulent exsudation.

CAUSES.—Friction and pressure; heat and cold; acrid discharges, as that of coryza; leucorrhœa, or gonorrhœa; unhealthy state of the urine and fæces; dentition; dyspepsia; tension of the skin as in anasarca.

DIAGNOSIS.—From *erysipelas*, by the redness being lighter and more superficial, and the swelling less; by the absence of heat and pain; and by its milder character and more favourable termination. From *roseola*, by the peculiar rosy tint of the latter. From *rubeola* and *scarlatina*, by the semi-lunar patches of the first, and the great extent and deep-red hue of the last. Also by their peculiar symptoms and contagious character.

PROGNOSIS.—Favourable.

TREATMENT.—When idiopathic, these blotches disappear without treatment, or yield to gentle aperients, the warm bath, and tonics. If symptomatic, the treatment is that of the primary disease.

When Erythema nodosum occurs in women, the menstrual function is usually disordered, and chalybeate tonics are required.

URTICARIA.—NETTLE-RASH.

VARIETIES.—1. Urticaria evanida. 2. Urticaria febrilis.

1. URTICARIA EVANIDA.

SYMPTOMS.—An eruption resembling in appearance, and in the intolerable smarting which attends it, the stinging of nettles. The spots often appear suddenly, especially if the skin be rubbed or scratched, and seldom last many hours, sometimes not many minutes, but vanish, to appear on another part. Sometimes the rash assumes the form of long wheals, like blows from a whip or cane. The swellings are always firm, and contain no liquid. In some persons the rash lasts only a few days, in others many months or years, appearing and disappearing at intervals, generally disappearing in the day, to return in the evening. It is accompanied by slight feverishness, and terminates in desquamation.

Causes. — *Predisposing.* Hepatic derangement. — *Exciting.* Handling the nettle; shell-fish; mushrooms; honey; vinegar; cucumbers; salad. Strawberries and several other fruits and articles of diet will cause it in certain persons; also valerian, turpentine, and copaiba. It almost invariably follows the first tapping of a hydatid cyst.

Diagnosis.—By its close resemblance to the sting of the nettle, the itching that attends it, and its fugitive character.

Prognosis.—It generally disappears under the use of simple remedies; but may last for months or years.

Treatment.—If caused by irritating food, an emetic, followed by an aperient. In chronic cases, warm or vapour, alkaline or sulphur baths; with a strictly regulated diet, aperients, and alteratives. In obstinate cases, Fowler's solution (Form. 292). The smarting may be allayed by lotions of acetate of lead, or cyanide of potassium, or by the warm bath.

2. Urticaria Febrilis.

Symptoms.—This is generally caused by some article of food which has disagreed with the patient. There is more or less fever or constitutional disturbance, followed by heat and tingling on the body; and then by an eruption, beginning on the shoulders, loins, and inner surface of the arms and thighs, and round the knees, consisting of irregularly-shaped pale blotches, surrounded by a deep red border, but soon assuming an uniform deep red colour, and attended by intense itching. The blotches appear and disappear several times, and gradually subside in a few days or a week. There is generally an increase of itching and smarting towards evening. Sometimes there is much attendant erythema, and the face may be so swollen as to close the eyelids. Rarely the rash is of a deep venous tint. The *treatment* is that of Urticaria evanida, but more active. After an emetic of ipecacuanha, a saline aperient (Form. 242).

ROSEOLA.—ROSE-RASH.

Symptoms.—Slight febrile symptoms, succeeded by deep red patches of various size and form, appearing on different parts of the body, and generally disappearing in one or two days, or a week.

Varieties.—1. *Roseola infantilis.* An eruption of numerous small, distinct, circular patches, of a deep rose red colour, occurring in infants from dentition or intestinal irritation. 2. *Roseola æstiva.* This form is most common in children and females. It is preceded by feverishness. The rash, which is of a deep red colour, and attended with itching and pain, and sometimes with an inflamed throat, with some difficulty in swallowing, commonly appears between the third and seventh days on the face and neck, whence it rapidly spreads over the rest of the body, lasts about three or four days, and then disappears. 3. *Roseola autumnalis* is a less severe affection, occurring also chiefly in children, and presenting larger patches, seated mostly on the arms.—4. *Roseola annulata*, appearing, as the name implies, in rosy rings, enclosing healthy skin, and gradually spreading. The rash is most common on the belly, loins, buttocks, and thighs. It may be acute or chronic, and is generally dependent on some disorder of the alimentary canal.

CAUSES.—Teething; irritation of the stomach and bowels; drinking cold water when the body is heated; severe exercise. The disease is sometimes epidemic, spreading in schools and families, just as measles and scarlet fever do.

DIAGNOSIS.—From measles and scarlet fever, by the mildness of the constitutional symptoms, and the absence of the catarrhal symptoms of the one, and the sore throat of the other.

PROGNOSIS.—A favourable termination in a few days or a week.

TREATMENT.—Saline aperients, and diaphoretics two or three times a day; and an occasional warm bath.

ORDER II.

VESICULÆ.—VESICLES.

VARICELLA	Chicken-pox (p. 313).
ECZEMA	Running scall.
HERPES	Totter.
MILIARIA	Miliary Fever.

ECZEMA.—HUMID TETTER.

SYNONYMS.—Running scall; crusta lactea.

SPECIES.—1. Acute. 2. Chronic. 3. Impetiginosum.

1. ACUTE ECZEMA.

SYMPTOMS.—An eruption of a punctated rose-rash spreading quickly and becoming confluent; about the third day, the formation of almost microscopical vesicles corresponding to the primary rash. There is distressing irritation from the first. The fluid in the vesicles soon becomes opaque and turbid, and in four or five days is discharged, and dries into thin yellowish green scabs. Fresh vesicles form on the surrounding skin, while the parts already affected are kept moist by constant exsudation. When the eruption is of some standing, the skin presents a highly-inflamed surface, studded with numerous minute pores, covered with thin white membranes. Usual duration, from a week to a month.

VARIETIES.—*Eczema simplex.* A mild form, free from constitutional disturbance, mostly attacking women and young children on the arms and hands, generally terminating in resolution. When it attacks the fingers and parts covered by thick cuticle, it is ver distressing.—2. *Eczema rubrum*. The skin is inflamed, hot an tense, of a bright red colour, and covered with small vesicles su rounded by an inflamed areola. The rash generally terminates i about a week in free desquamation; but in severe cases the inflammation increases, the vesicles coalesce, the contained serum become opaque, and at length escapes as an irritating fluid, which forms loos thin incrustations, and these falling off, display a highly-inflamed su face. The disease either disappears in two or three weeks, the healing process beginning at the margins; or it becomes chronic —3. *Eczema impetiginosum*. In this form, the inflammation, which i still more acute and rapid in its progress, is accompanied by much swelling and tension, and some fever; and the contents of the vesicles becoming purulent, dry into soft yellow scabs, which fall off, and are reproduced, displaying a red inflamed surface covered with an ichorous serum. It terminates within a month, or may run into the chronic form. It is scarcely distinguished from impetigo, which is a pustular disease from the beginning.

CAUSES.—*Predisposing*. The female sex; spring and autumn.—*Exciting*. Intense heat; blisters, mercurial frictions (*eczema mercuriale*); the handling of dry powders, flour, metals, &c.; dentition; intestinal irritation.

DIAGNOSIS.—An abundance of watery vesicles with tenderness and smarting distinguish eczema from scabies. *Miliaria* is accompanied by fever and profuse perspiration. *Lichen* is papular. *Psoriasis* is dry and scaly.

PROGNOSIS.—*Favourable*, but the disease is often difficult of cure.

TREATMENT.—The mineral acids given internally, cooling drinks, simple diet, warm baths, water-dressing, local baths of linseed, marsh-mallow or bran, or poultices of potato-flour. The tingling and smarting may be relieved by decoction of poppy-heads, or by a lotion consisting of two grains of cyanide of potassium to an ounce of water. Alkaline lotions, and zinc or chalk applications are often of much service.

2. CHRONIC ECZEMA.

SYMPTOMS.—This is a sequel of the acute form, and often intractable. The skin, from the continued abundant discharge of acrid serum and the reproduction of the vesicles, is highly inflamed and marked by fissures at the joints. Sometimes there is but little moisture, and the surface is cracked and covered with shining crusts, beneath which the skin is of a bright-red colour. The disease often spreads from a small point over a considerable extent of surface, and is accompanied by intense itching and smarting, which is particularly distressing when the eruption occupies the inner surface of the thighs, the verge of the anus, or the vulva. When it attacks the face, the conjunctiva of the eye is involved, and there is much smarting, with some intolerance of light. The fingers and palm are also liable to this form: deep fissures run across the joints, both on the flexor and extensor sides, the parts are a little swollen and motion causes pain. The eruption often lasts for years, being heightened and renewed in spring and autumn; and sometimes, after the resources of art and the patience of the sufferer are exhausted, rapidly disappears.

Treatment.—Mineral acids with one of the bitter infusions; alkaline lotions externally; an alterative aperient at bed-time occasionally. In obstinate cases ♏iii to ♏v of liquor arsenicalis may be prescribed. The sulphur bath (Form. 43) may be used with advantage. The itching and smarting are best allayed by zinc ointment mixed with spirits of wine (ung. zinci ℥i, spt. vin. rect. ʒi) smeared over the surface, and renewed once or twice a day; or by simple cold-water dressing. Vaseline is a very good remedy. A handkerchief, moistened with a teaspoonful of chloroform, placed near the seat of irritation, and covered with the bedclothes, often allays the smarting. A solution of nitrate of silver (ten grains to the ounce) will also sometimes afford great relief. (G.)

HERPES.—TETTER.

Symptoms.—The rash begins as circumscribed groups of distinct vesicles on an inflamed base; but these soon coalesce, and their contents, which were at first watery, become yellowish white or yellow, escape, and form a firmly adherent scab, which on separating leaves an inflamed surface, very tender, and not very readily healed. The eruption is commonly preceded by slight constitutional symptoms, and sometimes by acute darting pain, which, when the rash appears, changes to heat and smarting. The disease is rarely attended with danger, and generally lasts about a week or ten days.

Varieties.—1. *Herpes phlyctenodes*, that which has no particular seat.—2. *Herpes labialis*, that which affects the lips. It may extend to the nose, cheeks, and chin; and may attack the mucous membrane of the lips and mouth. It is a very common accompaniment of catarrh, and of inflammatory affections of the mucous membrane of the mouth, throat, and stomach; and it often appears during attacks of pneumonia, ague, and especially relapsing fever.—3. *Herpes preputialis* attacks the internal or external surface of the prepuce, and is preceded and accompanied by itching and smarting. It is easily distinguished from syphilis when recent, and afterwards by its history. If a sore form, it is superficial and readily heals.—4. *Herpes zoster, zona, or the shingles*, has a characteristic appearance, position, and course. As the name implies, it surrounds the body like a zone or girdle, beginning somewhere about the mesial line, and travelling round one-half the body, following the direction of the intercostal nerves, below the nipple, at the lower part of the back and groin, or at the upper part of the thigh. It is often preceded for days, or longer, by acute darting pains. It usually runs a mild course, and disappears in two or three weeks—but in some cases there is considerable ulceration of the integument, and tenderness may linger a long time in the cicatrix.—5. *Herpes iris*, a very rare variety, consisting of four rings of different shades of colour.

Causes.—*Predisposing*. An east wind.—*Exciting*. Catarrh; inflammation of the mucous membranes; indigestion.

Diagnosis.—From *pemphigus*, by the smaller size and greater number of the vesicles. From *eczema*, by their larger size, the raised inflammatory base, and usually by the smaller size of the patches.

Treatment.—Gentle aperients with antimonials, a regulated diet, and local applications of warm mucilaginous liquids.

MILIARIA.—MILIARY FEVER.

Symptoms.—This disease sets in with rigors, extreme debility, depression, and a sense of tightness and oppression about the præcordia, with shortness of breath, and, in some instances, a teasing cough, followed by increased heat of surface, with wandering pains and restlessness. After these symptoms have continued from two to five or six days, a *profuse sweat*, of a sour, rank odour, breaks out, accompanied by a harassing pricking or itching of the skin. On an *uncertain day*, a number of small red or white papules, the size of millet-seeds, appear first on the neck and breast, whence they gradually extend to the trunk and extremities. After *ten* or *twelve hours*, a small vesicle forms on the top of each pimple; the contents are at first transparent, but become white; and they have a peculiarly offensive odour. In *two* or *three days* the vesicles break, and are succeeded by small crusts. The disease terminates in resolution, or desquamation. The febrile symptoms do not subside on the appearance of the eruption, but after a variable interval.

I have seen but one case of this disease; as an endemic affection we have no knowledge of it in Britain.

Causes.—*Predisposing*. Childhood; old age; the female sex; the period of childbirth; debility; dyspepsia.—*Exciting*. Immoderate sweating.

Diagnosis.—By the uncommon anxiety and dejection; the peculiarly fœtid, rank odour of the profuse perspiration. Afterwards the characteristic eruption.

Prognosis.—*Favourable*. The fever assuming a mild form, and remitting on the appearance of the eruption; the papulæ of a florid red colour—*Unfavourable*. Increase of fever; great anxiety and depression; coma; the sudden disappearance of the eruption followed by prostration.

Treatment.—A moderate temperature and tepid sponging. After an aloetic purge, sulphuric acid with bark or quinine. If there be much restlessness, opium.

ORDER III.

BULLÆ.—BLEBS.

PEMPHIGUS . . .	Vesicular Fever.
RUPIA	Atonic Ulcer.

PEMPHIGUS.—VESICULAR FEVER.

ONYMS. — Bullæ; phlyctena; pompholix; hydatis; febris a.

IPTOMS.—The rash is ushered in by lassitude, headache, sick- oppression, frequent pulse, and, in some instances, delirium. *uncertain day* an eruption takes place of red circular patches, soon terminate in pellucid blisters, similar to those produced burn, resting on an inflamed areola, and distended with a -coloured serum. They appear on the face, neck, trunk, arms, , and fauces, and measure half an inch or more in diameter. ew days the blisters either break and discharge a yellowish, , or sharp ichorous fluid, or they begin to shrink, and in a time disappear. Occasionally the fluid dries up into flakes iecrust (*P. foliaceus*).

RIETIES.—1. *P. infantilis* attacks young infants in lying-in als. It has been mistaken for syphilis.—2. *P. solitarius* racterized by the appearance of a single bleb at a time, at intervals.—3. *P. diutinus* is a chronic disease, occurring, for ost part, in middle-aged and old men, lasting for a considerable and sometimes extending over the entire body.—4. *P. ænosus*, the contents of the bullæ dark and fœtid, leaving gangrenous ulcers. It occurs in half-fed, overcrowded children.

USES.—*Predisposing*. The male sex; adult and old age; er season.—*Exciting*. Unwholesome and scanty food, bad ation, and all the causes of cachexia; especially syphillis.

GNOSIS.—From *vesicular eruptions*, by the large size and on of the vesicles. From *rupia*, by the absence of thick scabs. *ecthyma*, by the contents of the blebs being transparent. *erysipelas*, by the regular form and isolated situation of the rs.

GNOSIS.—*Favourable*, except in the 4th variety.

EATMENT.—In mild cases, gentle aperients, with quinine, and lrinks. If the patient be cachetic, alteratives with tonics or lants, and a generous diet.

e local treatment consists in puncturing the vesicles as they r; and if there is much pain, the use of warm poppy fomenta-

RUPIA.—ATONIC ULCER.

Synonym.—Ulcus atonicum.

Symptoms.—This disease consists in round, flattened and isolated blebs, about the size of a shilling, filled with serum, which changes after a time to pus. These blebs shrink, and become converted into thick brownish scabs, which, when they fall off, leave ulcers that either heal or continue open for a while. The disease attacks weakly and cachectic subjects, and runs a chronic course, lasting from a few weeks to several months. Its most common seat is the lower extremities.

Varieties.—1. *Rupia simplex* is the mildest form of the disease, and answers to the above description. 2. *Rupia prominens* is named from the greater thickness of the scabs, which are formed by several layers of hardened secretion, assume a conical shape, and an appearance not unlike that of an oyster shell in miniature. The blebs are larger, and the inflammation and subsequent ulceration more extensive than in rupia simplex. This form occurs chiefly in syphilitic subjects.—3. *Rupia escharotica* affects infants in the interval from birth to the first dentition, is accompanied by much constitutional disturbance, and sometimes terminates fatally. The ulcers left after the separation of the scabs heal slowly, secrete a fœtid sanies, and are apt to spread.

Causes.—*Predisposing*. Debility.—*Exciting*. Syphilis.

Diagnosis.—From *pemphigus*, by the thick laminated scab, the inflammatory areola, and subsequent ulceration. From *ecthyma*, by the blebs at first containing serum; but in severe cases, the secretions soon becoming purulent, render the diagnosis difficult.

Prognosis.—*Favourable*, except in severe cases of rupia escharotica.

Treatment.—*Local*. Warm baths; emollient applications, and when the ulcers are obstinate, nitrate of silver, dilute mineral acids or stimulating ointments.—*General*. Tonics or stimulants, with alteratives, according to the patient's state; and strict attention to diet, ventilation, and cleanliness:—the treatment, in a word, of cachexia.

ORDER IV.

PUSTULÆ.—PUSTULES.

VARIOLA	Small-pox (p. 304).
VACCINA	Cow-pox (p. 311).
ECTHYMA	Ecthyma.
IMPETIGO	Running Tetter.
ACNE	Pimple.
SYCOSIS	Simple Inflammation of the Hair Follicles.
EQUINIA	Glanders (p. 337).
PUSTULA MALIGNA	Malignant Pustule (p. 338).

ECTHYMA.

SYMPTOMS.—The eruption begins as scattered, inflamed, circumscribed spots, which increase, and attain a considerable size. Pustules form on the centre, and sometimes enlarge till they closely resemble the bullæ of rupia. In two or three days the pustules dry up, and thick scabs form, which, falling off, leave a purple discoloration, or in severe cases, and in greatly impaired constitutions, an unhealthy ulcer. The eruption is sometimes accompanied by pain, and slight fever.

CAUSES.—*Predisposing.* Childhood and old age.—*Exciting.* Cachexia.

DIAGNOSIS.—From *acne, impetigo, sycosis, favus,* and *scabies purulenta,* by the larger size of the pustules, and their inflamed and indurated base. From *variola,* by their size, the absence of the central depression, and their non-contagious character. From *vaccina,* by the cellular structure of the latter, and its contagious nature.

PROGNOSIS.—*Favourable;* but sometimes chronic and tedious.

TREATMENT.—Emollient applications, and, if the ulcers assume a chronic form, nitrate of silver, or the dilute nitric or muriatic acid, or stimulating ointments. Gentle aperients and alteratives, mineral tonics, wholesome food, pure air, exercise, cleanliness, and sea-bathing.

IMPETIGO.—CRUSTED TETTER.

SYNONYMS.—Eczema impetiginosum. Crusta lactea. Running tetter; scale; cowrap.

SYMPTOMS.—The eruption appears as clusters of small pustules, slightly raised above the skin, bursting in from one to three days, and discharging a purulent fluid, that hardens into thick, yellow, semi-transparent incrustations, resting on an irregular, inflamed base, *moistened* by a sero-purulent fluid. The eruption may disappear in a few weeks, or it may continue for months or years, th existing patches being succeeded by fresh groups of pustul There is some constitutional disturbance, with heat and itching o the parts affected.

Varieties.—1. *Impetigo figurata* generally occurs in defin patches on the cheeks, but may attack any part; it is most common in young children, during dentition.—2. *Impetigo sparsa* i more irregular in its distribution, and is most frequently seen o the extremities, and round the joints; it may be either acute o chronic.—3. *Impetigo larvalis* attacks the scalp, ears, and lips i infants. It also occurs on the cheek, which it covers with a thick yellowish white crust, resembling a mask, whence its name.

Causes.—*Predisposing.* Spring and autumn; infancy and childhood; the lymphatic temperament.—*Exciting.* Irritation o the skin; unwholesome diet; impure air; want of cleanliness.

Diagnosis.—The formation of clusters of small, not contagious pustules (psydracia), succeeded by whitish yellow or dark brown scabs. The pustules of *sycosis* are much smaller, and the exudation less. *Favus* is contagious, and the character of the crust distinct. (See Dermmycosis Favosa).

Prognosis.—*Favourable* in its acute, *obstinate* in its chroni form.

Treatment.—Emollient applications, tepid water, and gentl aperients. The troublesome itching may be relieved by zinc o lead lotions. In chronic impetigo, in addition to tepid baths alkaline lotions to the skin; the sulphur bath; the dilute acids, o a weak solution of nitrate of silver.

ACNE.—COPPER NOSE.

Symptoms.—This disease attacks the sebaceous follicles of th skin as isolated pustules, seated on a hard, red base, and terminating in indolent chronic tumours. Its primary form is, in most cases, a hard, red pimple. It is most commonly seen on the nose, cheeks, temples, and forehead, but frequently appears on the back and upper part of the chest, and sometimes on the neck and shoulders. It may exist in all these situations in the same person. It is a chronic disorder, not accompanied by constitutional symptoms; is most frequent from puberty to the age of thirty-five; and occurs in both sexes.

Varieties.—1. *Acne simplex* answers to the foregoing description, its most common seat being the shoulders and upper part of the chest; but it may occur on the face.—2. *Acne indurata* consists in the formation of large indurated tumours by the union of several of the smaller follicles. Its common seat is the face, but it often occupies the back of the trunk.—3. *Acne rosacea* is generally met with in old persons, chiefly on the nose and cheeks. As the name implies, the diseased parts have a rosy colour, which, however, is not permanent, but changes at length to a violet. In extreme cases, the superficial veins enlarge, and the cellular tissue, to some depth, becomes inflamed and hardened (acne indurata).—4. *Acne punctata* derives its name from a small black speck, which occupies the summit of each pimple.—5. *Acne sebacea* is named from the smooth waxy appearance of the pimples.

Diagnosis.—By its seat—the sebaceous follicles, the apertures of which occupy the centre of the pustules.

Prognosis.—In *acne simplex*, favourable. It often disappears of itself with the advance of age. *Acne indurata* and *acne rosacea* often defy all modes of treatment.

Causes.—Hereditary predisposition; dyspepsia; excess in eating and drinking; uterine disorders; change of life.

Treatment.—In the young and vigorous, a restricted diet, and the avoidance of stimulating liquors; gentle aperients; lotions of acetate of lead. In chronic cases, and in *acne indurata*, the same general treatment. The use of frictions, with an ointment of iodide of sulphur (gr. xx of the iodide to an ounce of lard), or a paste of sulphur and milk. Dilute acids, or the nitrate of silver, cautiously applied to the eruption, or a lotion of two grains of the cyanide of mercury to an ounce of distilled water, are also beneficial. This lotion should be applied with a camel's hair pencil, and after a short interval washed off with cold water. A course of alterative medicines may be given at the same time. A drop of creasote in a mucilaginous draught may also be given with advantage two or three times a day. *Acne rosacea* requires a very careful regulation of the diet, exercise, abstinence from stimulating liquors, avoidance of heated apartments, hot fires, and mental excitement, with the local application of the vapour douche, or the lotion of cyanide of mercury. (Form. 91.) In very obstinate cases, blisters have sometimes been applied with advantage.

SYCOSIS.—SIMPLE INFLAMMATION OF THE HAIR FOLLICLES.

Synonyms.—Folliculitis barbæ. Herpes pustulosus. Mentagra.

Symptoms.—A chronic tubercular, tuberculo-pustular, or pustular disease of the hair follicles, commonly affecting those of the chin, or upper lip. In the early stage of the disease, the area surrounding the hairs becomes hard, red and swollen, and is soon raised into distinct pimples or tubercles, red, tender, and irritable. They may remain in this condition; or, as is more common, they pass into yellow pustules, the centre of each being occupied by a hair. In severe cases the inflammatory area spreads so as to involve the whole of the skin, which is raised into tubercles studded with pustules. When suppuration is free, crusts are formed. The hairs are not affected by the disease, unless the suppuration ex enough to involve the bulbs, when they are loosened, but happens.

Cause.—Local irritation of the sebaceous follicles of t the same nature as the inflammatory varieties of acne. in strumous and syphilitic subjects appears to be the chi cause.

Diagnosis.—A tubercle or pustule, the centre of whi pied by a hair. Absence of the Microsporon mentagr 611); and a healthy condition of the hairs.

Prognosis.—It is a most inveterate disease.

Treatment.—If constitutional disease be present, and when the stomach will bear them, advantage will be de mineral tonics, and alteratives. (Forms. 118, 289.) A alkaline aperients are beneficial when there is acidi stomach, or defective secretion of bile. Locally, we mus irritation. Tepid fomentations, occasional poultices, an use of lead and zinc lotions are beneficial.

ORDER V.

PAPULÆ.—PIMPLES.

Lichen.
Prurigo.

LICHEN.

Synonyms.—Papulæ siccæ; scabies sicca vel agria.

Symptoms.—An eruption of small, hard pimples, of the the skin, or red, generally arranged in clusters, and accom severe itching. It is most common on the hands, forear and face, but may attack other parts. It is generally a but sometimes an acute disorder. It usually terminates in mation.

Varieties.—1. *Lichen simplex* answers to the above des —2. *Lichen strophulosus*, commonly known as *red gum, wh* or *tooth-rash*, attacks children at the breast, or during den an acute affection, and generally continues for three or fou It has received many names, according to the arrangemen pimples, and the colour of the skin.—3. *Lichen urticatus* is ch ized by the large size of the papulæ and their close resemb the sting of nettles. In *lichen agrius*, the papulæ are c and seated on a highly inflamed base; the pimples ulce discharge a sero-purulent fluid, which dries into small sc these, falling off, are replaced by thin scales. It is accomp ıse smarting pain.—4. *Lichen syphiliticus* is characterized by coppery hue of the rash (p. 616).

AUSES.—*Predisposing.* The seasons of spring and summer.—*iting.* Extreme heat; irritants; abuse of alcohol; jaundice; rders of the stomach and bowels; and in children, the irrita- of teething; syphilis.

IAGNOSIS.—By the papular form of the eruption, the severe ing, and its non-contagious character.

ROGNOSIS.—Troublesome, and sometimes difficult of cure.

REATMENT.—In its acute forms, and especially in severe cases ichen agrius, low diet, brisk aperients, the antiphlogistic regi- , and tepid emollient applications. Chronic cases require ulating applications, such as a wash of carbonate of potash, ments of iodide and biniodide of mercury, and sulphur and ne vapour.

PRURIGO OR PRURITUS.—ITCHING RASH.

YMPTOMS.—A chronic disease, in which the papulæ are of the ur of the skin, larger than those of lichen, and accompanied by lerable itching. It may occur on any part of the body, but is t common on the neck and shoulders. In some instances it cks the external parts of generation in both sexes, or the gin of the anus. The papulæ are apt to be torn by friction, and resent on their summit a minute clot of blood, which gives to rash a very characteristic appearance.

ARIETIES.—*Prurigo mitis* presents a smaller sized pimple than, *rurigo formicans,* and is attended with less itching. In the r disease, the itching is greatly increased by the warmth of —3. *Prurigo senilis* is accompanied by great dryness of skin.

AUSES.—*Predisposing.* Childhood and old age, and the seasons pring and summer.—*Exciting.* All causes of debility, and exia; want of cleanliness; unwholesome food, privation, fric- irritation of the skin or of the mucous membranes.

IAGNOSIS.—From *lichen,* by the larger size of the pimples, by lark spot on their surface, and by the more severe itching.

ROGNOSIS.—Very difficult of cure, especially in aged persons.

EATMENT.—Tepid or hot baths, and gentle aperients; lotions ad and zinc with glycerin.

ORDER VI.

SQUAMÆ.—SCALES.

LEPRA, or PSORIASIS . .	Scaly Leprosy.
PELLAGRA	Italian Leprosy.
PITYRIASIS	Dandriff.
ICHTHYOSIS	Fish-skin.

LEPRA, or PSORIASIS.—SCALY LEPROSY.

SYNONYMS.—Dry Tetter; Kushta of the Hindoos; Baras of the Arabs.

SYMPTOMS.—1. LEPRA.—The eruption begins in the form of small, red, round, shining spots, slightly raised above the skin, and soon becoming covered with a thin white scale, which, falling off, leaves the surface red and scaly. The spot increases in size, still retaining its circular form, raised at the circumference, and depressed towards the centre, with a peculiar shining, silvery appearance. These patches vary in size, from a quarter of an inch to an inch and a half. The knees and elbows are the parts commonly affected, but the disease may appear on any part of the body. The spots are often arranged symmetrically on the upper and lower extremities. In cases of long-standing, several of the original spots coalesce, and form large scaly patches of a very irregular shape, and the sensibility of the skin is destroyed.

2. PSORIASIS. Is the confluent and more chronic form. The patches are irregular, often of considerable size, slightly raised above the surface, fissured, and covered with a white scale. There is some itching, especially at night, but no marked constitutional disturbance. The backs and palms of the hands, and nails are often severely affected; Psoriasis palmaris (grocers' and bakers' itch) and Psoriasis dorsalis (affecting washerwomen) are familiar forms.

SUB-VARIETIES.—1. *L. alphoides* is characterized by the small size of the patches, and the silvery appearance of the scales.—2. *L. nigricans* is a rare disease, distinguished chiefly by its darker colour.—3. *L. guttata* generally attacks adults in the form of small, round, red patches, often blended with the other forms.—4. *P. diffusa* is more irregular in shape and size. The patches are often extensive, marked by large fissures, and commonly situated on the limbs.—5. *P. inveterata* is a very severe form of the disease, and generally occurs in the aged and weakly. The skin becomes hard, thickened, and covered with a shining scale, which, when removed, leaves a red, fissured, painful, and bleeding surface.—6. *P. gyrata* occurs in spiral-shaped stripes, generally on the back. It is very rare.

Causes.—*Predisposing.* Syphilis; autumn; adult age.—*Exciting.* Syphilis, acquired or inherited.

Diagnosis. From *favus*, *impetigo*, and *eczema*, by the total absence of moisture, and by its *scaly* nature. The pustular and vesicular forms produce *scabs*.

Prognosis.—The disease is essentially chronic, obstinate, and difficult of cure, and disappears and returns without obvious cause.

Treatment.—After a short course of mild aperients, and strict regulation of diet,—alterative medicines, such as Plummer's pill, or the fifth of a grain of the biniodide of mercury, with the external application of tar ointment, or of the mixed vapour of iodine and sulphur. In Psoriasis inveterata, preparations of arsenic, iodine, and mercury. (In Psoriasis inveterata attacking delicate anæmic females, Liquoris arsenicalis ♏v, Tr. ferri perchloridi ♏xx, Infus. quassiæ ℥i, is a good combination. The itching and smarting are sometimes greatly relieved by a lotion consisting of ten grains of cyanide of potassium in six ounces of almond emulsion.) (G.)

PELLAGRA.—ITALIAN LEPROSY.

Symptoms.—This disease is allied to psoriasis. It sets in in the spring of the year with dusky red shining patches on the feet and back of the hands, which gradually spread, become studded with tubercles, and covered with dry scales, intersected, as in psoriasis, by cracks and excoriations. The rash is accompanied by slight itching. It subsides and disappears towards autumn, returning the following spring in a more severe form, accompanied by anxiety, depression of spirits, and convulsive seizures. Towards the end of autumn the disease again subsides, but less completely, and reappears early the following year; and now extends to every part of the surface, the skin being dry, tough, and shrivelled like that of a mummy. Extreme debility, diarrhœa succeeded by dysentery, dropsy, and epilepsy, follow each other, and wear the patient away, or usher in dementia or mania.

Distribution.—The north of Italy, where one-sixth of the people are affected. The south of France; parts of Spain; and Corfu.

Causes.—Obscure. 90 per cent. are poor peasants.

Treatment.—The disease is believed to be incurable, and requires the persevering use of the remedies prescribed for psoriasis.

PITYRIASIS.—DANDRIFF.

Synonym.—Eczema squamosum.

Definition.—Non-contagious desquamation of the cuticle.

VARIETIES.—*P. simplex; P. rubra; P. sebacea.*

SYMPTOMS.—1. In *P. simplex* the disease consists in an ab desquamation of the cuticle in the form of branny scales, whi constantly renewed. The subjacent skin is usually red and The scalp is the commonest seat of the disease. It prefe hairy parts, but is met with in every other situation. The i of the skin is slight in some cases, severe in others. Ther constitutional disturbance.

Pityriasis capitis occurs in all ages, and often in ne infants; is attended by slight itching; and friction detaches branny scales. *Pityriasis nigra* is known by the black co the skin.

2. *P. rubra* is a more severe and general affection. The surface of the body is usually affected, the skin is red and dry, a cuticle is very rapidly formed, and as rapidly shed in the f large dry white branny scales or plates. The desquamat enormous, as in scarlatina, the thick cuticle of the hands a sometimes separating as a glove. The affection may be a chronic; and the hyperæmia of the skin varies from a brig milion tint to a natural blush. In this variety, there is als little constitutional disturbance, and the cutaneous irritation i paratively trifling.

P. sebacea. This variety is described in modern works o disease under the names of *Seborrhœa sicca* and *S. squamo* consists of superfluous exsudation of the sebaceous glands fo a dirty white or yellowish scurf, such as is commonly seen scalp of persons who seldom wash the head. On parts not c by the hair the exuviation forms a fine mealy looking but powder. Sometimes the whole surface of the body is af great accumulation of the secretion forms under the nails, a patient actually "lards the way as he goes" by the co shedding of the fatty scurf.

CAUSES.—*Predisposing.* Youth and old age; female debility.—*Exciting.* Irritation of the skin by heat, by the rays of the sun, or by chemical or mechanical irritants.

DIAGNOSIS.—Distinguished from the contagious diseases b absence of fungi.

PROGNOSIS.—Generally obstinate and difficult of cure.

TREATMENT.—Cleanliness; tepid baths: and tonic and alte medicines. Alkaline and lead lotions, ointment containing lead, or nitrate of mercury, and sulphurous baths. The it may be allayed by lotions containing prussic acid.

ICHTHYOSIS.—FISH SKIN.

SYMPTOMS.—The whole body, or certain parts only, especial palms of the hands, soles of the feet, face, eyelids, outer sur the limbs, and the joints, are covered by a number of small, thick, dry, dark brown rhomboidal scales, resembling somewhat the scales of a fish. The rash often has a very disagreeable odour, and is not accompanied by inflammation, pain, or itching of the skin.

Causes. The disease is congenital.

Treatment. No treatment can be expected to remove the disease, but warm baths and other appropriate remedies may be used to keep the skin soft and comfortable.

ORDER VII.

TUBERCULÆ.

LEPRA ARABUM	Leprosy.
FRAMBŒSIA	The Yaws.
MOLLUSCUM	Molluscum.
CHELOIDEA	Keloid.
MALUM ALEPPORUM . .	Aleppo Button.
MORPHŒA.	
ELEPHANTIASIS ARABUM .	Elephantiasis.
DELHI BOIL OR MOOLTAN SORE.	

LEPRA ARABUM.—LEPROSY.

Synonyms.—Elephantiasis Græcorum. Lepra Egyptiaca. Lepra Hebræorum.

Varieties.—L. tuberculosa. L. anæsthetica.

Symptoms.—1. *L. tuberculosa* commonly sets in with erythematous shining patches, upon which an eruption of soft, livid tumours, of variable size, and irregular shape, makes its appearance. The vivid colour subsequently fades, and the skin becomes tawny, thickened, and tubercular. The areolar tissue often becomes hypertrophied, and the parts affected ultimately attain an enormous size. The sensibility of the skin is heightened at first, but subsequently diminished. In very severe cases, the tubercles become inflamed and ulcerated, and discharge an offensive sanies, which concretes into black scabs. When the fingers and toes are affected, the bones may be destroyed in the process of ulceration. The constitutional symptoms are merely such as result from the prolonged sufferings of the patient. The disease may occur on any part, but is most common on the legs and face.

2. *L. anæsthetica.* Burning and pricking sensations usually precede this form; erythematous patches and large bullæ then appear, and result in circular spaces of a tawny brown colour, of a lighter shade than the skin in the dark races; the edges are raised and wrinkled or cracked, the centre depressed, pale, dry, glistening, and insensible. They are usually seated on the extremities, whence they gradually extend to the trunk. As the disease advances, the

toes and fingers become shining, slightly swollen and stiff
soles and palms present deep ragged furrows; ulcers form c
joints of the fingers and toes in the lines of flexion, and enla
sphacelation until these members drop off. The lobes of th
and the alæ of the nose become thickened, and then ulce
The voice becomes hoarse from ulceration of the throat; an
some years during which these processes have been goi
diarrhœa, or dysentery supervenes, and hastens the fatal i
(Morehead, "Diseases of India.")

Pathology.—The invasion of the fibrous element of the ski
areolar tissue, and the cutaneous nerves by minute ro
corpuscles and molecular matter.

Causes.—Unknown. It is propagated by hereditary tai
contact.

Prognosis.—Generally unfavourable.

Treatment —Stimulating applications externally, and ar
preparations or cantharides internally, in combination with
infusions. Nourishing food.

FRAMBŒSIA.—THE YAWS.

Symptoms.—This disease appears without marked premo
symptoms, in the form of clusters, of variable size and sha
small dark red spots resembling flea bites. On these spots p
are developed, which degenerate into indolent vegetations,
slightly inflamed, covered with thin dry scales, and resem
when found in circular groups, raspberries or mulberries. In
instances they become the seat of ulceration, and of a yell
bloody discharge, which concretes into scabs. The surrou
skin is generally indurated.

Causes. *Predisposing.* The climate of the West Indies,
parts of America and Africa; scrofula. It is very rare amo
white population.—*Exciting.* Contagion.

Diagnosis. By the peculiar appearance of the eruption.

Prognosis. Generally favourable. It sometimes assu
chronic form, and continues for years.

Treatment.—The local application of stimulants, such as t
oxide, or yellow iodide of mercury; caustic, or the actual ca
Internally, tonics and alteratives, and mercurial preparati
small doses; and in chronic cases, the preparations of a
Warm and vapour baths.

MOLLUSCUM.

Description.—Numerous indolent tubercles, from the siz
pea to that of a pigeon's egg, of various forms, sessile or

culated, of the natural colour of the skin, containing a little sebaceous matter, unaccompanied by any constitutional disorder, and not attended by pain, inflammation, or ulceration. They present a central depression, leading to an orifice, which is closed with a plug of discoloured sebaceous or albuminous matter. After the removal of this, a coarse needle may be passed down the tumour to some distance within the skin.

Pathology.—Morbid alteration of the hair follicles and sebaceous glands resulting in hypertrophy of one or the other.

Causes.—Obscure. One form of the disease is contagious.

Treatment.—If there be an accumulation of sebaceous matter, empty the little tumours and apply strong solutions (gr. v to ʒj) of sulphate of copper and nitrate of silver.

CHELOIDEA—KELOID.

Synonym.—Cancroide.

Description.—This is a rare disease, appearing as hard, indolent tubercles, varying in dimension from a few lines to a few inches, generally isolated, but sometimes in groups, with intervals of sound skin. They are of an irregular oval, square, or angular shape, of a rose or red colour, with a depressed centre, covered with a thin layer of wrinkled cuticle. Radiations, having a remote resemblance to a crab's claw, invade the surrounding skin, after a time undergo contraction, and then cause the characteristic puckered or cicatrized appearance of the skin. The usual situation of these tumours is the space between the mammæ. They are generally chronic, and unattended with danger.

Diagnosis.—By the peculiar appearance above described.

Treatment.—The local application of the vapours of sulphur, iodine, or mercury; of plasters containing iodine, or iodine and opium; and alkaline baths.

The disease advances slowly, and is unattended with danger. The tumours rarely ulcerate; they are generally chronic, but occasionally they disappear spontaneously, leaving a white mark like a scar.

MORPHŒA.

Description.—An alteration of the skin in patches sometimes as much as four inches in diameter, due to a marble or wax-like condensation, resulting in atrophy of blood vessels and nerves, and the formation of dense polished, white, insensitive areas bordered by a delicate ring of small blood vessels. When very wax-like it is called *M. alba*, when pigmented *M. nigra*. It is occasionally raised; more commonly depressed. In the subsequent course of the disease, the part usually becomes shrunken and atrophied, leading to retraction of the surrounding skin. It may disappear entirely after some years, or it may pass into *scleroderma* or fibroid hy the skin; a condition undistinguishable anatomicall phantiasis Arabum.

ELEPHANTIASIS ARABUM.—ELEPHANT

Synonyms.—Bucnemia. Barbadoes or Cochin leg sarcocele.

Symptoms.—The disease usually begins with rigor is followed by local inflammation of the lymphatics and glands, and sometimes of the veins. The part attack swollen and red, the vessels leading from it are hard and there is burning heat. The general and local sympt swelling, disappear after a few days, but recur again and irregular intervals. The part undergoes a gradual incr until it attains an enormous bulk. The skin now has a p or livid colour, is often scaly, rough, or fissured and c soft vegetations or horny excrescences, and more rarel In advanced stages deep seated suppuration, with offensi and sphacelus may take place in different parts of the the enlarged lymphatic glands: sometimes a milky lymph oozes in great quantities from the warty excresce skin (Morehead). The extremities—the lower more freq the upper, the scrotum, labia pudendi, and mamm parts usually affected.

Pathology.—Inflammation and hypertrophy of the vessels and glands, and of the integument. The dise contagious.

Cause.—The disease is prevalent in low, damp loc the coast in the East and West Indies, Japan, Coc Malabar, Egypt, Abyssinia, Brazil, and Polynesia.

Prognosis.—In the majority of cases the disease beco and is compatible with a long life; but when the health with by suppuration, the patient often succumbs.

Treatment.—That of pyrexia and local inflamma early stages. Friction and compression in the later, and when the disease becomes a chronic burden.

MALUM ALEPPORUM.—ALEPPO BUTT

Synonyms.—Biskra button. Sahara chancre. Caneot

Localities.—East and West Indies, Tropical part Arabia, Persia, Syria, Crete.

Definition.—A tubercular disease of the skin whi endemically at Bagdad, in several towns on the banks o and Euphrates, and particularly at Aleppo and Bussorah. Morocco and Algeria.

Symptoms.—The eruption of one or more tubercles varying in size. At first the tubercle is merely a lenticular eminence, which during the next four or five months gradually increases without local or general symptoms. Acute pain now sets in, followed by deep fissured and irregular ulceration, discharging a thick, ill-conditioned matter. After five or six months, a dry tenacious scab is formed, which shrivels and separates in one or two months, leaving a deep indelible scar. It attacks persons of all ages, sexes, and conditions of life. Children are attacked about the age of two or three; and at Aleppo, according to Mr. Guilhon, scarcely a single adult escapes. Dogs are also liable to it.

Cause.—Attributed at Aleppo to the use of water from a particular stream. A healthy constitution affords no protection. The disease is rarely complicated with scrofula; is not contagious; nor is it dangerous. There is no specific plan of treatment known. The following is a very similar, if it be not an identical affection.

DELHI BOIL.

Synonyms.—Lahore and Scinde boils. Mooltan Sore.

Locality.—Lahore, Scinde, Mooltan, Agra, Meerut, Roorkee, Umballa.

Description.—At first it resembles a mosquito bite, the light red spot increases in size, and becomes elevated above the surrounding skin. During the next two or three weeks it attains the size of a pea and is usually movable under the skin. During its subsequent growth it becomes vascular, fixed, the seat of a prickling, itching sensation, and the little tumour now spreads at the base. The summit of the tubercle has a shining transparent appearance, and with a lens one or two yellowish spots may be seen deeply seated in the tumour. A vesicle forms at the apex and discharges pale yellow serum. Ulceration now begins and spreads rapidly and centrifugally, first destroying the whole growth, and then invading, and more or less completely destroying, the neighbouring parts to the extent of one or two inches; healing then ensues, and a broad shallow unpuckered cicatrix remains. The parts affected are the extremities and the face. Dogs get the boil on the smooth skin of the nose. (J. Fleming, "Army Med. Rep.," 1868, p. 319.)

Cause.—Doubtless the deposit of ova or some irritant matter in the skin, by an insect, for the history corresponds to that of the parasitic tumours formed under the skin of the horse and cow by a species of botfly. So far, however, no positive evidence of parasitism has been adduced, the nature of the egg-like bodies described by Surgeon-Major Smith, in the volume above quoted, being very doubtful. Dr. Vandyke Carter attributes it ("Med. Chir. Trans." vol. lix.) to a fungus, and terms the affection "*mycosis cutis chronica.*"

Treatment.—That of an ordinary boil.

SCLEREMA.

Synonyms.—Scleriasis, Scleroderma, Xeroderma.

Definition.—An induration of the subcutaneous connective sooner or later, and in some degree involving the derm and ep and causing proportionate alteration of structure and disturb function.

The affections which come under this definition may perh formed into three classes.*

1. **Simple Sclerema**, in which there is induration without trophy. In this class may be placed—(a.) *simple atrophic sc* marked by the gradual disappearance of bloodvessels and ing of the connective tissue, so as to attach the skin more completely to the underlying parts. It may be *general*; affecting only the fingers and palm, or as the so-called Ad Keloid: or *scattered*, which will include morphœa, and many cases of partial sclerema; (b.) *Œdematous sclerema*, such as in children (scleroderma neonatorum), in chlorotic girls, a condition which Sir W. Gull has called adult cretinism, Ord, myxœdema; (c.) *Inflammatory sclerema*, such as may the application of a blister, or erysipelas; (d.) *Traumatic*, follows injuries, variolous and syphilitic diseases, burns, the the "cat," &c.

2. **Idiopathic Hypertrophic Sclerema.**

3. **Specific Hypertrophic Sclerema**, which includes t lowing:—

(a.) *Syphilitic hypertrophies* and *condylomata*; (b.) *Elephan* (c.) *Lepra Arabum*; (d.) *Molluscum*; (e.) *Keloid*—the tuberc distinguished from the cicatricial form.

ORDER VIII.

MACULÆ.—SPOTS.

The diseases belonging to this order are of little practical i ance. They consist either in change of colour (*colorationes*) of colour (*decolorationes*). To the former belong the co freckle (*lentigo*) and (*ephelis*), the mole (*spilus*), purpura, pet bruises, and the several forms of *nævus*; to the latter a uni colourless state of the skin (*albinismus*), and a partial abs colour (*vitiligo*).

---

* "Medico-Chir. Trans.," v. lix. p. 149.

OTHER DISEASES OF THE SKIN.

LUPUS.—THE WOLF.

Synonyms.—Lupus vorax; Herpes exedens; Formica corrosiva.

Symptoms.—1. The *superficial* form of lupus consists in the formation of slightly raised erythematous patches, limited by rounded borders. The cuticle tends to exfoliate, leaving the skin red, shining, and tender to the touch, and bearing a close resemblance to the recent scar of a superficial burn. The redness disappears on pressure. When the disease is arrested, it leaves the skin thin and shining, and as if seared by a hot iron. In some cases the sebaceous follicles are involved, and the reddened patch of skin becomes crusted, puckered, tuberculated by the raised orifices of the enlarged sebaceous follicles, and greasy. This form has been termed *Seborrhœa congestiva* by Hebra, and *Lupus erythematosus* by Cazenave.

2. The *deep-seated* form of the disease generally attacks the alæ of the nose, and is often preceded by redness, swelling, pain, and mucous discharge from the nostrils. The skin first swells and assumes a violet red colour. After an interval, a small ulcer forms covered by a scab, beneath which a gradual destruction takes place, first of the skin, then of the cartilages. In extreme cases, the whole nose, and even the palate and gums are destroyed; but in some instances the disease lasts for years without occasioning any great amount of destruction.

3. The *tubercular* form consists in numerous small, soft, red tubercles, which remain stationary for a few weeks, months, or years, and then suddenly become inflamed and enlarged; their bases unite, and their summits ulcerate, forming an irregular spreading ulcer, covered by a dark tough crust. The parts first attacked sometimes partially heal, leaving irregular scars, which become the seat of fresh tubercles and renewed ulceration. Its usual seat is the cheek, but it may occur on the neck and chest, and on the anterior surface of the extremities.

4. *Lupus with hypertrophy* is generally confined to the face, and consists in the formation of numerous soft, indolent tumours, which rarely ulcerate, but enlarge at their bases, and the skin and cellular tissue become hypertrophied. The entire face, in this manner, sometimes attains an enormous size, and is hideously disfigured.

These forms may exist together, leading to the destruction of the nose, eyelids, and lips, and producing frightful deformity. They are rarely accompanied by any marked constitutional symptoms.

Causes.—*Predisposing.* The scrofulous constitution.—*Exciting.* Syphilis.

Diagnosis.—From *acne*, by the absence of pustules. From *tubercular lepra*, by the insensibility of the skin, and the peculiar fawn colour of the tubercles in this latter disease. From *epithelioma* by the latter beginning in a single point, surrounded by a hard, cumscribed base, and subsequently by severe darting pains.

Prognosis.—*Favourable*, when recent and limited.—*Unfavo able*, when chronic and extensive.

Treatment.—Where the ulceration has not set in, friction w ointments of the iodides of sulphur and mercury. When ulcerat has begun nitrate of silver, chloride of antimony, and the nitr or iodides of mercury. Alteratives, such as iodide of potassium a mercury, should be given for a considerable time, and resumed a short intervals.

FURUNCULUS.—BOIL.

Symptoms.—Boils consist of hard, circumscribed, dark r tumours of the areolar tissue, attended by troublesome itchi and smarting, sometimes terminating in resolution, but mo frequently passing into suppuration and the slow discharge matter by a single orifice, or by several small openings. The bo follow each other in quick succession, and may continue to har the patient for weeks together. They usually appear on the ne back, and nates. There is but slight constitutional disturbance.

Carbuncles are boils of larger size and more marked charact and are attended by extensive sloughing of the cellular membra

Causes.—*Predisposing*. Debility, cachexia, and old age.—*Exciting*. Obscure. The mortality from carbuncles in the Met polis rose from 1, 2, 3, or 4 per million, per annum, from 1840 1846, to from 7 to 36 per million, per annum, in the interval betwe 1847 and 1854.

Diagnosis.—From *phlegmon*, by the round circumscribed form.

Prognosis.—Boils are often tedious, but rarely fatal; but ca buncle, especially in aged persons, is often attended with gre danger.

Treatment.—In mild cases, saline aperients, and poultices to th boils. In more severe cases, free incision and then poultices. I carbuncles, free crucial incisions, followed by poultices, and generous diet, with wine and stimulants. In lingering cases, course of alterative tonics (see Form. 147, 150, and 294). In mo cases of carbuncle we may give bark and ammonia at the outse Subsequently, quinine and acids.

ALOPECIA.—BALDNESS.

A parasitical form of the disease has been already described (p 614). The variety now under consideration is dependent upo simple atrophy of the hair bulbs from defective nutrition. Th disease may be limited (*A. circumscripta seu areata*) or it may i volve the whole of the head, and then the scalp and eyebrows present an ivory-like smoothness and polish. This is almost invariably the index of complete loss of hair from every part of the body. The general affection is usually attributable to two causes—viz., fever, especially occurring in the puerperal state, and syphilis. A general tonic treatment will be required, and locally cantharidine stimulants are beneficial in the regeneration of the hair.

DISORDERS OF THE SWEAT GLANDS.

Apart from the general derangements of the sudatory function treated of in various parts of this work, there remain for consideration the following: 1. Excessive local perspiration; 2. Bloody-Sweat; and 3. Metallic Sweat.

1. *Excessive Local Sweating.*—This is very obscure and troublesome. The hands and feet are the parts commonly affected. It is usually a chronic and sometimes an hereditary disorder, and is commonly associated with inherent debility of constitution. When the feet are affected they become tender and chafed. The *Treatment* consists in the frequent use of acid baths (Form. 39) and infrictions of belladonna liniment to contract the dilated blood-vessels. Chalybeate astringents, and other means for improving the health should be simultaneously adopted.

2. *Bloody Sweat* consists in the exudation of very dilute blood from the orifices of the sweat ducts, and is due to special hyperæmia of the sudoriparous glands. It is very rare, and is commonly referable to a vicarious endeavour to supply an imperfect menstrual effort. The treatment in such cases obviously consists in the restoration of the uterine function.

3. *Blue Sweat.*—Dr. Clapton has called attention to this phenomenon in cases of mild and chronic copper poisoning (*Med. Times and Gaz.* 1868). The observation is an important one, as showing the eliminative power of the skin, and pointing to a means by which we may hope to remove other and more deleterious metals from the system.

The affections of the skin which characterize secondary syphilis have been briefly described under Syphilis, page 577.

CHAPTER IX.

PARASITIC ANIMALS.

1. Intestinal Worms.
2. Other Parasitical Animals.

INTESTINAL WORMS.

1. TRICHOCEPHALUS DISPAR	Long Thread-
2. ASCARIS LUMBRICOIDES	Round Worm
3. ASCARIS VERMICULARIS	Thread-worm.
4. ANKYLOSTOMUM DUODENALE . . .	
5. TRICHINA SPIRALIS	Trichina.
6. TÆNIA	Tape-worm.
7. BOTHRIOCEPHALUS LATUS	Broad Tape-
8. DISTOMUM HEPATICUM	Liver Fluke.

TRICHOCEPHALUS DISPAR.—LONG THREAD-WO

SYNONYM.—Trichuris.

DESCRIPTION AND LOCALITY.—This species is distinguishe the common thread-worm by its greater length, the extreme t of the anterior two-thirds, and the increased size of the po third of the body. Also, in the case of the male, by the p

Fig. 106.



Fig. 107.



form of the spiculum and sheath, shown greatly magnified at b 106). The posterior part of the body is commonly found coil as in Fig. 107, which shows the worm in its natural size. little worms vary from an inch and a half to two inches in le The males are shorter and more slender than the females. eggs are oval. The parasite has been observed in Egypt, Eth France, and England. In this country it is rare—I have onl with it once—but in France it is very common. According Davaine, not less than one-half the inhabitants of Paris are af by this entozoon. It inhabits the large intestine, and chief cæcum.

The treatment is that of the common thread-worm; but injections ·e less necessary.

ASCARIS LUMBRICOIDES.—ROUND WORM.

Symptoms.—These vary with the number of the worms and the ırt of the alimentary canal which they occupy; sometimes there only one worm. The usual symptoms re an uneasy sensation in the abdomen, ›metimes amounting to actual pain, and ften described as a biting or gnawing; n irregular state of bowels; dysuria; a ariable and sometimes excessive ap- etite; fœtid breath, furred tongue, and rinding of the teeth in sleep. In young ıildren the constitutional symptoms often nount to those of infantile remittent ver (see p. 328). In most cases the eneral health does not suffer in any arked degree.

Fig. 108.



Description.—A smooth, greyish, round orm as thick as a goose quill, and varying om half a foot, to a foot in length.

The annexed woodcut, *a*, shows a ›ecimen of this worm of moderate size; ıe head, *b*, is magnified about fourfold. ; is terminated by three papillæ, which ın be spread out into a broad circular ıcker.

The posterior extremity of the female 'ig. 108) is slender and pointed. That f the male is curved.

The fecundity of this entozoon is pro- igious. Eschricht calculates that the ody of the mature female contains at one me as many as 64 millions of eggs.

They usually occupy the same intestine, ut are found both in the stomach and ırge intestine: occasionally they make ıeir way into the gall-bladder and bile ucts, and have sometimes caused abscess f the liver.

Causes.—*Predisposing.* Childhood.

Exciting.—The ova introduced into the alimentary canal, pro- ably with unripe fruit, raw vegetables, or with impure water.

Treatment.—The parasite is readily expelled by irritant purga- ves, such as the Pulvis scammonii compositus. Santonica, or, etter, crystallized santonin, is a specific against this entozoon. antonin is not a purgative, and therefore it may be given to the

Fig. 109.



Fig. 110.

most delicate children. The dose vari from gr. i. to gr. vi. It may be given a bedtime, and followed next morning by purge, such as gr. x to gr. xv of Pulv. scammonii compositus, or the purgative ma be combined with the anthelmintic. (Form 285.)

Cowhage (the hairs of the pod of Dolich pruriens) is a good remedy. (Form. 28 This dose may be given two or three night in succession, its use being preceded an followed by an aperient.

ASCARIS VERMICULARIS—THREA WORM.

Synonyms.—Oxyuris vermicularis. A carides. Maw-worm.

Symptoms.—This worm infects the rectu in considerable numbers, and causes gre irritation at the orifice. In consequence their small size they crawl out of the rectu into the vagina, and cause irritation a leucorrhœa. In adult males, they a among the causes of spermatorrhœa. Th constitutional symptoms are those described und Ascaris lumbricoides.

Diagnosis.—An active little worm, like a bit white thread, half an inch long. Fig. 110 represen the female eight times the natural size. Fig. 111 sh more highly magnified; *d*, stomach; *e*, œsophagus; anus; *h*, ovaries: *k*, oviduct. They are often foun massed together into large round balls. The ma is disproportionately small; both extremities a rounded and obtuse, and it has a pale silvery-gr colour. The females, which are much more numerou are distinguished by their thickness and whitenes and by the fine pointed tail.

Mode of Introduction.—Nothing is certainly know respecting the habitat of the parasite out of the bod It is supposed to be conveyed into the intestin in the embryonic condition by means of salads a unripe fruits.

Prognosis.—These worms are easily removed b remedies; but from their large numbers and rapi production, it is not easy to insure their complet expulsion. New broods are rapidly developed.

Treatment.—Injections are the most appropriate remedies. ℥iv to ℥vi Liquoris calcis, or the same quantity of Infusum anthemidis, or Infusum quassiæ, thrown into the rectum, are efficacious remedies. The worms are, however, discharged in considerable numbers by the use of aperients. (Form. 255, 258.)

ANKYLOSTOMUM DUODENALE.

Synonyms.—Dochmius, et strongylus duodenalis.

Localities.—Egypt and Italy.

Description.—A nematoid worm, the male about ¼ inch, and the female ⅓ an inch long. Mouth furnished with a cup-shaped sucker, on the edge of which are three pairs of hooks; and posterior to these, at the entrance of the gullet, three lancet-like blades (Fig. 111 in profile and front view, Leuckart). The eggs (Fig 112) closely resemble those of oxyuris, but they are more elongated, and open by an operculum.

Fig. 111.



Fig. 112.



Symptoms.—The parasite infests the upper part of the small intestine; it fixes itself by the hooked sucker, and incises the mucous membrane with the teeth exactly as a leech does. They cause considerable hæmorrhage, and their bites are followed by patches of ecchymosis in the sub-mucous tissue. When, as often occurs, they exist in great numbers, cutting pains in the abdomen are experienced, and the repeated attacks of hæmorrhage, and interference with intestinal digestion, cause anæmia ("*Egyptian chlorosis*"), ending in dropsy and exhaustion.

According to Dr. Sondiregger, 117 deaths occurred in 1880, amongst the workmen engaged in the St. Gothard tunnel.

Treatment.—Oil of male fern (ʒj to ʒij) is said to be the appropriate remedy.

TRICHINA SPIRALIS. TRICHINATOUS DISEASE.

Symptoms.—Extreme lassitude and depression; sleeplessness and loss of appetite; pyrexia, accompanied by severe muscular pains, and occasionally œdema of the joints, followed sometimes by painful and persistent contractions of the flexor muscles of the extremities. In many cases the disease sets in with diarrhœa, and it usually terminates in pneumonia. In some cases typhous symptoms come on, and the patient dies unconscious. The disease,

when fatal, runs its course within a month of the introduction
the parasite.

Morbid Anatomy.—Muscles pale, reddish grey, speckled wit
minute lighter coloured points, which, on microscopical examinatio
prove to be Trichinæ in all stages of development, lying free upo
and within the sheaths of the muscular fibres. They pervade a
the muscles, and have been observed in the substance of the heart.

Fig. 113.



Fig. 114.



Source of the Parasite.—Pigs in some part of Germany ar
infested with Trichinæ, and their propagation within the huma
body results from the ingestion of raw or imperfectly cooked por
or sausages. The domestic animals are readily infected by th
same means. Dr. W. Müller, of Homburg describes (*Lanc*
Jan. 23, 1864, p. 93) an epidemic of trichiasis in Hettstadt, i
Prussia, from eating imperfectly cooked sausages made of por
infected with the parasite. At one time 80 out of a populatio
of 5,500 were affected, and eighteen or twenty had previousl
died of it.

Man is infested with this parasite much more frequently tha
was at first supposed; for Dr. Zenker, of Dresden, found Trichin
in four out of 136 dissections.

The Trichinæ begin to develop almost immediately after the
introduction into the stomach, males, females, and innumerab
embryos being produced within the intestinal canal, whence, b
means of the circulation, the latter make their way to their favouri

the muscles, and produce the violent symptoms above ed, until they become enclosed within capsules, in which ɜy are harmless. Fig. 113 represents the animal incapsul- ongst the muscular fibres; Fig. 114 the free mature animal; ıouth; *b*, sudden alteration in the form of the intestine; ale organ.

on-encysted animals are not visible to the naked eye. The l also, unless they have undergone cretaceous degeneration, the aid of a pocket lens for their detection.

TMENT.—Since the parasite is carried into the most distant the body with astonishing rapidity, no remedy can be of il unless it obtain, like santonin, a speedy admission into d.

TÆNIA.—TAPE-WORM.

TOMS.—Those already described under Ascaris lumbricoides ɪe-worm occupies the whole track of the, intestines, but he ileum. Joints of the ;, Fig. 115) are passed ɜ fæces, or they escape atient moves about.

Fig. 115.



OSIS.—The appearance ints, or *proglottides*, in ions. They are flat, ılf an inch long, and a of an inch broad, and a little, round, cup- aperture upon one or de. Two species are h, the *T. solium*, and *mediocanellata*. In I find the latter by nore common. At first ɜre is very little to distinguish these two species of parasites. ry in length from four to twenty feet. T. mediocanellata is er and more robust form; it is known by the absence of ı and hooklets, and by the more ramified form of the uterine These forms are illustrated in Figs. 115 and 116. A, re- the anterior extremity of T. mediocanellata, natural size. ıhows the flat head, the sucking discs, and the absence of lets. C, one of the joints × about 2.

16 A, × 4, and B, × 2, show the corresponding parts of T. The ripe joint, or proglottis, is the adult hermaphrodite capable of maintaining an independent existence. The l organ in the centre is the uterus, or ovisac, and contains ls of ripe spherical eggs.

ɪOSIS.—It is easy to remove considerable portions of the ɪ various remedies. The entire worm is less frequently expelled. Search should always be made for the head. Until th is expelled, the patient is not effectually relieved; but when a number of the small joints at the upper end of the worm are expelle it is probable that the head has also been removed.

Fig. 116.



Source of the Parasit Tænia solium is derived from po which is liable to be infected wi its larval form, known as *Cysticerc cellulosæ.* Tænia mediocanellata in like manner admitted into t body by means of veal and be which often contain the larval fo of this species.

Prophylaxis.—In order to p vent the development of the pa site, all animal diet should perfectly cooked, so that the me when brought to table, should firm, and destitute of tremulousne and blood colour. Pork, and shee brains in particular, should be co pletely cooked. The pernicious ha of eating imperfectly cooked meat doubtless results in other diseas besides those due to parasites.

Treatment.—Half an ounce of oil of turpentine, followed af two hours by an ounce of castor oil. This treatment rarely fails remove the tape-worm, but it is open to the objection that t turpentine acts as a stimulant to the brain and urinary orga sometimes producing painful strangury. It is much less apt, howev to produce this effect if speedily followed by castor oil. Kousso, the form of infusion (ʒss—ʒi to Oss of water), taken at a sing dose. This is an extremely effective remedy. The liquid extr of the male fern-root in the dose of ʒi to ʒiii. It may be given capsules. This remedy never fails to expel the parasite.

The Kamela or Rottlera tinctoria in the dose of gr. 50 to gr. 1 in water.

These remedies should be given on an empty stomach: half ounce of castor oil being taken over night, the anthelmintic in t morning, and a second dose of castor oil two hours afterwar No food to be taken while the medicines are being administered.

BOTHRIOCEPHALUS LATUS.—BROAD TAPE-WORM.

Symptoms.—Those of Tænia. The Bothriocephalus latus is ve rare in England. It is as common in Switzerland and Russia Tænia is in England. It occurs in France, in common with t Tænia solium.

Diagnosis.—From the common tape-worm by the shape of the head, which is marked in the direction of its length by a groove, and by the absence of rostellum, hooklets, and suckers. The Proglottis is also quite distinct. The head, A and B, and some of the mature segments, C and D, are shown in the subjoined engraving; B and D are magnified. (Leuckart.)

Treatment.—That of the common tape-worm.

Fig. 117.



DISTOMUM HEPATICUM.—LIVER FLUKE.

This trematode worm infests the bile ducts of our graminivorous animals, especially the sheep, producing great thickening, dilatation, and obstruction of the ducts, leading to a sallow anæmic condition, and ending in emaciation and dropsical effusions. Man is occasionally infected. The following illustrative cases by Drs. Humble and Lush, is recorded in the *British Medical Journal*, 1881, vol. ii. p. 75. A labourer, aged 52, after becoming immensely stout, was overtaken with symptoms resembling those of gastric and hepatic cancer, attended by faintness, pallor, and anorexia. His illness extended over a period of about seven months—from September to March. Severe vomiting was an early and constant symptom, and there was tenderness of the right hypochondrium and ileum. Abscesses formed in connection with the rectum, with the separation of a slough, five inches by three. He improved for a time, but became worse, continued to sink, had rigors, and died about three months afterwards.

Fig. 118.



The upper part of the rectum was found thickened and narrow, and fistulous abscesses opened into it. The liver was greyish-red, tense, smooth, greasy, and easily broken down, and weighed three pounds. The hepatic ducts were considerably thickened and enlarged, and contained about twenty-six fully developed D. hepaticum.

Treatment.—Large doses of iodide of potassium are worth a trial.

OTHER ANIMAL PARASITES.

In addition to the animal parasites treated of in the preceding pages and in the body of the work (pp. 410, 435, 536, 550, 553, 600), the following are occasionally met with in man.

CESTOIDEA.—Tænia cucurbitina, grandis, saginata, acanthot flavopuncta, marginata, nana, and elliptica (T. canina). Bot cephalus cordatus. These parasites inhabit the alimentary c but may be carried to any part of the system.

TREMATODA.—Distomum crassum, lanceolatum, heteropl These parasites inhabit the portal vein and gall ducts. Disto ophthalmobium has been found in the eye. (?).

NEMATOIDEA.—Ascaris mystax (intestines); Filaria ocul lentis; Filaria bronchialis; Tetrastomum renale and Stron gigas (in the kidney); Spiroptera hominis and Dactylius aculeat (discharged from the bladder).

The *treatment* of these parasites will be determined by locality and the symptoms which they occasion. The tape-w require the same remedies as T. solium. The Ascaris mystax be expected to yield to the treatment prescribed under As lumbricoides. When the parasites are known to inhabit bladder, the injection of bitter infusions may be employed.

CHAPTER X.

POISONS.

THE subject of Poisons is here treated simply as a branch of the Practice of Medicine. For details the reader is referred to works on Toxicology, or Forensic Medicine. The antidotes for the principal poisons are given at the end of the chapter. The old division into: 1. Irritants, 2. Narcotics, 3. Narcotico-irritants, is retained for convenience. To these is added 4. Animal poisons.

---

1. IRRITANT POISONS.

DEFINITION.—Poisons which cause corrosion, inflammation, or irritation in the alimentary canal, with or without specific effects on other organs.

SYMPTOMS.—After an interval varying from a few seconds to half-an-hour or more, vomiting and purging, with pain in the stomach and bowels, increased by pressure; and accompanied by inflammatory fever, or extreme prostration of strength. Pain and constriction of the mouth, throat and gullet, accompanying or following the act of swallowing; intense thirst; hoarse voice, wheezing respiration, and cough; discharge of blood from the stomach and bowels; tenesmus; strangury, dysuria, or suppression of urine. Epileptiform convulsions and cutaneous eruptions are occasional symptoms. The remote constitutional effects, whether common or specific, are various.

MORBID APPEARANCES.—Marks of corrosion, inflammation, suppuration, or gangrene in the stomach and upper part of the alimentary canal, extending, in certain cases, to the gullet, throat and mouth, and through the whole length of the intestines. Perforation of one or other of these parts. In certain cases, signs of inflammation in the windpipe and lungs; in the peritoneum and pleura; in the rectum and bladder; in certain other cases, peculiar stains or indications of the action of the poison on the mouth, throat, gullet, stomach, and duodenum.

DIAGNOSIS.—*During life*, from English and Asiatic cholera, in many cases of irritant poisoning, by the bloody evacuations from the stomach and bowels, and in many other cases by the effect of the poison upon the mouth, throat, and gullet. In other instances, again, by the specific remote effects of the poison, (*e.g.*, inflamed eyes, gastritis, and rapid pulse, in poisoning by arsenic; salivation in poisoning by the preparations of mercury; jaundice, in poiso by phosphorus and the preparations of copper; pneumonia, and treme depression, in poisoning by tartar emetic; inflammati the urinary organs, in poisoning by cantharides and phosphor *After death*, by the traces of acute inflammation, and its sequences in the several portions of the alimentary canal; and many cases by appearances in the upper part of the canal ap priate to particular irritant poisons, or to the corrosive poisons sub-class of the irritants.

PROGNOSIS.—Dependent on the nature, dose, and concentra of the poison, the vehicle, the more or less prompt administratio an antidote, the state of the stomach (whether full or empty), the patient's age and strength.

MORTALITY.—This varies, in the case of the poisons containe this class, from more than half the cases to a rarely fatal result.

TREATMENT.—After the administration of an antidote (if exist), the prompt and complete evacuation of the stomach by stomach-pump (except in the case of strong corrosive poisons), emetics of common salt, mustard, ipecacuanha, or sulphate of assisted by large draughts of warm water, and tickling the thr with a feather or with the finger. After the evacuation of stomach, the free use of milk, gruel, barley-water, and abstine from all solid food. When inflammation runs high, ice or ic water; when great tenderness is present, leeches followed by wa fomentations. When the bowels cease to discharge blood, and patient suffers from tenesmus or constipation, one or two ta spoonfuls of castor oil, with twenty drops or half a drachm laudanum, mixed with a small quantity of hot milk. Extre prostration will require the use of larger doses of laudanum, w wine or brandy. When fever runs high, it may be necessar draw blood from the arm. Occasional symptoms, and sympto peculiar to certain persons only, must be treated in the sa manner as the same symptoms due to other causes.

2. NARCOTIC POISONS.

DEFINITION.—Poisons which act on the brain and spinal marr and give rise to symptoms referable to those organs alone.

SYMPTOMS.—After an interval, varying from a few seconds to or two hours, the patient is seized with giddiness, headache, dimn of vision, singing in the ears, drowsiness passing into stupor, ending in coma, with palsy, epileptiform convulsions, or teta spasms.

MORBID APPEARANCES.—Often very slight. The brain healt or the veins and sinuses gorged with blood, with serum in ventricles and at the base. In rare instances extravasation blood.

DIAGNOSIS.—From the close resemblance of the symptoms of rcotic poisoning to some forms of apoplexy, a satisfactory distinc-on is often impossible. But in ordinary apoplexy a want of lateral symmetry, such as inequality of the pupils, or a difference the degree of palsy, or convulsion on the two sides, points to rebral hæmorrhage.

PROGNOSIS.—This, too, cannot be laid down for the entire class the chances of recovery vary greatly with the poison that has een taken.

TREATMENT.—The prompt use of the stomach-pump, and. until at can be procured, of emetics of common salt, mustard, ipecacu ana, or sulphate of zinc. The cold affusion in the early stage of e poisoning. The patient to be kept awake by forced exercise, flicking the hands and feet with a wet towel. After the complete acuation of the stomach, strong coffee or tea, and diffusible stim-ants, freely administered. The bowels to be relieved by full doses castor oil. So long as the surface continues cold and livid, assid-ous friction, and warm bottles to the feet and pit of the stomach, the hot-air bath. In extreme cases, artificial respiration, and gal-anic shocks passed from the spine of the neck to the pit of the omach. *This is the treatment of cases of poisoning by opium.* In isoning by *prussic acid*, the cold affusion is the first remedy to be nployed; and in cases which survive some minutes or hours, heat nd assiduous friction, to restore warmth to the surface, must take e place of the compulsory exercise necessary in poisoning by pium, and other narcotics.

For the treatment of poisoning by chloroform, see page 422.

---

3. NARCOTICO-IRRITANT POISONS.

DEFINITION.—Poisons which produce the combined effects of ritants and narcotics; the irritant action being generally less iolent than in the case of pure irritants, and delirium of more ommon occurence than in poisoning by the pure narcotics.

SYMPTOMS.—At an interval varying from about an hour to three r four hours after swallowing the poison (which, in many cases, has peculiar taste), giddiness, disorders of the senses of sight and earing, delirium, convulsions, tetanic spasms, stupor passing into oma; preceded or accompanied by vomiting and purging, with ain and tenderness of the abdomen. As a general rule the narcotico-rritants act chiefly or wholly as narcotics in very large doses, and mainly as irritants in small ones.

MORBID APPEARANCES.—Not strongly marked or uniform. Signs f inflammation in the stomach and bowels, with cerebral congestion.

DIAGNOSIS.—From most of the pure irritants by the presence of symptoms of narcotic poisoning. From the pure narcot presence of more or less irritation in the alimentary canal

The following indications of particular poisons or poisons may be added.

Delirium affords a presumption of poisoning by bellado cyamus, stramonium, or some plant belonging to the S Symptoms of *intoxication* give a like presumption of t alcohol, æther, chloroform, or of some liquid or gaseous hydr *Tetanic convulsions* are nearly conclusive of the presence of *extreme muscular weakness* affords a presumption of the of hemlock, gelsemium, aconite, tobacco, lobelia inflata, Calabar bean; *sudden prostration* following quickly on lowing of the poison afford a strong presumption of the prussic or oxalic acid; and a very slow and weak puls poisoning by digitalis.

PROGNOSIS.—Dependent chiefly on the early or late c ment of the treatment, and on the circumstances mention Narcotics.

TREATMENT.—The prompt use of the stomach-pump, or o followed by aperients and enemata, if required. The re treatment to be determined by the symptoms present; i those of irritant poisoning, the treatment proper to the irr chiefly of narcotic poisoning, the treatment prescribe Narcotic Poisons.

4. ANIMAL POISONS.

1. SNAKE-BITES. *Symptoms.*—Rapid loss of strength, mate paralysis of the cerebro-spinal nervous system; and later involving the ganglia of the heart. Pain in the bit followed by swelling and extravasation of blood in the areola Swelling of the member, and extreme lassitude and de follow the bite of the common viper. (Pelias Berus.)

2. SCORPION AND INSECT STINGS.—The sting of the fo proaches in severity that of the poisonous snakes. It is very and is followed by swelling, vomiting, faintness, and so death. Stings of the wasp and bee tribe are only dangero the parts about the base of the tongue are stung in th swallowing. Bugs, sand-flies, mosquitoes, and several other of gnats, and ants, rarely produce any other inconvenien local irritation, with more or less inflammatory swelling.

Treatment.—For snake bites, the simultaneous applicat tight ligature round the part, and continued suction of the After this has been effectually done, the application of a pen caustic, such as strong solutions of caustic potash, or chl zinc. If the breathing or heart show signs of failure, respiration and diffusible stimulants must be resorted t most hopeful means of preventing paralysis of the cardiac the subcutaneous injection of $\frac{1}{60}$ grain of sulphate of atrophia ry hour. Scorpion stings require similar treatment. The im-diate application of solution of ammonia to the puncture prevents inflammatory irritation consequent on insect stings. But when se occur about the fauces, and suffocation impends, the trachea st be opened.

ANTIDOTES TO THE PRINCIPAL POISONS.

IDS, MINERAL, VEGETABLE, AND ORGANIC (such as carbolic acid).—Calcined magnesia or its carbonate; common or prepared chalk, whiting, or compound chalk powder; a dilute solution of carbonate of soda, or potash; in an emergency, the plaster ceiling crushed and mixed with water; soap suds, or oil

ETHER.—Same as for chloroform. (See p. 657.)

LCOHOL.—The stomach pump, and cold affusion.

LUM.—Calcined Magnesia.

MMONIA AND ITS CARBONATE.—Vinegar and water, oil.

NTIMONY, CHLORIDE OF.—Magnesia, carbonate of soda.

RSENIOUS ACID AND THE SOLUBLE ARSENITES.—Magnesia suspended in milk; the hydrated sesquioxide of iron; or powdered charcoal; a mixture of oil and lime water.

ARYTA, SOLUBLE SALTS OF.—Sulphate of magnesia or of soda.

ARYTA, CARBONATE OF.—Sulphate of magnesia with weak vinegar.

ARBOLIC ACID.—Chalk, magnesia, oil.

HLORINE.—Ammonia; magnesia.

HLORAL HYDRATE.—That of opium. (See p. 657.)

HLOROFORM.—(See p. 422.)

COPPER SOLUBLE SALTS OF.—White of egg; iron filings.

CYANIDE OF POTASSIUM.—A mixed solution of sulphate and perchloride of iron, and the treatment for prussic acid.

HYDROCYANIC ACID.—After cold affusion, liquor chlorinii, the mixed oxides of iron diffused through water, ammonia, and the treatment of asphyxia. (See p. 657.)

IODINE. Starch; a very dilute solution of caustic potash or soda.

IRON, SULPHATE OF. Carbonate of soda or carbonate of ammonia.

LEAD, SOLUBLE SALTS OF. Sulphate of soda or magnesia.

LEAD, CARBONATE OF. Sulphate of magnesia with weak vinegar.

LIME.—Vinegar and water.

MERCURY, SOLUBLE SALTS OF.—White of egg; flour and water.

NITRO-BENZOLE.—Stomach pump, and cold affusion.

Oil of Bitter Almonds.—That of hydrocyanic acid.

Opium and Morphia.—The stomach-pump or mustard
electro-magnetism, &c. (See p. 657.)

Oxalic Acid and the Soluble Oxalates. — Commo
whiting, prepared chalk, or compound chalk powder, m

Phosphorus.—After an emetic of sulphate of copper, 40 m
oil of turpentine in mucilage, every quarter of an hour.
four doses magnesia diffused through water, or susp
mucilage, may be given with advantage.

Potash and its Carbonates.—Vinegar and water; oil.

Silver, Nitrate of.—Solution of common salt.

Soda and its Carbonates.—Vinegar and water; oil.

Strychnia.—Chloroform, nicotine and conia, and tincture o

Sulphuret of Potassium.—Weak solution of chlorine.

Tartar Emetic.—Tannin; tincture of bark, catechu; st

Zinc, Chloride and Sulphate of. A dilute solution of c
of soda.

CLASSIFICATION OF REMEDIES AND FORMULÆ, ETC.

EPT when otherwise stated, the medicines prescribed in the wing Formulæ are those of the British Pharmacopœia of 1867 the *imperial weights and measures* adópted in that work are of se employed here. They are as follows :—

Weights.

1 pound ℔j. = 16 ounces = 7000 grains.
1 ounce ℥j. = 437·5 ,,

Measures.

1 gallon . Cj. = 8 pints . . = Oviii.
1 pint . Oj. = 20 fluid ounces = f℥xx.
1 fluid ounce f℥j. = 8 drachms . = ʒviii.
1 drachm . ʒj. = 60 minims . = ♏ lx.

e doses are full doses for Adult Males, unless otherwise stated. For Adult Females they must be somewhat diminished, according to the judgment of the practitioner. In prescribing for younger persons of either sex, the subjoined table of doses may be safely followed. The dose for the Adult Male is taken at 60 grains or 60 minims.

	Gr. or ♏.		Gr. or ♏.
ult male	lx. or 1	3 years	x. or $\frac{1}{6}$
years.	xxx. or $\frac{1}{2}$	1 year	vi. or $\frac{1}{10}$
ears	xx. or $\frac{1}{3}$	6 months	iii. or $\frac{1}{20}$
ear	xv. or $\frac{1}{4}$	3 months	ii. or $\frac{1}{30}$

Except when otherwise indicated, each prescription is for a single se, and such as may be repeated every four or six hours.

STIMULANTS.

1. GENERAL STIMULANTS.

(Including Diffusible Stimulants and Stimulant Antispasmodics.)

1. Ammoniæ carbonas	Dose	gr. iii. to gr. x.
2. Liquor ammoniæ	,,	♏ v. — ♏ x.
3. Liquor ammoniæ acetatis	,,	ʒ ii. — ʒvi.
4. Liquor atropiæ sulphatis and liquor atropiæ	,,	♏ iii. — ♏v.
5. Spiritus ammoniæ aromaticus	,,	♏ xx. — ʒj.
6. Spiritus chloroformi	,,	ʒss. — ʒii.

7. Ammoniæ hydrochloras . . . . . . Do
8. Æther (sulphuricus) . . . . „
9. Spiritus ætheris nitrosi . . . . „
10. Mistura spiritûs vini Gallici . . . . . . „
11. Oleum anethi, anthemidis, anisi, carui, caryophylli, cinnamomi, juniperi, sabinæ, lavandulæ, terebinthinæ, rorismarini, menthæ (viridis et piperitæ), myristicæ, pimentæ, cajuputi, pulegii, limonis, rutæ „
12. Spiritus camphoræ, cajuputi, armoraciæ compositus, juniperi, menthæ piperitæ, myristicæ, lavandulæ, and rorismarini „
13. Tinctura aurantii; assafœtidæ; belladonnæ; benzoini; buchu; capsici; cardamomi composita; cascarillæ; castorei; chloroformi composita; cinchonæ flavæ; cinchonæ composita; cinnamomi; gentianæ composita; guaiaci ammoniata; lavandulæ composita, limonis; lupuli; myrrhæ; serpentariæ; sumbul; valerianæ; valerianæ ammoniata; and zingiberis . . . . ,
14. Camphora . . . . ,
15. Aqua camphoræ . . . . ,
16. Moschus . . . . „
17. Assafœtida . . . . ,
18. Kreasotum . . . . ,
19. Phosphorus . . . . „
20. Sumbul radix . . . . „

The aqua camphoræ, the distilled waters (aqua a culi, cinnamomi, pulegii, pimentæ, menthæ—virid and the tonic infusions (infusum anthemidis, calumbæ, caryophylli, cascarillæ, cinchonæ flavæ, ci compositum, chiratæ, krameriæ, lupuli, quassiæ, valerianæ), are appropriate vehicles for the stronge the syrups (especially the syrupus aurantii and z used to impart an agreeable flavour.

Stimulants in the form of Draught

1. ℞. Ammoniæ carbonatis gr. x. Liq. ammoniæ acetatis ʒiii. Syrupi aurantii ʒj. Aquæ ℥iss. Fiat haustus.

2. ℞. Sp. ammoniæ aromatici fʒss.
Træ. lavandulæ compositæ ʒj.
Aquæ ℥j. M.

3. ℞. Træ. gu
fʒss.
Decocti
f℥iss. I

4. ℞. Mistur
Ammon.

5. ℞. Spiritû
Tincturæ
Infusi val

Spiritûs ætheris ♏xxx.
Spiritûs ammon. arom. ʒss.
Spiritûs cajuputi ʒss.
Infusi cascarillæ ℥iss. M.

. Moschi gr. xx.
Pulv. tragacanthæ co. ʒss.
Aquæ cinnamomi ℥iss. M.

. Tr. valerianæ ammoniatæ.
Tincturæ assafœtidæ āā ʒj.
Aquæ pimentæ ℥iss. M.

. Radicis armoraciæ excisæ ℥ii.
Seminis sinapis ℥jss.
Baccæ juniperi contusæ ℥iii.
Vini Xerici Oiii.

st for one week and strain. se, a wine-glassful. *Non-cinal*).

℞. Olei terebinthinæ ʒiv.
Ovi vitelli, unius.
Sacchari ℥ss.
Aquæ ℥iv. M (¼—⅛.)

(The whole, mixed with a pint of gruel, may be also used as an enema in certain cases).

11 ℞. Kreasoti ♏i.
Mist, uræ amygdalæ ℥iss. M.

12. ℞. Tincturæ belladonnæ ♏xx.
Ammoniæ carbonatis gr. v.
Misturæ camphoræ ℥iss. M.

13. ℞. Phosphori gr. v.
Olei olivæ f ℥ss.

Digest a fortnight in the dark and add—

Olei carui ♏iv.

(Dose, 15 drops cautiously increased, in milk. *Non-official*.

Stimulants in the form of Bolus, and Powder.

℞. Terebinthinæ Canadensis gr. v.
Pulv. glycyrrhizæ, quantum sufficit. Fiat bolus.

15. ℞. Camphoræ.
Moschi āā gr. x. M.

(The powder to be taken in barley water; in hysteria).

. STIMULANTS ACTING LOCALLY UPON CERTAIN SYSTEMS OR PARTS.

THROUGH THE NERVES ON THE MUSCULAR SYSTEM.

(*a.*) *On the Voluntary Muscle.*

xtractum nucis vomicæ . dose gr. ¼. gradually increased to gr. ii.
quor strychniæ . . ,, ♏v. (= $\frac{1}{24}$ gr.) to ♏x. (= $\frac{1}{12}$ gr.)

℞. Strychniæ gr. j.
lve in a few drops of alcohol, d then mix intimately with sufficient extract of gentian and liquorice powder to make 24 pills (one for a dose).

In the Form of Mixture.

℞. Liquoris strychniæ, ♏iii.
Quiniæ disulphatis, gr. ii.
Acidi hydrochlorici dil. ♏v.
Aquæ cinnamomi ℥iss. ft. H

18. ℞. Tinct. ferri perchlor. ♏x.
Liquoris strychniæ ♏iv.
Aquæ pulegii ℥ j. Ft. H.

(b.) *On the Involuntary Muscle.*

ON THE UTERUS.

1. Pulveris ergotæ gr. xl.
2. Extractum ergotæ liquidum ; dose, ♏xv. to ʒj.
3. Infusum ergotæ ; dose, ℥j. to ℥ii.
4. Tinctura ergotæ ; dose, ʒj. to ʒii.

ON THE URINARY ORGANS.

Cantharis vesicatoria.	Dose in powder gr. ⅛, cautiously increased
Cantharidis tinctura.	„ ♏x., cautiously increased.
Sabinæ tinctura.	„ ♏xx.—ʒj.
Sabinæ oleum.	„ ♏i.—v.

In the Form of Draught.

19. ℞. Tinct. cantharidis ♏x.
Tinct. ferri perchloridi ♏xv
Aquæ pimentæ ℥iss. M.

20. ℞. Tincturæ sabinæ ʒss.
Spiritûs myristicæ ʒss.
Infusi buchu ℥iss. M.

21. ℞. Olei sabinæ ♏ii.
Spiritûs chloroformi ʒss.
Aquæ ℥iss. M.

ON THE MUCOUS MEMBRANES.

Copaiba	dose ♏xx.	to ʒii.
Copaiba oleum	„ ♏v.	—♏xx.
Pulvis cubebæ	„ gr. xx.	—gr. xxx.
Cubebæ oleum.	„ ♏v.	—♏xx.
Confectio piperis	„ gr. lx.	—cxx.
Balsamum Peruvianum . . .	„ ♏xv.	—♏xxx.
Confectio terebinthinæ . . .	„ gr. xxx.	—l.
Balsamum tolutanum . . .	„ gr. xx.	—gr. xxx.
Syrupus tolutanus	„ ʒj.	—ʒii.
Tinctura tolutana	„ ʒss.	—ʒj.
Tictura benzoini composita . .	„ ʒss.	—ʒj.
Oleum terebinthinæ. . . .	„ ♏x.	—ʒj.
Terebinthina Canadensis . . .	„ gr. v.	—xx.

In the Form of Draught, &c.

22. ℞. Capaibæ ʒss.
Liquoris potassæ ♏x.
Syrupi tolutani ʒss.
Aq. menth, pip. ℥iss. M.

23. ℞. Pulveris cubebæ ʒss.
Syrupi papaveris ʒj.
Aquæ cinnamomi ℥iss. M

24. ℞. Tinct. benzoini co. ʒss.
Syrupi tolutani ʒj.
Pulv. tragacanth. gr. c.
Aquæ ℥iss. M.

In the form of a Pill or Powder.

25. ℞. Copaibæ,
Magnesiæ āā gr. x. fiant
boli duo.

26. ℞. Pulveris cubebæ ʒi.
Sodæ bicarbonatis ʒss.
Fiat pulvis.

Inhalations.

Vapor chlorinii. Vapor kreasoti. Vapor iodinii.

---

3. EXTERNAL AND LOCAL STIMULANTS.

1. CAUSTICS.

Acidum nitricum. Acidum sulphuricum. Acidum arseniosum.

Argenti nitras.

Cupri sulphas.

4. Liquor ammoniæ fortior.
5. Liq. hydrargyri nitratis acidus.
6. Soda caustica.
7. Potassa caustica.
8. Zinci chloridum et sulphas.

2. VESICANTS.

Charta epispastica.

Emplastrum cantharidis.

Liquor epispasticus.

4. Liuimentum crotonis.
5. Oleum sinapis.

3. RUBEFACIENTS.

Acetum cantharidis.

Acidum aceticum; hydrochloricum dilutum; nitricum dilutum; nitro-hydrochloricum dilutum; sulphuricum dilutum; sulphurosum.

Armoraciæ radix.

Linimentum ammoniæ: camphoræ; camphoræ compositum; chloroformi; hydrargyri; iodinii; saponis; sinapis compositum; terebinthinæ; terebinthinæ aceticum.

5. *Emplastrum* ammoniaci cum hydrargyro; galbani; picis; resinæ; calefaciens.
6. *Liquor* ammoniæ; calcis chlorinatæ; sodæ chlorinatæ.
7. Mezerei extractum æthereum.
8. *Oleum* cajuputi; caryophylli; crotonis; rutæ; rorismarini; terebinthinæ.
9. Phosphorus.
10. *Pix* Burgundica; liquida; resina; terebinthinæ Canadensis. Thus Americanum; balsamum Peruvianum; balsamum tolutanum.
11. Sinapis cataplasma.
12. *Spiritus* ammoniæ aromaticus; cajuputi; camphoræ; chloroformi; rectificatus; tenuior; rorismarini.
13. Sulphuris iodidum.
14. *Tinctura* arnicæ; cantharidis; capsici; iodinii; pyrethri.
15. *Unguentum* antimonii tartarati: calomelanos; hydrargyri iodidi rubri; hydrargyri nitratis; hydrargyri oxidi rubri; hydrargyri ammoniati; iodinii compositum; kreasoti; picis liquidæ; resinæ; elemi; cantharidis; sulphuris; terebinthinæ; sabinæ.
16. Zinci sulphas.

Stimulant Lotions.

27. ℞ Acidi nitrici.
Acidi hydrochlor. āā ♏xx.
Aquæ f ℥viii. M. fiat lotio.

28. ℞ Acidi sulphurici diluti,
Aquæ destillatæ āā f ℥ss.
M.

29. ℞. Acidi sulphurosi,
Aquæ, partes æquales. M.

30. ℞. Liq. ammoniæ fort. f ℥j.
Spiritûs rorismarini f ℥ss.
Tinct. camphoræ f ℥ii. M.
(A highly-stimulant application.)

31. ℞. Zinci sulphatis gr. vi.
Spiritûs rorismarini,
Tincturæ lavandulæ co
positæ āā ʒiss.
Aquæ f ℥vss. M.
(Red wash.)

Stimulant Collyria.

32. ℞. Aluminis gr. v.
Aquæ ℥j. Solve.

33. ℞. Argenti nitratis gr. j.
Aquæ ℥j. Solve.

34. ℞. Cupri sulphatis gr. v.
Aquæ ℥j. Solve.

35. ℞. Zinci sulphatis gr. ii.
Vini Opii ʒii.
Aquæ ℥j. Solve.

36. ℞. Hydrarg perchloridi gr.
Aquæ destillatæ f ℥j. Sol

37. ℞. Potassii iodidi gr. vii.
Iodinii gr. iii.
Aquæ destillatæ Oj. Sol

Stimulant Baths.

38. ℞. Acidi hydrochlorici ℥ii.-
℥iv.
Aquæ q. s. M.

39. ℞. Acidi nitro-hydrochlorici
diluti Oj.
Aquæ tepidæ (96°) q.s. M.
(The acid may be used in the proportion of ℥vi. to 8 gallons, as a bath or lotion.)

40. ℞. Kreasoti ʒii.
Glycyrini ℥ii.
Aquæ calidæ Cxxx. M.

41. ℞ Iodinii ʒii.
Liquoris potassæ f ℥ii.
Aquæ calidæ Cxxx. M.

42. ℞. Hydrargyri perchlor. gr.
Acidi hydrochlorici ʒj.
Aquæ Cxxx. Solve.

43. ℞. Sulphuris præcipitati ℥i
Sodæ hyposulphitis ℥j.
Acidi sulphurici diluti ℥
Aquæ Cxxx. M.

Stimulant Liniments.

44. ℞. Liquoris ammoniæ f ℥ss.
Linimenti saponis f ℥iss. M.

45. ℞. Tincturæ cantharidis f ℥ss.
Linimenti saponis f ℥iss.
(A good application to chilblains.)

46. ℞. Camphoræ gr. c.
Olei terebinthinæ f ℥ss.
Linimenti camphoræ co.
℥ss M.

47. ℞. Pulv. seminis sinapis gr. c.
Acidi acetici f ℥ss.
Olei terebinthinæ f ℥i
M.

48. ℞. Antimonii tartarati gr.
Aquæ rosæ f ℥ii.
Tincturæ cantharidis f
M.

49. ℞. Acidi sulphurici ʒiss.
Olei terebinthinæ ℥ss.
Olei olivæ f ℥iss. M. cau

50. ℞. Olei cajuputi f ℥iss.
Linimenti camphoræ com
positi f ℥ss. M.

Stimulant Ointments.

℞. Argenti nitratis gr. x.
Unguenti simplicis gr. c. M.

℞. Olei crotonis ʒj.
Adipis ℥j. M. fiat unguentum.

℞. Kreasoti ♏v.—xxx.
Adipis ℥ss. M.

℞. Camphoræ gr. xv.
Olei olivæ ʒss.
Adipis ℥j. M.

55. ℞. Camphoræ gr. xx.
Unguenti hydrargyri ℥ss M.

56. ℞. Potassæ carbonatis ℈j.
Sulphuris præcipitati ʒij.
Adipis ℥iv. M.

57. ℞. Cupri sulphatis gr. xxx.
Acidi sulphurici diluti ♏x.
Adipis ℥j. M.

Stimulant Gargles.

℞. Tincturæ capsici ℥ss.—℥j.
Syrupi ℥j.
Aquæ rosæ ℥vi; M.

9. ℞. Vini rubri Lusitanici ℥vi.
Tincturæ capsici ℥ss. M.

℞. Acidi hydrochlorici dil ʒss.
Mellis rosæ ℥j.
Decocti hordei ℥viss. M.

61. ℞. Infusi rosæ acidi ℥iiiss.
Tincturæ myrrhæ ℥ss.
Sacchari ℥ss. M. ft. gargarisma.

62. ℞. Mucilaginis acaciæ ℥viiss.
Olei terebinthinæ ℥ss. M.

63. ℞. Potassæ chloratis gr. c.
Acidi hydrochlorici ʒii,
Aquæ ℥viiss.

Stimulant Enemata.

Enema assafœtidæ.

4. ℞. Olei terebinthinæ.
Tincturæ assafœtidæ ā ℥ss.
Decocti hordei Oj. M.

Enema terebinthinæ.

65. ℞ Spiritûs rectificati ℥ss.
Infusi serpentariæ ℥iiss.
M.

Stimulant Powders.

The salts of zinc, copper, and mercury.

Fumigations.

6. ℞. Sulphuris ℥ss.—℥iss.
Iodinii gr. xx.—l. M.

A twelfth part of this powder to be used at a time. The vapours of sulphur and of iodine may also be used separately, in obstinate cutaneous diseases.)

7. ℞. Calomelanos gr. vi.—xxx.

69. ℞. Manganesii binoxidi ʒj.
Sodii chloridi ℥iii.
Mix, then add—
Acidi sulphurici f ℥j.
Aquæ f ℥ii.

(Chlorine is given off from this mixture on applying heat.)

69. ℞. Hydrarg. sulphureti gr. xx.—xxx.

4. NARCOTICS, ANODYNES, AND SEDATIVES AND THEIR DOSES.

(Including Antispasmodics belonging to these Classes.

1. Æther, ♏xx.—ʒj ; as vapor ʒj.—ʒii.
2. Acidum hydrocyanicum dilutum, ♏iii.—♏viii.
3. Aconiti extractum, gr. j.—gr. ii. Aconiti tinctura, ♏v.—♏x
   The doses to be cautiously increased. Aconitia (only use externally).
4. Atropiæ liquor, ♏iii.—v. A. sulphatis liquor, ♏iii.—v.
5. Belladonnæ extractum, gr. ¼—gr. j. Tinctura belladonnæ, ♏
   —♏xx.
6. Bismuthi carbonas gr. v.—xx. ; subnitratis gr. v.—xx. ; Liqu
   b. et ammoniæ citratis ʒss.—ʒii. ; trochisci (gr. ii. subnitra in each) i.—vi.
7. Cannabis Indicæ extractum, gr. ¼—gr. j. ; tincturæ cannab
   Indicæ ♏v.—ʒss.
8. Cerii oxalas, gr. j.—gr. ii.
9. Chloralis hydras, gr. x.—xl.
10. Chloroformi spiritus, ♏xv.—ʒii. ; as vapor ʒj.—ʒii.
11. Colchici cormus et semen. Extractum colchici, gr. ¼—gr. i
    Extracti colchici acetici, gr. ½—gr. ii. Vinum colchici, ♏
    —ʒss. Tinctura colchici seminum ♏x.—ʒss.
12. Conii extractum, xv.—lxxx. Tinctura Conii fructûs, (inert
    Succus Conii, ʒj.—℥ii.
13. Digitalis folia, gr. ½.—gr. iss. Infusum Digitalis, ʒii.—ʒi
    Tinctura Digitalis, ʒx.—℥ss. Digitalinum gr. $\frac{1}{60}$—$\frac{1}{30}$.
14. Hyoscyami folia, gr. v.—gr. x. Extractum Hyoscyami, gr.
    xx. Tinctura Hyoscyami, ♏x.—℥ii.

    Lactucæ extractum, gr. v.—xv.

    Laurocerasi aqua, ♏v.—xxx.
15. Lobeliæ inflatæ pulvis, gr. j.—gr. v. Tinctura Lobeliæ, ♏x.—
    ℥ss. Tinctura Lobeliæ ætherea, ♏x.—℥ss.
16. Morphia, gr. ¼—gr. j. Morphiæ hydrochloras, gr. ¼—gr.
    Liquor Morphiæ hydrochloratis (gr. j. in ℥ii.), ♏xv.—℥i
    Trochisci morphiæ (gr. j. in 36 lozenges), 1 to 15 durin the day. Trochisci morphiæ et ipecacuanhæ (gr. j. in 3 lozenges).

    (The subcutaneous use of morphia is often a dangerous proceed ing, and the first dose by this method should never exceed of a gr., and it is well when we are unacquainted with the con stitution of the patient to introduce $\frac{1}{60}$ gr. of atropia pre viously.)
17. Opium, gr. j.—gr. vi.

    Extractum opii, gr. ¼—gr. ii.

    Enema opii (ʒss. of laudanum = gr. ii. opium, to starch f ℥ii.).

    Extractum opii liquidum (gr. j. of extract in about ♏xxiii.).

    Pilula saponis composita (gr. j. in v.), gr. v.—gr. x.

Pilula styracis composita L. (gr. j. in v.), gr. v.—gr. x.
—— plumbi cum opio (gr. j. in viii.), gr. iv.—viii.
Pulvis cretæ aromaticus cum opio (gr. j. in xl.), gr. x.—xl.
—— kino compositus (gr. j. in xx.), gr. v.—xx.
—— ipecacuanhæ compositus (gr. j. in x.), gr. v.—xv.
—— opii compositus (gr. j. in x.), gr. ii.—v.
Tinctura opii (gr. j. in ♏xv.), ♏v.—ʒss.
—— camphoræ composita) gr. j. in ℥ss.), ʒss.—f ℥ss.
Trochisci morphiæ ($\frac{1}{36}$ gr. morph. hydroch. in. each), i.—vi.
—— morphiæ et ipecacuanhæ ($\frac{1}{36}$ gr. and $\frac{1}{12}$ gr.), i.—vi.
—— opii (gr. j. extract in 10 lozenges), 1 to 5 during the day.
Vinum opii (gr. j. in ♏xxiii.), ♏v. xl.

18. Papaveris syrupus, ʒj. ; extractum, gr. ii.—v.
Physostigmatis extractum gr. $\frac{1}{16}$—$\frac{1}{4}$.

19. Stramonii folia et semina, gr. ii.—gr. x. Extractum stramonii, gr. $\frac{1}{4}$—gr. iii. Tinctura stramonii ♏x.—xx.

20. Tabaci enema (tobacco gr. xx.—boiling water f ℥viii.). Dose, the whole.

21. Veratria, gr. $\frac{1}{12}$—$\frac{1}{8}$.

Narcotics, &c., in the form of Draught.

70. ℞. Tincturæ opii ♏xx.
Aquæ cinnamomi,
Aquæ puræ āā ʒvi. M.

71. ℞. Potassæ bicarb. gr. xx.
Aquæ menthæ viridis f ℥j.
Tincturæ opii ♏xxv. M.
(To be taken with ʒj of lemon juice).

72. ℞. Tincturæ opii ♏xxx.
Liq. ammoniæ acetatis ℥j.
Aquæ cinnamomi,
Syrupi tolutani āā f ℥ss. M.

73. ℞. Acidi sulphurici diluti ♏xv
Tincturæ opii ♏x. vel tincturæ hyoscyami ʒss.
Tincturæ digitalis ♏x.
Infusi quassiæ ℥iss. M.

74. ℞. Acidi hydrocyanici diluti ♏v.
Misturæ amygdalæ ℥iss. M.

75. ℞. Bismuthi carbonatis gr. x.
Acidi hydrocyanici dilut. ♏v.
Mucilaginis acaciæ f ℥j.
Syrupi aurantii ʒj. M.

76. ℞. Tincturæ digitalis ♏x.
Aquæ camphoræ,
Aq. cinnamomi āā ʒvj. M.

77. ℞. Potassæ nitratis gr. xv.
Tincturæ digitalis ♏x.
Liq. ammoniæ acetatis ʒii.
Syrupi hemidesmi ʒj. M.
Aquæ destillatæ ℥iss.

78. ℞. Træ. seminis colchici ♏xv.
Infusi digitalis ʒiv.
Aquæ cinnamomi ℥iss. M.

Narcotics, &c., in the form of Pill.

79. ℞. Bismuthi subnitratis gr. x.
Extracti hyoscyami gr. v.
ut fiant pilulæ duæ.

80. ℞. Extracti hyoscyami gr. $\frac{1}{4}$.
Pulv. ipecac. comp. gr. x.
M. fiant pilulæ duæ.

81. ℞. Pulveris digitalis,
——— scillæ.
Extr. hyoscyami āā gr. v.
M. in pilulas tres divide.

82. ℞. Camphoræ pulveris,

Ext. hyoscyami āā gr. ii. ss.
Sp. rectificati q. s. ft. pil.

83. ℞. Pulv. ipecacuanhæ gr. ii.
Morphiæ hydrochlor. gr. $\frac{1}{8}$
In pilulas duas divide.

84. ℞. Cerii oxalatis gr. ii.
Extracti lactucæ gr. viii
Fiant pilulæ duæ.

Narcotics, &c., in the form of Powder.

85. ℞. Pulv. ipecac. comp. gr. j.
Sacchari gr. xx. M.
(Divide into four powders. For young infants. Each powder contains $\frac{1}{40}$ gr. of opium.

86. ℞. Camphoræ gr. iii.
Spirit. vin. rect. ♏ii.
Pulv. ipecac. c. gr. v.
(A powder to be taken at b
time).

Sedatives in the form of Vapour.

1. Vapor acidi hydrocyanici.
2. Vapor conii.

---

5. EXTERNAL SEDATIVE APPLICATIONS.

1. Cataplasma conii.
2. Chloroformum.
3. Decoctum papaveris.
4. Emplastrum belladonnæ (Resin and Extr. B. p. æ.) ; opii (gr
of powder in gr. x.).
5. Extractum aconiti ; belladonnæ ; conii ; opii ; opii liquidum.
6. Linimentum aconiti; belladonnæ; chloroformi; opii (gr. j. in ʒss
7. Unguentum aconitæ (gr. viii. in ℥j.) ; atropiæ (gr. viii. in ℥j
belladonnæ (gr. lxxx. to ℥j.) ; gallæ cum opio (gr. j. in ab
gr. xiv.) ; veratriæ (gr. viii. in ℥j.)

Several preparations of the Pharmacopœia enumerated among n cotics and sedatives (pp. 648, *et seq.*) also admit of external applic tion. All substances, too, which produce cold by evaporation otherwise, may be said to belong to the class of sedatives.

Sedative Lotions.

87. ℞. Tincturæ opii ♏xxx.
Aquæ ℥j. M. fiat lotio.

88. ℞. Tincturæ opii,
Acidi hydrocyanici dil. āā partes æquales.
M. fiat lotio.

89. ℞. Acidi hydrocyanici dil. ʒiss.
Misturæ amygdalæ f ℥viss.
M. fiat lotio.

90. ℞. Extracti belladonnæ,
Extracti opii ana gr. ii.
Aquæ ℥j. M. fiat lotio

91. ℞. *Potassii cyanidi gr. x.
Mist. amygdalæ ℥vi.
(* *Non-officinal.*)

92. ℞. Vini opii ♏xx.
Aquæ laurocerasi ℥j.

Cold Applications.

3. ℞ Ammoniæ hydrochloratis
Potassæ nitratis āā ℥iv.
Aquæ ℥viii.

Mix. (This is applicable whenever intense cold is required.)

94. ℞. Ammoniæ nitratis,
Aquæ āā lb. j. Solve.

(In winter, mix equal parts of snow and common salt. In summer, two parts of pounded ice and one of salt.)

Sedative Fomentations.

5. ℞. Opii gr. c.
Aquæ ferventis Oi. M.

96. ℞. Extracti aconiti gr. lx.
Aquæ ferventis Oi. M.

Sedative Ointments.

7. ℞. Plumbi acetatis gr. xxx.
Acidi hydrocyanici dil. ʒiii.
Unguenti simplicis ℥iii. M.

98. ℞. Potassii cyanidi gr. xii.
Olei amygdalæ ʒii.
Unguenti simplicis ℥ii. M.

Sedative Enemata and Suppositories.

Enema opii; E. tabaci.
Suppositoria morphiæ. S. plumbi composita.

99. ℞. Pilulæ saponis co. gr. v.
Fiat suppositorium.

---

6. STIMULANTS, IN COMBINATION WITH NARCOTICS, SEDATIVES, AND ANODYNES.

(Including Stimulant and Anodyne Antispasmodics.)

In the form of Draught.

00. ℞. Tr. valerianæ ammon. ℥ss.
Spiritûs ætheris ʒj.
Tincturæ hyoscyami ʒss.
Aquæ camphoræ f ℥j. M.

01. ℞. Tincturæ digitalis ♏xv.
Sp. ammon. comp. ʒss
Aquæ camphoræ ℥iss. M.

02. ℞. Moschi gr. x.
Ætheris,
Tincturæ opii āā ♏xx.
Aquæ cinnamomi f ℥j. M.

03. ℞. Aquæ camphoræ ℥iii.
Spiritûs ætheris,
Tincturæ camphoræ compositæ,
Syrupi papav. āā ʒj. M.

104. ℞. Tinct. opii ʒss
Mist. camphoræ f ℥j. M.

105. ℞. Tincturæ opii ♏x.
Spiritûs ætheris ♏xl.
Aquæ camphoræ ℥iss. M.

106. ℞. Tinct. colchici seminum,
Spir. ammoniæ co. āā ʒss.
Infusi serpentariæ ℥iss. M.

In the form of Pill.

107. ℞. Pil. assafœtidæ compositæ
Camphoræ āā gr. v.
Fiant pilulæ duæ.

108. ℞. Castorei gr v.
Pil. saponis comp. gr. iii.
Olei menthæ pulegii gtt. j.
Fiant pilulæ duæ.

109. ℞. Camphoræ gr. v.
Olei cajuputi ♏ii
Pulveris opii gr.
Extracti hyoscya
Fiant pilulæ duæ.

110. ℞. Kreasoti ♏i.
Pilulæ saponis c
gr. iii.
Ext. hyoscyami g
Fiant pilulæ duæ.

7. EXTERNAL APPLICATIONS (STIMULANT and SED

111. ℞. Olei cajuputi f ℥iss.
Tincturæ opii f ℥ss.
Lin. terebinthinæ ʒii. M.

112. ℞. Linimenti belladonnæ,
Linimenti chloroformi
partes æquales. M.

113. ℞. Tincturæ canthar
Linimenti camph
Liquoris ammonia
Tincturæ opii ʒiii

114. ℞. Olei crotonis ♏x
Linimenti saponi
Tincturæ opii f

ENEMATA (Stimulant and Sedative).

115. ℞. Tincturæ assafœtidæ f ℥ss.
Tincturæ opii ʒj.
Decocti hordei Oss. M.

116. ℞. Camphoræ gr. x
Olei terebinthinæ
Decocti hordei O

---

8. TONICS.

1. MINERAL.

Mineral Acids.

1.	Acidum hydrochloricum dilutum	dose ♏x. to
2.	Acidum nitricum dilutum	,, ♏x. —
3.	Acidum nitro-hydrochloricum dilutum	,, ♏x. —
4.	Acidum phosphoricum dilutum	,, ♏x. —
5.	Acidum sulphuricum aromaticum	,, ♏x. —
6.	Acidum sulphuricum dilutum	,, ♏x. —

Preparations of Iron.

7.	Ferri et ammoniæ citras	dose gr. v. to
8.	Ferri arsenias	,, gr. $\frac{1}{16}$ —
9.	Ferri carbonas saccharata	,, gr. x. —
10.	Ferri iodidum	,, gr. v. —
11.	Ferri et quiniæ	,, gr. v. —
12.	Ferrum tartaratum	,, gr. v. —
13.	Ferri oxidum magneticum.	,, gr. v. — gr

14.	Ferri peroxidum humidum	dose gr. cc. to ℥ss.
15.	Ferri peroxidum hydratum	,, gr. v. — ʒj.
16.	Ferri phosphas	,, gr. v. — gr. xx.
17.	Ferri sulphas	,, gr. j. — gr. x.
18.	Ferri sulphas exsiccata	,, gr. j. — gr. x.
19.	Ferri sulphas granulata	,, gr. j. — gr. x.
20.	Ferrum redactum	,, gr. j. — gr. x.
21.	Liquor ferri perchloridi	,, ♏iij. — ♏x.
22.	Liquor ferri pernitratis	,, ♏iij. — ♏x.
23.	Mistura ferri aromatica	,, ℥j. — ℥ii.
24.	Mistura ferri composita	,, ℥j. — ℥ij.
25.	Pilula ferri carbonatis	,, gr. v. — gr. xx.
26.	Pilula ferri iodidi (gr. v. = gr. i¼ nearly FeI)	,, gr. v. — gr. xx.
27.	Syrupus ferri iodidi (ʒj. = gr. ivss FeI)	,, ʒss — ʒii.
28.	Syrupus ferri phosphatis	,, ʒj. — ʒiv.
29.	Tinctura ferri acetatis	,, ♏x. — ♏xxx.
30.	Tinctura ferri perchloridi	,, ♏x. — ♏xxx.
31.	Trochisci ferri redacti (1 gr. in each)	,, j. — vi.
32.	Vinum ferri; et v. f citratis	,, ʒj. — ʒiv.
33.	Emplastrum ferri	

Preparations of Zinc.

34.	Zinci acetas	dose gr. ii. to gr. v.
35.	Zinci carbonas	,, gr. ii. — gr. v.
36.	Zinci oxidum	,, gr. ii. — gr. v., or more.
37.	Zinci sulphas	,, gr. ii. — gr. v., or more.
38.	Zinci valerianas	,, gr. j. — gr. v.

Preparation of Copper.

39.	Cupri sulphas	dose gr. ¼ to gr. ii.

Preparations of Arsenic.

40.	Acidum arseniosum	dose gr. $\frac{1}{60}$ to gr. $\frac{1}{8}$.
41.	Ferri arsenias	,, gr. $\frac{1}{16}$ to gr. ½.
42.	Liquor arsenicalis (gr. iv. in f ℥j., or $\frac{1}{24}$ gr. in ♏v.)	dose ♏v.—x.
43.	Liquor arsenici hydrochloricus (gr. iv. AsO_3 in f ℥j., or $\frac{1}{24}$ in ♏v.)	dose ♏ii. — ♏viii.
44.	Liquor sodæ arseniatis (gr. iv. in f ℥j., or $\frac{1}{24}$ gr. in ♏v.)	♏v.—x.

Preparations of Silver.

45.	Argenti oxidum	dose gr. ½ to gr. j.
46.	Argenti nitras	,, gr. ¼ — gr. j.

2. VEGETABLE TONICS AND THEIR DOSES.

Unless otherwise specified the doses are as follows:

Extractum	dose gr. iii. to gr. x.
Decoctum Infusum	,, f. ℥ss. — f. ℥ii.
Tinctura	,, ʒss. — ʒii.

47. Anthemidis extractum, infusum.
48. Aurantii infusum. infusum compositum, syrupus, tinctura.
49. Beberiæ sulphas—gr. j. to x.
50. Calumbæ extractum, infusum, tinctura.
51. Cascarillæ infusum, tinctura.
52. Chiratæ infusum, tinctura.
53. Cinchonæ flavæ extractum liquidum (ʒss. to ʒiss.), decoct
infusum, tinctura.
54. Cinchonæ (pallidæ) tinctura composita.
55. Cuspariæ infusum.
56. Gentianæ extractum, infusum compositum, tinctura.
57. Lupuli extractum, infusum, tinctura.
58. Nucis vomicæ extractum (gr. ¼ to gr. ii.), tincturæ (♏x
♏xx.).
59. Pareiræ extractum; extractum liquidum (ʒss. to ʒiss); decoc
60. Quassiæ extractum, infusum.
61. Quiniæ sulphas (gr. j. to gr. v.), tinctura composita (ʒj. to ʒ
vinum (ʒss. to ʒj.).
62. Serpentariæ infusum, tinctura.
63. Strychnia (gr. $\frac{1}{32}$ to gr. $\frac{1}{12}$); liquor (♏v. = $\frac{1}{24}$ gr.) ♏iii. to ♏

Tonics in the form of Draught.

117. ℞. Quinæ sulphatis gr. ii.
Tincturæ aurantii ʒj.
Infusi rosæ acidi ℥iss. M.

118. ℞. Liquoris arsenicalis ♏v.
Infusi lupuli ℥iss. M.

119. ℞. Acidi nitrici diluti ♏xv.
Infusi anthemidis ℥iss. M.

120. ℞. Infusi aurantii ℥iss.
Træ serpentariæ ʒss. M.

121. ℞. Beberiæ sulphatis gr. v.
Infusi chiratæ ℥iss.

122. ℞. Infusi calumbæ ℥iss.
Acidi nitro-hydrochlorici
diluti ♏xv. M.

123. ℞. Sodæ bicarbonatis gr. xx.
Tincturæ cascarillæ ʒj.
Infusi calumbæ ℥iss. M.

124. ℞. Infusi cuspariæ ℥iss.
Liq. strychniæ ♏iv. M.

125. ℞. Infusi cascarillæ ℥j.
Tincturæ aurantii ʒj. M

126. ℞. Infusi lupuli ℥iss.
Tincturæ nucis vomicæ
♏x. M.

127. ℞. Dec. cinchonæ flavæ
Acidi sulphurici dil.
M.

128. ℞. Infusi lupuli ℥iss.
Extr. pareiræ liquid
Acidi hydrochlorici d
♏x. M.

129. ℞. Træ. ferri perchl
♏xx.
Infusi quassiæ ℥iss.

130. ℞. Ferri et quiniæ cit
gr. v.
Syrupi aurantii flori
Aquæ cinnamomi ℥is

131. ℞. Ferri et ammoniæ c
tis gr. x.
Spiritûs ammoniæ a
ʒss.
Aq. menthæ pip. ℥iss

182. ℞. Ferri iodidi gr. v.
Spiritûs myristicæ ʒ
Aquæ menth. puleg.
M.

133. ℞. Ferri sulphatis gr. iii.
Magnesiæ sulphatis ʒss.
Acidi sulphurici dil. ʒss.
Aq. menth. pip. ℥iss. M.

134. ℞. Acidi phosphorici dil. ℥ii.
Syrupi aurantii ʒj.
Aquæ f ℥xix. M. (To be used as a common drink.)

Tonics in the form of Pills.

135. ℞. Cupri sulphatis gr. ¼.
Pilulæ saponis co. gr. ii.
Micæ panis gr. ii. ft. pil.

136. ℞. Zinci valerianatis gr. ii.
Extracti lupuli gr. iii.
M. Fiat pilula.

137. ℞. Ferri sulphatis exsiccatæ gr. v.
Extracti anthemidis gr. v.
Fiant pilulæ duæ.

138. ℞. Quiniæ sulphatis gr. j.
Extr. gentianæ gr. iv. M.

139. ℞. Argenti oxidi gr. j.
Extr. gentianæ gr. iv. M.

140. ℞. Argenti nitratis gr. ½.
Extr. hyoscyami gr. iv. M.

Tonics in the form of Powder.

141. ℞. Ferri redacti gr. iii.
Pulv. cinnam. co. gr. v.
Misce. fiat pulvis.

142. ℞. Ferri carbonatis saccharatæ gr. x.
Pulveris cinnam. co. gr. v.
Fiat pulvis.

143. ℞. Ferri phosphatis gr. iii.
Pulveris cinnam. co. gr. v.
Misce, fiat pulvis.

144. ℞. Pulveris cinchonæ ʒi.
Pulveris cinnam. co. gr. v.
Fiat pulvis.

---

9. ASTRINGENTS.

(*a.*) *Mineral.*

1.	The mineral acids.	
2.	Alumen	dose gr. x. to gr. c.
3.	Alumen exsiccatum	„ gr. v. — gr. xv.
4.	Argenti nitras	„ gr. ¼ — gr. j.
5.	Cadmii iodidi, et unguentum (used externally).	
6.	Mistura cretæ	„ ℥j. — ℥ii.
7.	Cupri sulphas	„ See Tonics, p. 672.
8.	Ferri perchloridi, liquor et tinctura „ pernitratis liquor „ sulphas exsiccata, et granulata	
9.	Plumbi acetas,	„ gr. j. — gr. v.
10.	Zinci acetas, et sulphas	„ gr. ii. — gr. v.

(*b.*) *Vegetable.*

1.	Belæ extractum liquidum	dose ʒj. to ʒii.
2.	Catechu, pallidum	„ gr. x. — gr. xxx.
3.	„ pulvis compositus	„ gr. v. — gr. xxx.
4.	„ tinctura	„ ʒss. — ʒii.

5.	Catechu infusum	dose	℥j.	to	℥ii
6.	,, trochisci	,,	ii.	—	xx
7.	Cinchona pallida	,,	gr. xxx.	–	gr.
8.	Cinchonæ tinctura composita	,,	ʒss.	—	ʒii
9.	Granati radicis decoctum	,,	℥j.	—	℥ii
10.	Hæmatoxyli decoctum	,,	℥j.	—	℥ii
11.	Hæmatoxyli extractum	,,	gr. x.	—	ʒs
12.	Kino pulvis compositus (one gr. opium in gr. xx.)	,,	gr. v.	—	gr.
13.	Kino tinctura	,,	ʒss.	—	ʒii
14.	Krameriæ extractum	,,	gr. v.	—	x.
15.	Krameriæ infusum	,,	℥iss.	—	℥ii
16.	Krameriæ tinctura	,,	ʒss.	—	ʒii.
17.	Kreasotum	,,	♏i.	—	♏ii
18.	Kreasoti mistura	,,	℥j.	—	℥ii
19.	Maticæ infusum	,,	℥ss.	—	℥iv
20.	Pterocarpi lignum				
21.	Lavandulæ tinctura composita	,,	ʒss.	—	℥ii
22.	Quercûs decoctum	,,	℥j.	—	℥ii
23.	Gallæ pulvis	,,	gr. x.	—	ʒs
24.	Gallæ tinctura	,,	ʒss.	—	ʒii
25.	Acidi tannici trochisci	,,	ii.	—	xx
26.	Acidi tannici suppositoria	,,	gr. x.	—	gr.
27.	Acidum gallicum, et tannicum	,,	gr. j.	—	gr.
28.	Acidi gallici, et A. tannici, glycerinum.	,,	♏x.	—	♏x
29.	Rosæ (Gallicæ) infusum acidum . . .	,,	℥j.	—	℥ii
30.	Rosæ (Gallicæ) confectio	,,	ʒss.	—	ʒii.
31.	Rosæ (Gallicæ) syrupus	,,	ʒss.	—	ʒii.
32.	Rosæ caninæ confectio	,,	ʒss.	—	ʒii
33.	Ulmi decoctum	,,	f ℥ii.	—	f ℥
34.	Uvæ ursi infusum	,,	f ℥j.	—	℥ii.

(c.) *Mineral and Vegetable.*

1.	Pilula plumbi cum opio	dose	gr. ii.	to	gr.
2.	Pulvis cretæ aromaticus	,,	gr. x.	—	gr.
3.	Pulvis cretæ aromaticus cum opio . .	,,	gr. x.	—	gr.

Astringents in the form of Mixture or Draught.

145. ℞. Aluminis gr. x.
Syrupi ʒj.
Infusi rosæ acidi ℥iss M.

146. ℞. Acidi sulph. diluti ♏xx.
Infusi rosæ acidi f ℥iss.
Syrupi rhœados f ʒj. M.

147. ℞. Acidi nitro-hydrochlorici diluti ♏xv.
Infusi uvæ ursi ℥iss. M.

148. ℞. Misturæ cretæ ℥j.
Tincturæ opii ♏v.
Tincturæ catechu ʒj.

149. ℞. Træ. ferri perchloridi
Infusi quassiæ ℥iss.

150. ℞. Liquoris ferri pernitr
♏xv.
Syrupi aurantii floris ʒ
Aquæ ℥iss. M.

151. ℞. Extracti belæ liquidi ʒj.
Infusi cuspariæ ℥iss. M.

152. ℞. Tincturæ cinchonæ compositæ ʒj.
Infusi uvæ ursi ℥iss. M.

153. ℞. Træ. lavandulæ compositæ ʒj.
Infusi krameriæ ℥iss. M.

154. ℞. Syrupi rosæ Gallicæ ʒj.
Infusi catechu ℥iss. M.

155. ℞. Acidi gallici gr. v.
Tincturæ opii ♏v.
Infusi rosæ acidi ℥iss. M.

156. ℞. Tincturæ krameriæ ʒj.
Decoct. hæmatoxyli ℥iss.
M.

Astringents in the form of Pill.

157. ℞. Pilulæ plumbi cum opio gr. iii.—gr. v.

158. ℞. Acidi gallici gr. iii
Plumbi acetatis gr. j.
Conf. rosæ Gal. q. s. ut fiat pil.

159. ℞. Acidi gallici gr. iiss.
Morphiæ gr. $\frac{1}{16}$
Confectionis rosæ Gallicæ, quantum sufficit ut fiat pilula.

160. ℞. Cupri sulphatis gr. ¼.
Pulveris opii gr. ¼.
Confec. rosæ C. gr. iii,
fiat pil.

See also Formulæ, p. 675.

Astringents in the form of Powder.

161. ℞. Pulv. cinchonæ pallidæ gr. xl.
Acidi gallici gr. ii.
Misce ut fiat pulvis.

162. ℞. Pulveris cretæ aromatici cum opio gr. x.
Pulv. catechu comp. gr. x.
M.

Astringent Lotions.

163. ℞. Argenti nitratis gr. ii.–xl.
Aquæ destillatæ ℥j. Solve.

164. ℞. Liquoris calcis ℥j.
Olei olivæ ℥ii. M.

165. ℞. Cupri sulphatis gr. iii.-xl.
Aquæ camphoræ ℥j. S.

166. ℞. Acidi tannici gr. x.
Acidi hydrochlorici dil. ʒss.
Aquæ ℥j. Solve.

167. ℞. Liquoris plumbi subacetatis ♏xx.
Glycyrini ʒj.
Aquæ rosæ ℥viij. Misce.

168. ℞. Liq. plumbi subacet. ʒss.
Spiritûs rectificati ♏xxx.
Aquæ destillatæ ℥viii.

169. ℞. Zinci chloridi gr. j.
Aquæ ℥j. Solve.

170. ℞. Zinci sulphatis gr. v.
Tincturæ lavandulæ compositæ ♏xxx.
Aquæ ℥j. Solve.

171. ℞. Zinci sulphatis gr. j. to x.
Aquæ rosæ ℥j. Solve.

Astringent Injections.

172. ℞. Aluminis gr. c.
Decocti quercûs Oj. S.

173. ℞. Cupri sulphatis gr. ii.–x.
Aquæ ℥j. S. et fiat injectio.

174. ℞. Liq. ferri perchloridi ♏iii.
Aquæ ℥j. M. et ft. injectio.

175. ℞. Liq. plumb. subacet. ♏x.
Extracti opii liquidi ʒss.
Aquæ destillatæ ℥j.

176. ℞. Zinci sulphatis,
Aluminis ana. gr. ii.
Aquæ ℥j. Solve.

Astringent Collyria.

177. ℞. Aluminis gr. iii. to gr. x.
Aquæ ℥j. Solve.

178. ℞. Argenti nitratis gr. j.—v.
Aquæ destillatæ f ℥j.

179. ℞. Cupri sulphatis gr. j.—v.
Aquæ ℥j. Fiat collyrium.

180. ℞. Hydrargyri perchlor. gr
Aquæ ℥j. S. Ft. collyri

181. ℞. Plumbi acetatis gr. ii.
Aquæ destillatæ ℥j.

182. ℞. Zinci sulphatis gr. j.—
Vini opii ʒj.
Aquæ ʒvii. Fiat co
rium.

Astringent Gargles.

183. ℞. Aluminis ʒj.
Acidi sulphurici arom. ʒss.
Tincturæ myrrhæ ʒii.
Decocti cinchonæ ℥vi. M.

184. ℞. Glycerini acidi tannici
Infusi rosæ acidi ℥vi.

Astringent Ointments.

185. ℞. Argenti nitratis gr. xx.
Adipis ℥j. M. Fiat unguentum.

186. ℞. Acidi sulphurici ʒss.
Adipis ℥j. Ft. unguentum

187. ℞. Cretæ præcipitatæ ℥i.
Olei olivæ ʒij.
Adipis ℥ss. Misce.

188. ℞. Cupri sulphatis gr. x
Adipis ℥j. M.

189. ℞. Hydrargyri perchlor. g
Adipis ℥j. M.

190. ℞. Liq. plumbi subacet.
Adipis ℥j. Misce.

---

10. DEPRESSENTS.

1.	Acidum hydrocyanicum dilutum . . .	dose ♏ii.	to ♏v
2.	Antimonii oxidum	„ gr. j.	— gr.
3.	Antimonium sulphuratum	„ gr. j.	— gr.
4.	Antimonium tartaratum	„ gr. $\frac{1}{8}$	— gr.
5.	Antimoniale vinum (gr. j. in ℥ss.) . .	„ ʒss.	— ʒii.
6.	Antimonialis pulvis (i gr. terox. in iii grs.)	„ gr. iii.	— gr.
7.	Colchici seminis tinctura	„ ♏xx.	— ʒj.
8.	Colchici extractum	„ gr. j.	— gr.
9.	Colchici extractum aceticum	„ gr. j.	— gr.
10.	Colchici vinum	„ ♏xx.	— ʒii.
11.	Digitalis infusum	„ ʒii.	— ʒiv.
12.	Digitalis tinctura	„ ♏x.	— ʒss.
13.	Digitalinum	„ gr. $\frac{1}{60}$	— gr.

Ipecacuanhæ pulvis	dose gr. v.	to gr. x.
Ipecacuanhæ vinum	,, ♏xv.	— ʒj.
Lobeliæ tinctura	,, ♏xx.	— ʒj.
Lobeliæ tinctura ætherea	,, ♏xx.	— ʒj.
Scillæ syrupus	,, ʒj.	— ʒii.
Scillæ tinctura	,, ʒss.	— ʒj.
Tabaci enema	,, ℥iv.	— ℥viii.
Veratri viridis pulvis	,, gr. j.	— gr. iii.
Veratri viridis tinctura	,, ♏v.	— ♏xx.

It must be borne in mind that these are *depressent* doses.

Depressents in the form of Draught or Mixture.

℞. Vini antimonialis ʒss.
Aquæ destillatæ ℥iss. M.

℞. Vini colchici ʒj.
Aquæ camphoræ ℥iss.
M.

℞. Tr. veratri viridis ♏xv.
Aquæ anethi ℥iss. M.

℞. Tincturæ digitalis ♏xv.
Aquæ cinnamomi ℥iss.
M.

195. ℞. Acid. hydrocyanici dil. ♏v.
Misturæ amygdalæ ℥iss.
M.

196. ℞. Vini ipecacuanhæ ♏xv.
Aquæ cinnamomi ℥iss.
M.

Depressents in the form of Powder.

℞. Antimonii tartarati gr. j.
Sacchari albi gr. xxxi.
M.

vide into parts proportioned to he age, and give one, three, or our times a day.)

198. ℞. Antimonii tartarati gr. j. Hydrargyri c. cretâ gr. xii. Sacchari albi ʒj. Misce, et in pulveres octo divide, sumat unam quartis horis.

---

11. EMETICS.

here are two classes of emetics; the one consisting of stimulants, other of depressents. A certain dose of either class of substances excite vomiting. The following formulæ comprise medicines of classes:—

℞. Vini antimonialis ℥ss.

℞. Vini ipecacuanhæ ℥ss.

℞. Pulv. ipecacuanhæ gr. xx.
Vini Antimonialis ℥ss.
Aquæ menthæ piperitæ
ʒx. M. fiat haustus.

℞. Zinci sulph. gr. xx. to xl.
Aquæ cinnamomi ℥iss.
M.

203. ℞. Cupri sulphatis gr. x.
Aquæ ℥iss. Ft. h.

204. ℞. Sinapis pulveris ℥ss.
Aquæ ℥iv.
(In cases of poisoning.)

205. ℞. Ammoniæ carbonatis.
Pulv. ipecacuanhæ gr. xx.
Tincturæ capsici ʒii.

Aquæ menthæ piperitæ f ℥ii. M.

(When the sensibility of the stomach is impaired, as in poisoning with opium.)

206. ℞. Tabaci foliorum ℥j.
Aquæ tepidæ q. s.

Bruise the leaves and apply poultice to the epigastri (Must be removed as soo sickness takes place.)

12. DIAPHORETICS.

There are also two classes of diaphoretics; the one consistin stimulants, the other of depressents. Both classes are compris the following formulæ :—

Diaphoretics in the form of Draught.

207. ℞. Liquoris ammoniæ acetatis ʒiii.
Aquæ camphoræ ℥iss. M.

208. ℞. Potassæ nitratis gr. xx.
Vini antimonialis ʒss.
Liq. ammoniæ acet. ʒii.
Aq. menthæ pip. ℥iss. M.

209. ℞. Ammoniæ carbonatis gr. x.
Spiritus chloroformi ʒj.
Aquæ ℥iss. M.

210. ℞. Spiritus ætheris nit ʒj.
Liq. ammoniæ acet.
Syrupi hemidesmi ʒj
Aq. ℥iss. M.

211. ℞. Potassæ nitratis ʒss.
Tincturæ opii ♏xv.
Mist. amygd. ℥iss.

212. ℞. Tr. guaiaci ammon. ʒ
Tincturæ opii ♏v.
Aquæ pimentæ ℥iss.

Diaphoretics in the form of Powders.

213. ℞. Pulv. ipecacuanhæ gr. x.

214. ℞. Pulv. ipecacuanhæ co. gr. x.
Antimonii tartarati gr. $\frac{1}{6}$. M.

215. ℞. Pulv. ipecacuanhæ g
Pulv. antimonialis x.
Sacchari gr. vi. M.

As a hypodermic injection.

From $\frac{1}{20}$ to $\frac{1}{10}$ of a grain of nitrate or hydrochlorate of pilocar in a few drops of water (not officinal).

13. EXPECTORANTS.

There are also two classes of expectorants; the one stimulant, other depressent. Expectorants of both classes are to be found in following preparations and formulæ :—

1. Acidum benzoicum . . . . dose gr. v. to gr. x
2. Ammoniacum . . . . ,, gr. v. — gr. c

Ammoniaci mistura	dose	℥ss.	to ℥iss.
Antimonium tartaratum	,,	gr. ⅛	— gr. ¼.
Balsamum Peruvianum	,,	ʒss.	— ʒi.
Balsamum tolutanum	,,	ʒss.	— ʒi.
Benzoinum	,,	gr. xx.	— gr. l.
Benzoini composita tinctura (Friar's balsam)	,,	ʒss.	— ʒii.
Galbanum	,,	gr. x.	— gr. l.
Ipecacuanhæ pulvis	,,	gr. j.	— gr. v.
Ipecacuanhæ vinum	,,	♏x.	— ʒss.
Ipecacuanhæ pulvis composita	,,	gr. ii.	— gr. v.
Lobelia inflata	,,	gr. j.	— gr. v.
Lobeliæ tinctura	,,	♏x.	— ʒss.
Lobeliæ ætherea tinctura	,,	♏x.	— ʒss.
Scillæ pilula composita	,,	gr. v.	— gr. x.
Scillæ syrupus	,,	ʒj.	— ʒii.
Scillæ tinctura	,,	♏x.	— ʒss.
Senegæ infusum	,,	℥j.	— ℥ii.
Senegæ tinctura	,,	ʒj.	— ʒii.
Tinctura tolutana	,,	♏xx.	— ♏xl.
Vinum antimoniale	,,	ʒss.	— ʒj.

Expectorants in the form of Draughts.

. ℞. Ammon. carbonatis gr.
Spiritûs chloroformi ʒss.
Decocti senegæ ℥iss. M.

. ℞. Balsami Peruviani ʒss.
Glycerini ʒj.
Mist. amygdalæ ℥iss.

. ℞. Ammoniæ carbonatis
Ammon. benzoatis ā gr. v.
Vini ipecacuanhæ ♏x.
Decocti senegæ ℥iss. M.

. ℞. Vini ipecacuanhæ ♏x.
Syrupi papaveris ʒj.
Spiritûs ammon. arom. ʒss.
Aquæ camphoræ ℥iss. M.

. ℞. Syrupi scillæ f ʒss.
Misturæ ammoniaci ℥iss. M.

. ℞. Balsami copaibæ ʒss.
Vitelli ovi ʒj.
Aquæ cinnamomi ℥iss.
Fiat emulsio.

222. ℞. Liquoris ammoniæ acetatis ʒiii.
Syrupi scillæ ʒi.
Decocti senegæ ℥j. M

223. ℞. Træ lobeliæ ætheresæ ʒss.
Tincturæ scillæ ʒss.
Aquæ camphoræ ℥iss. M.

224. ℞. Vini antimonialis ♏xl.
Liquoris ammon. acet. ʒj.
Oxymellis scillæ ʒj.
Aquæ pimentæ ℥j. M.

225. ℞. Vini ipecacuanhæ ♏xl.
Potassæ bicarbonatis gr. xx.
Aquæ ℥iss. M. (to be taken with a tablespoonful of lemon-juice.)

Expectorants in the form of Pills.

. ℞. Pilulæ scillæ co. gr. v.
Fiat Pilula.

227. ℞. Pil. ipecacuanhæ cum scillâ gr. v. Fiat pil

228. Antimonii tartarati gr. ⅛.
Pulv. ipecacuanhæ co. gr. viii.
Mucilaginis acaciæ gr.ii.
Fiant pilulæ duæ.

229. ℞ Pilulæ scillæ composit
Extracti conii āā gr.
Fiant pilulæ duæ.

---

14. DEMULCENTS.

1. Acaciæ gummi. Mucilago Acaciæ.
2. Amygdalæ (dulces). Pulvis amygdalæ compositus. Mist amygdalæ. Oleum amygdalæ. Oleum olivæ. Cetace Manna. Lac.
3. Amyli mucilago.
4. Decoctum hordei, cetrariæ, ulmi.
5. Glycyrrhizæ radix. Pulvis glycyrrhizæ. Extractum glycyrrh
6. Glycerinum.
7. Lini semen. Infusum lini.
8. Mel.
9. Rosæ caninæ confectio.
10. Syrupus floris aurantii, hemidesmi, mori, rhœados, tolutanus.
11. Tragacantha. Mucilago tragacanthæ. Pulvis tragacanthæ c positus.

Demulcents in the form of Draughts.

230. ℞. Cetacei gr. c.
Vitelli ovi ʒj.
Syrupi tolutani ʒj.
Aquæ cinnam. ℥j. M.

231. ℞. Mannæ optimæ gr. c.
Infusi lini Oii. M.

232. ℞. Mucilaginis tragacanthæ.
Lactis vaccini ana ℔j.
Sacchari ʒj. M.

233. ℞. Syrupi hemidesmi ʒ
Decocti hordei ℥xviii

234. ℞. Decocti cetrariæ ℥xv
Syrupi mori ℥ii.

235. ℞. Decocti ulmi ℥xviii.
Confec. rosæ caninæ
M.

236. ℞. Misturæ amygdalæ ℥
Glycerini ℥iv. M.

---

15. EMOLLIENTS.

1. Decoctum papaveris.
2. Cataplasma lini, C. fermenti.
3. Glycyrinum.
4. Oleum amygdalæ, lini, olivæ.
5. Unguentum cetacei, simplicis.
6. Cera alba.
7. Sapo, linimentum saponis, plastrum saponis.
8. Linimentum calcis.

---

16. LAXATIVES, APERIENTS, CATHARTICS, ENEMATA

1. Aloe Barbadensis . . . . dose gr. v. to gr. x
2. Aloes decoctum compositum . . . . . . „ ℥ss. — ℥ii.
3. „ Enema . . . . „ ℥x. — ℥xx

4.	Aloes extractum	Dose	gr. v.	to gr. x.
5.	,, extractum Barb. et Socot	,,	gr. v.	— gr. x.
6.	,, pilula	,,	gr. v.	— gr. x.
7.	Aloe Socotrina	,,	gr. v.	— gr. x.
8.	Aloes tinctura	,,	ʒj.	— ℥j.
9.	,, vinum	,,	ʒii.	— ʒvi.
10.	Amygdalæ oleum	,,	℥j.	— ℥ii.
11.	Cambogia	,,	gr. ii.	— gr. v.
12.	Colocynthis: extractum colocynthidis compositum	,,	gr. v.	— gr. x.
13.	Pilula colocynthidis composita			
14.	Pilula colocynthidis et hyoscyami			
15.	Crotonis oleum	,,	♏i.	— ♏iii.
16.	Elaterium	,,	gr. $\frac{1}{16}$	— gr. j.
17.	Extractum colocynthidis compositum	,,	gr. v.	— gr. x.
18.	Fel bovinum purificatum	,,	gr. v.	— gr. x.
19.	Fici pulpa	,,	℥ss.	— ℥j.
20.	Hydrargyrum: calomelas	,,	gr. j.	— gr. x.
21.	Hydrargyrum cum cretâ	,,	gr. j.	— gr. v.
22.	Jalapæ pulvis	,,	gr. v.	— gr. xx.
23.	Jalapæ extractum	,,	gr. v.	— gr. x.
24.	,, pulvis compositus (gr. v. in gr. xv.)	,,	gr. xv.	— gr. l.
25.	,, pulvis scammonii compositus (about gr. v. in gr. xv.)	,,	gr. x.	— gr. xx.
26.	,, resina	,,	gr. v.	— gr. x.
27.	,, tinctura	,,	ʒj.	— ʒii.
28.	Magnesia, et magnesia levis	,,	gr. xx.	— gr. l.
29.	Magnesiæ carbonas, et carbonas levis	,,	gr. xx.	— gr. l.
30.	Magnesiæ carbonatis liquor	,,	℥j.	— ℥ii.
31.	Magnesiæ sulphas	,,	gr. l.	— ℥ss.
32.	Magnesiæ sulphatis enema	,,	℥xvii.	
33.	Manna	,,	gr. l.	— ℥j.
34.	Pilula aloes et assafœtidæ	,,	gr. v.	— gr. x.
35.	Pilula aloes et myrrhæ	,,	gr. v.	— gr. x.
36.	Pilula calomelanos composita	,,	gr. v.	— gr. x.
37.	Pilula cambogiæ composita	,,	gr. v.	— gr. x.
38.	Pilula hydrargyri	,,	gr. v.	— gr. x.
39.	Pilula rhei composita	,,	gr. v.	— gr. x.
40.	Podophylli pulvis	,,	gr. x.	— gr. xx.
41.	Podophylli resina	,,	gr. ¼	— gr. j.
42.	Potassæ sulphas	,,	gr. xv.	— gr. lx.
43.	Potassæ tartras	,,	gr. c.	— gr. cc.
44.	Potassæ tartras acida	,,	gr. l.	— gr. c.
45.	Pruni pulpa	,,	℥ss.	— ℥j.
46.	Rhamni succus	,,	ʒss.	— ʒj.
47.	Rhamni syrupus	,,	ʒj.	— ʒiv.
48.	Rhei extractum	,,	gr. x.	— gr. xx.
49.	Rhei infusum	,,	℥j.	— ℥iv.
50.	Rhei pilula composita	,,	gr. v.	— gr. x.
51.	Rhei pulvis	,,	gr. xv.	— gr. l.

52. Rhei pulvis compositus	dose	gr. xxx	to gr. c
53. Rhei syrupus	,,	ʒj.	— ʒiv.
54. Rhei tinctura	,,	ʒii.	— ℥j.
55. Ricini oleum	,,	ʒii.	— ℥j.
56. Scammoniæ radicis pulvis	,,	gr. x.	— gr. x
57. Scammoniæ resina	,,	gr. v.	— gr. x.
58. Scammonii confectio	,,	gr. xx.	— gr. l.
59. ,, mistura	,,	℥j.	— ℥ii.
60. ,, pulvis compositus (gr. iv. in gr. viii.)	,,	gr. x.	— gr. x
61. ——— extractum colocynthidis compositum	,,	gr. v.	— gr. x.
62. ——— pilula colocynthidis composita	,,	gr. v.	— gr. x.
63. ——— pilula colocynthidis, et hyoscyami	,,	gr. v.	— gr. x.
64. Scammonium	,,	gr. v.	— gr. x.
65. Senna Alexandrina, et Indica			
66. Sennæ confectio	,,	gr. l.	— ccc.
67. Sennæ infusum	,,	℥j.	— ℥ii.
68. Sennæ syrupus	,,	ʒj.	— ʒiv.
69. Sennæ tinctura	,,	ʒj.	— ʒiv.
70. Sodæ et potassæ tartras	,,	gr. c.	— ℥ss.
71. Sodæ sulphas	,,	gr. cc.	— ℥j.
72. Sodii chloridum	,,	gr. c.	— ℥ss.
73. Sulphur, præcipitatum et sublimatum	,,	gr. cc.	— ℥ss.
74. Terebinthinæ enema	,,	℥xvi.	
75. Terebinthinæ oleum	,,	℥ss.	— ℥ii.

Laxatives, Aperients, Cathartics, in the form of Draught.

237. ℞. Potassæ tartratis gr. c.
Decocti aloes comp. f℥iss.
M.

238. ℞. Olei crotonis ♏i.
Olei ricini f ℥j. Ft. h.

239. ℞. Magnesiæ sulphatis gr. cc.
Mannæ gr. l.
Infusi sennæ ℥iss. Ft. h.

240. ℞. Pulveris rhei gr. x.
Potassæ tartratis ʒss.
Infusi sennæ ℥iss.
Tincturæ sennæ ʒii. Ft. h.

241. ℞. Sodæ et potassæ tart. ʒss.
Aq. menthæ pip. ℥iss. Ft. h.

242. ℞. Magnesiæ carbonatis gr. x.
Magnesiæ sulphatis gr. l.
Tincturæ zingiberis ♏xv.
Aquæ menthæ piperitæ ℥iss. Fiat haustus.

243. ℞. Tincturæ cardamomi c
positæ ℥ii.
Magnesiæ carbonatis gr
Infusi rhei ℥iss. Ft.

244. ℞. Infusi rosæ acidi ℥iss.
Magnesiæ sulphatis gr
Syrupi rosæ ʒj. M.

245. ℞. Potassæ tartratis gr. c.
Mannæ gr. lx.
Aquæ pimentæ ℥iss.

246. ℞. Olei ricini,
Olei terebinthinæ,
Mucil. acaciæ āā ℥ss.

247. ℞. Tincturæ sennæ ʒii.
Vini aloes ʒii.
Syrupi zingiberis ʒj.
Aq. menthæ pip. ʒiss.

248. ℞. Olei ricini ℥ss.
Vitelli ovi unius.
Aquæ carui ℥j.

Laxatives, Aperients, Cathartics, in the form of Pills.

9. ℞. Calomelanos gr. j.
Pil. coloc. et hyos. gr. viii.
Olei anethi ♏i.
In pilulas duas divide.

0. ℞. Extr. colocynth. comp.
Calomelanos āā gr. v.
Fiant pilulæ duæ.

1. ℞. Resinæ scammoniæ,
Calomelanos,
Ext. colocynthidis comp.
āā gr. iiss
Olei carui quantum suf.
Fiant pilulæ duæ.

252. ℞. Olei crotonis ♏i.
Pulv. aloes q. s. M. Ft. pil.

253. ℞. Resinæ podophylli gr. ss.
Extr. colocynthidis comp. gr. v.
Fiat pilula.

254. Pilulæ hydargyri gr. iii.
Extracti colocynthidis compositi gr. vii.
M. Ft. pil. ii.

Laxatives, &c., in the form of Powder.

5. ℞. Pulv. jalapæ compositi ʒss.
Calomelanos gr. iii.
Ft. pulv.

56. ℞. Pulv. rhei gr. xx.
Potassæ bitartratis gr. l.
Pulv. aromatici gr. v. M.

257. ℞. Pulv. rhei gr. xx.
Calomelanos gr. iii.
Pulveris aromatici gr. v.
M.

258. ℞. Pulv. scammoniæ co. gr. x
Calomelanos gr. v. M.

Laxatives, &c., in the form of Electuary.

59. ℞. Confectio sulphuris gr. c.
Pulveris cinnam. co. gr. xx. M.

260. ℞. Confec. scammonii gr. xxx.
Resinæ podophylli gr. ¼
M.

---

17. PURGATIVE ENEMATA.

. Enema aloes.
. Enema magnesiæ sulphatis.
3. Enema terebinthinæ.
4. Enema assafœtidæ.

61. ℞. Infusi anthemidis f ℥x.
Sodæ sulphatis ℥j. M.

62. ℞. Ext. colocynthidis co. gr. xl.
Infusi sennæ ℥xii. M.

263. ℞. Decocti hordei ℥x.
Ovi vitelli unius.
Olei ricini ℥j. Ft. enema.

264. ℞. Sodii chloridi ℥ii.
Decocti hordei Oi. Ft E.

---

18. DIURETICS.

(*a.*) *Saline.*

1. Ammoniæ acetatis liquor . . . . dose ʒii. to ʒvi.
2. Ammoniæ benzoas . . . . „ gr. x. — gr. xx.
3. Lithiæ carbonas . . . . „ gr. iii. — gr. viii.

4.	Lithiæ citras	dose gr. v.	to gr
5.	Potassæ carbonas	,, gr. x.	— gr
6.	Potassæ acetas	,, gr. x.	— }
7.	Potassæ bicarbonas	,, gr. x.	—
8.	Potassæ chloras	,, gr. x.	— gr.
9.	Potassæ citras	,, gr. xxx.	— gr.
10.	Potassæ liquor	,, ♏xv.	— ♏
11.	Potassæ nitras	,, gr. x.	— gr.
12.	Potassæ tartras acida	,, gr. xxx.	— gr.
13.	Potassæ tartras	,, gr. xxx.	— gr.
14.	Sodæ liquor	,, ♏xv.	— ♏l
15.	Sodæ acetas	,, gr. xxx.	— gr.
16.	Sodæ bicarbonas	,, gr. x.	— gr.
17.	Sodæ citro-tartras effervescens	,, gr. lx.	— gr.
18.	Sodæ et potassæ tartras (S. tartarata)	,, gr. c.	— gr.

(*b.*) *Vegetable.*

19.	Ætheris nitrosi spiritus.	dose ʒss.	— ʒii
20.	Armoraciæ spiritus compositus	,, ʒj.	— ʒii.
21.	Buchu infusum	,, f ℥j.	— f ℥
22.	Buchu tinctura	,, ʒss.	— ʒii.
23.	Copaiba	,, ♏xx.	— ʒss
24.	Copaibæ oleum	,, ♏iii.	— ♏x
25.	Cubebæ pulvis	,, gr. xx.	— gr.
26.	Cubebæ oleum	,, ♏iii.	— ♏x
27.	Digitalinum	,, gr. $\frac{1}{60}$	— gr.
28.	Digitalis pulvis	,, gr. $\frac{1}{2}$	— gr.
29.	Digitalis infusum	,, ʒss.	— ʒiv
30.	Digitalis tinctura	,, ♏x.	— ♏x
31.	Juniperi oleum	,, ♏iv.	— ♏v
32.	Juniperi spiritus	,, ʒiss.	— ʒi.
33.	Pareiræ decoctum	,, ℥j.	— ℥ii.
34.	,, extractum liquidum	,, ʒss.	— ʒii.
35.	Sabinæ pulvis	,, gr. iv.	— gr.
36.	Sabinæ oleum	,, ♏i.	— ♏ii
37.	Sabinæ tinctura	,, ♏xx.	— ʒi.
38.	Sapo duris et mollis	,, gr. x.	— gr.
39.	Scillæ pulvis	,, gr. v.	— gr.
40.	Scillæ syrupus	,, ʒj.	— ʒii.
41.	Scillæ tinctura	,, ♏xv.	— ʒj.
42.	Scillæ pilula composita	,, gr. v.	— gr.
43.	Scoparii succus	,, ʒss.	— ʒii.
44.	Senegæ decoctum	,, ℥j.	— ℥ii.
45.	Taraxaci decoctum	,, ℥j.	— ℥ii.
46.	Taraxaci extractum	,, gr. x.	— gr.
47.	Taraxaci succus	,, ʒii.	— ℥i.
48.	Terebinthina Canadensis	,, gr. x.	— gr.
49.	Terebinthinæ oleum	,, ʒss.	— ʒii.
50.	Terebinthinæ confectio	,, gr. lx.	— gr.
51.	Uvæ ursi infusum	,, ℥j.	— ℥ii.

(c.) *Animal.*

antharidis tinctura . . . . . dose ♏v. to ♏xx.

Diuretics in the form of Draught, &c.

℞. Ammoniæ benzoatis gr. x.
Ext. pareiræ liquidi ʒj.
Decocti pareiræ ℥iss. M.

℞. Lithiæ citratis gr. x.
Acidi citrici gr. xx.
Syrupi aurantii ʒss.
Aquæ f ℥ii. Solve.
be taken in a state of effer-
nce with gr. xiv. bicarbonate
la dissolved in f ℥ii. water.

℞. Potassæ acetatis gr. xl.
Infusi digitalis ʒii.
Sp. ætheris nitrosi ʒj.
Decocti taraxaci ℥iss. ft. H.

℞. Pot. tartratis acidæ ℥ss.
Corticis limonis, et saccharı, q. s.
Aquæ ferventis Oii.
(For a common drink).

269. ℞. Sodæ et potas. tart. gr. lx.
Spiritûs juniperi ʒj.
Succi scoparii ʒss.
Decocti taraxaci ℥iss. M.

270. ℞. Copaibæ ʒss.
Vitelli ovi q. s.
Sacchari ʒj.
Aquæ menthæ virid. ʒiss.
M. fiat emulsio.

271. ℞. Infusi buchu ℥iss.
Spiritûs juniperi co. ʒj.

272. ℞. Taraxaci succi ℥j.

273. ℞. Tincturæ cantharidis ♏x.
Decocti pareiræ ℥iss. M.

274. ℞. Træ. seminis colchici ʒss.
Potassæ acetatis gr. lx.
Aquæ fœniculi ℥iss. M.

Diuretics in the form of Pill, Powder, &c.

℞. Pilulæ scillæ comp. gr. x.
Calomelanos gr. ¼
Olei juniperi ♏j.
Ft. pil. ii.

℞. Pulv. digitalis gr. j.—ii.
Hydrargyri pilulæ gr. ii.
Pilulæ scillæ co. gr. vi.
M. et in pilulas ii. divide.

℞. Digitalini gr. $\frac{1}{60}$.
Pulveris scillæ,
Extracti taraxaci ana gr. v.
Misce et ft. pil. ii.

℞. Potassæ nitratis gr. x.
Potassæ tart. acidæ gr. xx.
Fiat pulvis.

279. ℞. Olei cubebæ ♏xx.
Saponis duri gr. x.
Pulv. glycyrrh. q. s. ut fiant boli duo.

280. ℞. Terebinthinæ Canadensis gr. v.
Olei cubebæ ♏i.
Pulveris glycyrrhizæ q. s.
Fiat bolus.

281. ℞. Extracti taraxaci ℥ss.
Pulveris scillæ gr. xl.
Confec. terebinthinæ ℥ss.
Suc. taraxaci, quantum suf. ut fiat electuarium.

---

19. ANTHELMINTICS.

1. Calcis liquor (as an enema) . . dose ℥ii. to ℥iv.
2. Kusso infusum . . . . . . „ ℥iv. — ℥viii.
3. Filicis extractum liquidum . . „ ʒj. — ʒiii.

4. Filicis maris pulvis . . . . . dose gr. xx. to
5. Granati corticis decoctum . . ,, ℥ii. —
6. Granati corticis pulvis . . . . ,, gr. xx. —
7. Kamela . . . . ,, gr. xxx.—
8. Mucuna pruriens (*non-officinal*) ,, gr. xx. —
9. Pulvis scammonii compositus . ,, gr. v. —
10. Quassiæ infusum (as an enema). ,, ℥ii. —
11. Santoninum . . . . ,, gr. j. —
12. Terebinthinæ oleum . . . . . ,, ʒss. —

282. ℞. Olei terebinthinæ ʒj.
Decocti hordei ℥j. M. ft.h.

283. ℞. Mucunæ prurientis gr. x.
Theriacæ ʒj. M.

284. ℞. Extracti filicis liquidi ʒj.

Pulv. tragacant
Aq. menthæ pi

285. ℞. Santonini gr. ii
Pulv. scammo
gr. viii. Fiat

20. EMMENAGOGUES.

1. Rutæ oleum, dose ♏ii. to mv.
2. Sabinæ oleum, dose ♏i. to ♏v.
3. Sabinæ tincturæ, dos
4. Chalybeate tonics.

286. ℞. Ferri et ammon. cit. gr. x.
Tincturæ sabinæ ♏xx.
Aquæ cinnamomi ℥iss. M.

287. ℞. Olei rutæ ♏iv.
Pulveris myrrhæ gr. iv.

Pulveris aloes
Fiant pil. duæ.

288. ℞. Olei sabinæ ♏i
Saponis q. s.
Fiant pil. duæ.

21. ANTACIDS.

1. Ammoniæ liquor, acetas, carbonas, benzoas, phosphas.
2. Ammoniæ spiritus aromaticus.
3. Guaiaci tinctura ammoniata.
4. Valerianæ tinctura ammoniata.
5. Calcis liquor, liquor saccharatus; calcis carbonas pra
,, ,, chlorinata; creta præparata.
6. Cretæ mistura, pulvis aromaticus, pulvis aromaticus
7. Lithiæ carbonas, citras.
8. Potassæ liquor; acetas; carbonas; bicarbonas; citras;
tartras acida.
9. Sodæ liquor; carbonas; carbonas exsiccata; bicarbon
et potassæ tartras; citro-tartras effervescens.
10. Magnesia; magnesia levis; magnesiæ carbonas; carbo
11. Pulvis rhei compositus.
12. Sapo mollis, durus.

(For Formulæ, see Diuretics, &c.)

22. ANTISEPTICS AND DISINFECTANTS.

1. Acidum aceticum.
2. Acidum carbolicum.
3. Acidi carbolici glycerinum.
4. Carbo.
5. Carbo animalis.
6. Cataplasma carbonis, fermenti, sodæ chlorinatæ.
7. Kreasotum.
8. Liquor calcis chlorinatæ.
9. Liquor chlorinii.
10. Liquor sodæ chlorinatæ.
11. Pix liquida.
12. Potassæ permanganatis liquor.
13. Zinci chloridum.

---

23. ALTERATIVES AND THEIR DOSES.

1. Acidum nitro-hydrochloricum dilutum; acidum arseniosum $\frac{1}{30}$ to $\frac{1}{16}$ gr.; liquor arsenicalis ♏ii. to ♏ x.; liquor arsenici hydrochloricus ♏ii.—♏viii.; liquor sodæ arseniatis ♏v. to ♏x.
2. Antimonium sulphuratum; antimonium tartaratum; vinum antimoniale (gr. ¼ in ℥j.); antimonii oxidum gr. j. to gr. v.; pulvis antimonialis gr. v. to gr. x.
3. Brominium dose ½ to gr. ii. Potassii brcmidi gr. iii. to ʒj.
4. Dulcamaræ infusum ℥j.—℥ii. (inert).
5. Ferri arsenias gr. $\frac{1}{16}$—gr. ½.
6. Ferri iodidum gr. j. to gr. x.; syrupus ferri iodidi (gr. ivss. in ʒj.); pilula ferri iodidi gr. v. to gr. x.
7. Hemidesmi syrupus ʒj. (inert).
8. Hydrargyrum cum cretâ gr. iii. to gr. viii.; H. perchloridum gr. $\frac{1}{16}$ to gr. ¼.
9. Hydrargyri iodidum rubrum gr. $\frac{1}{16}$ to gr. ¼;—iodidum viride gr. j. to gr. iii.;—oxidum rubrum; pilula; linimentum; unguentum; unguentum hydrargyri ammoniati; unguentum hydrargyri iodidi rubri; unguentum hydrargyri nitratis; unguentum hydrargyri oxidi rubri; hydrargyri emplastrum; emplastrum ammoniaci cum hydrargyro. Calomelas gr. ¼ to gr. ii., pilula calomelanos composita, unguentum calomelanos.
10. Iodinii tinctura ♏v. to ♏xxx.; linimentum; unguentum compositum.
11. Potassii iodidi gr. j. to gr. x.; emplastrum; unguentum; unguentum iodinii compositum; tinctura iodinii; linimentum iodinii.
12. Morrhuæ oleum.
13. Sarsæ decoctum compositum; extractum liquidum.

Alteratives in the form of Draught.

289. ℞. Liq. hydrarg. perchlor. ʒj.
Tinct. chloroformi co. ʒss.
Aquæ menthæ pip. ℥iss.
M.

290. ℞. Potassii iodidi gr. v.
Infusi aurantii ℥iss.
Ft. h.

291. ℞. Syrupi ferri iodidi ʒj.
Decocti sarsæ co. ℥iss.
Ft. h.

292. ℞. Liquoris arsenicalis ♏v.
Tinct. chlorof. co. ♏xx.
Infusi aurantii ℥iss.
Ft. h.

293. ℞. Liq. sodæ arseniatis ♏v.
Sodæ bicarbonatis gr. lx.
Aq. pimentæ ℥iss. Ft. h.

294. ℞. Liq. arsenici
chlorici ♏iii.
Aquæ anethi ℥iss.

Alteratives in the form of Pill and Powder.

295. ℞. Calomelanos gr. iii.
Pil. saponis comp. gr. xviii.
Fiant pil. xii.

296. ℞. Hydrarg. iodidi rubri gr. j.
Extracti sarsæ ʒj.
Fiant pil. xii.

297. ℞. Hydrarg. c. cretâ gr. xx.
Antimonii tartarati gr. j.
Sacchari gr. lx.
Fiant pulveres decem.

298. ℞. Calomelanos gr. iii
Pulv. opii gr. j.
Pulv. glycyrrhizæ
Fiant pulveres decem
for a dose.)

299. ℞. Hydrarg. c. cretâ
Sacchari albi gr. v
Fiat pulvis.

300. ℞. Ferri arseniatis gr
Pulv. cinnam. co.
Fiant pulveres decem

Alteratives in the form of Bath.

301. ℞. Potassii sulphidi ℥x.
Aquæ calidæ cx.
Fiat balneum.

GLOSSARIAL INDEX.

Abscess. (*Abscessus, ûs m.*, fr. *abscedo*, to escape), 62.
Acne. Pimple (ἄχνη, scurf), 630.
Ægophony. (αἴξ, a goat, φωνὴ, the voice), 158, 469.
Amaurosis, *is, f.* Blindness (ἀμαυρὸς, obscure), 601.
Amblyopia, *æ, f.* Impaired vision (ἀμβλὺς, weak, ὤψ, the eye) 392.
Amenorrhœa, *æ, f.* (α, priv., μὴν, a month, ῥέω, to flow), 561.
Anæmia, *æ, f.* Want of blood (α, priv., αἷμα , blood), 255.
Anæsthesia, *æ, f.* (α, priv., α αἴσθησις, sensation), 381.
Anasarca, *æ, f.* (ἀνὰ, through, σάρξ, the flesh), 268.
Aneurism. (ἀνευρύνω, to dilate), 437.
Angina, *æ. f.* Choking (ἄγχω, to throttle), 420.
Anorexia, *æ,* f. (α, not ὄρεξις, an appetite), want of appetite, 190.
Anuria, *æ, f.* Suppression of urine (α, priv., οὐρέω, to pass urine), 554.
Aphonia, *æ, f.* Loss of voice (α, priv., φωνὴ, sound), 446.
Aphtha, *æ, f.* Thrush (ἀφθὰ, fr. ἅπτω, to inflame), 483.
Apnœa, *æ, f.* Breathlessness (α, priv., πνέω, to breathe), 31.
Apoplexia, *æ, f.* (ἀποπληξία, fr. ἀποπλήσσω, to strike down), 73, 367.
Arachnitis, *ĭdis, f.* (ἀράχνη, a spider's web, and *itis*), 359.
Ascaris, *ĭdis, f.* (ἀσκαρὶς, fr. ἀσκαρίζω, to jump), 648.
Ascites, *æ, m.* Dropsy of the belly (ἀσκίτης, fr. ἀσκὸς, a sack), 522.
Asphyxia. Apparent death (α, priv., σφύξις, the pulse), 31.
Asthenia. (α, priv., σθένος, strength), 30, 428.
Asthma, *ătis, n.* (ἄσθμα, fr. ἀσθμάζω, to gasp), 457.
Astigmatism, *Astigmatismus, i, m.* (fr. α, not στίγμα, a spot), 601.
Atavism. *Atavismus, i, m.* (*atăvus*, a grandfather), 4.
Atheroma, *ătis, n.* A morbid deposit (ἀθάρη, porridge), 79, 436.
Atrophy. Wasting (α, priv., τροφὴ, nourishment), 77.

Bronchitis, *ĭdis, f.* (βρόγχος, the windpipe, *itis*), 453.
Bronchocele, *es, f.* βρόγχος, the windpipe, κήλη, a tumour), 492.
Bulimia, *æ, f.* (βοῦ, excess, λιμὸς, hunger), 34.

Cachexia, *æ, f.* Bad habit of body (κακὴ, bad, ἕξις, habit), 258.
Calculus, *i, m.* (Lat. *calculus*, a little stone), 531, 547.
Cancer, *cri, m.* and *n.* A malignant disease (*cancer*, a crab), 77.
Carcinoma, *atis, n.* Cancer (καρκῖνος, a crab), 83.
Carditis, *ĭdis, f.* (καρδία, the heart, and *itis*), 428.

Catalepsy, *Catalepsis.* (*κατάληψις, εως, ἡ,* fr. *καταλαμβάνω*, seize), 406.
Catamenia, *orum, pl, n.* (*κατὰ*, according to, *μὴν*, the month),
Catarrhus, *i. m.* A cold (*κατὰ*, down, *ῥέω*, to flow), 451.
Cephalalgia, *æ, f.* Headache (*κεφαλὴ*. the head, *ἄλγος*, pain),
Cheloidea, *æ, f.* A cutaneous disease (*χέλυς*, a tortoise, *εἶδος*, ness), 639.
Chloasma, *ătis, n.* (*χλοάζω*, to be green), 612.
Chlorosis, *is, f.* Green sickness (*χλωρὸς*, green), 258.
Cholera, *æ, f.* (*χολὴ*, bile, *ῥέω*, to flow), 516.
Chorea, *æ, f.* (*χορεία*, a dancing), 398.
Choroiditis, *ĭdis, f.* (*χόριον*, skin, *εἶδος*, likeness, and *itis*,) 592
Chronic, *Chronicus, a, um.* (*χρόνος*, time), 19.
Cirrhosis, *is f.* Hob-nail liver (*κιῤῥὸς ἁ ὀν*, tawny), 526.
Clonic, *Clonicus, a, um.* (*χλόνος*, commotion), 96.
Celica, *æ, f.* (*κῶλον*, the colon), 512.
Coma, *ătis, n.* Complete loss of sensation and voluntary mot (*κῶμα, ατος, τὸ*, deep sleep), 204.
Congestion. Fulness of blood (*congestio*, fr. *congero*, to heap up),
Corneitis, *ĭdis, f.*, and *Cornea, æ, f.* (*cornu*, a horn, *itis*), 588.
Cyanosis, *is, f.* Blue disease (*κύανος*, blue), 434.
Cystitis, *ĭdis, f.* (*κύστις*, a bladder, *itis*), 557.

Delirium, *i, n.* Wandering (*deliro*, to rave), 111.
Dermmycosis, *is, f.*, a contraction for dermato-mycosis. (Fr. *δέ ατος, τὸ*, the true skin, *μύκης*, a fungus), 615.
Diabetes, *is m.* (*διὰ*, through *βαίνω*, to pass), 554.
Diaphoretic, that which increases a flow of the sweat (*διαφορέ* dissipate, disperse), 680.
Diarrhœa, *æ*, f. (*διὰ*, through *ῥέω*, to flow), 234.
Diphtheria, *æ, f.* (*διφθερόω*, to cover with skin), 322.
Diuretic, that which increases the flow of urine (*δια οὗρον*, by of the urine),
Dropsy. (*ὕδρρωψ*, fr. *ὕδωρ*, water), 268.
Dysentery, *Dysenteria, æ, f.* (*δὺς*, with difficulty, *ἔντερον*, bowels), 506.
Dysmenorrhœa, *æ, f.* (*δὺς*, difficult, *μὴν*, a month, *ῥέω*, to f 562.
Dyspepsia, *æ, f.* (*δὺς*, difficult, *πέπτω*, to concoct), 497.
Dysphagia (*δὺς*, with difficulty, *φάγω*, to eat), 438.
Dysphonia, *æ, f.* (*δὺς*, difficult, *φωνὴ*, voice), 490.
Dyspnœa, *æ, f.* (*δὺς*, with difficulty, *πνέω*, to breathe), 184.
Dysuria, *æ, f.* (*δὺς*, with difficulty, *οὐρέω*, to pass urine), 559.

Ecthyma, *ătis, n.* Cutaneous pustules (*ἐκθύω*, to break out), 62
Eczema, *atis, n.* Running scab (*ἐκζέω*, to boil up), 623.
Electrode. (*ἤλεκτρον*, amber, *ὁδὸς*, a way), 402.
Elephantiasis, *is, f.* (*ἐλεφαντίασις*, fr. *ἐλέφας*, an elephant),
Embolism, *Embolismus, i, m.* (fr. *ἐμβάλλω*, to drive in), 78.
Emphysema, *ătis, n.* (*ἐμφύσημα*, fr. *ἐμφυσάω*, to inflate), 460.

hotonos, *adj.* (ἔμπροσθεν, forwards, τείνω, to bend), bent vards, 400.

ia, *ătis*, *n.* Pus (ἐν, within, πύον, pus), 478.

ory, *Emunctorium*, *i*, *n.* (fr. *emungo*, to carry off.)

litis, *ĭdis*, *f.* (ἐν, in κεφαλή, head, *itis*), 359.

igogue, that which excites a flow of the menses (ἐν, at, μήνη, month ; ἄγω, to induce), 688.

c. Indigenous (ἐν, among, δῆμος, a people ; or, (ἐν, in, δῆμος, district), 292, 550.

ditis, *ĭdis*, *f.* (ἔνδον, within, καρδία, the heart, *itis*), 427.

s, *ĭdis*, *f.* (ἔντερον, the bowels, itis), 405.

, *pl.*, *Entozoon*, *i*, *n.* (ἐντὸς, within, ζῶον, an animal), 435.

s, *is*, *f.* Incontinence of urine (ἐν in, οὐρέω, to pass urine), 558.

ĭdis, *f.* Freckles (ἐφηλὶς, fr. ἐπὶ and ἥλιος, the sun), 624.

ic. Prevalent (ἐπὶ, among, δῆμος, a people), 284.

mycosis, *is*, *f.*, contraction for epidermato-mycosis. (fr. δερμὶς, the cuticle, μύκης, a fungus), 612–4.

r. Falling sickness (ἐπιληψία ; ἐπιλαμβάνω, to seize upon),).

, *æ*, *f.* Glanders (*equus*, a horse), 337.

las, *ătis*, *n.* (ἐρυσίπελας, fr. ἐρύω, to draw, πέλας, near), 270.

na, *ătis*, *n.* Inflammatory blush (ἐρυθαίνω, to redden), 620.

mata, *pl*, *Exanthema*, *ătis*, *n.* (ἐξανθέω, to break out into spots), 304, 620.

la, *æ*, *f.* (dim. of *febris*), 262.

is, *f.* (*ferveo*, to be hot), 274.

sia, *æ*, *f.* The yaws (*framboise*, Fr., a raspberry), 638.

na, *æ*, *f.* (γάγγραινα, fr. γράω, to eat), 62.

gia, *æ*, *f.* Pain in the stomach (γαστὴρ, the stomach, ἄλγος, in), 498.

s, *ĭdis*, *f.* (γαστὴρ, the stomach, *itis*), 496.

ynia. (γαστὴρ, the stomach, ὀδύνη, pain, *itis*), 498.

nteritis, *ĭdis*, *f.* (γαστὴρ, the stomach, ἔντερον, the bowels,), 515.

tis, *idis*, *f.* (*gingivæ*, the gums, *itis*), 487.

na, *atis*, *n.* (fr. γλαυκὸς sea-green), 599.

s, *ĭdis*, *f.* (γλῶσσα, the tongue, *itis*), 488.

œa, *æ*, *f.* (γονὴ, seed, ῥέω, to flow), 575.

emesis, *is*, *f.* (αἷμα, blood, ἔμεσις, vomiting), 495.

ocele. (αἷμα, blood, κήλη, a tumour), 571.

uria, *æ*, *f.* Bloody urine (αἷμα, blood, οὐρέω, to void urine), 3, 548.

tysis, *is*, *f.* Spitting of blood (αἷμα, blood, πτύσις, spitting), 7, 467.

rhage. Bleeding (αἷμα, blood, ῥήγνυμι, to burst forth), 266.

rhoides. Hæmorrhois, *idis*, *f.* (αἷμα, blood, ῥέω, to flow), 514.

A remittent fever (ἑκτικὸς, habitual), 327.

[illegible]

[illegible] hardening violent action, [illegible] inflammation, 53.

[illegible] pregnancy, [illegible] a covering

[illegible] to [illegible] 450.

Laryngitis, idis, f. (λάρυγξ, the larynx, *itis*), 443.

[illegible] λέπρος, scaly, 634.

Leucocythaemia, ae, f. (λευκός, white, κύτος, a cell, and αἷμα, bloo

Leucorrhoea, ae, f. The whites (λευκός, white, ῥέω, to flow),

Lichen, enis, m. A cutaneous disease (λειχήν, a lichen), 632.

Lumbago, inis, f. (*lumbus*, the loins), 352.

Lumbricus, i, m. (*Ascaris lumbricoides*) round worm (*lubric*
ery), 647.

Lupus, *i, m.* (*lupus*, a wolf), 643.

nia, æ, f. (μαίνομαι, to be furious), 113, 403.
rasmus, i, m. Atrophy (μαραίνω, to wither), 294.
læna, æ, f. Hæmorrhage from the bowels (μέλαινα, black), 509.
lancholia, æ, f. (μέλαινα, black, χολὴ, bile), 114, 415.
lanosis, is, f. A morbid product of a black colour (μέλας, μέλανος, black), 83.
lasma, ătis, n. (Fr. μέλας, black), 261.
ningitis, ĭdis, f. (μῆνιγξ, a membrane, itis), 359.
norrhagia, æ, f. Flooding (μὴν, a month, ῥήγνυμι, to burst forth), 563.
ntagra, æ, f. (mentum, the chin, ἄγρα, seizure), 616.
etritis, ĭdis, f. Inflammation of the womb (μήτρα, the womb, itis), 333, 565.
liaria, æ, f. Miliary fever (milium, a millet seed), 626.
imōsis, is, f. (μῖμος, a mimic), 261.
ollities, ei, f. Softening (mollis, soft), 344.
olluscum, i, n. (molluscum, the bunch of the tree acer), 638.
yelitis, ĭdis, f. Inflammation of the spinal cord (μυελὸς, marrow, itis), 373.
yopia, æ, f. Near sight (μύω, to wink, ὤψ, ὠπὸς, ἡ, the eye), 602.

arcotic, narcōticus, a, um. (ναρκόω, to stupefy), 241.
ephritis, ĭdis, f. (νεφρὸς, the kidney, itis), 539.
euralgia, æ, f. (νεῦρον, a nerve, ἄλγος, pain), 377.
oma, æ, f. A corroding sore (νομὴ, ῆς, ἡ, spreading of fire), 486.
oseræsthesia. Morbid sensation (νοσηρὸς, unhealthy, αἴσθησις, sensation), 96.
ystagmus. Involuntary movements of the eyeball. (νυστάζω, to nod), 392.

Œdēma, ătis, n. (οἰδέω, to swell), 61–268.
Œsophagitis, ĭdis, f. (οἴσω, to carry, φάγω, to eat, itis), 493.
Oophoritis, Oŏphorum, i, n., an ovary (ᾠὸν, an egg, φέρω, to bear, itis), 573.
Ophthalmia, æ, f. Inflammation of the eye (ὀφθαλμὸς, the eye), 583.
Opisthotonos, adj. (ὄπισθε, at the back, τείνω, to bend), bent backwards, 400.
Osteo-malacia, æ, f. (ὀστέον, a bone, μαλακία, softness), 344.
Otitis, ĭdis, f. (οὖς, ὠτὸς, the ear, itis), 602.

Palpitatio, ōnis, f. (palpito, to throb), 418.
Paracentesis, is, f. Tapping (παρὰ, through, κεντέω, to pierce), 479.
Paralysis, is, f. Palsy (παραλύω, to relax), 382–7.
Paraplegia, æ, f. Palsy of the lower half of the body (παραπλήσσω, to strike), 384.
Parotitis, ĭdis, f. (παρὰ, near, ὠτὸς, of the ear), 491.
Pellagra, æ, f. (pellis agria, wild skin; or φελλὸς, the bark of the cork-tree, and ἄγριος, wild), 610.
Pemphigus, i. m. (πέμφιγος, of a small blister), 627.
Pericarditis, ĭdis, f. (περὶ, around, καρδία, the heart, itis), 423.

Peritonitis, *ĭdis*, *f*. (*περιτόναιον*, fr. *περὶ*, around, *τείνω*, to exten *itis*), 520.

Pertussis, *is*, *f*. Whooping-cough, (*pertussis*, a severe cough), 46

Pestis, *is*, *f*. The plague (Lat. *pestis*), 325.

Pĕtĕchiæ, *a*, *æ*, *f*. (*pĕtĕchio*, a fleabite), small purple spots, 194

Phlebitis, *ĭdis*, *f*. Inflammation of the veins (*φλὲψ*, *φλεβὸς*, a ve 440.

Phlegmasia, *æ*, *f*. (*φλέγμα*, a burning. fr. *φλέγω*, to burn), 441

Phlegmon, *Phlegmŏnē*, *es*, *f*. (fr. *φλέγω*, to burn), 62.

Phlogosis, *is*, *f*. (*φλόγωσις*, a burning, *φλογόω*, to inflame), 26

Phrenitis, *idis*, *f*. (*φρὴν*, *φρενὸς*, the mind, *itis*), 359.

Phthisis, *is*, *f*. Consumption (*φθίσις*, fr. *φθίω*, to consume), 469.

Pityriasis, *is*, *f*. Dandriff (*πίτυρον*, bran), 635.

Plethora. Fulness of blood (*πληθώρα*, fulness), 254.

Pleuritis, *ĭdis*, *f*. Inflammation of the pleura (*πλευρὰ*, the side),

Pleurodynia. (*πλευρὰ*, the side, *ὀδύνη*, pain), 351.

Pleurosthotonos, *adj*. (*πλευρόθεν*, from one side, *τείνω*, to be bent sideways, 400.

Pneumonia, *æ*, *f*. Inflammation of the lungs (*πνεύμων*, the lung),

Pneumothorax, *ācis*, *f*. Air in the pleura (*πνεῦμα*, air, *θώραξ*, chest), 480.

Podagra, *æ*, *f*. Gout (*ποδὸς*, of a foot, *ἄγρα*, seizure), 353.

Polyæmia, *æ*, *f*. (*πολὺς*, much, *αἷμα*, blood), 254.

Polypus, *i*, *m*. (*πολὺς*, many, *πους*, a foot), 569.

Porrigo, *ĭnis*, *m*. and *f*. (*porrum*, a leak), 617,

Prurigo, *ĭnis*, *f*., Pruritus. (*prurigo*, itching, *prurio*, to itch),

Psora, *æ*, *f*. The itch (*ψώρα*), 608.

Psoriasis, *is*, *f*. Dry scall (*ψώρα*, the itch), 634.

Ptosis, *is*, *f*. (fr. *πτόω*, to fall), 389.

Puerperal. (*pucr*, a boy, *pario*, to bring forth), 331.

Purpura, *æ*, *f*. Scurvy (*purpura*, a shell-fish yielding a purple d 345.

Pyæmia, *æ*, *f*. (*πύον*, pus, *αἷμα*, blood), 328, 439.

Pyogenic. (*pyogenicus*, *a*, *um*, fr. *πύον*, pus, *γεννάω*, to form),

Pyrexia, *æ*, *f*. Fever, (*πύρεξις*, fr. *πῦρ*; *ἔχω*, to hold), 274.

Pyrosis, *is*, *f*. Water-brash (*πύρωσις*, burning), 503.

Quinsy. (*cynanche*, fr. *κύων*, a dog, *ἄγχω*, to strangle), 489.

Rachitis, *ĭdis*, *f*. Rickets (*ῥάχις*, the back), 342.

Retinitis, *ĭdis*, *f*. Inflammation of the retina (*rete*, a net, and *itis*),

Rheumatism, *Rheumatismus*, *i*, *m*. (fr. *ῥεῦμα*, a fluxion), 348.

Rubeola, *æ*, *f*. Measles (*rubeo*, to be red), 313.

Rupia, *æ*, *f*. A cutaneous disease (*ῥύπος*, filth), 628.

Scabies, *ei*, *f*. The itch (*scabies*, fr. *scabo*, to scratch), 608.

Scarlatina, *adj*., *us*, *a*, *um*, scarlet. Febris understood, 316.

Sciatica, *æ*, *f*. Pain in the hip (*ἰσχιὰς*, fr. *ἰσχίον*, the hip), 380.

Scirrhus, *i*, *m*. Hard cancer (*σκίῤῥος*, *ου*, *ὁ*, fr. *σκίρος*, bit o marble), 77.

Sclerotitis, *ĭdis*, *f.* (σκληρὸς, hard, and *itis*), 587.
Scorbutus, *i*, *m.* Scurvy (Lat. *scorbutus*), 347.
Scrofula, *æ*, *f.* King's evil (*scrofula*, a little pig), 3, 340.
Scybala, *plur.*, hard fæces. (σκύβαλον, ου, τὸ, dung), 510–11.
Septicæmia, *æ*, *f.* (fr. σήπω, to putrify, αἷμα, the blood), 329.
Spermatorrhœa, *æ*, *f.* (σπέρμα, seed, ῥέω, to flow), 581.
Splenitis, *ĭdis*, *f.* Inflammation of the spleen (σπλὴν, the spleen, *itis*), 537.
Staphyloma, *atis*, *n.* A protrusion (σταφυλή, ῆς, ἡ, a grape), 597.
Stomatitis, *ĭdis*, *f.* Inflammation of the mouth (στόμα, the mouth, *itis*), 482.
Strabismus, squinting. (στρέφω, to turn aside), 387.
Stridulus, *a*, *um.* Creaking, 450.
Struma, *pl.*, *us*, *i*, *m.* King's evil (στρῶμα, a heaping up), 3, 340.
Sycosis, *is*, *f.* Chin-welk (συκόω, to convert into a fig), 616, 631.
Syncope, *es*, *f.* Fainting (συγκόπτω, to cut down), 239, 421.
Syphilis, *ĭdis*, *f.* (fr. σὺν, together, φιλέω, to love), 488.

Tabes (*is*, *f.*) mesenterica. (*tabes*, a consumption, μεσεντέριον, the mesentery) 522.
Tænia, *æ*, f. Tape-worm (*tænia*, a riband, from τείνω, to stretch), 651.
Tenesmus, or os, *i*, *m.* Straining (τείνω, to strain, τεινεσμὸς), 514.
Tetanus, *i*, *m.* Locked jaw (τείνω, to stretch), 400.
Thrombosis, *is*, *f.* (fr. θρόμβος, a clot of blood), 78, 435.
Tic-douloureux. (Fr. *tic*, a convulsive motion, *douloureux*, painful), 378.
Tonic, *tonicus*, *a*, *um.* (fr. τείνω, to tighten), 240.
Tonsillitis, *ĭdis*, *f.* (*tondeo*, to clip ? and *itis*), 483.
Tormina, *en*, *ĭnis*, *n.* (fr. *torqueo*, to rack), griping pains, 513.
Tracheitis, *ĭdis*, *f.* (τραχεῖα ἀρτηρία, rough artery, *itis*), 449.
Trismus, *i*, *m.* Locked jaw (τρισμὸς, fr. τρίζω, to gnash the teeth, 400.
Tympanites, *æ*, *m.* Drum-belly (τυμπανοειδὴς, like a drum), 514.
Typhoid. (*typhus*, and εἶδος, like), 292.
Typhous. (*typhosus*, pertaining to typhus), 286.
Typhus, *i*, *m.* (τυφὸς, fr. τυφόω, to stupefy), 284.

Urticaria, *æ*, *f.* Nettle-rash (*urtica*, a nettle), 621.

Vaccina, *æ*, *f.* Cow-pox (*vaccinus*, belonging to a cow), 311.
Varicella, *æ*, *f.* Chicken-pox (dim. of *varus*, a spot), 311.
Variola, *æ*, *f.* Small-pox (dim. of *varus*, a spot), 304.
Varioloid. (variola, small-pox, εἶδος, like), 307.
Vibices, *vibex*, *ĭcis*, *f.* Purple blotches of the skin, 293.

Zymotic. Contagious and infectious diseases (ζύμωσις, fermentation, fr. ζυμόω, to ferment). An inappropriate term, 20.

INDEX.

Abdomen, dropsy of, 522
„ examination of, 138
Abscess, 63
Absence of mind, 101
Absorption, physiology of, 69
„ remedies which promote, 70, 245
Abstraction, 101
Acarus folliculorum, 609
„ scabiei, 609
Achorion Schönleinii, 617
Acne, 630
Addison's disease, 261
Ægophony, 158, 469
Age, its influence on disease, 6
„ „ mortality, 7
Ague, 275
Air, change of, 211, 131
Air and light, 211
„ impure, as a cause of disease, 14
„ in the chest, 480
Albumin, 38
„ in urine, 133
„ estimation of, 133
Alcoholism, 416
Aleppo button, 640
Alopecia, 644
Alopecia areata, 613
Alteratives, or Catalytics, 236
„ doses and formulæ, 689
Amaurosis, 601
Amenorrhœa, 561
Amentia, 112
Amphoric resonance, 158
„ respiration, 157
Anæmia, 255
Anæsthesia, 381
„ facial, 381
Anasarca, 268
Aneurism of the aorta, 437
„ „ heart, 434
Aneurismal varix, 170
Angina pectoris, 420
Animal heat, 97
Anodynes, doses and formulæ, 668
„ and stimulants, formulæ, 671
Anorexia, 190
Antacids, formulæ, 688
Anthelmintics, doses and formulæ, 687
Anthrax, treatment of, 644
Antidotes for the poisons, 659
Antiseptics and disinfectants,
Antispasmodics, 668, 671
Antispasmodics, sedative, 668
„ stimulant and sed
Anuria, 554
Aorta, aneurism of, 437
Aperients, 234
„ doses and formulæ,
Aphonia, 446
Aphthæ, 483
Apoplexy, 367
Appetite, the, 190
Arachnitis, cerebral, 359
„ spinal, 374
Arcus senilis, 80
Areolar tissue, dropsy of, 268
Arteries, degeneration of, 436
„ functions of, 56
„ obliteration of, 435
Ascaris lumbricoides, 647
„ vermicularis, 648
Ascites, 522
Aspect of sick room, 210, 248
Asphyxia, 31
Assimilation, primary and secon
Association (of ideas), 101
Asthma, 457
Astigmatism, 601
Astringents, 233
„ doses and formul
Atavism, 4
Atheroma, 79, 436
Atmospheric impurities, influ
on health, 14
„ pressure, effect on
Atrophy, 72, 77
„ of the bones, 344
„ „ brain, 372
„ „ heart, 428
„ „ liver, 529
„ „ retina, 594
Attention, 110
Auscultation of the abdomen,
„ „ heart, 166,
„ „ lungs, 155
„ „ tympanum

Barracks, site and arrange
222
Bile, composition and use of, 3
„ in urine, tests of, 132

Bilharzia hæmatobia, 550
Biliary concretions, 531
„ congestion, 525
Bladder, inflammation of, 558
„ stone in, 547
„ diseases of, 557
„ irritable 560
Bleeder disease, 267
Bleeding from the bladder, 133, 548
„ „ bowels, 509
„ „ lungs, 197, 467
„ „ stomach, 495
Blindness, 601
Blood, cause of buffy coat in, 42
„ circulation of, 54
„ corpuscles, 42
„ crystals, 44
„ fulness of, 254
„ growth of, 41
„ letting, 242
„ loss of, effects of, 256
„ physiology and pathology of, 41
„ quantity of, 41
„ spitting, 197, 467
„ variation of, in disease, 45
„ vomiting of, 495
Bloody flux, 506
„ urine, 133, 548
Blue disease, 434
Boils, 644
Bones, softening of, 344
Bothriocephalus latus, 652
Bowels, disorders of, 192, 504
„ hæmorrhage from, 509
„ inflammation of, 292, 504-6
„ invagination of, 511
„ looseness of, 508
„ obstruction of, 510
„ perforation of, 294, 511
„ ulceration of, 294, 505
Brachialgia, 380
Brain, abscess of, 364
„ atrophy of, 372
„ circulation through, 72
„ diagnosis of diseases of, 363
„ fever, 284, 359
„ functions of, 97
„ hæmorrhage in, 367
„ hypertrophy of, 372
„ induration of, 372
„ inflammation of, 359
„ softening of, 371
„ structure of, 84
„ water on, 364
Breast pang, 420
Breath, odour of, 190
Bright's disease, 540-2
Bronchial polypi, 455
„ respiration, 156
„ tubes, dilatation of, 458
Bronchitis, 453
Bronchcele, 492
Bronchophony, 158
Bruit anæmic, 257
„ de diable, 167, 169, 257
Bruit de mouche, 169
„ de râpe, 167
„ de scie, 167
„ de soufflet, 167, 169, 418
„ musculaire, 169
Buboes, 287, 294
Buffy coat in blood, cause of, 42
Bulimia, 34

CACHEXIA, 258
Calculi, biliary, 531
„ urinary, 547
Cancer, 77, 488, 501, 569
Cancrum oris, 486
Capillaries, fatty degeneration of, 80
„ functions of, 57
„ influence of nerves on, 59, 90
„ „ of remedies on, 240
„ state of, in inflammation, 59
Carbon, elimination of, 47, 50, 51
Carbonic acid gas, quantity expired, 47
Carbuncle, 644
Carcinoma, 83
„ of the liver, 537
„ „ stomach, 501
„ „ uterus, 569
Carditis, 428
Carminatives, 233
Catalepsy, 406
Catalytic medicines, 236
Catamenia—Menses, 561
Cataract, 599
Catarrhus—Catarrh, 451
„ Vesicæ, 558
Catarrhus epidemicus, 452
Cathartics, 234
„ doses and formulæ, 682
Caustics,
Cænurus cerebralis, 410
Cell theory, 76
Cellulitis venenata, 335
Cephalalgia, 356
Cerebro-spinal meningitis, 291
Cerebral disease, diagnosis of, 363
Chalk-stones, 355
Chancre, 576
Cheek, gangrene of, 486
Cheloidea, 639
Chest, capacity of, 146
„ dropsy of, 461
„ examination of, 144
„ measurement of, 145
Chicken-pox, 313
Chionyphe Carteri, 619
Chloasma, 612
Chlorides, 130, 288
Chloroform, administration of, 422
„ resuscitation from, 422
Chlorosis, 258
Cholagogues, 234
Cholera, English, 515
„ Asiatic, 516
Chordee, 575
Chorea Sancti Viti, 398
Choreic hemiplegia, 382

Choroid, diseases of, 592 *et seq.*
Chyle, 40
,, in urine—Chyluria, 130, 552
Chyme, 40
Cicatrization, 63
Circulation, physiology and pathology of, 54. 193
,, cerebral, 72
,, hepatic, 72
,, influence of nerves on, 59, 91, 95
,, remedies which act on, 236
,, venous, 68, 194
Cirrhosis, 526
Cleanliness, 212
Clergyman's sore throat, 490
Climate, its influence on health, 9, 213
,, change of, 213
Clothing, 209
Cold, action of, 241, 247
,, common, 451
Colica—Colic, 512
,, pictonum, 513
Colitis, 506
Coma, 204
Comparison, 101
Conception (mental), 100
Condiments, 233
Congestion, 65, 266
,, cerebral, 73, 367
Conjunctiva, inflammation of, 583
Constipation, 510
Consumption, 469
Contagion, prevention of, 251, 290, 298
Convulsions, 96, 400, 406, 409
Coryza, 451
Cornea, inflammation of, 588
Cough, whooping, 462
Coughing, 195
Countenance, expression of, in disease, 205, 388
Coup de soleil, 360
Cow-pox, 311
Crepitation, 157
Cretinism, 112
Croup, 449
,, spasmodic or false, 450
Cutaneous diseases, 607
Cyanosis, 434
Cynanche maligna, 321
,, trachealis, 449
Cysticercus, 652
Cystin, 129
Cystitis, 557
Cystorrhœa, 558

DANDRIFF, 635
Deafness, 604
Death by apnœa, 31
,, by asthenia, 30
,, by syncope, 31
,, causes of, 28
Debility, state of the circulation in, 94
Delhi boil, 641
Delirium, febrile, 111
Delirium traumaticum, 416
,, tremens, 111, 416
Delusions, 108
Dementia, 113
Demulcents, formulæ, 652
Dengue, 279
Dentition, painful, 487
Deodorants, &c., 227
Depressents, 240
,, doses and formulæ,
Dermmycosis circinata, 615
,, favosa, 617
,, sycosis, 616
Diabetes, 554
Diagnosis, 23
Diaphoretics, doses and formul
Diarrhœa, 190, 234, 508, 525
Diathesis, 2
Diet in disease, 230
Dietaries, 223
Digestion, 39
Diphtheria, 322
Disease, causes of, 13, 21
,, classification of, 19, 21
,, diagnosis of, 23
,, fluctation of, 13
,, forms of, 19
,, nomenclature of, 20
,, prognosis of, 23
,, symptoms and signs of
,, terminations of, 19
,, treatment of, 25
Disinfectants, &c., 228
Disinfection, 298
Displacements of the womb,
Dissection-wounds, 335
Distomum hæmatobium, 550
Diuresis, 557
Diuretics, doses and formulæ,
Doses, tables of, 661 *et seq.*
Dracunculus, 610
Drainage, 210
Dreams, analysis of, 108
Dropped hand, 396
Dropsy, 268, 522
,, of the abdomen, 522
,, ,, areolar tissue,
,, ,, chest, 461
,, ,, heart, 426
,, cardiac, 430
,, encysted, 545, 574
,, hepatic, 526
,, ovarian, 574
,, pulmonary, 461
,, renal, 541 *et seq.*
,, spinal, 377
,, theory of, 71
Drum-belly, 514
Dwelling, the, as affecting hea
Dysenteria—Dysentery, 506
Dysmenorrhœa, 562
Dyspepsia, 497
Dysphonia clericorum, 490
Dyspnœa, table of causes of,
Dysuria, 198, 559

EAR, diseases of, 602
Echinococcus in the heart, 435
" " liver, 536
Ecthyma, 629
Eczema, 623
" impetiginosum, 624
" marginatum, 616
" squamosum, 635
Effusion, 62
Electricity, animal, 98
" atmospheric, 13
" medicinal use of, 402
" remedial use of, 386, 402
Elephantiasis, 637, 640
Embolia and Embolism, 78, 439, 435
Emetics, 233
" doses and formulæ, 679
Emmenagogues, doses and formulæ, 688
Emollients, formulæ, 682
Emotions, 104
Empysema, 460
Employment as a cause of disease, 15
Empyema, 478
Enemata, 235
Encephalitis, 359
Endocarditis, 427
Endosmose and Exosmose, 69
Enteritis, 504
Entozoa, 435, 600
Enuresis, 558
Ephelis, 642
Ephemeral fever, 262
Epidemic constitutions, 13
Epidermmycosis decalvans, 613
" tonsurans, 614
" versicolor, 612
Epilepsy, 409
Epileptic hemplegia, 383
Epithelium in urine, 134
Equinia, 337
Eruptive fevers, 304
Erysipelas, 70
Erythema, 620
Etiology, 21
Eustachian tube, disease of, 604
Exanthemata, 304, 620
Excito-motory system, 92
" " pathology of, 93
Excretion, physiology of, 46 *et seq.*
Exercise, 207
Exhaustion, treatment of, 239
Exophthalmic goitre, 493
Expiration, noisy, 195
Epithelioma, 488, 569
Expectorants, doses and formulæ, 680
Expectoration, the, 196
Extravasation, 194
Eye, diseases of, 583
" inflammation of, 583 *et seq.*
" normal appearance of, 591

FACE, paralysis of, 387
" anæsthesia of, 381
Fæces, the, 40, 192
Fainting, 239, 421
Falling sickness, 409
Family constitution, 3
Famine fever, 300
Farcinoma—Farcy, 337
Fat in urine, 130, 552
Fatty degeneration, 78
" " of the arteries, 79, 436
" " " cornea, 80
" " " heart, 428
" " " liver, 535
Favus, 617
Febricula, 62
Fever, cerebro-spinal, 291
" dandy, 279
" enteric, 292
" ephemeral, 262
" eruptive, 304
" hectic, 327
" infantile, 328
" infectious, 284
" inflammatory, 263
" intermittent, 275
" miliary, 626
" milk, 335
" puerperal, 331
" pyogenic, 229
" relapsing, 300
" remittent, 278
" " infantile, 328
" rheumatic, 348
" scarlet, 316
" simple, 262
" typhoid, 292
" typhus, 284
" vesicular, 627
" yellow, 281
Fevers, classification of, 274
" eruptive, 304
" general observations on, 274, 284
" management of cases of, 290, 298
" prevention of contagion, 251, 290, 298
Fibrin, formation of, 42
Filaria Medinensis, 610
" oculi, 600
" sanguinis, 553
Floccitatio, 203
Flooding, 563–7–9
Food, administration of in sickness, 249
" classification of, 37
" unwholesome, effect on health, 15
" what kinds most digestible, 37
Formulæ, 661
Frambœsia, 638
Fremitus, vocal, 158
Friction sounds, 159
Fungus foot of India, 619
Furunculus, 644

GALL-BLADDER, distension of, 528
Gall-stones, 531
Gangrene, 62, 64
" of the lungs, 467
" " mouth, 486

Gangrene of the skin, 338
Gastralgia, 498
Gastric juice, action of, 36
Gastritis, 496–7
Gastrodynia, 495
Gastro-enteritis mucosa, 515
Genital organs, diseases of, 561
Gingivitis, 487
Glanders, 337
Glands, structure of, 67
Glaucoma, 599
Gleet, 576
Glossary, 691
Glossitis, 488
Goitre, 492
„ exophthalmic, 493
Gonorrhœa, 575
Gonorrhœal ophthalmia, 586
Gout, 353
Granulation, 63
Gravel, 546
Green-sickness, 258
Guinea-worm, 610
Gullet, diseases of, 493
Gums, diagnosis by, 188
„ inflammation of, 487
Gutta serena, 601

Habit, 101
Habits, influence of, on health, 17, 212
Hæmatemesis, 192, 495
Hæmatocele, pelvic, 571
Hæmatozoa, 552
Hæmaturia, 133, 548
„ endemic, 550
„ intermittent, 549
Hæmophilia, 267
Hæmoptysis, 197, 467
Hæmorrhage, 65, 266
„ cerebral, 72, 367
„ pelvic, 571
„ retinal, 595
„ from the bladder, 133, 548
„ „ bowels, 509
„ „ kidney, 133, 548
„ „ lungs, 197, 467
„ „ stomach, 495
„ „ uterus, 563
„ treatment of, 244
Hæmorrhœa petechialis, 345
Hæmorrhoids, 514
Hair, diseases of, parasitical, 613 *et seq.*
„ „ non-parasitical, 631, 628
Hay fever, 460
Headache, 356
Health, means of preserving, 207 *et seq.*
„ and disease, 1
„ influence of external conditions on, 9, 13
„ in town and country, 15
Hearing, disturbance of, 203
Heart, action of, 54
„ aneurism of, 434
„ atrophy of, 428
Heart, diagnosis of
„ dilatation of,
„ diseases of, 4
„ dropsy of, 42
„ entozoic dise
„ examination
„ fatty degener
„ hypertrophy
„ impulse of, 1
„ inflammation
„ movements o
„ neuralgia of,
„ palpitation of
„ position of, 1
„ rhythm of, 16
„ sounds of, 166,
„ spasm of, 421
„ valves of, thei
„ valvular disea
Heartburn, 503
Heat, animal, 97
Hectic fever, 327
Hemicrania, 357
Hemiplegia, 382
Hepatitis, 525
„ gummosa, 5
Hereditary predispositi
Herpes, 625
„ circinata, 615
„ exedens, 643
„ tondens, 614
Hiccough, 195
Hippuric acid, 126
Hospitals, construction
ment of, 219
Hot springs, 216
Humming-top sound, 25
Hunger and thirst, 34,
Hydatids, 365, 435, 536
Hydrocephalus, 364
Hydronephrosis, 545
Hydropericardium, 426
Hydrophobia, 403
Hydrops—Dropsy, 268
Hydrorachis, 377
Hydrothorax, 478
Hygiène, private, 203
„ public, 212
Hypertrophy, 77
„ of the heart,
Hypnotics, or soporifics, 2
Hypochondriasis, 115, 415
Hypopyon, 588
Hysteria, 406
Hysterical asthma, 460
„ hemiplegia, 383
„ pain, 357, 379
Hysteritis, 331, 565

Icterus, 532
„ neonatorum, 534
Ichthyosis, 635
Idiocy, 112
Idiosyncrasis, 5
Illusion, 100

sions spectral, 105
sive transformations, 107
agination, 104
becility, 112
petigo, 629
continence of urine, 558
dications and contra-indications, 26
digestion, 497
fantile jaundice, 534
„ remittent fever, 328
„ syphilis, 581
„ tetanus, 402
fection, prevention of, 251, 290, 298
flammation, acute, 263
„ causes which modify, 264
„ chronic, 265
„ related to nutrition, 59
„ terminations of, 62, 265
„ theory of, 59
„ treatment of, 242
„ varieties of, 62
nflammatory fever, 263
nfluenza, 452
ngesta and egesta, 51
noculation, syphilitic, 579
„ vaccine, 311
nsolatio, 360
nspiration, noisy, 194
ntemperance, effect of, on health, 16
ntermittent fever, 275
ntertrigo, 621
ntestinal irritation, puerperal, 334
„ worms, 646
ntestines, disorders of, treatment of, 504
„ distension by air, 514
„ hæmorrhage from, 509.
„ intussusception of, 511
„ large, inflammation of, 506
„ obstruction of, 510
„ perforation of, 293-4, 511
„ small, inflammation of, 504
„ torpor of, 510
„ ulceration of, 294, 505
Intus-susceptio, 511
Iritis, 589
Irritant poisons, 655
Irritation, constitutional, 95, 263
„ intestinal, puerperal, 334
„ peritoneal puerperal, 334
„ spinal, 375
Ischuria, renalis, 554
Iseriberi, 405
Isothermal lines in relation to disease, 11
Itch, 608

JAUNDICE, 532
„ of infants, 534

KAKKE, 405
Keloid 639
Kerion, 614
Kidney, albumenoid degeneration of, 546
„ calculi in, 526, 534
Kidney, cystic diseases of, 545
„ fatty degeneration of, 546
„ gouty, 354
„ granular disease of, 542
„ inflammation of, 539
„ tubercle and cancer of, 546
King's evil, 340
Kyestein, 132

LARYNGISMUS stridulus, 450
Laryngitis, 443
Laryngoscope, use of, 446
Larynx, diseases of, 443
Laxatives, doses and formulæ, 234
Lead colic, 513
„ palsy, 396
Lens, diseases of, 599
Lentigo, 626
Lepra, 634
„ Arabum, 637
Leprosy, 637
„ Italian, 635
Leucin, 530
Leucocythæmia, 260
Leucorrhœa, 564
Lichen, 632
Life, theories of nature of, 32
Light and air, 211, 249
Lips, diagnosis by, 186
Lithiasis, 546
Lithates of ammonia and soda, 127
Lithic acid. (See Uric acid.)
Liver, abscess of, 528
„ acute atrophy of, 529
„ albuminoid degeneration of, 535
„ circulation through, 72
„ cirrhosis of, 526
„ congestion of, 524
„ fatty degeneration of, 535
„ function of, 39
„ hydatid tumours of, 536
„ inflammation of, 525
„ malignant diseases of, 537
„ syphilitic diseases of, 535
Locked jaw, 400
Locomotor ataxy, 394
Logic, 102
Lousiness, 610
Lumbago, 352
Lunacy, 111
Lungs, and liver, reciprocal action of, 39, 525
„ bleeding from, 197, 467
„ capacity of, 146
„ collapse of, 455
„ consumption of, 469
„ emphysema of, 460
„ examination of, 146
„ functions of, 46
„ gangrene of, 467
„ inflammation of, 464
„ tubercular diseases of, 469
Lupus, 643
Luxury, influence of, on health, 17
Lymph, 41

Lymphatics, 70
  " inflammation of, 335

MADNESS, 113, 403, 412, 416
  " canine, 403
Malacosteon, 344
Mal-assimilation, 40
Malignant diseases, 82, 488, 501, 537, 569
  " pustule, 338
Malum Alepporum, 640
Mania, 113, 403, 412, 416
Marasmus, 294
Mastication, 35
Measles, 313
  " German, 320
Meconium, 39
Medicine, administration of, 249
Medicines, doses of, 661 *et seq.*
Megrim, 357
Melæna, 509
Melancholia, 114, 415
Melanosis, 83
Melasma, 261
Memory, 100
Meningitis, 359
  " spinal, 374
  " tubercular, 359
Menorrhagia, 563
Menses, the, 561
Menstruation, difficult, 562
  " excessive, 563
  " normal, 561
  " suppressed, 561
Mentagrophyte, 616
Mercurial stomatitis, 485
  " tremors, 397
Metallic tinkling, 158, 481
  " breath sounds, 481
Metastasis, 68
Metritis, 338, 565
Microsporon Audouini, 6[illegible]
  " furfur, 613
  " mentagrophytes, 616
Miliaria—Miliary fever, 626
Milk fever, 335
Milky urine, 130, 552
Mimosis inquieta, 261
Mind, disorders of, 112 *et seq.*
  " physiology and pathology of, 98
Mineral waters, 215
Moisture, its influence on health, 12
Mollities ossium, 344
Molluscum, 638
Monomania, 114
Morbus Addisonii, 261
Morphœa, 639
Morbilli, 313
Mortality at different ages, 7
  " in males and females, 7
  " in town and country, 15
  " relation to occupation, 15
Mouth, gangrene of, 486
  " inflammation of, 482

Mucous rale, 158
Mucus, property of, in
Mumps, 491
Murmurs, cardiac, 166
Muscæ volitantes, 602
Muscular action, disor
  " rheumatism,
  " sound, 156
Mycetoma, 618
Myelitis, 373
Myopia, 602

NARCOTIC poisons, 656
Narcotico-acrid poisons
Narcotics, 241, 246
  " action of, on
  " doses and for
  " and stimulant
Nephritis, 539
Nerves, effect on the he
  " " mc
  " properties of,
Nervous diseases, 356
  " pain, 377, *et seq*
  " state, 261
  " system, physiol logy of, 83, 199, 356
Nettle-rash, 621
Neuralgia, 377
  " hysterical, 37
  " of the face, 37
Nitrogen, elimination o
Noma, 486
Nomenclature, medical,
Nosology, 21
Nurse, duties of, 250
Nursing, 248
Nutrition and secretion,
  " disorders

OCULAR spectra, 106
Œdema, 61, 268
Œsophagus, diseases of,
Oidium albicans, 484
Onychomycosis, 615
Oophoritis, 573
Ophthalmia, catarrhal, 5
  " gonorrhœal,
  " purulent, 58
  " rheumatic, 58
  " strumous, 58
Ophthalmoscope, use of,
Optic disc and nerve, *et seq.*
Organisation, 63
Osteo-malacia, 344
Otitis, 602
Otorrhœa, 604
Ovarian tumours and dr
Ovary, inflammation of,
Overcrowding, 217
Oxalate of lime, 127
Oxyuris,

PAIN, 200, 377, *et seq.*
Painter's colic, 513
Palpitation, 418
Palsy, 382
  „ lead. 396
  „ shaking, 392
  „ wasting, 395
Pancreas, diseases of, 538
  „ function of, 38
Paracentesis cranii, 367
  „ thoracis, 479
  „ abdominis, 523
  „ pericardii, 426
Paralysis, 382, 387
  „ agitans, 392
  „ bulbar, 391
  „ general, 390
  „ infantile, 393
  „ metallic, 396, 397
  „ of the face, 387
  „ „ insane, 390
  „ „ nerves of sensation, 831
Paraplegia, 384
  „ reflex, 385
Parasites, animal, 435, 536, 551–53, 600, 609-11
  „ vegetable, 132, 484, 503, 613, *et seq.*
Parotitis, 491
Passions, 104
Pathology, general, 32
  „ of the circulation, 54
  „ „ fluids, 33
  „ „ nervous system, 93
  „ structural, 75
Paupers, health of, 218
Pectoriloquy, 158
Pediculi, 595
Pellagra, 610
Pelvic hæmatocele, 571
Pemphigus, 627
Perception, 100
Percussion of abdomen, 142
  „ chest, 153
Perforation of the stomach, 501
  „ „ bowels, 294, 511
Pericarditis, 423
Pericardium, adherent, 426
  „ dropsy of. 426
  „ inflammation of, 423
Peritonitis, 520
  „ puerperal, 332
  „ tubercular, 521
Perspiration, 49
  „ abnormal, 645
Pertussis, 462
Pestis, 325
Petechiæ, 194
Petit mal, 409
Phlebitis, 440
Phlegmasia dolens, 441
Phlegmon, 62
Phlogosis, 263
Phosphates, 128
Phosphoric acid, estimation of, 127
Phrenitis, 359
Phthisis pulmonalis, 469
Phthiriasis, 610
Physiology and pathology, 32
  „ of the fluids, 33
  „ of the solids, 75
Piles, 514
Pityriasis, 635
  „ versicolor, [illegible]2
Plague, 325
Plastic bronchitis, 455
Plethora, 254
Pleuritis—Pleurisy, 477
Pleurodynia, 351
Plica Polonica, 618
Pneumonia, 464
Pneumothorax, 480
Podagra, 353
Poisons, action of, on the nerves. 88
  „ animal, 284, 337–8, 575–6
  „ antidotes for, 659
  „ irritant, 655
  „ narcotic, 656
  „ narcotic-acrid, 657
Polio-myelitis anterior, 393
Polydipsia, 35
Polypi, uterine, 569
Porrigo decalvans, 613
  „ lupinosa, 617
  „ scutulata, 614, 617
Posture, influence of, on cerebral circulation, 74
  „ of the body, in disease, 205
Predisposition, hereditary, 3
Pregnancy, signs of, 199
Presbyopia, 602
Prescriptions, 661
Priapism, 199
Prisoners, health of, 218
Prisons, construction and arrangement of, 218
Prognosis, 23
Prolapsus of the womb, 571
Protein, 38
Prurigo, or Pruritus, 633
Psoriasis, 634
Ptosis, 389
Puberty, 6
Puerile respiration, 156
Puerperal fevers, 331
Pulmonary consumption, 469
Pulse, the, 170
  „ character and varieties of, 177, 180
  „ diurnal variations of, 175
  „ effect of emotions on, 175
  „ „ exercise on, 175
  „ „ food on, 175
  „ „ sleep on, 175
  „ in debility, 176
  „ in disease, 172, 179
  „ influence of posture, 174
  „ „ pressure, 176
  „ „ sex on, 173

Pulse, influence of temperament, 174
„ „ temperature, 176
„ in pulmonary consumption, 472
„ number of, at different ages, 171, 173
„ ratio of, to respiration, 183
„ venous, 69
Pupil, diagnosis by, 202, 247
Purgatives, 234
„ doses and formulæ, 682
Purging, 508
Purpura, 345
Pus, properties of, in urine, 134
Pustula maligna, 338
Putrid sore throat, 317, 322
Pyæmia, 328, 439, 441
Pyelitis, 547
Pyrosis, 503

QUINSY, 489

RACHITIS, 342
Râles, 157
Rashes, 304, 620
Reasoning, the process of, 102
„ impairment of, 103
Reflex action, 85, 92
Relapsing fever, 300
Remedies, classification of, 661
Remittent fever, 278
„ „ infantile, 328
Resolution, 62
Respiration, abnormal, 156
„ amphoric, 157
„ bronchial, 156
„ function of, 46
„ normal, 149
„ puerile, 156
„ in disease, 194
Respirations, at different ages, 182
„ diurnal variations of, 182
„ during sleep, 182
„ in different postures, 182
„ in two sexes, 182
„ number of, 181
„ proportion of, to pulse, 183
Restoratives, 236
Retina, normal appearance of, 591
„ detachment of, 596
„ diseases of, 594, *et seq.*
Retroversion of the womb, 572
Rheumatism, 348
„ gonorrhœal, 575
Rhonchus, varieties of, 157
Rickets, 342
Ringworm of the body, 615
„ „ scalp, 614
Risus sardonicus, 400
Roseola—Rose rash, 622
Rötheln, 320
Rubeola, 313
Rubefacients, 665
Rupia, 628

SAILORS, preservation of health
Saliva, in disease, 189
„ in digestion, 35
Salivation, 485
Salts, elimination of, 52
Sarcina ventriculi, 192, 503
Scabies, 608
Scall head, 617
Scarlatina—Scarlet fever, 316
Sciatica, 380
Sclerosis of the spinal cord, 39
Sclerotic, inflammation of, 587
Scorbutus, 347
Scrofula, 3, 340
Scurvy, 345
Seasons, effects of, on health, 10
Secretion, morbid, 68
„ physiology of, 46, *et seq*
„ remedies which promot
Sedatives, 241, 246
„ and stimulants, formula
„ doses and formulæ, 668
Semen in urine, 134
Sensation, disorders of, 96, 200, 3
„ paralysis of nerves of, 3
Sense, organs of, 99
Septicæmia, 329
Serum, 44
Sex, its influence on disease, 5
„ „ on mortality, 5
Sexual organs, diagnosis by, 199
Shaking palsy, 392
Shelter, 210
Sibilus, 157
Sick, management of the, 248
Sickness, influence of age on, 9
Sighing, 194
Sight, disturbance of, 202
„ defects of, 601-2
Signs of disease, 22
Sight and soil, 209
Skin, diseases of, 607
„ „ classification of, 6
„ „ definitions of, 608
„ „ non-parasitical, 6
„ „ parasitical, 608
„ „ syphilitic, 577
„ functions of, 48
Sleep, 74
Small-pox, 304
Smell, disturbance of, 203
Sneezing, 195
Snuffles, 58
Sobbing, 195
Soldiers, preservation of health of, 22
Somnambulism, 110
Soporifics or Hypnotics, 246
Sore-throat, inflammatory, 317, 322, 48
Spasm of the heart, 420
„ tonic and clonic, 96
Spectral illusions, 105
Spermatorrhœa, 581
Sphygmograph, the, 180
Spina bifida, 377
Spinal apoplexy, 377

oncussion, 377
ord, inflammation of, 373
liagnosis of, 373
ffusion, 377
rritation, 375
neningitis, 374
clerosis, 391
ystem, pathology of, 373
ter, the, 151
of blood, 197, 467
diseases of, 277, 537
96
g, 202, 387
ony's fire, 278
s's dance, 398
oma posticum, 597
f systems, 254
194
eters, 146
nts, 87, 237, 246
action of, on the nerves, 246
and sedatives, formulæ, 671
doses and formulæ, 661
h, acidity of, 503
atony of, 502
cancer of, 501
congestion of, 494
hæmorrhage from, 495
inflammation of, 496
neuralgia of, 498
perforation of, 501
self-digestion of, 500
ulcer of, 499
hics, 233
tis, 482
the bladder, 547
nus, 202, 387
ry, 198, 559
3, 340
s tendinum, 203
ion, 159
n urine, tests for, 131
estimation of, 131
ic acid, estimation of, 127
oke, 360
sion of urine, 554
of bile, 529
ation, 62, 76
enal cachexia, 261
omposition of, 48
lands, diseases of, 645
ox, 313
631
parasitic, 616
hetic nerve, functions of, 89
diarrhœa, 509
vomiting, 504
hies, 91
matology, 22
, 239, 421
anginosa, 420
, 488, 576
infantile, 581
inoculation of, 579
local, 576-81

Syphilis secondary, 535, 589
„ transmission of, 579
Systems, states of, 254

TABES dorsalis, 394
„ mesenterica, 522
Tænia echinococcus, 419, 435, 536
„ tape-worm, 651
Taste, derangements of, 189
Teeth, diagnosis by, 189
„ cutting of the, 487
Temperaments, 1
Temperature, isothermal lines, 11
„ its effect on health, 9
„ variations of, in the body, 97, 204
Tetanus, 400
„ neonatorum, 402
Tetter, 625
„ crusted, 629
„ dry, 634
„ humid, 623
„ running, 623
Therapeutics, general outline of, 230
Thirst, 35, 190
Thread-worms, 648
Thrombosis, 78, 435-9
Thrush, 483
Tic-douloureux, 378
Tinea circinata, 615
„ decalvans, 613
„ favosa, 617
„ sycosis, 616
„ tonsurans, 614
„ versicolor, 612
Tongue, cancer of, 488
„ diagnosis by, 186
„ inflammation of, 488
Tonics, 240
„ doses and formulæ, 672
Tonsillitis, 489
Torpor intestinorum, 510
Torticollis, spasmodic, 399
Torula cerevisiæ, 132, 503
Touch, impairment of, 201
Town life, influence of, on health, 14, 211
Tracheitis, 449
Treatment of disease, 26
Trembles, the, 392
Tremor mercurialis, 397
Trichina spiralis, 649
Trichocephalus dispar, 646
Trichomonas vaginalis, 571
Trichophyton tonsurans, 615
„ sporuloides, 618
Trichuris, 646
Trismus, 400
„ nascentium, 402
Tubercle, 81, 470, 521, 601
Tumours, malignant, 81
Tympanites, 514
Tympanum, examination of, 604
„ perforation of, 605
„ auscultation of, 605

Tympanum, inflation of, 605
Typhomania, 293
Typhous state, 286, 293
Typhus fever, 284
,, icterodes, 281
,, abdominal, 292
Tyrosin, 530

ULCERATION, 64
,, of the bowels, 294, 505
,, ,, stomach, 499
Uræmia, 517, 554
Urates of ammonia and soda, 355
Urea and uric acid, composition of, 50, 124
,, estimation of, 124
Ureter, stone in, 547
Uric acid, 125
Urinary calculi, 547
,, deposits, 124 *et seq.*
,, organs, diagnosis by, 198
,, ,, diseases of, 539
,, tubes, casts of, 135
Urine, the, in health and disease, 49, 119
,, bloody, 133, 548
,, chylous, 130, 552
,, difficulty in voiding, 198, 559
,, fatty, 552
,, immoderate flow, 554-7
,, incontinence of, 558
,, morbid, 130
,, properties of, 119
,, retention of, 198
,, saccharine, 130, 554
,, suppression of, 198, 554
,, tables of solids contained in, 137
,, tests for, 122 *et seq.*
Urticaria, 621
Uterus, cancer of, 568
,, congestion of, 563, 566
,, displacements of, 571
,, fibrous tumours of, 569
,, hæmorrhage from, 563, 568
,, inflammation of, 333, 505
,, ulceration of, 566

VACCINIA, cow-pox, 311
Vaccination, 311
Vaginitis, 564
Varicella, 311
Variola, 304
Varioloid, 307
Veins, diseases of, 439
,, inflammation of, 440
,, structure of, 68
Venous circulation, 68
,, murmur, 257
,, pulse, 60, 194
Ventilation, 47, 211, 24
Vesicants, 665
Vis medicatrix naturæ,
Vision, defects of, 601-2
,, disturbance of, 2
,, long or old, 602
,, short, 602
Vital principle, 32
Vocal sounds, 158
Voice, loss of, 446
Volition, 100
Vomited matters, 191
Vomiting, 191
,, of blood, 192,
,, sarcinæ, 503
,, sympathetic, 5

WARMING, 212
Waste of the body, 77
Water, elimination of, 4
,, brash, 503
,, impure, its effect
,, in the belly, 522,
,, ,, chest, 473
,, ,, head, 364
,, ,, heart, 426
,, ,, spinal she
,, ,, supply, 21
Watering-places, &c., 21
Waters, mineral, 215
Wealth, an indirect caus
Weights and measures, 6
White leg, 441
Whites, the, 564
Whooping-cough, 462
Windpipe, diseases of, 45
Womb, cancer of, 77, 50
,, congestion of, 56
,, displacements of,
,, fibrous tumours
,, hæmorrhage from
,, inflammation of,
,, ulceration of, 566
Wool sorters' disease, 33
Workhouses, constructio
Worms, intestinal, 646
Wry-neck, spasmodic, 39

YAWNING, 194
Yaws, the, 638
Yellow fever, 81

PRINTED BY BALLANTYNE, HANSON AND CO.
LONDON AND EDINBURGH